DELAWARE TECHNICAL COMMUNITY COLLEGE

CONTRACT # DTCC C9004020007

SPECIFICATIONS
FOR

OWENS CAMPUS
DENTAL HEALTH CENTER AT THE CARTER PARTNERSHIP BUILDING

IN

Owens Campus
21179 College Drive,
Georgetown, DE 19947

PREPARED
BY

TEVEBAUGH ARCHITECTURE
2 MILL RD, SUITE 210
WILMINGTON, DE

ISSUED FOR
BIDDING


PAGE LEFT INTENTIONALLY BLANK

SECTION 00 01 07


SEALS PAGE

1.1 DESIGN PROFESSIONALS OF RECORD

Architect:
William J. Lenihan, AIA
Tevebaugh Associates, Inc.
Two Mill Road, Suite 210
Wilmington, DE 19806
302-984-1400
DE License No.: S5-7202
All specification 00 to 13 and 33 unless noted otherwise.



MEP Engineer:
Dave Hoffman
Gipe Associates, Inc.
8719 Brooks Drive
Easton, MD 21601
(410) 822-8688
DE License No.:
Specification Sections 01 91 13, 01 91 15, 07 84 13; Divisions 21 to 28



PAGE LEFT INTENTIONALLY BLANK

SECTION 00 01 10
TABLE OF CONTENTS

A. Specifications for this project are arranged in accordance with the Construction Specification Institute numbering system and format. Section numbering is discontinuous and all numbers not appearing in the Table of Contents are not used for this Project.

B. DOCUMENTS BOUND HEREWITH

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENT

00 01 01 PROJECT TITLE PAGE

00 01 07 SEALS PAGE

00 01 10 TABLE OF CONTENTS

00 01 15 LIST OF DRAWING SHEETS

00 11 16 INVITATION TO BID

00 21 13 GENERAL REQUIREMENTS

00 41 13 BID FORM

00 43 13 BID BOND

00 52 13 STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

(SAMPLE AIA A101-2017)

(SAMPLE AIA A101-2017 – EXHIBIT A)

DTCC AMENDMENT TO AGREEMENT BETWEEN OWNER AND CONTRACTOR A101 2017

00 61 13.13 PERFOMANCE BOND

00 61 13.16 PAYMENT BOND

00 62 11 SUBMITTAL COVER SHEET

00 62 76 APPLICATION AND CERTIFICATE FOR PAYMENT FORMS

(SAMPLE AIA G702 & G703)

00 63 13 REQUEST FOR INTERPRETATION FORM

00 63 25 SUBSTITUTION REQUEST FORM

00 63 33 AIA DOCUMENTS G710 - 2019: SUPPLIMENTAL INSTRUCTION FORMS

00 63 46 AIA DOCUMENTS G714 - 2017: CONSTRUCTION CHANGE DIRECTIVE

00 63 63 AIA DOCUMENT G701 - 2019: CHANGE ORDER

00 65 16 AIA DOCUMENT G704 - 2017: CERTIFICATE OF SUBSTANTIAL COMPLETION

00 65 19.13 AIA DOCUMENT G706 - 1994: CONTRACTOR'S AFFIDAVIT OF PAYMENT OF DEBTS AND CLAIMS

00 65 19.16 AIA DOCUMENT G706A - 1994: CONTRACTOR'S AFFIDAVIT OF RELAEASE OF LIENS

00 65 19.19 AIA DOCUMENT G707 - 1994: CONSENT OF SURETY TO FINAL PAYMENT

00 72 13 GENERAL CONDITIONS TO THE CONTRACT A201 - 2017

00 73 14 DTCC AMENDMENTS TO THE AIA A201 - 2017 DTCC

00 73 46 WAGE DETERMINATION SCHEDULE

FEDERAL CONTRACT AWARD REQUIREMENTS

00 81 13 GENERAL REQUIREMENTS

00 81 14 DRUG TESTING FORMS

00 81 15 AFFADAVIT FOR CRAFT TRAINING COMPLIANCE

DIVISION 01 - GENERAL REQUIREMENTS

01 10 00 SUMMARY

01 21 00 ALLOWANCES

01 21 16 ALLOWANCE AUTHORIZATION FORM

01 23 00 ALTERNATES

01 25 00 SUBSTITUTION PROCEDURES

01 26 00 CONTRACT MODIFICATION PROCEDURES

01 29 00 PAYMENT PROCEDURES

01 32 00 CONSTRUCTION PROGRESS DOCUMENTATION

01 33 00 SUBMITTAL PROCEDURES

01 40 00 QUALITY REQUIREMENTS

01 42 00 REFERENCES

01 50 00 TEMPORARY FACILITIES AND CONTROLS

01 60 00 PRODUCT REQUIREMENTS

01 74 19 CONSTRUCTION WASTE MANAGEMENT

01 77 00 CLOSEOUT PROCEDURES

01 78 23 OPERATION AND MAINTENANCE DATA

01 78 39 PROJECT RECORD DOCUMENTS

01 91 13 GENERAL COMMISSIONING REQUIREMENTS

01 91 15 HVAC COMMISSIONING REEQUIREMENTS

DIVISION 02 - EXISTING CONDITIONS

02 41 19 SELECTIVE DEMOLITION

DIVISION 03 - CONCRETE

03 35 43 POLISHED CONCRETE FINISHING

DIVISION 04 – MASONRY

04 01 20.63 BRICK MASONRY REPAIR

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00 ROUGH CARPENTRY

06 41 00 ARCHITECTURAL WOOD CASEWORK

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 84 13 FIRE PROTECTION, HVAC & PLUMBING PENETRATION FIRESTOPPING

07 92 00 JOINT SEALANTS

07 92 19 ACOUSTICAL JOINT SEALANTS

DIVISION 08 – OPENINGS

08 06 71 DOOR HARDWARE SCHEDULE

08 12 13 HOLLOW METAL FRAMES

08 14 16 FLUSH WOOD DOORS

08 31 13 ACCESS DOORS AND FRAMES

08 41 13 ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

08 71 00 DOOR HARDWARE

08 80 00 GLAZING

DIVISION 09 – FINISHES

09 22 16 NON-STRUCTURAL METAL FRAMING

09 29 00 GYPSUM BOARD

09 30 13 CERAMIC TILING

09 51 13 ACOUSTICAL PANEL CEILINGS

09 65 13 RESILIENT BASE AND ACCESSORIES

09 65 19 RESILIENT TILE AND PLANK FLOORING

09 68 13 TILE CARPETING
09 91 23 INTERIOR PAINTING

DIVISION 10 – SPECIALTIES
10 14 23.16 ROOM-IDENTIFICATION PANEL SIGNAGE
10 26 00 WALL AND DOOR PROTECTION
10 28 00 TOILET, BATH, AND LAUNDRY ACCESSORIES
10 44 13 FIRE PROTECTION CABINETS
10 44 16 FIRE EXTINGUISHERS
10 73 13 AWNINGS

DIVISION 12 – FURNISHINGS
12 24 13 ROLLER WINDOW SHADES
12 35 53.16 PLASTIC-LAMINATE-CLAD LABORATORY CASEWORK
12 48 13 ENTRANCE FLOOR MATS AND FRAMES

DIVISION 13 - SPECIAL CONSTRUCTION
13 49 00 RADIATION PROTECTION

DIVISION – 21 FIRE SUPPRESSION
21 05 00 COMMON WORK RESULTS FOR FIRE PROTECTION
21 05 05 FIRE SUPPRESSION SYSTEM PIPING, FITTINGS & VALVES
21 10 03 WATER BASED FIRE SUPPRESSION SYSTEM – SPRINKLERS

DIVISION 22 – PLUMBING
22 05 00 COMMON WORK RESULTS FOR PLUMBING
22 05 05 PLUMBING PIPING, FITTINGS AND VALVES
22 07 01 PLUMBING INSULATION
22 40 00 PLUMBING FIXTURES
22 40 05 PLUMBING EQUIPMENT
22 61 13 COMPRESSED-AIR PIPING FOR DENTAL SYSTEMS
22 61 19 COMPRESSED AIR EQUIPMENT FOR DENTAL SYSTEMS
22 62 13 VACUUM PIPING FOR DENTAL SYSTEMS
22 62 19 VACUUM EQUIPMENT FOR DENTAL SYTEMS

DIVISION 23 – HEATING, VENITLATING AND AIR CONDITIONING

23 05 00 COMMON WORK RESULTS FOR HVAC

23 05 05 HVAC PIPING, FITTINGS AND VALVES

23 05 48 VIBRATION CONTROLS FOR HVAC, PLUMBING AND FIRE PROTECTION EQUIPMENT

23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC AND PLUMBING

23 06 00 HEATING, VENTILATING, AND AIR CONDITIONING EQUIPMENT

23 07 01 HVAC INSULATION

23 09 00 INSTRUMENTATION AND CONTROLS OF HVAC AND PLUMBING SYSTEMS

23 30 00 HVAC AIR DISTRIBUTION

DIVISION 26 – ELECTRICAL

26 05 01 COMMON WORK RESULTS FOR ELECTRICAL

26 05 02 ELECTRICAL DEMOLITION FOR REMODELING

26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

26 05 28 ELECTRICAL FIRESTOPPING

26 05 29 HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

26 05 33 RACEWAYS ABD BOXES FOR ELECTRICAL SYSTEMS

26 05 53 IDENTIFICATIONS FOR ELECTRICAL SYSTEMS

26 08 00 COMMISSIONING OF ELECTRICAL SYSTEMS

26 09 23 LIGHTING CONTROL DEVICES

26 24 16 PANELBOARDS

26 27 26 WIRING DEVICES

26 43 13 SURGE PROTECTIVE DEVICES

26 51 00 INTERIOR LIGHTING

DIVISION 27 – COMMUNICATIONS

27 15 13 DATA, VOICE AND VIDEO SYSTEMS

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

28 31 11 FIRE ALARM SYSTEM

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 13 13 CONCRETE PAVING

32 13 73 CONCRETE PAVING JOINT SEALANTS

32 91 13 SOIL PREPARATION

32 92 00 TURF AND GRASSES

END OF SECTION

SECTION 00 01 15
LIST OF DRAWING SHEETS

GENERAL

CS01	COVER SHEET
LS001	BUILDING CODE
LS002	LIFE SAFETY PLAN

ARCHITECTURAL

AD100	DEMOLITION PLANS
A101	NEW CONSTRUCTION FLOOR PLAN
A110	NEW CONSTRUCTION REFLECTED CEILING PLAN
A120	ROOF PLAN AND DETAILS
A301	EXTERIOR ELEVATION AND DETAILS
A401	ACCESSSIBILITY STANDARD
A402	ENLARGED RESTROOM PLANS AND ELEVATIONS
A410	ENLARGED PLANS AND ELEVATIONS
A531	PARITION SCHEDULE AND DETAILS
A601	DOOR SCHEDULE, WINDOW SCHEDULE & DETAILS
A801	FINISH LEGEND, SCHEDULE & DETAILS
A801	FINISH PLANS
A901	EQUIPMENT & FURNITURE PLAN
A910	CASEWORK SECTIONS
A911	CASEWORK SECTIONS

STRUCTURAL

S001	COVER SHEET
S101	FOUNDATION PLAN
S102	ROOF FRAMING PLAN
S401	FOUNDATION DETAILS & SECTIONS
S501	FRAMING DETAILS & SECTIONS
S502	FRAMING DETAILS & SECTIONS

MECHANICAL

M001	MECHANICAL TITLE SHEET
MD101	FIRST FLOOR PLAN – HVAC – DEMOLITION
MD102	ROOF PLAN – HVAC – DEMOLITION
M101	FIRST FLOOR PLAN – HVAC – NEW WORK
MP101	FIRST FLOOR PLAN – MECHANICAL PIPING – NEW WORK
M102	ROOF PLAN – HVAC
M301	DETAILS – HVAC
M302	DETAILS – HVAC
M303	DETAILS – HVAC
M401	CONTROLS – HVAC
M402	CONTROLS – HVAC
M403	CONTROLS – HVAC
M501	SCHEDULES – HVAC

FIRE PROTECTION

F101	FIRE PROTECTION ZONING DIAGRAM

PLUMBING

P001	PLUMBING TITLE SHEET
PD101	FIRST FLOOR PLAN – PLUMBING – DEMOLITION
PD102	ROOF PLAN – PLUMBING – DEMOLITION
P101	FIRST FLOOR PLAN – PLUMBING – NEW WORK
P102	ROOF PLAN – PLUMBING – NEW WORK
P301	DETAILS – PLUMBING
P302	DETAILS – PLUMBING
P303	DETAILS – PLUMBING
P304	DETAILS – PLUMBING
P401	RISERS – PLUMBING
P402	RISERS – PLUMBING
P403	RISERS – PLUMBING
P501	SCHEDULES – PLUMBING

ELECTRICAL

E001	LEGEND AND ABBREVIATIONS ELECTRICAL
E002	LIGHTING FIXTURE SCHEDULE
ED101	FIRST FLOOR PLAN – LIGHTING – DEMOLITION
ED201	FIRST FLOOR PLAN – POWER AND SPECIAL SYSTEM– DEMOLITION
E201	FIRST FLOOR PLAN – LIGHTING
E301	FIRST FLOOR PLAN – POWER
E302	ROOF PLAN – ELECTRICAL
E401	FIRST FLOOR PLAN - FIRE ALARM
E501	SCHEMATIC POWER RISER DIAGRAM
E502	SCHEMATIC FIRE ALARM RISER DIAGRAM
E601	SCHEDULES ELECTRICAL
E701	DETAILS ELECTRICAL
E702	DETAILS ELECTRICAL
E703	DETAILS ELECTRICAL
E704	DETAILS ELECTRICAL
E705	DETAILS ELECTRICAL
E706	DETAILS ELECTRICAL

END OF SECTION

PAGE LEFT INTENTIONALLY BLANK

SECTION 00 11 16
INVITATION TO BID

Public notice is hereby given that sealed bids for Delaware Technical Community College Contract No. #DTCC C004020007 **Dental Health Center** located at **Owens Campus 21225 College Drive, Georgetown, DE 19947**. Bids will be received at Carter Partnership Building **21225 College Dr, Georgetown, DE 19947** in the **Faucett Lecture Hall #529** until **2 pm** local time on **December 3, 2026**, at which time they will be publicly opened and read aloud. Bidders bear the risk of late delivery. Any bids received after the stated time will be returned unopened.

Delaware Technical Community College is expanding its educational and patient care facilities through the development of a new Dental Health Center at the Carter Partnership Center on the Georgetown Campus. The renovation includes a new exterior sidewalk, entrance, and canopy that lead into a welcoming reception and waiting area. The facility will feature new unisex restrooms, a break room, reception area, dental operatories, X-ray alcoves, a dental laboratory, sterilization laboratory, computer laboratory, storage rooms, and a dedicated dental mechanical room.

The project also includes comprehensive interior and exterior improvements, including new architectural finishes, millwork and carpentry, mechanical and electrical upgrades, concrete trenching and patching, limited roofing repairs, and minor structural modifications to support the new program requirements.

A Pre-Bid Meeting will be held at the Carter Partnership Building **21225 College Dr, Georgetown, DE 19947** in the **Faucett Lecture Hall #529** on **November 12, 2026** at **1 pm** local time for the purpose of establishing the listing of subcontractors and answering questions. **ATTENDANCE AT THIS MEETING IS MANDATORY.**

Sealed bids shall be addressed to the Delaware Technical Community College, Carter Lecture Hall Room # 529; 21225 College Dr, Georgetown, DE 19947. The outer envelope should clearly indicate: **"DTCC CONTRACT NO. DTCC C9004020007 SEALED BID - DO NOT OPEN."**

Contract documents may be obtained at the office of TEVEBAUGH ARCHITECTURE OFFICE: 2 MILL RD., SUITE 210 WILMINGTON, DE. 19806 at no cost.

Construction documents will be available for review at the following locations: TEVEBAUGH ARCHITECTURE OFFICE: 2 MILL RD., SUITE 210 WILMINGTON, DE. 19806.

Bidders will not be subject to discrimination on the basis of race, creed, color, sex, sexual orientation, gender identity or national origin in consideration of this award, and Minority Business Enterprises, Disadvantaged Business Enterprises, Women-Owned Business Enterprises and Veteran-Owned Business Enterprises will be afforded full opportunity to submit bids on this contract. Each bid must be accompanied by a bid security equivalent to ten percent of the bid amount and all additive alternates. The successful bidder must post a performance bond and payment bond in a sum equal to 100 percent of the contract price upon execution of the contract. The Owner reserves the right to reject any or all bids and to waive any informalities therein. The Owner may extend the time and place for the opening of the bids from that described in the advertisement, with not less than two calendar days notice by certified delivery, facsimile machine or other electronic means to those bidders receiving plans.

END OF SECTION

SECTION 00 21 13

INSTRUCTIONS TO BIDDERS

TABLE OF ARTICLES

1. GENERAL

2. BIDDER'S REPRESENTATION

3. BIDDING DOCUMENTS

4. BIDDING PROCEDURES

5. CONSIDERATION OF BIDS

6. POST-BID INFORMATION

7. PERFORMANCE BOND AND PAYMENT BOND

8. FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

ARTICLE 1: GENERAL

1.1 DEFINITIONS

1.1.1 Whenever the following terms are used, their intent and meaning shall be interpreted as follows:

1.2 STATE: The State of Delaware.

1.3 AGENCY: Contracting State Agency as noted on cover sheet.

1.4 DESIGNATED OFFICIAL: The agent authorized to act for the Agency.

1.5 BIDDING DOCUMENTS: Bidding Documents include the Bidding Requirements and the proposed Contract Documents. The Bidding Requirements consist of the Advertisement for Bid, Invitation to Bid, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the Bid Form (including the Non-collusion Statement), and other sample bidding and contract forms. The proposed Contract Documents consist of the form of Agreement between the Owner and Contractor, as well as the Drawings, Specifications (Project Manual) and all Addenda issued prior to execution of the Contract.

1.6 CONTRACT DOCUMENTS: The Contract Documents consist of the, Instructions to Bidders, Supplementary Instructions to Bidders (if any), General Conditions, Supplementary General Conditions, General Requirements, Special Provisions (if any), the form of agreement between the Owner and the Contractor, Drawings (if any), Specifications (Project Manual), and all addenda.

1.7 AGREEMENT: The form of the Agreement shall be AIA Document A101, Standard Form of Agreement between Owner and Contractor where the basis of payment is a STIPULATED SUM. In the case of conflict between the instructions contained therein and the General Requirements herein, these General Requirements shall prevail.

1.8 GENERAL REQUIREMENTS (or CONDITIONS): General Requirements (or conditions) are instructions pertaining to the Bidding Documents and to contracts in general. They contain, in summary, requirements of laws of the State; policies of the Agency and instructions to bidders.

1.9 SPECIAL PROVISIONS: Special Provisions are specific conditions or requirements peculiar to the bidding documents and to the contract under consideration and are supplemental to the General Requirements. Should the Special Provisions conflict with the General Requirements, the Special Provisions shall prevail.

1.10 ADDENDA: Written or graphic instruments issued by the Owner/Architect prior to the execution of the contract which modify or interpret the Bidding Documents by additions, deletions, clarifications or corrections.

1.11 BIDDER OR VENDOR: A person or entity who formally submits a Bid for the material or Work contemplated, acting directly or through a duly authorized representative who meets the requirements set forth in the Bidding Documents.

1.12 SUB-BIDDER: A person or entity who submits a Bid to a Bidder for materials or labor, or both for a portion of the Work.

1.13 BID: A complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Bidding Documents.

1.14 BASE BID: The sum stated in the Bid for which the Bidder offers to perform the Work described in the Bidding Documents as the base, to which Work may be added or from which Work may be deleted for sums stated in Alternate Bids (if any are required to be stated in the bid).

1.15 ALTERNATE BID (or ALTERNATE): An amount stated in the Bid, where applicable, to be added to or deducted from the amount of the Base Bid if the corresponding change in the Work, as described in the Bidding Documents is accepted.

1.16 UNIT PRICE: An amount stated in the Bid, where applicable, as a price per unit of measurement for materials, equipment or services or a portion of the Work as described in the Bidding Documents.

1.17 SURETY: The corporate body which is bound with and for the Contract, or which is liable, and which engages to be responsible for the Contractor's payments of all debts pertaining to and for his acceptable performance of the Work for which he has contracted.

1.18 BIDDER'S DEPOSIT: The security designated in the Bid to be furnished by the Bidder as a guaranty of good faith to enter into a contract with the Agency if the Work to be performed or the material or equipment to be furnished is awarded to him.

1.19 CONTRACT: The written agreement covering the furnishing and delivery of material or work to be performed.

1.20 CONTRACTOR: Any individual, firm or corporation with whom a contract is made by the Agency.

1.21 SUBCONTRACTOR: An individual, partnership or corporation which has a direct contract with a contractor to furnish labor and materials at the job site, or to perform construction labor and furnish material in connection with such labor at the job site.

1.22 CONTRACT BOND: The approved form of security furnished by the contractor and his surety as a guaranty of good faith on the part of the contractor to execute the work in accordance with the terms of the contract.

1.23 CUSTOM FABRICATION: As defined in 29 Del. C. § 6902, the term “custom fabrication” means the offsite fabrication, assembly, or other production of non-standard goods or materials, including components, fixtures or parts thereof, specifically for a public works project. Such goods and materials shall include those used in the following trades or systems: (1) Plumbing or pipe fitting systems, including heating, ventilating, air-conditioning, refrigeration systems, sheet metal or other duct systems; (2) Electrical systems; (3) Mechanical insulation work; (4) Ornamental iron work; and (5) Commercial signage that does not attempt or appear to direct the movement of traffic on highways or roadways or interfere with, imitate, or resemble any official traffic sign, signal or device.

ARTICLE 2: BIDDER'S REPRESENTATION

2.1 PRE-BID MEETING

2.1.1 A pre-bid meeting for this project will be held at the time and place designated. Attendance at this meeting is a pre-requisite for submitting a Bid, unless this requirement is specifically waived elsewhere in the Bid Documents.

2.2 By submitting a Bid, the Bidder represents that:

2.2.1 The Bidder has read and understands the Bidding Documents and that the Bid is made in accordance therewith.

2.2.2 The Bidder has visited the site, become familiar with existing conditions under which the Work is to be performed, and has correlated the Bidder's personal observations with the requirements of the proposed Contract Documents.

2.2.3 The Bid is based upon the materials, equipment, and systems required by the Bidding Documents without exception.

2.2.4 Bidder has accounted for the possibility of price increases due to the direct and indirect effect of tariffs, other international events, inflation, and supply chain interruptions. Change Orders will be denied if they are based upon any of these events. Bidder is expected to account for these possibilities and include them in the bid.

2.3 JOINT VENTURE REQUIREMENTS

2.3.1 For Public Works Contracts, each Joint Venturer shall be qualified and capable to complete the Work with their own forces.

2.3.2 Included with the Bid submission, and as a requirement to bid, a copy of the executed Joint Venture Agreement shall be submitted and signed by all Joint Venturers involved.

2.3.3 All required Bid Bonds, Performance Bonds, Material and Labor Payment Bonds must be executed by both Joint Venturers and be placed in both of their names.

2.3.4 All required insurance certificates shall name both Joint Venturers.

2.3.5 Both Joint Venturers shall sign the Bid Form.

2.3.6 Both Joint Venturers shall include their Federal E.I. Number with the Bid.

2.3.7 In the event of a mandatory Pre-bid Meeting, each Joint Venturer shall have a representative in attendance.

2.3.8 Due to exceptional circumstances and for good cause shown, one or more of these provisions may be waived at the discretion of the State.

2.4 ASSIGNMENT OF ANTITRUST CLAIMS

2.4.1 As consideration for the award and execution by the Owner of this contract, the Contractor hereby grants, conveys, sells, assigns and transfers to the State of Delaware all of its right, title and interests in and to all known or unknown causes of action it presently has or may now or hereafter acquire under the antitrust laws of the United States and the State of Delaware, relating to the particular goods or services purchased or acquired by the Owner pursuant to this contract.

ARTICLE 3: BIDDING DOCUMENTS

3.1 COPIES OF BID DOCUMENTS

3.1.1 Bidders may obtain complete sets of the Bidding Documents from the Architectural/Engineering firm designated in the Advertisement or Invitation to Bid in the number and for the deposit sum, if any, stated therein.

3.1.2 Bidders shall use complete sets of Bidding Documents for preparation of Bids. The issuing Agency nor the Architect assumes no responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.

3.1.3 Any errors, inconsistencies or omissions discovered shall be reported to the Architect immediately.

3.1.4 The Agency and Architect may make copies of the Bidding Documents available on the above terms for the purpose of obtaining Bids on the Work. No license or grant of use is conferred by issuance of copies of the Bidding Documents.

3.2 INTERPRETATION OR CORRECTION OF BIDDING DOCUMENTS

3.2.1 The Bidder shall carefully study and compare the Bidding Documents with each other, and with other work being bid concurrently or presently under construction to the extent that it relates to the Work for which the Bid is submitted, shall examine the site and local conditions, and shall report any errors, inconsistencies, or ambiguities discovered to the Architect.

3.2.2 Bidders or Sub-bidders requiring clarification or interpretation of the Bidding Documents shall make a written request to the Architect at least seven days prior to the date for receipt of Bids. Interpretations, corrections and changes to the Bidding Documents will be made by written Addendum. Interpretations, corrections, or changes to the Bidding Documents made in any other manner shall not be binding.

3.2.3 The apparent silence of the specifications as to any detail, or the apparent omission from it of detailed description concerning any point, shall be regarded as meaning that only the best commercial practice is to prevail and only material and workmanship of the first quality are to be used. Proof of specification compliance will be the responsibility of the Bidder.

3.2.4 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all permits, labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for the proper execution and completion of the Work.

3.2.5 The Owner will bear the costs for all impact and user fees associated with the project.

3.3 SUBSTITUTIONS

3.3.1 The materials, products and equipment described in the Bidding Documents establish a standard of quality, required function, dimension, and appearance to be met by any proposed substitution. The specification of a particular manufacturer or model number is not intended to be proprietary in any way. Substitutions of products for those named will be considered, providing that the Vendor certifies that the function, quality, and performance characteristics of the material offered is equal or superior to that specified. It shall be the Bidder's responsibility to assure that the proposed substitution will not affect the intent of the design, and to make any installation modifications required to accommodate the substitution.

3.3.2 Requests for substitutions shall be made in writing to the Architect at least ten days prior to the date of the Bid Opening. Such requests shall include a complete description of the proposed substitution, drawings, performance and test data, explanation of required

installation modifications due the substitution, and any other information necessary for an evaluation. The burden of proof of the merit of the proposed substitution is upon the proposer. The Architect's decision of approval or disapproval shall be final. The Architect is to notify Owner prior to any approvals.

3.3.3 If the Architect approves a substitution prior to the receipt of Bids, such approval shall be set forth in an Addendum. Approvals made in any other manner shall not be binding.

3.3.4 The Architect shall have no obligation to consider any substitutions after the Contract award.

3.4 ADDENDA

3.4.1 Addenda will be mailed or delivered to all who are known by the Architect to have received a complete set of the Bidding Documents.

3.4.2 Copies of Addenda will be made available for inspection wherever Bidding Documents are on file for that purpose.

3.4.3 No Addenda will be issued later than 2 calendar days prior to the date for receipt of Bids except an Addendum withdrawing the request for Bids or one which extends the time or changes the location for the opening of bids.

3.4.4 Each bidder shall ascertain prior to submitting his Bid that they have received all Addenda issued, and shall acknowledge their receipt in their Bid in the appropriate space. Not acknowledging an issued Addenda could be grounds for determining a bid to be non-responsive.

ARTICLE 4: BIDDING PROCEDURES

4.1 PREPARATION OF BIDS

4.1.1 Submit the bids on the Bid Forms included with the Bidding Documents.

4.1.2 Submit the original Bid Form for each bid. Bid Forms may be removed from the project manual for this purpose.

4.1.3 Execute all blanks on the Bid Form.

4.1.4 Where so indicated by the makeup on the Bid Form, express sums in both words and figures, in case of discrepancy between the two, the written amount shall govern.

4.1.5 BID ALL REQUESTED ALTERNATES AND UNIT PRICES, IF ANY. If there is no change in the Base Bid for an Alternate, enter "No Change". The Contractor is responsible for verifying that they have received all addenda issued during the bidding period. Work required by Addenda shall automatically become part of the Contract.

4.1.6 Make no additional stipulations on the Bid Form and do not qualify the Bid in any other manner.

4.1.7 Each copy of the Bid shall include the legal name of the Bidder and a statement whether the Bidder is a sole proprietor, a partnership, a corporation, or any legal entity, and each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further give the state of incorporation and have the corporate

seal affixed. A Bid submitted by an agent shall have a current Power of Attorney attached, certifying agent's authority to bind the Bidder.

4.1.8 Bidder shall complete the Non-Collusion Statement form included with the Bid Forms and include it with their Bid.

4.1.9 In the construction of all Public Works projects for the State of Delaware or any agency thereof, preference in employment of laborers, workers or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State.

4.1.10 Each bidder shall include a signed Affidavit for the Bidder certifying compliance with OMB Regulation 4104 - "Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on "Large Public Works Projects." "Large Public Works" is based upon the current threshold required for bidding Public Works as set by the Purchasing and Contracting Advisory Council.

4.2 BID SECURITY

4.2.1 All bids shall be accompanied by a deposit of either a good and sufficient bond to the agency for the benefit of the agency, with corporate surety authorized to do business in this State, the form of the bond and the surety to be approved by the agency, or a security of the bidder assigned to the agency, for a sum equal to at least 10% of the bid plus all add alternates, or in lieu of the bid bond a security deposit in the form of a certified check, bank treasurer's check, cashier's check, money order, or other prior approved secured deposit assigned to the State. The bid bond need not be for a specific sum, but may be stated to be for a sum equal to 10% of the bid plus all add alternates to which it relates and not to exceed a certain stated sum, if said sum is equal to at least 10% of the bid. The Bid Bond form used shall be the standard OMB form (attached). The bid bond may be an electronic bond and need not be transmitted as a paper document.

4.2.2 The Agency has the right to retain the bid security of Bidders to whom an award is being considered until either a formal contract has been executed and bonds have been furnished or the specified time has elapsed so the Bids may be withdrawn or all Bids have been rejected.

4.2.3 In the event of any successful Bidder refusing or neglecting to execute a formal contract and bond within 20 days of the awarding of the contract, the bid bond or security deposited by the successful bidder shall be forfeited.

4.3 SUBCONTRACTOR LIST

4.3.1 In accordance with Title 29, Chapter 69, Section 6962(d)(10)b of the Delaware Code, each Bidder shall submit with their Bid a completed List of Sub-Contractors included with the Bid Form. NAME ONLY ONE SUBCONTRACTOR FOR EACH TRADE. The bidder must list **in each category** the full name and address (City & State) of the sub-contractor that the Bidder will be using to perform the work and provide material for that subcontractor category. Should the Bidder's listed subcontractor intend to provide any of their subcontractor category of work through a third-tier contractor, the Bidder shall list that third-tier contractor's full name and address (City & State). **If the Bidder intends to perform any category of work itself, it must list its full name and address.** For clarification, if the Bidder intends to perform the work themselves, the Bidder **may not** insert "not applicable", "N/A", "self" or anything other than its own full name and address (City & State). To do so shall cause the bid to be rejected. In addition, the failure to produce a completed subcontractor list with the bid submittal shall cause the bid to be

rejected. If you have more than three (3) third-tier contractors to report in any subcontractor category, print out additional page(s) containing the appropriate category, complete the rest of your list of third-tier contractors for that category, notate the addition in parentheses as (CONTINUATION) next to the subcontractor category and an asterisk (*) next to any additional third-tier contractors, and submit it with your bid.

4.3.2 It is the responsibility of the Contractor to ensure that their Subcontractors are in compliance with the provisions of this law. Also, if a Contractor elects to list themselves as a Subcontractor for any category, they must specifically name themselves on the Bid Form and be able to document their capability to act as Subcontractor in that category in accordance with this law.

4.4 AFFIDAVIT OF CONTRACTOR QUALIFICATIONS

4.4.1 In accordance with Title 29, Chapter 69, Section 6962(d)(10)b.3 of the Delaware Code, each Bidder shall submit with their Bid the Affidavit of Contractor Qualifications certifying that the Bidder will abide by the contractor's qualifications outlined in the construction bid specifications for the duration of the contract term. After a contract has been awarded the successful bidder shall not substitute another subcontractor whose name was submitted on the Subcontractor Form except for the reasons in the statute and not without written consent from the awarding agency. Failure to utilize the subcontractors on the list will subject the successful bidder to penalties as outlined in the General Requirements Section 5.2 of the contract.

4.5 AFFIDAVIT OF CRAFT TRAINING COMPLIANCE

4.5.1 In accordance with Title 29, Chapter 69, Section 6962(c)(13) of the Delaware Code, contractors and subcontractors must provide craft training for journeyman and apprentice levels if **all** of the following apply:

A. A project meets the prevailing wage requirement under Title 29, Chapter 69, Section 6960 of the Delaware Code.
B. The contractor employs 10 or more total employees.
C. The project is not a federal highway project

Failure to provide required craft training on the project may subject the successful contractor and/or subcontractor(s) to penalties as outlined in Title 29, Chapter 69, Section 6962(c)(13) of the Delaware Code.

Bidders shall submit the Affidavit of Craft Training Compliance prior to contract execution.

4.6 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

4.6.1 During the performance of this contract, the contractor agrees as follows:

A. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take affirmative action to ensure the applicants are employed, and that employees are treated during employment, without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: Employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in

conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.

B. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

4.7 PREVAILING WAGE REQUIREMENT

4.7.1 Wage Provisions: For renovation and new construction projects whose costs exceed the thresholds contained in Delaware Code, Title 29, Section 6960, the minimum wage rates for various classes of laborers and mechanics shall be as determined by the Department of Labor, Division of Industrial Affairs of the State of Delaware.

4.7.2 The employer shall pay all mechanics and labors employed directly upon the site of work, or engaged in custom fabrication work, as that term is defined in Article 1.23 herein and as also as defined in 29 Del. C § 6902 and described in 29 Del. C. § 6960(b), regardless of where the work is performed, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than those stated in the specifications, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics.

4.7.3 As per 29 Del. C. § 6960(b), the scale of the wages to be paid must be posted by the employer in a prominent and easily accessible place at the site of the work. There may be withheld from the employer so much of accrued payments as may be considered necessary by the Department of Labor to pay laborers and mechanics employed by the employer the difference between the rates of wages required by the contract to be paid laborers and mechanics on the work and rates of wages received by such laborers and mechanics to be remitted to the Department of Labor for distribution upon resolution of any claims.

4.7.4 Every contract based upon these specifications shall contain a stipulation that sworn payroll information, as required by the Department of Labor, be furnished weekly. The Department of Labor shall keep and maintain the sworn payroll information for a period of 6 months from the last day of the work week covered by the payroll.

4.8 SUBMISSION OF BIDS

4.8.1 Enclose the Bid, the Bid Security, and any other documents required to be submitted with the Bid.

4.8.2 Deposit Bids at the designated location prior to the time and date for receipt of bids indicated in the Advertisement for Bids. Bids received after the time and date for receipt of bids will be marked “LATE BID” and returned.

4.8.3 Bidder assumes full responsibility for timely delivery at location designated for receipt of bids.

4.8.4 Oral, telephonic, paper or telegraphic bids are invalid and will not receive consideration.

4.8.5 Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids, provided that they are then fully in compliance with these Instructions to Bidders.

4.8.6 Compliance with Federal Bureau of Investigation rules mandates training for Contractors, Subcontractors, their employees, and custodial workers with access to locations that have access to Criminal Justice Information Services (CJIS). The contract awardee must have fingerprinting and background checks done for all Subcontractors and employees.

4.9 MODIFICATION OR WITHDRAW OF BIDS

4.9.1 Prior to the closing date for receipt of Bids, a Bidder may withdraw a Bid by personal request and by showing proper identification to the Architect. A request for withdraw by letter or fax, if the Architect is notified in writing prior to receipt of fax, is acceptable. A fax directing a modification in the bid price will render the Bid informal, causing it to be ineligible for consideration of award. Telephone directives for modification of the bid price shall not be permitted and will have no bearing on the submitted proposal in any manner.

4.9.2 Bidders submitting Bids that are late shall be notified as soon as practicable and the bid shall be returned.

4.9.3 A Bid may not be modified, withdrawn or canceled by the Bidder during a thirty (30) day period following the time and date designated for the receipt and opening of Bids, and Bidder so agrees in submitting their Bid. Bids shall be binding for 30 days after the date of the Bid opening.

ARTICLE 5: CONSIDERATION OF BIDS

5.1 OPENING/REJECTION OF BIDS

5.1.1 Unless otherwise stated, Bids received on time will be publicly opened and will be read aloud. An abstract of the Bids will be made available to Bidders.

5.1.2 The Agency shall have the right to reject any and all Bids. A Bid not accompanied by a required Bid Security or by other data required by the Bidding Documents, or a Bid which is in any way incomplete or irregular is subject to rejection.

5.1.3 If the Bids are rejected, it will be done within thirty (30) calendar days of the Bid opening.

5.2 COMPARISON OF BIDS

5.2.1 After the Bids have been opened and read, the bid prices will be compared and the result of such comparisons will be made available to the public. Comparisons of the Bids may be based on the Base Bid plus desired Alternates. The Agency shall have the right to accept Alternates in any order or combination.

5.2.2 The Agency reserves the right to waive technicalities, to reject any or all Bids, or any portion thereof, to advertise for new Bids, to proceed to do the Work otherwise, or to abandon the Work, if in the judgment of the Agency or its agent(s), it is in the best interest of the State.

5.2.3 An increase or decrease in the quantity for any item is not sufficient grounds for an increase or decrease in the Unit Price.

5.2.4 The prices quoted are to be those for which the material will be furnished F.O.B. Job Site and include all charges that may be imposed during the period of the Contract.

5.2.5 No qualifying letter or statements in or attached to the Bid, or separate discounts will be considered in determining the low Bid except as may be otherwise herein noted. Cash or separate discounts should be computed and incorporated into Unit Bid Price(s).

5.2.6 Bidder must account for the possibility of price increases due to the direct and indirect effect of tariffs or other international events, inflation, and supply chain interruptions. Change Orders will be denied if they are based upon any of these events. Bidder is expected to account for these possibilities and include them in the bid.

5.3 DISQUALIFICATION OF BIDDERS

5.3.1 An agency shall determine that each Bidder on any Public Works Contract is responsible before awarding the Contract. Factors to be considered in determining the responsibility of a Bidder include:

A. The Bidder's financial, physical, personnel or other resources including Subcontracts;

B. The Bidder's record of performance on past public or private construction projects, including, but not limited to, defaults and/or final adjudication or admission of violations of the Prevailing Wage Laws in Delaware or any other state;

C. The Bidder's written safety plan;

D. Whether the Bidder is qualified legally to contract with the State;

E. Whether the Bidder supplied all necessary information concerning its responsibility; and,

F. Any other specific criteria for a particular procurement, which an agency may establish; provided however, that, the criteria be set forth in the Invitation to Bid and is otherwise in conformity with State and/or Federal law.

G. Any Bidder who is debarred in another State and/or by the United States Government is also debarred in Delaware.

5.3.2 If an agency determines that a Bidder is nonresponsive and/or nonresponsible, the determination shall be in writing and set forth the basis for the determination. A copy of the determination shall be sent to the affected Bidder within five (5) working days of said determination.

5.3.3 In addition, any one or more of the following causes may be considered as sufficient for the disqualification of a Bidder and the rejection of their Bid or Bids.

5.3.3.1 More than one Bid for the same Contract from an individual, firm or corporation under the same or different names.

5.3.3.2 Evidence of collusion among Bidders.

5.3.3.3 Unsatisfactory performance record as evidenced by past experience.

5.3.3.4 If the Unit Prices are obviously unbalanced either in excess or below reasonable cost analysis values.

5.3.3.5 If there are any unauthorized additions, interlineation, conditional or alternate bids or irregularities of any kind which may tend to make the Bid incomplete, indefinite or ambiguous as to its meaning.

5.3.3.6 If the Bid is not accompanied by the required Bid Security and other data required by the Bidding Documents.

5.3.3.7 If any exceptions or qualifications of the Bid are noted on the Bid Form.

5.4 ACCEPTANCE OF BID AND AWARD OF CONTRACT

5.4.1 A formal Contract shall be executed with the successful Bidder within twenty (20) calendar days after the award of the Contract.

5.4.2 Per Section 6962(d)(13)a., Title 29, Delaware Code, “The contracting agency shall award any public works contract within thirty (30) days of the bid opening to the lowest responsive and responsible Bidder, unless the Agency elects to award on the basis of best value, in which case the election to award on the basis of best value shall be stated in the Invitation To Bid. Any public school district and its board shall award public works contracts in accordance with this section’s requirements except it shall award the contract within 60 days of the bid opening.”

5.4.3 Each Bid on any Public Works Contract must be deemed responsive by the Agency to be considered for award. A responsive Bid shall conform in all material respects to the requirements and criteria set forth in the Contract Documents and specifications.

5.4.4 The Agency shall have the right to accept Alternates in any order or combination, and to determine the low Bidder on the basis of the sum of the Base Bid, plus accepted Alternates.

5.4.5 The successful Bidder shall execute a formal contract, submit the required Insurance Certificate, and furnish good and sufficient bonds, unless specifically waived in the General Requirements, in accordance with the General Requirement, within twenty (20) days of official notice of contract award. The successful Bidder shall provide, at least two business days prior to contract execution, copies of the Employee Drug Testing Program for the Bidder and all listed Subcontractors. Bonds shall be for the benefit of the Agency with surety in the amount of 100% of the total contract award. Said Bonds shall be conditioned upon the faithful performance of the contract. Bonds shall remain in affect for period of two (2) years after the date of the Certificate of Final Payment.

5.4.6 If the successful Bidder fails to execute the required Contract, Bond and all required information, as aforesaid, within twenty (20) calendar days after the date of official Notice of the Award of the Contract, their Bid guaranty shall immediately be taken and become the property of the State for the benefit of the Agency as liquidated damages, and not as a forfeiture or as a penalty. Award will then be made to the next lowest qualified Bidder of the Work or readvertised, as the Agency may decide.

5.4.7 Each bidder shall supply with its bid its taxpayer identification number (i.e., federal employer identification number or social security number) and should the vendor be awarded a contract, such vendor shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

5.4.8 The Bid Security shall be returned to the successful Bidder upon the execution of the formal contract. The Bid Securities of unsuccessful bidders shall be returned within thirty (30) calendar days after the opening of the Bids.

ARTICLE 6: POST-BID INFORMATION

6.1 CONTRACTOR'S QUALIFICATION STATEMENT

6.1.1 Bidders to whom an award of a Contract is under consideration shall, if requested by the Agency, submit a properly executed AIA Document A305, Contractor's Qualification Statement, unless such a statement has been previously required and submitted.

6.2 Bidders to whom an award of a Contract has been made must produce their Delaware Business License before the Contract can be executed.

ARTICLE 7: PERFORMANCE BOND AND PAYMENT BOND

7.1 BOND REQUIREMENTS

7.1.1 The cost of furnishing the required Bonds, that are stipulated in the Bidding Documents, shall be included in the Bid.

7.1.2 If the Bidder is required by the Agency to secure a bond from other than the Bidder's usual sources, changes in cost will be adjusted as provide in the Contract Documents.

7.1.3 The Performance and Payment Bond forms used shall be the standard OMB forms (attached).

7.2 TIME OF DELIVERY AND FORM OF BONDS

7.2.1 The bonds shall be dated on or after the date of the Contract.

7.2.2 The Bidder shall require the attorney-in-fact who executes the required bonds on behalf of the surety to affix a certified and current copy of the power of attorney.

7.2.3 The Performance Bond and/or the Payment Bond may be electronic bonds and need not be transmitted as paper documents.

ARTICLE 8: FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

8.1 Unless otherwise required in the Bidding Documents, the Agreement for the Work will be written on AIA Document A101, Standard Form of Agreement Between Owner and Contractor Where the Basis of Payment is a Stipulated Sum.

END OF SECTION

PAGE LEFT INTENTIONALLY BLANK

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

BID FORM

For Bids Due: December 3, 2026 **To:** Delaware Technical Community College

21179 College Drive
Georgetown, Delaware 19947

Name of Bidder: _____

Delaware Business License No.: _____ **Taxpayer ID No.:** _____

(Other License Nos.): _____

Phone No.: ( ) _____ - _____ Fax No.: ( ) _____ - _____

The undersigned, representing that he has read and understands the Bidding Documents and that this bid is made in accordance therewith, that he has visited the site and has familiarized himself with the local conditions under which the Work is to be performed, and that his bid is based upon the materials, systems and equipment described in the Bidding Documents without exception, hereby proposes and agrees to provide all labor, materials, plant, equipment, supplies, transport and other facilities required to execute the work described by the aforesaid documents for the lump sum itemized below:

$_____

ALLOWANCE

Sum above should include a contingency allowance of $20,000 for unforeseen conditions.

UNIT PRICES

This contract does not contain any unit price items.

ALTERNATES

Alternate prices conform to applicable project specification section. Refer to specifications for a complete description of the following Alternates. An “ADD” or “DEDUCT” amount is indicated by the crossed out part that does not apply.

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

Alternate #1 – ATC System by Siemens Controls

Base Bid: Provide ATC system and integration by any listed ATC vendor/manufacturer as specified in Specification Section 230900 "Instrumentation and Controls of HVAC and Plumbing Systems".

Base Bid ATC Vendor.
Alternate: ATC system by Siemens Controls

Add: _____
($)

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

BID FORM

I/We acknowledge Addendums numbered _____ and the price(s) submitted include any cost/schedule impact they may have.

This bid shall remain valid and cannot be withdrawn for thirty (30) days from the date of opening of bids (60 days for School Districts and Department of Education), and the undersigned shall abide by the Bid Security forfeiture provisions. Bid Security is attached to this Bid.

The Owner shall have the right to reject any or all bids, and to waive any informality or irregularity in any bid received.

This bid is based upon work being accomplished by the Sub-Contractors named on the list attached to this bid.

Should I/We be awarded this contract, I/We pledge to achieve substantial completion of all the work within _____ calendar days of the Notice to Proceed.

The undersigned represents and warrants that he has complied and shall comply with all requirements of local, state, and national laws; that no legal requirement has been or shall be violated in making or accepting this bid, in awarding the contract to him or in the prosecution of the work required; that the bid is legal and firm; that he has not, directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken action in restraint of free competitive bidding.

Upon receipt of written notice of the acceptance of this Bid, the Bidder shall, within twenty (20) calendar days, execute the agreement in the required form and deliver the Contract Bonds, and Insurance Certificates, required by the Contract Documents.

I am / We are an Individual / a Partnership / a Corporation

By _____ Trading as _____
(Individual's / General Partner's / Corporate Name)

_____
(State of Corporation)

Business Address: _____
_____
_____
_____

Witness: _____ **By:** _____
(Authorized Signature)

(SEAL)

_____
(Title)

Date: _____

ATTACHMENTS

Sub-Contractor List
Non-Collusion Statement
Affidavit of Employee Drug Testing Program
Affidavit of Contractor Qualifications
Bid Security
(Others as Required by Project Manuals)

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

BID FORM

SUBCONTRACTOR LIST

In accordance with Title 29, Chapter 69, Section 6962(d)(10)b of the Delaware Code, the following subcontractor listing must accompany any bid submittal. The bidder must list **in each category** the full name and address (City & State) of the sub-contractor that the bidder will be using to perform the work and provide material for that subcontractor category. Should the bidder's listed subcontractor intend to provide any of their subcontractor category of work through a third-tier contractor, the bidder shall list that third-tier contractor's full name and address (City & State). **If the bidder intends to perform any category of work itself, it must list its full name and address.** For clarification, if the bidder intends to perform the work themselves, the bidder **may not** insert "not applicable", "N/A", "self" or anything other than its own full name and address (City & State). To do so shall cause the bid to be rejected. In addition, the failure to produce a completed subcontractor list with the bid submittal shall cause the bid to be rejected. If you have more than three (3) third-tier contractors to report in any subcontractor category, print out additional page(s) containing the appropriate category, complete the rest of your list of third-tier contractors for that category, notate the addition in parentheses as (CONTINUATION) next to the subcontractor category and an asterisk (*) next to any additional third-tier contractors, and submit it with your bid.

Subcontractor Category	Subcontractor	Address (City & State)	Subcontractors tax-payer ID # or Delaware Business license #
1.			
2.			
3.			
4.			
5.			

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

BID FORM

NON-COLLUSION STATEMENT

This is to certify that the undersigned bidder has neither directly nor indirectly, entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding in connection with this proposal submitted this date *(to the Office of Management and Budget, Division of Facilities Management)*.

All the terms and conditions of DTCC Contract No. DTCC_22C900404-CYD have been thoroughly examined and are understood.

NAME OF BIDDER: _____

AUTHORIZED REPRESENTATIVE (TYPED): _____

AUTHORIZED REPRESENTATIVE (SIGNATURE): _____

TITLE: _____

ADDRESS OF BIDDER: _____

_____

_____

E-MAIL: _____

PHONE NUMBER: _____

Sworn to and Subscribed before me this _____ day of _____ 2022.

My Commission expires _____. NOTARY PUBLIC _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

BID FORM

AFFIDAVIT
OF
EMPLOYEE DRUG TESTING PROGRAM

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors implement a program of mandatory drug testing for Employees who work on Large Public Works Contracts funded all or in part with public funds.

We hereby certify that we have in place or will implement during the entire term of the contract a Mandatory Drug Testing Program for our employees on the jobsite, including subcontractors, that complies with this regulation:

Contractor/Subcontractor Name: _____

Contractor/Subcontractor Address: _____

_____

_____

Authorized Representative (typed or printed): _____

Authorized Representative (signature): _____

Title: _____

Sworn to and Subscribed before me this _____day of _____ 2022.

My Commission expires _____. NOTARY PUBLIC _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

21225 College Drive, Georgetown, DE 19947
Delaware Technical Community College
Dental Health Center At Carter Partnership Center Georgetown Campus
DTCC # C9004020007

BID FORM

AFFIDAVIT
OF
CONTRACTOR QUALIFICATIONS

We hereby certify that we will abide by the contractor's qualifications outlined in the construction bid specifications for the duration of the contract term.

In accordance with Title 29, Chapter 69, Section 6962(d)(10)b.3 of the Delaware Code, after a contract has been awarded the successful bidder shall not substitute another subcontractor whose name was submitted on the Subcontractor Form except for the reasons in the statute and not without written consent from the awarding agency. Failure to utilize the subcontractors on the list will subject the successful bidder to penalties as outlined in the General Requirements Section 5.2 of the contract.

Contractor Name: _____

Contractor Address: _____

_____

_____

Authorized Representative (typed or printed): _____

Authorized Representative (signature): _____

Title: _____

Sworn to and Subscribed before me this _____day of _____ 2022.

My Commission expires _____. NOTARY PUBLIC _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED FOR YOUR BID TO BE CONSIDERED.

PAGE LEFT INTENTIONALLY BLANK

STATE OF DELAWARE

BID BOND

TO ACCOMPANY PROPOSAL
(Not necessary if security is used)

KNOW ALL MEN BY THESE PRESENTS That: _____ _____of _____ in the County of _____ _____and State of _____as **Principal**, and _____ _____ of _____ in the County of _____ and State of _____ as **Surety**, legally authorized to do business in the State of Delaware ("**State**"), are held and firmly unto the **State** in the sum of ten percent (10%) of the total amount of the base bid plus ten percent (10%) of the total amount of all additive alternates not to exceed _____ _____ Dollars ($_____) of amount of bid on Contract No. C9004020007, to be paid to the **State** for the use and benefit of Delaware Technical Community College for which payment well and truly to be made, we do bind ourselves, our and each of our heirs, executors, administrators, and successors, jointly and severally for and in the whole firmly by these presents.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH That if the above bonded **Principal** who has submitted to Delaware Technical Community College a certain proposal to enter into this contract for the furnishing of certain material and/or services within the **State**, shall be awarded this Contract, and if said **Principal** shall well and truly enter into and execute this Contract as may be required by the terms of this Contract and approved by the Delaware Technical Community College Contract to be entered into within twenty days after the date of official notice of the award thereof in accordance with the terms of said proposal, then this obligation shall be void or else to be and remain in full force and virtue.

Sealed with _____ seal and dated this _____day of _____ in the year of our Lord two thousand and _____ (20___).

SEALED, AND DELIVERED IN THE
Presence of

_____
Name of Bidder (Organization)

Corporate Seal

By: _____
Authorized Signature

Attest _____

_____
Title

_____
Name of Surety

Witness:_____

By: _____

_____
Title

PAGE LEFT INTENTIONALLY BLANK

SECTION 00 52 13

STANDARD FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR A101-2017

The contract to be utilized on this project shall be the “Standard Form of Agreement Between Owner and Contractor” AIA Document A101-2017, including AIA Document A101 – 2017 Exhibit A, as well as Supplements to A101-2017 and Exhibit A and the State of Delaware’s General Requirements.

PAGE LEFT INTENTIONALLY BLANK

DRAFT

AIA® Document A101® – 2017

Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum

AGREEMENT made as of the « » day of « » in the year « »
(In words, indicate day, month and year.)

BETWEEN the Owner:
(Name, legal status, address and other information)

« »« »
« »
« »
« »

and the Contractor:
(Name, legal status, address and other information)

« »« »
« »
« »
« »

for the following Project:
(Name, location and detailed description)

« »
« »
« »

The Architect:
(Name, legal status, address and other information)

« »« »
« »
« »
« »

The Owner and Contractor agree as follows.

ADDITIONS AND DELETIONS: The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

The parties should complete A101®–2017, Exhibit A, Insurance and Bonds, contemporaneously with this Agreement. AIA Document A201®–2017, General Conditions of the Contract for Construction, is adopted in this document by reference. Do not use with other general conditions unless this document is modified.



ELECTRONIC COPYING of any portion of this AIA® Document to another electronic file is prohibited and constitutes a violation of copyright laws as set forth in the footer of this document.

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

TABLE OF ARTICLES

1 THE CONTRACT DOCUMENTS

2 THE WORK OF THIS CONTRACT

3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION

4 CONTRACT SUM

5 PAYMENTS

6 DISPUTE RESOLUTION

7 TERMINATION OR SUSPENSION

8 MISCELLANEOUS PROVISIONS

9 ENUMERATION OF CONTRACT DOCUMENTS

EXHIBIT A INSURANCE AND BONDS

ARTICLE 1 THE CONTRACT DOCUMENTS

The Contract Documents consist of this Agreement, Conditions of the Contract (General, Supplementary, and other Conditions), Drawings, Specifications, Addenda issued prior to execution of this Agreement, other documents listed in this Agreement, and Modifications issued after execution of this Agreement, all of which form the Contract, and are as fully a part of the Contract as if attached to this Agreement or repeated herein. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. An enumeration of the Contract Documents, other than a Modification, appears in Article 9.

ARTICLE 2 THE WORK OF THIS CONTRACT

The Contractor shall fully execute the Work described in the Contract Documents, except as specifically indicated in the Contract Documents to be the responsibility of others.

ARTICLE 3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION

§ 3.1 The date of commencement of the Work shall be:
(Check one of the following boxes.)

[« »] The date of this Agreement.

[« »] A date set forth in a notice to proceed issued by the Owner.

[« »] Established as follows:
(Insert a date or a means to determine the date of commencement of the Work.)

« »

If a date of commencement of the Work is not selected, then the date of commencement shall be the date of this Agreement.

§ 3.2 The Contract Time shall be measured from the date of commencement of the Work.

§ 3.3 Substantial Completion

§ 3.3.1 Subject to adjustments of the Contract Time as provided in the Contract Documents, the Contractor shall achieve Substantial Completion of the entire Work:
(Check one of the following boxes and complete the necessary information.)

[« »] Not later than « » (« ») calendar days from the date of commencement of the Work.

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

[« »] By the following date: « »

§ 3.3.2 Subject to adjustments of the Contract Time as provided in the Contract Documents, if portions of the Work are to be completed prior to Substantial Completion of the entire Work, the Contractor shall achieve Substantial Completion of such portions by the following dates:

Portion of Work	Substantial Completion Date

§ 3.3.3 If the Contractor fails to achieve Substantial Completion as provided in this Section 3.3, liquidated damages, if any, shall be assessed as set forth in Section 4.5.

ARTICLE 4 CONTRACT SUM

§ 4.1 The Owner shall pay the Contractor the Contract Sum in current funds for the Contractor's performance of the Contract. The Contract Sum shall be « » ($ « »), subject to additions and deductions as provided in the Contract Documents.

§ 4.2 Alternates

§ 4.2.1 Alternates, if any, included in the Contract Sum:

Item	Price

§ 4.2.2 Subject to the conditions noted below, the following alternates may be accepted by the Owner following execution of this Agreement. Upon acceptance, the Owner shall issue a Modification to this Agreement.
(Insert below each alternate and the conditions that must be met for the Owner to accept the alternate.)

Item	Price	Conditions for Acceptance

§ 4.3 Allowances, if any, included in the Contract Sum:
(Identify each allowance.)

Item	Price

§ 4.4 Unit prices, if any:
(Identify the item and state the unit price and quantity limitations, if any, to which the unit price will be applicable.)

Item	Units and Limitations	Price per Unit ($0.00)

§ 4.5 Liquidated damages, if any:
(Insert terms and conditions for liquidated damages, if any.)

« »

§ 4.6 Other:
(Insert provisions for bonus or other incentives, if any, that might result in a change to the Contract Sum.)

« »

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

ARTICLE 5 PAYMENTS

§ 5.1 Progress Payments

§ 5.1.1 Based upon Applications for Payment submitted to the Architect by the Contractor and Certificates for Payment issued by the Architect, the Owner shall make progress payments on account of the Contract Sum to the Contractor as provided below and elsewhere in the Contract Documents.

§ 5.1.2 The period covered by each Application for Payment shall be one calendar month ending on the last day of the month, or as follows:

« »

§ 5.1.3 Provided that an Application for Payment is received by the Architect not later than the « » day of a month, the Owner shall make payment of the amount certified to the Contractor not later than the « » day of the « » month. If an Application for Payment is received by the Architect after the application date fixed above, payment of the amount certified shall be made by the Owner not later than « » (« ») days after the Architect receives the Application for Payment.
(Federal, state or local laws may require payment within a certain period of time.)

§ 5.1.4 Each Application for Payment shall be based on the most recent schedule of values submitted by the Contractor in accordance with the Contract Documents. The schedule of values shall allocate the entire Contract Sum among the various portions of the Work. The schedule of values shall be prepared in such form, and supported by such data to substantiate its accuracy, as the Architect may require. This schedule of values shall be used as a basis for reviewing the Contractor's Applications for Payment.

§ 5.1.5 Applications for Payment shall show the percentage of completion of each portion of the Work as of the end of the period covered by the Application for Payment.

§ 5.1.6 In accordance with AIA Document A201™–2017, General Conditions of the Contract for Construction, and subject to other provisions of the Contract Documents, the amount of each progress payment shall be computed as follows:

§ 5.1.6.1 The amount of each progress payment shall first include:

.1 That portion of the Contract Sum properly allocable to completed Work;

.2 That portion of the Contract Sum properly allocable to materials and equipment delivered and suitably stored at the site for subsequent incorporation in the completed construction, or, if approved in advance by the Owner, suitably stored off the site at a location agreed upon in writing; and

.3 That portion of Construction Change Directives that the Architect determines, in the Architect's professional judgment, to be reasonably justified.

§ 5.1.6.2 The amount of each progress payment shall then be reduced by:

.1 The aggregate of any amounts previously paid by the Owner;

.2 The amount, if any, for Work that remains uncorrected and for which the Architect has previously withheld a Certificate for Payment as provided in Article 9 of AIA Document A201–2017;

.3 Any amount for which the Contractor does not intend to pay a Subcontractor or material supplier, unless the Work has been performed by others the Contractor intends to pay;

.4 For Work performed or defects discovered since the last payment application, any amount for which the Architect may withhold payment, or nullify a Certificate of Payment in whole or in part, as provided in Article 9 of AIA Document A201–2017; and

.5 Retainage withheld pursuant to Section 5.1.7.

§ 5.1.7 Retainage

§ 5.1.7.1 For each progress payment made prior to Substantial Completion of the Work, the Owner may withhold the following amount, as retainage, from the payment otherwise due:
(Insert a percentage or amount to be withheld as retainage from each Application for Payment. The amount of retainage may be limited by governing law.)

« »

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

§ 5.1.7.1.1 The following items are not subject to retainage:
(Insert any items not subject to the withholding of retainage, such as general conditions, insurance, etc.)

« »

§ 5.1.7.2 Reduction or limitation of retainage, if any, shall be as follows:
(If the retainage established in Section 5.1.7.1 is to be modified prior to Substantial Completion of the entire Work, including modifications for Substantial Completion of portions of the Work as provided in Section 3.3.2, insert provisions for such modifications.)

« »

§ 5.1.7.3 Except as set forth in this Section 5.1.7.3, upon Substantial Completion of the Work, the Contractor may submit an Application for Payment that includes the retainage withheld from prior Applications for Payment pursuant to this Section 5.1.7. The Application for Payment submitted at Substantial Completion shall not include retainage as follows:
(Insert any other conditions for release of retainage upon Substantial Completion.)

« »

§ 5.1.8 If final completion of the Work is materially delayed through no fault of the Contractor, the Owner shall pay the Contractor any additional amounts in accordance with Article 9 of AIA Document A201–2017.

§ 5.1.9 Except with the Owner's prior approval, the Contractor shall not make advance payments to suppliers for materials or equipment which have not been delivered and stored at the site.

§ 5.2 Final Payment

§ 5.2.1 Final payment, constituting the entire unpaid balance of the Contract Sum, shall be made by the Owner to the Contractor when

.1 the Contractor has fully performed the Contract except for the Contractor's responsibility to correct Work as provided in Article 12 of AIA Document A201–2017, and to satisfy other requirements, if any, which extend beyond final payment; and

.2 a final Certificate for Payment has been issued by the Architect.

§ 5.2.2 The Owner's final payment to the Contractor shall be made no later than 30 days after the issuance of the Architect's final Certificate for Payment, or as follows:

« »

§ 5.3 Interest

Payments due and unpaid under the Contract shall bear interest from the date payment is due at the rate stated below, or in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.
(Insert rate of interest agreed upon, if any.)

« » % « »

ARTICLE 6 DISPUTE RESOLUTION

§ 6.1 Initial Decision Maker

The Architect will serve as the Initial Decision Maker pursuant to Article 15 of AIA Document A201–2017, unless the parties appoint below another individual, not a party to this Agreement, to serve as the Initial Decision Maker.
(If the parties mutually agree, insert the name, address and other contact information of the Initial Decision Maker, if other than the Architect.)

« »
« »
« »
« »

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

§ 6.2 Binding Dispute Resolution
For any Claim subject to, but not resolved by, mediation pursuant to Article 15 of AIA Document A201–2017, the method of binding dispute resolution shall be as follows:
(Check the appropriate box.)

[« »] Arbitration pursuant to Section 15.4 of AIA Document A201–2017

[« »] Litigation in a court of competent jurisdiction

[« »] Other *(Specify)*

« »

If the Owner and Contractor do not select a method of binding dispute resolution, or do not subsequently agree in writing to a binding dispute resolution method other than litigation, Claims will be resolved by litigation in a court of competent jurisdiction.

ARTICLE 7 TERMINATION OR SUSPENSION

§ 7.1 The Contract may be terminated by the Owner or the Contractor as provided in Article 14 of AIA Document A201–2017.

§ 7.1.1 If the Contract is terminated for the Owner's convenience in accordance with Article 14 of AIA Document A201–2017, then the Owner shall pay the Contractor a termination fee as follows:
(Insert the amount of, or method for determining, the fee, if any, payable to the Contractor following a termination for the Owner's convenience.)

« »

§ 7.2 The Work may be suspended by the Owner as provided in Article 14 of AIA Document A201–2017.

ARTICLE 8 MISCELLANEOUS PROVISIONS

§ 8.1 Where reference is made in this Agreement to a provision of AIA Document A201–2017 or another Contract Document, the reference refers to that provision as amended or supplemented by other provisions of the Contract Documents.

§ 8.2 The Owner's representative:
(Name, address, email address, and other information)

« »
« »
« »
« »
« »
« »

§ 8.3 The Contractor's representative:
(Name, address, email address, and other information)

« »
« »
« »
« »
« »
« »

§ 8.4 Neither the Owner's nor the Contractor's representative shall be changed without ten days' prior notice to the other party.

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

§ 8.5 Insurance and Bonds

§ 8.5.1 The Owner and the Contractor shall purchase and maintain insurance as set forth in AIA Document A101™–2017, Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum, Exhibit A, Insurance and Bonds, and elsewhere in the Contract Documents.

§ 8.5.2 The Contractor shall provide bonds as set forth in AIA Document A101™–2017 Exhibit A, and elsewhere in the Contract Documents.

§ 8.6 Notice in electronic format, pursuant to Article 1 of AIA Document A201–2017, may be given in accordance with AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, if completed, or as otherwise set forth below:
(If other than in accordance with AIA Document E203–2013, insert requirements for delivering notice in electronic format such as name, title, and email address of the recipient and whether and how the system will be required to generate a read receipt for the transmission.)

« »

§ 8.7 Other provisions:

« »

ARTICLE 9 ENUMERATION OF CONTRACT DOCUMENTS

§ 9.1 This Agreement is comprised of the following documents:

.1 AIA Document A101™–2017, Standard Form of Agreement Between Owner and Contractor

.2 AIA Document A101™–2017, Exhibit A, Insurance and Bonds

.3 AIA Document A201™–2017, General Conditions of the Contract for Construction

.4 AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, dated as indicated below:
(Insert the date of the E203-2013 incorporated into this Agreement.)

« »

.5 Drawings

Number	Title	Date

.6 Specifications

Section	Title	Date	Pages

.7 Addenda, if any:

Number	Date	Pages

Portions of Addenda relating to bidding or proposal requirements are not part of the Contract Documents unless the bidding or proposal requirements are also enumerated in this Article 9.

.8 Other Exhibits:
(Check all boxes that apply and include appropriate information identifying the exhibit where required.)

[« »] AIA Document E204™–2017, Sustainable Projects Exhibit, dated as indicated below:
(Insert the date of the E204-2017 incorporated into this Agreement.)

« »

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

[« »] The Sustainability Plan:

Title	Date	Pages

[« »] Supplementary and other Conditions of the Contract:

Document	Title	Date	Pages

.9 Other documents, if any, listed below:
(List here any additional documents that are intended to form part of the Contract Documents. AIA Document A201™–2017 provides that the advertisement or invitation to bid, Instructions to Bidders, sample forms, the Contractor's bid or proposal, portions of Addenda relating to bidding or proposal requirements, and other information furnished by the Owner in anticipation of receiving bids or proposals, are not part of the Contract Documents unless enumerated in this Agreement. Any such documents should be listed here only if intended to be part of the Contract Documents.)

« »

This Agreement entered into as of the day and year first written above.

OWNER *(Signature)*	**CONTRACTOR** *(Signature)*
« »« »	« »« »
(Printed name and title)	*(Printed name and title)*

DRAFT

AIA Document A101® – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A101," and "AIA Contract Documents" are registered trademarks and may not be used without permission. This draft was produced by AIA software at 07:56:27 ET on 03/10/2022 under Order No.9934642352 which expires on 05/24/2022, is not for resale, is licensed for one-time use only, and may only be used in accordance with the AIA Contract Documents® Terms of Service. To report copyright violations, e-mail copyright@aia.org.
User Notes: (1282755637)

Amendment to Contract for Construction
Between
Delaware Technical and Community College
And

The parties hereby agree and reaffirm that the AIA Document A101 – 2017 "Standard Form of Agreement between Owner and Contractor" between Delaware Technical and Community College ("Owner") and_____, a _____ corporation ("Contractor"), dated _____shall govern this transaction as supplemented by A201-2017 General Conditions for Construction and amended herein ("Contract Documents"). At times Owner and Contractor shall be collectively referred to the "Parties".

The parties expressly agree to enter into this amendment ("Amendment") which shall govern in the event of a conflict between the terms of the Contract Documents or any document referenced or incorporated therein, and that any contrary provision of any such document shall be superseded hereby. The parties agree to this Amendment as follows:

1. Contractor represents and warrants that it has not employed or retained any company or person, other than a bona fide employee working primarily for the firm offering professional services, to solicit or secure this agreement, and that he has not been paid or agreed to pay any person, company, corporation, individual, or firm, other than a bona fide employee working primarily for the firm offering professional services, any fee, commission, percentage, gift, or any other consideration, contingent upon or resulting from the award or making of this agreement;

2. All provisions of the Bid Package and Project manual are incorporated herein by reference as though fully set forth. In the event of a conflict between any provision of the Bid Package or Project Manual and the bid or proposal submitted by Contractor, the Bid Package and Project Manual shall control.

3. In the event the attached contract or aggregate of contracts is in excess of $500,000 for new construction (including painting and decorating) or $45,000 for alteration, repair, renovation, rehabilitation, demolition or reconstruction (including painting and decorating of buildings or works) and requires or involves the employment of mechanics and/or laborers, then the minimum wages to be paid to the various classes of laborers and mechanics shall be based upon greater of the Davis-Bacon Wage Rates (if the project is federally funded) or the wages that will be determined by the Delaware Department of Labor, Division of Industrial Affairs, to be prevailing in the county in which the work is to be performed.

4. Contractor shall pay all mechanics and laborers employed directly upon the site of the work, unconditionally and not less often than once a week and without subsequent deduction or rebate on any account, the full amounts accrued at time of payment, computed at wage rates not less than the prevailing wages, regardless of any contractual relationship which may be alleged to exist between the employer and such laborers and mechanics, and shall provide sworn payroll information, as required by the Department of Labor, on a weekly basis.

5. All changes to the scope of construction shall be authorized in writing by Owner in advance. Owner shall not be liable for payment of any change order that has not received prior written authorization. The cost of any change order shall be set forth therein. If no such provision is set forth in the change order, then the cost to the Owner shall be the Contractor's costs for wages, labor costs other than wages, wage taxes, materiel, equipment rentals, insurance and subcontracts attributable to the additional activity plus a reasonable sum for overhead and profit not to exceed 15%;

6. Preference in employment of laborers, workers or mechanics shall be given to bona fide legal citizens of the State who have established citizenship by residence of at least 90 days in the State. Contractor shall pay a penalty to the Secretary of Finance equal to the amount of compensation paid to any person in violation of this section;

7. Contractor shall not substitute another subcontractor for any subcontractor whose name was set forth in the statement which accompanied the bid without the written consent of Owner. Contractor shall pay a penalty equal to 150% of the amount of the proposal or subcontract submitted by the subcontractor identified in the accompanying statement for violating this paragraph.

8. Payments are due 30 days after receipt of a valid Application for Payment. Payments due and unpaid after 30 days shall bear simple interest at the rate of 1 percent per month not greater than 12% annual percentage rate;

9. Final payment shall not be due until all non-conforming work has been corrected and all other provisions of the agreement have been met, including, but not limited to, all reporting requirements. Furthermore, a written release of mechanics' liens signed by all persons who would otherwise be entitled to avail themselves of the provisions of Chapter 27 of Tile 25 of the Delaware Code, containing a notarized, verified certification signed by the Contractor that all of the persons signing the release constitute all of the persons who have furnished materials and performed labor in and for the construction, erection, building, improvement, alteration and repair to the date of the release and who would be entitled otherwise to file mechanics' liens claims shall be provided simultaneously with the receipt of final payment;

10. Owner may terminate this agreement or suspend work hereunder for any reason authorized by applicable Delaware law;

11. §6.2 is hereby deleted. The parties reserve all remedies available at law or equity for any dispute not resolved in accordance with §6.1;

12. §7.1.1 is hereby deleted and there shall be no Termination Fee paid to Contractor. Any reference to a Termination Fee in §14.4.3 of the A201-2017 is also deleted.

13. Any and all references to attorney's fees in §10.3.3 of the A201-2017 is deleted.

14. Exhibit A Insurance and Bonds is hereby deleted. Simultaneous with the execution of the this contract, Contractor shall also execute a good and sufficient bond for the benefit of Owner, with corporate surety authorized to do business in this State, in a sum equal to 100% of the contract price and the bond form used shall be the standard form issued by the Office of Management and Budget. The bond shall be conditioned upon the faithful compliance and performance by the successful bidder of each and every term and condition of the contract and the proposal and plans and specifications thereof, at the time and in the manner prescribed by the contract and the plans and specifications, including the payment in full, to every firm furnishing materiel or performing labor in the performance of the contract, of all sums of money due it for such labor or materiel. The bond shall also contain the Contractor's guarantee to indemnify and save harmless the Owner from all costs, damages and expenses growing out of or by reason of Contractor's failure to comply and perform the work and complete the contract in accordance with its terms. No firm or surety, in any action brought under 29 Del C §6962, or any successor law, or on the bond required by such statute, shall assert as a defense to such action the claim that the bond given contained a limitation or restriction not provided for by Chapter 69, Title 29 of the Delaware Code, the provisions of which are incorporated herein by reference as though fully set forth. Contractor shall obtain all insurance required by Owner and provide proof thereof prior to execution.;

15. Owner shall have the right to terminate the contract upon receipt of notice from Contractor's surety that bond claims have been made or are anticipated to be made against Contractor on this or any other project of Contractor. If Owner elects to terminate the contract pursuant to this paragraph, it shall be deemed a termination for cause.

16. Owner may, when it considers that its interests so require, cause judgment to be confessed upon the bond. All sums received through confession of judgment shall be paid for the credit of the Owner to the Secretary of Finance;

17. Owner or any of its duly authorized representatives shall have access to any documents, books, papers, and records of Contractor (which are directly pertinent to a specific grant program) for the purpose of making an audit, examination, excerpts, and transcriptions. Contractor shall maintain all required records for at least three years after Owner makes final payment and all pending matters are closed;

18. Contractor shall submit a report to Owner not less frequently than monthly covering the general progress of the job and describing any problems or factors contributing to delay;

19. During the performance of this contract, the contractor agrees as follows:

The contractor will not discriminate against any employee or applicant for employment because of race, creed, color, sex, sexual orientation gender identity, pregnancy, or national origin. The contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, color, sex, sexual orientation, gender identity, pregnancy, or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.

The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants receive consideration for employment without regard to race, creed, color, sex, sexual orientation or national origin.

20. The parties agree that this agreement shall be governed by and construed pursuant to the laws of The State of Delaware, and that the Delaware courts shall have sole and exclusive jurisdiction of any dispute arising under this agreement.

IN WITNESS WHEREOF, the parties, through their acknowledged and duly authorized agents set forth below, have set their hand and seal on this indenture on this _____ day of March 27th, 2026.

Delaware Technical and Community College

_____(Seal)
Mark T. Brainard, President

(Contractor)

_____(Seal)
By:

SECTION 00 54 14
SUPPLEMENT TO A101-2017 – EXHIBIT A - INSURANCE & BONDS

The following supplements modify the "Standard Form of Agreement Between Owner and Contractor," AIA Document A101-2017 Exhibit A Insurance and Bonds. Where a portion of the Standard Form of Agreement is modified or deleted by the following, the unaltered portions of the Standard Form of Agreement shall remain in effect.

ARTICLE A.2 OWNER'S INSURANCE

A.2.1 General

Delete paragraph A.2.1 in its entirety.

A.2.2 Liability Insurance

Delete paragraph A.2.2 in its entirety, except in the case of school projects this paragraph shall remain.

A.2.3 Required Property Insurance

Delete paragraph A.2.3 in its entirety.

A.2.4 Optional Extended Property Insurance

Delete paragraph A.2.4 in its entirety.

A.2.5 Other Optional Insurance

Delete paragraph A.2.5 in its entirety.

ARTICLE A.3 CONTRACTORS INSURANCE AND BONDS

A.3.1.1 Strike the last sentence of the paragraph.

A.3.1.3 Additional Insured Obligations

In the first sentence after "coverage to include (1)" delete "(1) the Owner,".

Strike the remainder of the first sentence beginning at the semicolon "; and (2) the Owner" through the end of the sentence.

Delete the second sentence in its entirety.

A.3.2.2.1 Insert "$1,000,000.00" in the blank for each occurrence.
Insert "$3,000,000.00" in the blank for general aggregate.
Insert "$3,000,000.00" in the blank for aggregate for products-completed operations hazard.

A.3.2.3 Insert "$1,000,000.00" in the blank for per accident.

A.3.2.6 Insert “$500,000.00” in the blank for each accident.
Insert “$500,000.00” in the blank for each employee.
Insert “$500,000.00” in the blank for policy limit.

A.3.2.8 Insert “$1,000,000.00” in the blank for per claim.
Insert “$3,000,000.00” in the blank for in the aggregate.

A.3.2.9 Insert “$1,000,000.00” in the blank for per claim.
Insert “$3,000,000.00” in the blank for in the aggregate.

A.3.2.10 Insert “$2,000,000.00” in the blank for per claim.
Insert “$4,000,000.00” in the blank for in the aggregate.

A.3.2.11 Strike in its entirety.

A.3.2.12 Strike in its entirety.

A.3.3.2.1 Delete paragraph 3.3.2.1 in its entirety

A.3.3.2.2 Strike in its entirety.

A.3.3.2.3 Insert “$1,000,000.00” in the blanks for per claim.
Insert “$3,000,000.00” in the blanks for in the aggregate.

A.3.4 Insert the actual contract price in both the Payment Bond and the Performance Bond Penal Sum blanks. It must be 100% of the contract price.

Strike the last sentence in this section and replace with “Payment and Performance Bonds shall be in the standard form issued by the Delaware Office of Management and Budget.”

END OF SECTION

PERFORMANCE BOND

Bond Number: _____

KNOW ALL PERSONS BY THESE PRESENTS, that we, _____, as principal ("**Principal**"), and _____, a _____ corporation, legally authorized to do business in the State of Delaware, as surety ("**Surety**"), are held and firmly bound unto the Delaware Technical Community College ("**Owner**"), in the amount of _____ ($_____), to be paid to **Owner**, for which payment well and truly to be made, we do bind ourselves, our and each and every of our heirs, executors, administrations, successors and assigns, jointly and severally, for and in the whole, firmly by these presents.

Sealed with our seals and dated this _____ day of _____, 2026.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH, that if **Principal**, who has been awarded by **Owner** that certain contract known as Contract No. DTCC C9004020007dated the _____ day of _____, 2026 (the "Contract"), which Contract is incorporated herein by reference, shall well and truly provide and furnish all materials, appliances and tools and perform all the work required under and pursuant to the terms and conditions of the Contract and the Contract Documents (as defined in the Contract) or any changes or modifications thereto made as therein provided, shall make good and reimburse **Owner** sufficient funds to pay the costs of completing the Contract that **Owner** may sustain by reason of any failure or default on the part of **Principal**, and shall also indemnify and save harmless **Owner** from all costs, damages and expenses arising out of or by reason of the performance of the Contract and for as long as provided by the Contract; then this obligation shall be void, otherwise to be and remain in full force and effect.

Surety, for value received, hereby stipulates and agrees, if requested to do so by **Owner**, to fully perform and complete the work to be performed under the Contract pursuant to the terms, conditions and covenants thereof, if for any cause **Principal** fails or neglects to so fully perform and complete such work.

Surety, for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of **Surety** and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition or change in or to the Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any work to be performed or any monies due or to become due thereunder; and **Surety** hereby waives notice of any and all such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers and hereby expressly stipulates and agrees that

any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to **Surety** as though done or omitted to be done by or in relation to **Principal**.

Surety hereby stipulates and agrees that no modifications, omissions or additions in or to the terms of the Contract shall in any way whatsoever affect the obligation of **Surety** and its bond.

Any proceeding, legal or equitable, under this Bond may be brought in any court of competent jurisdiction in the State of Delaware. Notices to **Surety** or Contractor may be mailed or delivered to them at their respective addresses shown below.

IN WITNESS WHEREOF, **Principal** and **Surety** have hereunto set their hand and seals, and such of them as are corporations have caused their corporate seal to be hereto affixed and these presents to be signed by their duly authorized officers, the day and year first above written.

PRINCIPAL

Name: _____

Witness or Attest: Address: _____

_____ By: _____(SEAL)
Name: Name:
Title:

(Corporate Seal)

SURETY

Name: _____

Witness or Attest: Address: _____

_____ By: _____(SEAL)
Name: Name:
Title:

(Corporate Seal)

END OF SECTION

PAYMENT BOND

Bond Number: _____

KNOW ALL PERSONS BY THESE PRESENTS, that we, _____, as principal ("**Principal**"), and _____, a _____ corporation, legally authorized to do business in the State of Delaware, as surety ("**Surety**"), are held and firmly bound unto Delaware Technical Community College ("**Owner**"), in the amount of _____ ($_____), to be paid to **Owner**, for which payment well and truly to be made, we do bind ourselves, our and each and every of our heirs, executors, administrations, successors and assigns, jointly and severally, for and in the whole firmly by these presents.

Sealed with our seals and dated this _____ day of_____, 2022.

NOW THE CONDITION OF THIS OBLIGATION IS SUCH, that if **Principal**, who has been awarded by **Owner** that certain contract known as Contract No. DTCC C9004020007 dated the _____ day of _____, 2026 (the "Contract"), which Contract is incorporated herein by reference, shall well and truly pay all and every person furnishing materials or performing labor or service in and about the performance of the work under the Contract, all and every sums of money due him, her, them or any of them, for all such materials, labor and service for which **Principal** is liable, shall make good and reimburse **Owner** sufficient funds to pay such costs in the completion of the Contract as **Owner** may sustain by reason of any failure or default on the part of **Principal**, and shall also indemnify and save harmless **Owner** from all costs, damages and expenses arising out of or by reason of the performance of the Contract and for as long as provided by the Contract; then this obligation shall be void, otherwise to be and remain in full force and effect.

Surety, for value received, for itself and its successors and assigns, hereby stipulates and agrees that the obligation of **Surety** and its bond shall be in no way impaired or affected by any extension of time, modification, omission, addition or change in or to the Contract or the work to be performed thereunder, or by any payment thereunder before the time required therein, or by any waiver of any provisions thereof, or by any assignment, subletting or other transfer thereof or of any work to be performed or any monies due or to become due thereunder; and **Surety** hereby waives notice of any and all such extensions, modifications, omissions, additions, changes, payments, waivers, assignments, subcontracts and transfers and hereby expressly stipulates and agrees that any and all things done and omitted to be done by and in relation to assignees, subcontractors, and other transferees shall have the same effect as to **Surety** as though done or omitted to be done by or in relation to **Principal**.

Surety hereby stipulates and agrees that no modifications, omission or additions in or to the terms of the Contract shall in any way whatsoever affect the obligation of **Surety** and its bond.

Any proceeding, legal or equitable, under this Bond may be brought in any court of competent jurisdiction in the State of Delaware. Notices to **Surety** or Contractor may be mailed or delivered to them at their respective addresses shown below.

IN WITNESS WHEREOF, **Principal** and **Surety** have hereunto set their hand and seals, and such of them as are corporations have caused their corporate seal to be hereto affixed and these presents to be signed by their duly authorized officers, the day and year first above written.

PRINCIPAL

Name: _____

Witness or Attest: Address: _____

_____ By: _____(SEAL)
Name: Name:
Title:

(Corporate Seal)

SURETY

Name: _____

Witness or Attest: Address: _____

_____ By: _____(SEAL)
Name: Name:
Title:

(Corporate Seal)

END OF SECTION

TEVEBAUGH
ARCHITECTURE

SUBMITTAL COVER SHEET

CONTRACTOR STAMP

Submittal N°	Spec Section - Submittal No. eg:
Spec Section	Section of Specifications Referenced
Paragraph	Paragraph of Specifications Referenced
Description	Detailed description of submittal contents

Project

Dental Health Center
21225 College Dr
Georgetown, DE 19947

Client

Delaware Technical Community College
21179 College Dr
Georgetown, DE 19947

Architect

Tevebaugh Architecture
2 Mill Road, Suite 210
Wilmington, DE 19806

TEVEBAUGH STAMP

Architect's review is for conformance with project design concepts. The contractor is responsible for confirming and correlating all quantities and dimensions relating to fabrication process, techniques of construction, and coordination of the work of all trades. Review neither extends nor alters any contractual obligations of the Architect or Contractor.

- ☐ Reviewed
- ☐ Reviewed with Notations
- ☐ Revise & Resubmit
- ☐ Rejected

By: Date: DD / MM / YY

Comments:
Architect's response comments

CONSULTANT STAMP

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G702® – 1992

Application and Certificate for Payment

TO OWNER:

PROJECT:

APPLICATION NO:

PERIOD TO:

CONTRACT FOR:

CONTRACT DATE:

PROJECT NOS: / /

Distribution to:
OWNER ☐
ARCHITECT ☐
CONTRACTOR ☐
FIELD ☐
OTHER ☐

FROM CONTRACTOR:

VIA ARCHITECT:

CONTRACTOR'S APPLICATION FOR PAYMENT

Application is made for payment, as shown below, in connection with the Contract.
AIA Document G703®, Continuation Sheet, is attached.

1. ORIGINAL CONTRACT SUM ..... $ _____

2. NET CHANGE BY CHANGE ORDERS ..... $ _____

3. CONTRACT SUM TO DATE *(Line 1 ± 2)* ..... $ _____

4. TOTAL COMPLETED & STORED TO DATE *(Column G on G703)* ..... $ _____

5. RETAINAGE:

a. _____% of Completed Work
(Columns D + E on G703) $ _____

b. _____% of Stored Material
(Column F on G703) $ _____

Total Retainage *(Lines 5a + 5b, or Total in Column I of G703)*..... $ _____

6. TOTAL EARNED LESS RETAINAGE ..... $ _____
(Line 4 minus Line 5 Total)

7. LESS PREVIOUS CERTIFICATES FOR PAYMENT ..... $ _____
(Line 6 from prior Certificate)

8. CURRENT PAYMENT DUE ..... $

9. BALANCE TO FINISH, INCLUDING RETAINAGE
(Line 3 minus Line 6) $ _____

CHANGE ORDER SUMMARY	ADDITIONS	DEDUCTIONS
Total changes approved in previous months by Owner	$	$
Total approved this month	$	$
TOTAL	$	$
NET CHANGES by Change Order	$	

The undersigned Contractor certifies that to the best of the Contractor's knowledge, information and belief the Work covered by this Application for Payment has been completed in accordance with the Contract Documents, that all amounts have been paid by the Contractor for Work for which previous Certificates for Payment were issued and payments received from the Owner, and that current payment shown herein is now due.

CONTRACTOR:

By: _____ Date: _____

State of:

County of:

Subscribed and sworn to before me this day of

Notary Public:

My commission expires:

ARCHITECT'S CERTIFICATE FOR PAYMENT

In accordance with the Contract Documents, based on on-site observations and the data comprising this application, the Architect certifies to the Owner that to the best of the Architect's knowledge, information and belief the Work has progressed as indicated, the quality of the Work is in accordance with the Contract Documents, and the Contractor is entitled to payment of the AMOUNT CERTIFIED.

AMOUNT CERTIFIED ..... $ _____

(Attach explanation if amount certified differs from the amount applied. Initial all figures on this Application and on the Continuation Sheet that are changed to conform with the amount certified.)

ARCHITECT:

By: _____ Date: _____

This Certificate is not negotiable. The AMOUNT CERTIFIED is payable only to the Contractor named herein. Issuance, payment and acceptance of payment are without prejudice to any rights of the Owner or Contractor under this Contract.

AIA Document G702® – 1992. Copyright © 1953, 1963, 1965, 1971, 1978, 1983 and 1992 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "G702," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations of AIA Contract Documents, e-mail copyright@aia.org.

AIA® Document G703™ – 1992

Continuation Sheet

AIA Document G702™, Application and Certification for Payment; G702™CMa–1992, Application and Certificate for Payment; or G732™–2009, Application and Certificate for Payment, Construction Manager as Adviser Edition, containing Subcontractor's signed certification is attached.
In tabulations below, amounts are stated to the nearest dollar.
Use Column I on Contracts where variable retainage for line items may apply.

APPLICATION NO:
APPLICATION DATE:
PERIOD TO:
ARCHITECT'S PROJECT NO:

A	B	C	D	E	F	G		H	I
			WORK COMPLETED						
ITEM NO.	DESCRIPTION OF WORK	SCHEDULED VALUE	FROM PREVIOUS APPLICATION *(D + E)*	THIS PERIOD	MATERIALS PRESENTLY STORED *(Not in D or E)*	TOTAL COMPLETED AND STORED TO DATE *(D + E + F)*	% *(G ÷ C)*	BALANCE TO FINISH *(C − G)*	RETAINAGE *(If variable rate)*
	GRAND TOTAL								

Sample

AIA Document G703™ – 1992. Copyright © 1963, 1965, 1966, 1967, 1970, 1978, 1983 and 1992 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

TEVEBAUGH
ARCHITECTURE

REQUEST FOR INFORMATION

PROJECT: DTCC Dental Health Center at the Carter Partnership Building

RFI NUMBER:

NUMBER: DTCC #C9004020007
TEVEBAUGH #25040

DATE:

SUBJECT:

REFERENCE:

REQUEST:

By: Date Reply Requested:

REPLY:

By: Date:

PAGE LEFT INTENTIONALLY BLANK

SECTION 00 63 25
SUBSTITUTION REQUEST FORM

To: Tevebaugh Associates, Inc.

Two Mill Road, Suite 210

Wilmington, DE 19806

Project Dental Health Center at the Carter Partnership Building Georgetown Campus

Prime Contract _____

Contractor Company Name _____

The following product is submitted in lieu of the specified product(s) for the above-referenced project:

Specification Section or Drawing_____

Paragraph or Detail_____

Specified Item _____

Substituted Manufacturer_____

Substituted Product Name _____

Substituted product manufacturer’s contact information

Company Address _____

_____

_____

Company Telephone _____

Technical Contact _____

Technical Email _____

Local Rep Name _____

Local Rep Telephone _____

Local Rep Email _____

Reason for not giving priority to specified items:

_____

_____

The attached data includes descriptions, specifications, drawings, photographs, performance, and test data adequate for the evaluation of the proposed substitution request. The applicable portions of the data have been highlighted, and non-applicable information has been redacted or clearly omitted from the documentation. The documentation has been provided in a line-by-line comparison to the basis of design product performance criteria established by the drawings and specifications.

The undersigned prime contractor certifies that the following statements are correct, unless specifically clarified in writing, via the substitution request form in this section:

1. The proposed substitution has been reviewed and coordinated with the Contract Documents.
2. The proposed substitution does not affect dimensions required by the drawings or specifications
3. The proposed substitution does not affect the work of other prime contractors
4. The undersigned will be responsible for changes to the design, including architectural and engineering design, detailing, or construction costs associated with the proposed substitution.

5. The proposed substitution will have no adverse effect on the construction schedule, or specified warranty requirements.

6. Maintenance and service parts are readily available to local suppliers servicing the site location at the time of bid.

7. The function, appearance, and quality of the proposed substitution is better than or equal to the specified item.

Attachments (Provide description of attachments next to applicable heading)

Drawings

_____

_____

Specifications

_____

_____

Technical Data

_____

_____

Submitted by:

_____ _____

(Signature of Prime Contractor's Representative) (Prime Contract)

_____ _____

(Printed Name of Prime Contractor's Representative) (Date)

Drawings affected by proposed substitution: (☐ No effect / or describe below)

_____

_____

Description of changes to the contract documents as a result of proposed substitution:

(☐ No effect / or describe below)

List of applicable building codes that apply to the implementation of proposed substitution for this project:
(No effect / or describe below)

Effects that this substation has on other prime contracts: (☐ No effect / or describe below)

List any differences between basis of design and proposed substitution:

(☐ No difference / or describe below)

END OF SECTION

AIA® Document G710™ – 2017

Architect's Supplemental Instructions

PROJECT: *(name and address)*	**CONTRACT INFORMATION:** Contract For: Date:	**ASI INFORMATION:** ASI Number: Date:
OWNER: *(name and address)*	**ARCHITECT:** *(name and address)*	**CONTRACTOR:** *(name and address)*

The Contractor shall carry out the Work in accordance with the following supplemental instructions without change in Contract Sum or Contract Time. Proceeding with the Work in accordance with these instructions indicates your acknowledgment that there will be no change in the Contract Sum or Contract Time.
(Insert a detailed description of the Architect's supplemental instructions and, if applicable, attach or reference specific exhibits.)

ISSUED BY THE ARCHITECT:

ARCHITECT *(Firm name)*

SIGNATURE

PRINTED NAME AND TITLE

DATE

Sample

AIA Document G710™ – 2017. Copyright © 1979, 1992 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G714™ – 2017

Construction Change Directive

PROJECT: *(name and address)*	CONTRACT INFORMATION: Contract For: Date:	CCD INFORMATION: Directive Number: Date:
OWNER: *(name and address)*	ARCHITECT: *(name and address)*	CONTRACTOR: *(name and address)*

The Contractor is hereby directed to make the following change(s) in this Contract:
(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits.)

PROPOSED ADJUSTMENTS

1. The proposed basis of adjustment to the Contract Sum or Guaranteed Maximum Price:

   ☐ Lump Sum (increase) (decrease) of $

   ☐ Unit Price of $ per

   ☐ Cost, as defined below, plus the following fee:
   (Insert a definition of, or method for determining, cost)

   ☐ As follows:

2. The Contract Time is proposed to (be adjusted) (remain unchanged). The proposed adjustment, if any, is (an increase of days) (a decrease of days).

NOTE: The Owner, Architect and Contractor should execute a Change Order to supersede this Construction Change Directive to the extent they agree upon adjustments to the Contract Sum, Contract Time, or Guaranteed Maximum price for the change(s) described herein.

When signed by the Owner and Architect and received by the Contractor, this document becomes effective IMMEDIATELY as a Construction Change Directive (CCD), and the Contractor shall proceed with the change(s) described above.

Contractor signature indicates agreement with the proposed adjustments in Contract Sum and Contract Time set forth in this CCD.

ARCHITECT *(Firm name)*	OWNER *(Firm name)*	CONTRACTOR *(Firm name)*
SIGNATURE	SIGNATURE	SIGNATURE
PRINTED NAME AND TITLE	PRINTED NAME AND TITLE	PRINTED NAME AND TITLE
DATE	DATE	DATE

AIA Document G714™ – 2017. Copyright © 1987, 2001, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G701™ – 2017

Change Order

PROJECT: *(name and address)*	CONTRACT INFORMATION: Contract For: Date:	CHANGE ORDER INFORMATION: Change Order Number: Date:
OWNER: *(name and address)*	ARCHITECT: *(name and address)*	CONTRACTOR: *(name and address)*

The Contract is changed as follows:
(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits. Also include agreed upon adjustments attributable to executed Construction Change Directives.)

The original (Contract Sum) (Guaranteed Maximum Price) was	$
The net change by previously authorized Change Orders	$
The (Contract Sum) (Guaranteed Maximum Price) prior to this Change Order was	$
The (Contract Sum) (Guaranteed Maximum Price) will be (increased) (decreased) (unchanged) by this Change Order in the amount of	$
The new (Contract Sum) (Guaranteed Maximum Price), including this Change Order, will be	$
The Contract Time will be (increased) (decreased) (unchanged) by	( ) days.
The new date of Substantial Completion will be	

NOTE: This Change Order does not include adjustments to the Contract Sum or Guaranteed Maximum Price, or the Contract Time, that have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER.

ARCHITECT *(Firm name)*	CONTRACTOR *(Firm name)*	OWNER *(Firm name)*
SIGNATURE	SIGNATURE	SIGNATURE
PRINTED NAME AND TITLE	PRINTED NAME AND TITLE	PRINTED NAME AND TITLE
DATE	DATE	DATE

CAUTION: You should sign an original AIA Contract Document, on which this text appears in RED. An original assures that changes will not be obscured.

AIA Document G701™ – 2017. Copyright © 1979, 1987, 2000, 2001 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. Purchasers are permitted to reproduce ten (10) copies of this document when completed. To report copyright violations of AIA Contract

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G704™ – 2017

Certificate of Substantial Completion

PROJECT: *(name and address)*	CONTRACT INFORMATION: Contract For: Date:	CERTIFICATE INFORMATION: Certificate Number: Date:
OWNER: *(name and address)*	ARCHITECT: *(name and address)*	CONTRACTOR: *(name and address)*

The Work identified below has been reviewed and found, to the Architect's best knowledge, information, and belief, to be substantially complete. Substantial Completion is the stage in the progress of the Work when the Work or designated portion is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use. The date of Substantial Completion of the Project or portion designated below is the date established by this Certificate.
(Identify the Work, or portion thereof, that is substantially complete.)

ARCHITECT *(Firm Name)*	SIGNATURE	PRINTED NAME AND TITLE	DATE OF SUBSTANTIAL COMPLETION

WARRANTIES
The date of Substantial Completion of the Project or portion designated above is also the date of commencement of applicable warranties required by the Contract Documents, except as stated below:
(Identify warranties that do not commence on the date of Substantial Completion, if any, and indicate their date of commencement.)

WORK TO BE COMPLETED OR CORRECTED
A list of items to be completed or corrected is attached hereto, or transmitted as agreed upon by the parties, and identified as follows:
(Identify the list of Work to be completed or corrected.)

The failure to include any items on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents. Unless otherwise agreed to in writing, the date of commencement of warranties for items on the attached list will be the date of issuance of the final Certificate of Payment or the date of final payment, whichever occurs first. The Contractor will complete or correct the Work on the list of items attached hereto within ( ) days from the above date of Substantial Completion.

Cost estimate of Work to be completed or corrected: $

The responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work, insurance, and other items identified below shall be as follows:
(Note: Owner's and Contractor's legal and insurance counsel should review insurance requirements and coverage.)

The Owner and Contractor hereby accept the responsibilities assigned to them in this Certificate of Substantial Completion:

CONTRACTOR *(Firm Name)*	SIGNATURE	PRINTED NAME AND TITLE	DATE
OWNER *(Firm Name)*	SIGNATURE	PRINTED NAME AND TITLE	DATE

AIA Document G704™ – 2017. Copyright © 1963, 1978, 1992, 2000 and 2017 by The American Institute of Architects. All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G706™ – 1994

Contractor's Affidavit of Payment of Debts and Claims

PROJECT: *(Name and address)*

ARCHITECT'S PROJECT NUMBER:

CONTRACT FOR:

TO OWNER: *(Name and address)*

CONTRACT DATED:

OWNER ☐
ARCHITECT ☐
CONTRACTOR ☐
SURETY ☐
OTHER ☐

STATE OF:

COUNTY OF:

The undersigned hereby certifies that, except as listed below, payment has been made in full and all obligations have otherwise been satisfied for all materials and equipment furnished, for all work, labor, and services performed, and for all known indebtedness and claims against the Contractor for damages arising in any manner in connection with the performance of the Contract referenced above for which the Owner or Owner's property might in any way be held responsible or encumbered.

EXCEPTIONS:

SUPPORTING DOCUMENTS ATTACHED HERETO:

1. Consent of Surety to Final Payment. Whenever Surety is involved, Consent of Surety is required. AIA Document G707™, Consent of Surety to Final Payment, may be used for this purpose.
   Indicate attachment: ☐ Yes ☑ No

The following supporting documents should be attached hereto if required by the Owner:

1. Contractor's Release or Waiver of Liens, conditional upon receipt of final payment
2. Separate Releases or Waivers of Liens from Subcontractors and material and equipment suppliers, to the extent required by the Owner, accompanied by a list thereof
3. Contractor's Affidavit of Release of Liens (AIA Document G706A™)

CONTRACTOR: *(Name and address)*

BY:

(Signature of authorized representative)

(Printed name and title)

Subscribed and sworn to before me on this date:

Notary Public:

My Commission Expires:

CAUTION: You should sign an original AIA Contract Document, on which this text appears in RED. An original assures that changes will not be obscured.

AIA Document G706™ – 1994. Copyright © 1970 and 1994 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** Purchasers are permitted to reproduce ten (10) copies of this document when completed. To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

Sample

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G706A™ – 1994

Contractor's Affidavit of Release of Liens

PROJECT: *(Name and address)*

ARCHITECT'S PROJECT NUMBER:

CONTRACT FOR:

TO OWNER: *(Name and address)*

CONTRACT DATED:

OWNER ☐
ARCHITECT ☐
CONTRACTOR ☐
SURETY ☐
OTHER ☐

STATE OF:

COUNTY OF:

The undersigned hereby certifies that to the best of the undersigned's knowledge, information and belief, except as listed below, the Releases or Waivers of Lien attached hereto include the Contractor, all Subcontractors, all suppliers of materials and equipment, and all performers of Work, labor or services who have or may have liens or encumbrances or the right to assert liens or encumbrances against any property of the Owner arising in any manner out of the performance of the Contract referenced above.

EXCEPTIONS:

SUPPORTING DOCUMENTS ATTACHED HERETO:

1. Contractor's Release or Waiver of Liens, conditional upon receipt of final payment.
2. Separate Releases or Waivers of Liens from Subcontractors and material and equipment suppliers, to the extent required by the Owner, accompanied by a list thereof.

CONTRACTOR: *(Name and address)*

BY:

(Signature of authorized representative)

(Printed name and title)

Subscribed and sworn to before me on this date:

Notary Public:

My Commission Expires:

CAUTION: You should sign an original AIA Contract Document, on which this text appears in RED. An original assures that changes will not be obscured.

AIA Document G706A™ – 1994. Copyright © 1970 and 1994 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** Purchasers are permitted to reproduce ten (10) copies of this document when completed. To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

Sample

PAGE LEFT INTENTIONALLY BLANK

AIA® Document G707™ – 1994

Consent of Surety to Final Payment

PROJECT: *(Name and address)*

ARCHITECT'S PROJECT NUMBER:

CONTRACT FOR:

TO OWNER: *(Name and address)*

CONTRACT DATED:

OWNER ☐
ARCHITECT ☐
CONTRACTOR ☐
SURETY ☐
OTHER ☐

In accordance with the provisions of the Contract between the Owner and the Contractor as indicated above, the
(Insert name and address of Surety)

, SURETY,

on bond of
(Insert name and address of Contractor)

, CONTRACTOR,

hereby approves of the final payment to the Contractor, and agrees that final payment to the Contractor shall not relieve the Surety of any of its obligations to
(Insert name and address of Owner)

, OWNER,

as set forth in said Surety's bond.

IN WITNESS WHEREOF, the Surety has hereunto set its hand on this date:
(Insert in writing the month followed by the numeric date and year.)

(Surety)

(Signature of authorized representative)

Attest:
(Seal)

(Printed name and title)

CAUTION: You should sign an original AIA Contract Document, on which this text appears in RED. An original assures that changes will not be obscured.

AIA Document G707™ – 1994. Copyright © 1970 and 1994 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** Purchasers are not permitted to reproduce this document. To report copyright violations of AIA Contract Documents, e-mail The American Institute of Architects' legal counsel, copyright@aia.org.

Sample

PAGE LEFT INTENTIONALLY BLANK

SECTION 00 72 13

GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION
A201 - 2017

The General Conditions of this Contract are as stated in the American Institute of Architects Document AIA A201 (2017 Edition) entitled General Conditions of the Contract for Construction as revised by the Supplementary General Conditions and is part of this project manual as if herein written in full.

PAGE LEFT INTENTIONALLY BLANK

AIA® Document A201® – 2017

General Conditions of the Contract for Construction

for the following PROJECT:
(Name and location or address)

THE OWNER:
(Name, legal status and address)

THE ARCHITECT:
(Name, legal status and address)

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

For guidance in modifying this document to include supplementary conditions, see AIA Document A503™, Guide for Supplementary Conditions.

TABLE OF ARTICLES

1 GENERAL PROVISIONS

2 OWNER

3 CONTRACTOR

4 ARCHITECT

5 SUBCONTRACTORS

6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

7 CHANGES IN THE WORK

8 TIME

9 PAYMENTS AND COMPLETION

10 PROTECTION OF PERSONS AND PROPERTY

11 INSURANCE AND BONDS

12 UNCOVERING AND CORRECTION OF WORK

13 MISCELLANEOUS PROVISIONS

14 TERMINATION OR SUSPENSION OF THE CONTRACT

15 CLAIMS AND DISPUTES

Sample

Init.
/

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

INDEX
(Topics and numbers in bold are Section headings.)

Acceptance of Nonconforming Work
9.6.6, 9.9.3, **12.3**
Acceptance of Work
9.6.6, 9.8.2, 9.9.3, 9.10.1, 9.10.3, 12.3
Access to Work
3.16, 6.2.1, 12.1
Accident Prevention
10
Acts and Omissions
3.2, 3.3.2, 3.12.8, 3.18, 4.2.3, 8.3.1, 9.5.1, 10.2.5, 10.2.8, 13.3.2, 14.1, 15.1.2, 15.2
Addenda
1.1.1
Additional Costs, Claims for
3.7.4, 3.7.5, 10.3.2, 15.1.5
Additional Inspections and Testing
9.4.2, 9.8.3, 12.2.1, **13.4**
Additional Time, Claims for
3.2.4, 3.7.4, 3.7.5, 3.10.2, 8.3.2, **15.1.6**
Administration of the Contract
3.1.3, **4.2**, 9.4, 9.5
Advertisement or Invitation to Bid
1.1.1
Aesthetic Effect
4.2.13
Allowances
3.8
Applications for Payment
4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5.1, 9.5.4, 9.6.3, 9.7, 9.10
Approvals
2.1.1, 2.3.1, 2.5, 3.1.3, 3.10.2, 3.12.8, 3.12.9, 3.12.10.1, 4.2.7, 9.3.2, 13.4.1
Arbitration
8.3.1, 15.3.2, **15.4**
ARCHITECT
4
Architect, Definition of
4.1.1
Architect, Extent of Authority
2.5, 3.12.7, 4.1.2, 4.2, 5.2, 6.3, 7.1.2, 7.3.4, 7.4, 9.2, 9.3.1, 9.4, 9.5, 9.6.3, 9.8, 9.10.1, 9.10.3, 12.1, 12.2.1, 13.4.1, 13.4.2, 14.2.2, 14.2.4, 15.1.4, 15.2.1
Architect, Limitations of Authority and Responsibility
2.1.1, 3.12.4, 3.12.8, 3.12.10, 4.1.2, 4.2.1, 4.2.2, 4.2.3, 4.2.6, 4.2.7, 4.2.10, 4.2.12, 4.2.13, 5.2.1, 7.4, 9.4.2, 9.5.4, 9.6.4, 15.1.4, 15.2
Architect's Additional Services and Expenses
2.5, 12.2.1, 13.4.2, 13.4.3, 14.2.4
Architect's Administration of the Contract
3.1.3, 3.7.4, 15.2, 9.4.1, 9.5
Architect's Approvals
2.5, 3.1.3, 3.5, 3.10.2, 4.2.7
Architect's Authority to Reject Work
3.5, 4.2.6, 12.1.2, 12.2.1
Architect's Copyright
1.1.7, 1.5
Architect's Decisions
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 4.2.14, 6.3, 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4.1, 9.5, 9.8.4, 9.9.1, 13.4.2, 15.2
Architect's Inspections
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 13.4
Architect's Instructions
3.2.4, 3.3.1, 4.2.6, 4.2.7, 13.4.2
Architect's Interpretations
4.2.11, 4.2.12
Architect's Project Representative
4.2.10
Architect's Relationship with Contractor
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5, 3.7.4, 3.7.5, 3.9.2, 3.9.3, 3.10, 3.11, 3.12, 3.16, 3.18, 4.1.2, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.3.2, 13.4, 15.2
Architect's Relationship with Subcontractors
1.1.2, 4.2.3, 4.2.4, 4.2.6, 9.6.3, 9.6.4, 11.3
Architect's Representations
9.4.2, 9.5.1, 9.10.1
Architect's Site Visits
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
Asbestos
10.3.1
Attorneys' Fees
3.18.1, 9.6.8, 9.10.2, 10.3.3
Award of Separate Contracts
6.1.1, 6.1.2
Award of Subcontracts and Other Contracts for Portions of the Work
5.2
Basic Definitions
1.1
Bidding Requirements
1.1.1
Binding Dispute Resolution
8.3.1, 9.7, 11.5, 13.1, 15.1.2, 15.1.3, 15.2.1, 15.2.5, 15.2.6.1, 15.3.1, 15.3.2, 15.3.3, 15.4.1
Bonds, Lien
7.3.4.4, 9.6.8, 9.10.2, 9.10.3
Bonds, Performance, and Payment
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**, 11.1.3, **11.5**
Building Information Models Use and Reliance
1.8
Building Permit
3.7.1
Capitalization
1.3
Certificate of Substantial Completion
9.8.3, 9.8.4, 9.8.5
Certificates for Payment
4.2.1, 4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4, 15.1.4
Certificates of Inspection, Testing or Approval
13.4.4

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Certificates of Insurance
9.10.2
Change Orders
1.1.1, 3.4.2, 3.7.4, 3.8.2.3, 3.11, 3.12.8, 4.2.8, 5.2.3, 7.1.2, 7.1.3, **7.2**, 7.3.2, 7.3.7, 7.3.9, 7.3.10, 8.3.1, 9.3.1.1, 9.10.3, 10.3.2, 11.2, 11.5, 12.1.2
Change Orders, Definition of
7.2.1
CHANGES IN THE WORK
2.2.2, 3.11, 4.2.8, **7**, 7.2.1, 7.3.1, 7.4, 8.3.1, 9.3.1.1, 11.5
Claims, Definition of
15.1.1
Claims, Notice of
1.6.2, 15.1.3
CLAIMS AND DISPUTES
3.2.4, 6.1.1, 6.3, 7.3.9, 9.3.3, 9.10.4, 10.3.3, **15**, 15.4
Claims and Timely Assertion of Claims
15.4.1
Claims for Additional Cost
3.2.4, 3.3.1, 3.7.4, 7.3.9, 9.5.2, 10.2.5, 10.3.2, **15.1.5**
Claims for Additional Time
3.2.4, 3.3.1, 3.7.4, 6.1.1, 8.3.2, 9.5.2, 10.3.2, **15.1.6**
Concealed or Unknown Conditions, Claims for
3.7.4
Claims for Damages
3.2.4, 3.18, 8.3.3, 9.5.1, 9.6.7, 10.2.5, 10.3.3, 11.3, 11.3.2, 14.2.4, 15.1.7
Claims Subject to Arbitration
15.4.1
Cleaning Up
3.15, 6.3
Commencement of the Work, Conditions Relating to
2.2.1, 3.2.2, 3.4.1, 3.7.1, 3.10.1, 3.12.6, 5.2.1, 5.2.3, 6.2.2, 8.1.2, 8.2.2, 8.3.1, 11.1, 11.2, **15.1.5**
Commencement of the Work, Definition of
8.1.2
Communications
3.9.1, **4.2.4**
Completion, Conditions Relating to
3.4.1, 3.11, 3.15, 4.2.2, 4.2.9, 8.2, 9.4.2, 9.8, 9.9.1, 9.10, 12.2, 14.1.2, 15.1.2
COMPLETION, PAYMENTS AND
9
Completion, Substantial
3.10.1, 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, 9.10.3, 12.2, 15.1.2
Compliance with Laws
2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14.1.1, 14.2.1.3, 15.2.8, 15.4.2, 15.4.3
Concealed or Unknown Conditions
3.7.4, 4.2.8, 8.3.1, 10.3
Conditions of the Contract
1.1.1, 6.1.1, 6.1.4
Consent, Written
3.4.2, 3.14.2, 4.1.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3, 13.2, 15.4.4.2
Consolidation or Joinder
15.4.4
CONSTRUCTION BY OWNER OR BY
SEPARATE CONTRACTORS
1.1.4, **6**
Construction Change Directive, Definition of
7.3.1
Construction Change Directives
1.1.1, 3.4.2, 3.11, 3.12.8, 4.2.8, 7.1.1, 7.1.2, 7.1.3, **7.3**, 9.3.1.1
Construction Schedules, Contractor's
3.10, 3.11, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Contingent Assignment of Subcontracts
5.4, 14.2.2.2
Continuing Contract Performance
15.1.4
Contract, Definition of
1.1.2
CONTRACT, TERMINATION OR SUSPENSION
OF THE
5.4.1.1, 5.4.2, 11.5, **14**
Contract Administration
3.1.3, **4**, 9.4, 9.5
Contract Award and Execution, Conditions Relating to
3.7.1, 3.10, 5.2, 6.1
Contract Documents, Copies Furnished and Use of
1.5.2, 2.3.6, 5.3
Contract Documents, Definition of
1.1.1
Contract Sum
2.2.2, 2.2.4, 3.7.4, 3.7.5, 3.8, 3.10.2, 5.2.3, 7.3, 7.4, **9.1**, 9.2, 9.4.2, 9.5.1.4, 9.6.7, 9.7, 10.3.2, 11.5, 12.1.2, 12.3, 14.2.4, 14.3.2, 15.1.4.2, **15.1.5, 15.2.5**
Contract Sum, Definition of
9.1
Contract Time
1.1.4, 2.2.1, 2.2.2, 3.7.4, 3.7.5, 3.10.2, 5.2.3, 6.1.5, 7.2.1.3, 7.3.1, 7.3.5, 7.3.6, 7, 7, 7.3.10, 7.4, 8.1.1, 8.2.1, 8.2.3, 8.3.1, 9.5.1, 9.7, 10.3.2, 12.1.1, 12.1.2, 14.3.2, 15.1.4.2, 15.1.6.1, 15.2.5
Contract Time, Definition of
8.1.1
CONTRACTOR
3
Contractor, Definition of
3.1, 6.1.2
Contractor's Construction and Submittal Schedules
3.10, 3.12.1, 3.12.2, 4.2.3, 6.1.3, 15.1.6.2
Contractor's Employees
2.2.4, 3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3, 11.3, 14.1, 14.2.1.1
Contractor's Liability Insurance
11.1
Contractor's Relationship with Separate Contractors and Owner's Forces
3.12.5, 3.14.2, 4.2.4, 6, 11.3, 12.2.4

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Contractor's Relationship with Subcontractors
1.2.2, 2.2.4, 3.3.2, 3.18.1, 3.18.2, 4.2.4, 5, 9.6.2, 9.6.7, 9.10.2, 11.2, 11.3, 11.4
Contractor's Relationship with the Architect
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5.1, 3.7.4, 3.10, 3.11, 3.12, 3.16, 3.18, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.4, 15.1.3, 15.2.1
Contractor's Representations
3.2.1, 3.2.2, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.8.2
Contractor's Responsibility for Those Performing the Work
3.3.2, 3.18, 5.3, 6.1.3, 6.2, 9.5.1, 10.2.8
Contractor's Review of Contract Documents
3.2
Contractor's Right to Stop the Work
2.2.2, 9.7
Contractor's Right to Terminate the Contract
14.1
Contractor's Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 9.2, 9.3, 9.8.2, 9.8.3, 9.9.1, 9.10.2, 9.10.3
Contractor's Superintendent
3.9, 10.2.6
Contractor's Supervision and Construction Procedures
1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.4, 7.3.6, 8.2, 10, 12, 14, 15.1.4
Coordination and Correlation
1.2, 3.2.1, 3.3.1, 3.10, 3.12.6, 6.1.3, 6.2.1
Copies Furnished of Drawings and Specifications
1.5, 2.3.6, 3.11
Copyrights
1.5, **3.17**
Correction of Work
2.5, 3.7.3, 9.4.2, 9.8.2, 9.8.3, 9.9.1, 12.1.2, **12.2**, 12.3, 15.1.3.1, 15.1.3.2, 15.2.1
Correlation and Intent of the Contract Documents
1.2
Cost, Definition of
7.3.4
Costs
2.5, 3.2.4, 3.7.3, 3.8.2, 3.15.2, 5.4.2, 6.1.1, 6.2.3, 7.3.3.3, 7.3.4, 7.3.8, 7.3.9, 9.10.2, 10.3.2, 10.3.6, 11.2, 12.1.2, 12.2.1, 12.2.4, 13.4, 14
Cutting and Patching
3.14, 6.2.5
Damage to Construction of Owner or Separate Contractors
3.14.2, 6.2.4, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damage to the Work
3.14.2, 9.9.1, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damages, Claims for
3.2.4, 3.18, 6.1.1, 8.3.3, 9.5.1, 9.6.7, 10.3.3, 11.3.2, 11.3, 14.2.4, 15.1.7
Damages for Delay
6.2.3, 8.3.3, 9.5.1.6, 9.7, 10.3.2, 14.3.2
Date of Commencement of the Work, Definition of
8.1.2
Date of Substantial Completion, Definition of
8.1.3
Day, Definition of
8.1.4
Decisions of the Architect
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 6.3, 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4, 9.5.1, 9.8.4, 9.9.1, 13.4.2, 14.2.2, 14.2.4, 15.1, 15.2
Decisions to Withhold Certification
9.4.1, **9.5**, 9.7, 14.1.1.3
Defective or Nonconforming Work, Acceptance, Rejection and Correction of
2.5, 3.5, 4.2.6, 6.2.3, 9.5.1, 9.5.3, 9.6.6, 9.8.2, 9.9.3, 9.10.4, 12.2.1
Definitions
1.1, 2.1.1, 3.1.1, 3.5, 3.12.1, 3.12.2, 3.12.3, 4.1.1, 5.1, 6.1.2, 7.2.1, 7.3.1, 8.1, 9.1, 9.8.1, 15.1.1
Delays and Extensions of Time
3.2, **3.7.4**, 5.2.3, 7.2.1, 7.3.1, **7.4**, **8.3**, 9.5.1, **9.7**, 10.3.2, **10.4**, 14.3.2, **15.1.6**, 15.2.5
Digital Data Use and Transmission
1.7
Disputes
6.3, 7.3.9, 15.1, 15.2
Documents and Samples at the Site
3.11
Drawings, Definition of
1.1.5
Drawings and Specifications, Use and Ownership of
3.11
Effective Date of Insurance
8.2.2
Emergencies
10.4, 14.1.1.2, **15.1.5**
Employees, Contractor's
3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3.3, 11.3, 14.1, 14.2.1.1
Equipment, Labor, or Materials
1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Execution and Progress of the Work
1.1.3, 1.2.1, 1.2.2, 2.3.4, 2.3.6, 3.1, 3.3.1, 3.4.1, 3.7.1, 3.10.1, 3.12, 3.14, 4.2, 6.2.2, 7.1.3, 7.3.6, 8.2, 9.5.1, 9.9.1, 10.2, 10.3, 12.1, 12.2, 14.2, 14.3.1, 15.1.4
Extensions of Time
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3, 7.4, 9.5.1, 9.7, 10.3.2, 10.4, 14.3, 15.1.6, **15.2.5**
Failure of Payment
9.5.1.3, **9.7**, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Faulty Work
(See Defective or Nonconforming Work)
Final Completion and Final Payment
4.2.1, 4.2.9, 9.8.2, **9.10**, 12.3, 14.2.4, 14.4.3
Financial Arrangements, Owner's
2.2.1, 13.2.2, 14.1.1.4
GENERAL PROVISIONS
1

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Governing Law
13.1
Guarantees (See Warranty)
Hazardous Materials and Substances
10.2.4, **10.3**
Identification of Subcontractors and Suppliers
5.2.1
Indemnification
3.17, **3.18**, 9.6.8, 9.10.2, 10.3.3, 11.3
Information and Services Required of the Owner
2.1.2, **2.2**, 2.3, 3.2.2, 3.12.10.1, 6.1.3, 6.1.4, 6.2.5, 9.6.1, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Initial Decision
15.2
Initial Decision Maker, Definition of
1.1.8
Initial Decision Maker, Decisions
14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
Initial Decision Maker, Extent of Authority
14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
Injury or Damage to Person or Property
10.2.8, 10.4
Inspections
3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 12.2.1, 13.4
Instructions to Bidders
1.1.1
Instructions to the Contractor
3.2.4, 3.3.1, 3.8.1, 5.2.1, 7, 8.2.2, 12, 13.4.2
Instruments of Service, Definition of
1.1.7
Insurance
6.1.1, 7.3.4, 8.2.2, 9.3.2, 9.8.4, 9.9.1, 9.10.2, 10.2.5, **11**
Insurance, Notice of Cancellation or Expiration
11.1.4, 11.2.3
Insurance, Contractor's Liability
11.1
Insurance, Effective Date of
8.2.2, 14.4.2
Insurance, Owner's Liability
11.2
Insurance, Property
10.2.5, 11.2, 11.4, 11.5
Insurance, Stored Materials
9.3.2
INSURANCE AND BONDS
11
Insurance Companies, Consent to Partial Occupancy
9.9.1
Insured loss, Adjustment and Settlement of
11.5
Intent of the Contract Documents
1.2.1, 4.2.7, 4.2.12, 4.2.13
Interest
13.5
Interpretation
1.1.8, 1.2.3, **1.4**, 4.1.1, 5.1, 6.1.2, 15.1.1
Interpretations, Written
4.2.11, 4.2.12
Judgment on Final Award
15.4.2
Labor and Materials, Equipment
1.1.3, 1.1.6, **3.4**, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Labor Disputes
8.3.1
Laws and Regulations
1.5, 2.3.2, 3.2.3, 3.2.4, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, 10.2.2, 13.1, 13.3.1, 13.4.2, 13.5, 14, 15.2.8, 15.4
Liens
2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
Limitations, Statutes of
12.2.5, 15.1.2, 15.4.1.1
Limitations of Liability
3.2.2, 3.5, 3.12.10, 3.12.10.1, 3.17, 3.18.1, 4.2.6, 4.2.7, 6.2.2, 9.4.2, 9.6.4, 9.6.7, 9.6.8, 10.2.5, 10.3.3, 11.3, 12.2.5, 13.3.1
Limitations of Time
2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2.7, 5.2, 5.3, 5.4.1, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15, 15.1.2, 15.1.3, 15.1.5
Materials, Hazardous
10.2.4, **10.3**
Materials, Labor, Equipment and
1.1.3, 1.1.6, 3.4.1, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1.2, 10.2.4, 14.2.1.1, 14.2.1.2
Means, Methods, Techniques, Sequences and Procedures of Construction
3.3.1, 3.12.10, 4.2.2, 4.2.7, 9.4.2
Mechanic's Lien
2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
Mediation
8.3.1, 15.1.3.2, 15.2.1, 15.2.5, 15.2.6, **15.3**, 15.4.1, 15.4.1.1
Minor Changes in the Work
1.1.1, 3.4.2, 3.12.8, 4.2.8, 7.1, **7.4**
MISCELLANEOUS PROVISIONS
13
Modifications, Definition of
1.1.1
Modifications to the Contract
1.1.1, 1.1.2, 2.5, 3.11, 4.1.2, 4.2.1, 5.2.3, 7, 8.3.1, 9.7, 10.3.2
Mutual Responsibility
6.2
Nonconforming Work, Acceptance of
9.6.6, 9.9.3, **12.3**
Nonconforming Work, Rejection and Correction of
2.4, 2.5, 3.5, 4.2.6, 6.2.4, 9.5.1, 9.8.2, 9.9.3, 9.10.4, 12.2

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Notice
1.6, 1.6.1, 1.6.2, 2.1.2, 2.2.2., 2.2.3, 2.2.4, 2.5, 3.2.4, 3.3.1, 3.7.4, 3.7.5, 3.9.2, 3.12.9, 3.12.10, 5.2.1, 7.4, 8.2.2 9.6.8, 9.7, 9.10.1, 10.2.8, 10.3.2, 11.5, 12.2.2.1, 13.4.1, 13.4.2, 14.1, 14.2.2, 14.4.2, 15.1.3, 15.1.5, 15.1.6, 15.4.1
Notice of Cancellation or Expiration of Insurance
11.1.4, 11.2.3
Notice of Claims
1.6.2, 2.1.2, 3.7.4, 9.6.8, 10.2.8, **15.1.3**, 15.1.5, 15.1.6, 15.2.8, 15.3.2, 15.4.1
Notice of Testing and Inspections
13.4.1, 13.4.2
Observations, Contractor's
3.2, 3.7.4
Occupancy
2.3.1, 9.6.6, 9.8
Orders, Written
1.1.1, 2.4, 3.9.2, 7, 8.2.2, 11.5, 12.1, 12.2.2.1, 13.4.2, 14.3.1
OWNER
2
Owner, Definition of
2.1.1
Owner, Evidence of Financial Arrangements
2.2, 13.2.2, 14.1.1.4
Owner, Information and Services Required of the
2.1.2, **2.2**, 2.3, 3.2.2, 3.12.10, 6.1.3, 6.1.4, 6.2.5, 9.3.2, 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Owner's Authority
1.5, 2.1.1, 2.3.32.4, 2.5, 3.4.2, 3.8.1, 3.12.10, 3.14.2, 4.1.2, 4.2.4, 4.2.9, 5.2.1, 5.2.4, 5.4.1, 6.1, 6.3, 7.2.1, 7.3.1, 8.2.2, 8.3.1, 9.3.2, 9.5.1, 9.6.4, 9.9.1, 9.10.2, 10.3.2, 11.4, 11.5, 12.2.2, 12.3, 13.2.2, 14.3, 14.4, 15.2.7
Owner's Insurance
11.2
Owner's Relationship with Subcontractors
1.1.2, 5.2, 5.3, 5.4, 9.6.4, 9.10.2, 14.2.2
Owner's Right to Carry Out the Work
2.5, 14.2.2
Owner's Right to Clean Up
6.3
Owner's Right to Perform Construction and to Award Separate Contracts
6.1
Owner's Right to Stop the Work
2.4
Owner's Right to Suspend the Work
14.3
Owner's Right to Terminate the Contract
14.2, 14.4
Ownership and Use of Drawings, Specifications and Other Instruments of Service
1.1.1, 1.1.6, 1.1.7, **1.5**, 2.3.6, 3.2.2, 3.11, 3.17, 4.2.12, 5.3
Partial Occupancy or Use
9.6.6, **9.9**
Patching, Cutting and
3.14, 6.2.5
Patents
3.17
Payment, Applications for
4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5, 9.6.3, 9.7, 9.8.5, 9.10.1, 14.2.3, 14.2.4, 14.4.3
Payment, Certificates for
4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4
Payment, Failure of
9.5.1.3, **9.7**, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Payment, Final
4.2.1, 4.2.9, **9.10**, 12.3, 14.2.4, 14.4.3
Payment Bond, Performance Bond and
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**
Payments, Progress
9.3, **9.6**, 9.8.5, 9.10.3, 14.2.3, 15.1.4
PAYMENTS AND COMPLETION
9
Payments to Subcontractors
5.4.2, 9.5.1.3, 9.6.2, 9.6.3, 9.6.4, 9.6.7, 14.2.1.2
PCB
10.3.1
Performance Bond and Payment Bond
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**
Permits, Fees, Notices and Compliance with Laws
2.3.1, **3.7**, 3.13, 7.3.4.4, 10.2.2
PERSONS AND PROPERTY, PROTECTION OF
10
Polychlorinated Biphenyl
10.3.1
Product Data, Definition of
3.12.2
Product Data and Samples, Shop Drawings
3.11, **3.12**, 4.2.7
Progress and Completion
4.2.2, **8.2**, 9.8, 9.9.1, 14.1.4, 15.1.4
Progress Payments
9.3, **9.6**, 9.8.5, 9.10.3, 14.2.3, 15.1.4
Project, Definition of
1.1.4
Project Representatives
4.2.10
Property Insurance
10.2.5, **11.2**
Proposal Requirements
1.1.1
PROTECTION OF PERSONS AND PROPERTY
10
Regulations and Laws
1.5, 2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14, 15.2.8, 15.4
Rejection of Work
4.2.6, 12.2.1

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Releases and Waivers of Liens
9.3.1, 9.10.2
Representations
3.2.1, 3.5, 3.12.6, 8.2.1, 9.3.3, 9.4.2, 9.5.1, 9.10.1
Representatives
2.1.1, 3.1.1, 3.9, 4.1.1, 4.2.10, 13.2.1
Responsibility for Those Performing the Work
3.3.2, 3.18, 4.2.2, 4.2.3, 5.3, 6.1.3, 6.2, 6.3, 9.5.1, 10
Retainage
9.3.1, 9.6.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3
Review of Contract Documents and Field Conditions by Contractor
3.2, 3.12.7, 6.1.3
Review of Contractor's Submittals by Owner and Architect
3.10.1, 3.10.2, 3.11, 3.12, 4.2, 5.2, 6.1.3, 9.2, 9.8.2
Review of Shop Drawings, Product Data and Samples by Contractor
3.12
Rights and Remedies
1.1.2, 2.4, 2.5, 3.5, 3.7.4, 3.15.2, 4.2.6, 5.3, 5.4, 6.1, 6.3, 7.3.1, 8.3, 9.5.1, 9.7, 10.2.5, 10.3, 12.2.1, 12.2.2, 12.2.4, **13.3**, 14, 15.4
Royalties, Patents and Copyrights
3.17
Rules and Notices for Arbitration
15.4.1
Safety of Persons and Property
10.2, 10.4
Safety Precautions and Programs
3.3.1, 4.2.2, 4.2.7, 5.3, **10.1**, 10.2, 10.4
Samples, Definition of
3.12.3
Samples, Shop Drawings, Product Data and
3.11, **3.12**, 4.2.7
Samples at the Site, Documents and
3.11
Schedule of Values
9.2, 9.3.1
Schedules, Construction
3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Separate Contracts and Contractors
1.1.4, 3.12.5, 3.14.2, 4.2.4, 4.2.7, 6, 8.3.1, 12.1.2
Separate Contractors, Definition of
6.1.1
Shop Drawings, Definition of
3.12.1
Shop Drawings, Product Data and Samples
3.11, **3.12**, 4.2.7
Site, Use of
3.13, 6.1.1, 6.2.1
Site Inspections
3.2.2, 3.3.3, 3.7.1, 3.7.4, 4.2, 9.9.2, 9.4.2, 9.10.1, 13.4
Site Visits, Architect's
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
Special Inspections and Testing
4.2.6, 12.2.1, 13.4
Specifications, Definition of
1.1.6
Specifications
1.1.1, **1.1.6**, 1.2.2, 1.5, 3.12.10, 3.17, 4.2.14
Statute of Limitations
15.1.2, 15.4.1.1
Stopping the Work
2.2.2, 2.4, 9.7, 10.3, 14.1
Stored Materials
6.2.1, 9.3.2, 10.2.1.2, 10.2.4
Subcontractor, Definition of
5.1.1
SUBCONTRACTORS
5
Subcontractors, Work by
1.2.2, 3.3.2, 3.12.1, 3.18, 4.2.3, 5.2.3, 5.3, 5.4, 9.3.1.2, 9.6.7
Subcontractual Relations
5.3, 5.4, 9.3.1.2, 9.6, 9.10, 10.2.1, 14.1, 14.2.1
Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 7.3.4, 9.2, 9.3, 9.8, 9.9.1, 9.10.2, 9.10.3
Submittal Schedule
3.10.2, 3.12.5, 4.2.7
Subrogation, Waivers of
6.1.1, **11.3**
Substances, Hazardous
10.3
Substantial Completion
4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, **9.8**, 9.9.1, 9.10.3, 12.2, 15.1.2
Substantial Completion, Definition of
9.8.1
Substitution of Subcontractors
5.2.3, 5.2.4
Substitution of Architect
2.3.3
Substitutions of Materials
3.4.2, 3.5, 7.3.8
Sub-subcontractor, Definition of
5.1.2
Subsurface Conditions
3.7.4
Successors and Assigns
13.2
Superintendent
3.9, 10.2.6
Supervision and Construction Procedures
1.2.2, **3.3**, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.4, 8.2, 8.3.1, 9.4.2, 10, 12, 14, 15.1.4
Suppliers
1.5, 3.12.1, 4.2.4, 4.2.6, 5.2.1, 9.3, 9.4.2, 9.5.4, 9.6, 9.10.5, 14.2.1
Surety
5.4.1.2, 9.6.8, 9.8.5, 9.10.2, 9.10.3, 11.1.2, 14.2.2, 15.2.7
Surety, Consent of
9.8.5, 9.10.2, 9.10.3

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Surveys
1.1.7, 2.3.4
Suspension by the Owner for Convenience
14.3
Suspension of the Work
3.7.5, 5.4.2, 14.3
Suspension or Termination of the Contract
5.4.1.1, 14
Taxes
3.6, 3.8.2.1, 7.3.4.4
Termination by the Contractor
14.1, 15.1.7
Termination by the Owner for Cause
5.4.1.1, **14.2,** 15.1.7
Termination by the Owner for Convenience
14.4
Termination of the Architect
2.3.3
Termination of the Contractor Employment
14.2.2

TERMINATION OR SUSPENSION OF THE CONTRACT
14
Tests and Inspections
3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 10.3.2, 12.2.1, **13.4**
TIME
8
Time, Delays and Extensions of
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, **8.3**, 9.5.1, 9.7, 10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5
Time Limits
2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2, 5.2, 5.3, 5.4, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15.1.2, 15.1.3, 15.4
Time Limits on Claims
3.7.4, 10.2.8, 15.1.2, 15.1.3
Title to Work
9.3.2, 9.3.3

UNCOVERING AND CORRECTION OF WORK
12
Uncovering of Work
12.1
Unforeseen Conditions, Concealed or Unknown
3.7.4, 8.3.1, 10.3
Unit Prices
7.3.3.2, 9.1.2
Use of Documents
1.1.1, 1.5, 2.3.6, 3.12.6, 5.3
Use of Site
3.13, 6.1.1, 6.2.1
Values, Schedule of
9.2, 9.3.1
Waiver of Claims by the Architect
13.3.2
Waiver of Claims by the Contractor
9.10.5, 13.3.2, **15.1.7**
Waiver of Claims by the Owner
9.9.3, 9.10.3, 9.10.4, 12.2.2.1, 13.3.2, 14.2.4, **15.1.7**
Waiver of Consequential Damages
14.2.4, 15.1.7
Waiver of Liens
9.3, 9.10.2, 9.10.4
Waivers of Subrogation
6.1.1, **11.3**
Warranty
3.5, 4.2.9, 9.3.3, 9.8.4, 9.9.1, 9.10.2, 9.10.4, 12.2.2, 15.1.2
Weather Delays
8.3, 15.1.6.2
Work, Definition of
1.1.3
Written Consent
1.5.2, 3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.10.3, 13.2, 13.3.2, 15.4.4.2
Written Interpretations
4.2.11, 4.2.12
Written Orders
1.1.1, 2.4, 3.9, 7, 8.2.2, 12.1, 12.2, 13.4.2, 14.3.1

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 Basic Definitions

§ 1.1.1 The Contract Documents

The Contract Documents are enumerated in the Agreement between the Owner and Contractor (hereinafter the Agreement) and consist of the Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of the Contract, other documents listed in the Agreement, and Modifications issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties, (2) a Change Order, (3) a Construction Change Directive, or (4) a written order for a minor change in the Work issued by the Architect. Unless specifically enumerated in the Agreement, the Contract Documents do not include the advertisement or invitation to bid, Instructions to Bidders, sample forms, other information furnished by the Owner in anticipation of receiving bids or proposals, the Contractor's bid or proposal, or portions of Addenda relating to bidding or proposal requirements.

§ 1.1.2 The Contract

The Contract Documents form the Contract for Construction. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind (1) between the Contractor and the Architect or the Architect's consultants, (2) between the Owner and a Subcontractor or a Sub-subcontractor, (3) between the Owner and the Architect or the Architect's consultants, or (4) between any persons or entities other than the Owner and the Contractor. The Architect shall, however, be entitled to performance and enforcement of obligations under the Contract intended to facilitate performance of the Architect's duties.

§ 1.1.3 The Work

The term "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all other labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The Work may constitute the whole or a part of the Project.

§ 1.1.4 The Project

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner and by Separate Contractors.

§ 1.1.5 The Drawings

The Drawings are the graphic and pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules, and diagrams.

§ 1.1.6 The Specifications

The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, systems, standards and workmanship for the Work, and performance of related services.

§ 1.1.7 Instruments of Service

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.1.8 Initial Decision Maker

The Initial Decision Maker is the person identified in the Agreement to render initial decisions on Claims in accordance with Section 15.2. The Initial Decision Maker shall not show partiality to the Owner or Contractor and shall not be liable for results of interpretations or decisions rendered in good faith.

§ 1.2 Correlation and Intent of the Contract Documents

§ 1.2.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall be required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.

§ 1.2.1.1 The invalidity of any provision of the Contract Documents shall not invalidate the Contract or its remaining

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

provisions. If it is determined that any provision of the Contract Documents violates any law, or is otherwise invalid or unenforceable, then that provision shall be revised to the extent necessary to make that provision legal and enforceable. In such case the Contract Documents shall be construed, to the fullest extent permitted by law, to give effect to the parties' intentions and purposes in executing the Contract.

§ 1.2.2 Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade.

§ 1.2.3 Unless otherwise stated in the Contract Documents, words that have well-known technical or construction industry meanings are used in the Contract Documents in accordance with such recognized meanings.

§ 1.3 Capitalization

Terms capitalized in these General Conditions include those that are (1) specifically defined, (2) the titles of numbered articles, or (3) the titles of other documents published by the American Institute of Architects.

§ 1.4 Interpretation

In the interest of brevity the Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

§ 1.5 Ownership and Use of Drawings, Specifications, and Other Instruments of Service

§ 1.5.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service, including the Drawings and Specifications, and retain all common law, statutory, and other reserved rights in their Instruments of Service, including copyrights. The Contractor, Subcontractors, Sub-subcontractors, and suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of the Architect's or Architect's consultants' reserved rights.

§ 1.5.2 The Contractor, Subcontractors, Sub-subcontractors, and suppliers are authorized to use and reproduce the Instruments of Service provided to them, subject to any protocols established pursuant to Sections 1.7 and 1.8, solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Contractor, Subcontractors, Sub-subcontractors, and suppliers may not use the Instruments of Service on other projects or for additions to the Project outside the scope of the Work without the specific written consent of the Owner, Architect, and the Architect's consultants.

§ 1.6 Notice

§ 1.6.1 Except as otherwise provided in Section 1.6.2, where the Contract Documents require one party to notify or give notice to the other party, such notice shall be provided in writing to the designated representative of the party to whom the notice is addressed and shall be deemed to have been duly served if delivered in person, by mail, by courier, or by electronic transmission if a method for electronic transmission is set forth in the Agreement.

§ 1.6.2 Notice of Claims as provided in Section 15.1.3 shall be provided in writing and shall be deemed to have been duly served only if delivered to the designated representative of the party to whom the notice is addressed by certified or registered mail, or by courier providing proof of delivery.

§ 1.7 Digital Data Use and Transmission

The parties shall agree upon protocols governing the transmission and use of Instruments of Service or any other information or documentation in digital form. The parties will use AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, to establish the protocols for the development, use, transmission, and exchange of digital data.

§ 1.8 Building Information Models Use and Reliance

Any use of, or reliance on, all or a portion of a building information model without agreement to protocols governing the use of, and reliance on, the information contained in the model and without having those protocols set forth in AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, and the requisite AIA Document G202™–2013, Project Building Information Modeling Protocol Form, shall be at the using or relying party's sole risk and without liability to the other party and its contractors or consultants, the authors of, or contributors to, the building

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

information model, and each of their agents and employees.

ARTICLE 2 OWNER

§ 2.1 General

§ 2.1.1 The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization. Except as otherwise provided in Section 4.2.1, the Architect does not have such authority. The term "Owner" means the Owner or the Owner's authorized representative.

§ 2.1.2 The Owner shall furnish to the Contractor, within fifteen days after receipt of a written request, information necessary and relevant for the Contractor to evaluate, give notice of, or enforce mechanic's lien rights. Such information shall include a correct statement of the record legal title to the property on which the Project is located, usually referred to as the site, and the Owner's interest therein.

§ 2.2 Evidence of the Owner's Financial Arrangements

§ 2.2.1 Prior to commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract. The Contractor shall have no obligation to commence the Work until the Owner provides such evidence. If commencement of the Work is delayed under this Section 2.2.1, the Contract Time shall be extended appropriately.

§ 2.2.2 Following commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract only if (1) the Owner fails to make payments to the Contractor as the Contract Documents require; (2) the Contractor identifies in writing a reasonable concern regarding the Owner's ability to make payment when due; or (3) a change in the Work materially changes the Contract Sum. If the Owner fails to provide such evidence, as required, within fourteen days of the Contractor's request, the Contractor may immediately stop the Work and, in that event, shall notify the Owner that the Work has stopped. However, if the request is made because a change in the Work materially changes the Contract Sum under (3) above, the Contractor may immediately stop only that portion of the Work affected by the change until reasonable evidence is provided. If the Work is stopped under this Section 2.2.2, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided in the Contract Documents.

§ 2.2.3 After the Owner furnishes evidence of financial arrangements under this Section 2.2, the Owner shall not materially vary such financial arrangements without prior notice to the Contractor.

§ 2.2.4 Where the Owner has designated information furnished under this Section 2.2 as "confidential," the Contractor shall keep the information confidential and shall not disclose it to any other person. However, the Contractor may disclose "confidential" information, after seven (7) days' notice to the Owner, where disclosure is required by law, including a subpoena or other form of compulsory legal process issued by a court or governmental entity, or by court or arbitrator(s) order. The Contractor may also disclose "confidential" information to its employees, consultants, sureties, Subcontractors and their employees, Sub-subcontractors, and others who need to know the content of such information solely and exclusively for the Project and who agree to maintain the confidentiality of such information.

§ 2.3 Information and Services Required of the Owner

§ 2.3.1 Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, including those required under Section 3.7.1, the Owner shall secure and pay for necessary approvals, easements, assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.

§ 2.3.2 The Owner shall retain an architect lawfully licensed to practice architecture, or an entity lawfully practicing architecture, in the jurisdiction where the Project is located. That person or entity is identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.

§ 2.3.3 If the employment of the Architect terminates, the Owner shall employ a successor to whom the Contractor has no reasonable objection and whose status under the Contract Documents shall be that of the Architect.

§ 2.3.4 The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

site of the Project, and a legal description of the site. The Contractor shall be entitled to rely on the accuracy of information furnished by the Owner but shall exercise proper precautions relating to the safe performance of the Work.

§ 2.3.5 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall also furnish any other information or services under the Owner's control and relevant to the Contractor's performance of the Work with reasonable promptness after receiving the Contractor's written request for such information or services.

§ 2.3.6 Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor one copy of the Contract Documents for purposes of making reproductions pursuant to Section 1.5.2.

§ 2.4 Owner's Right to Stop the Work

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents as required by Section 12.2 or repeatedly fails to carry out Work in accordance with the Contract Documents, the Owner may issue a written order to the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work shall not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity, except to the extent required by Section 6.1.3.

§ 2.5 Owner's Right to Carry Out the Work

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such default or neglect. Such action by the Owner and amounts charged to the Contractor are both subject to prior approval of the Architect and the Architect may, pursuant to Section 9.5.1, withhold or nullify a Certificate for Payment in whole or in part, to the extent reasonably necessary to reimburse the Owner for the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect, or failure. If current and future payments are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner. If the Contractor disagrees with the actions of the Owner or the Architect, or the amounts claimed as costs to the Owner, the Contractor may file a Claim pursuant to Article 15.

ARTICLE 3 CONTRACTOR

§ 3.1 General

§ 3.1.1 The Contractor is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Contractor shall be lawfully licensed, if required in the jurisdiction where the Project is located. The Contractor shall designate in writing a representative who shall have express authority to bind the Contractor with respect to all matters under this Contract. The term "Contractor" means the Contractor or the Contractor's authorized representative.

§ 3.1.2 The Contractor shall perform the Work in accordance with the Contract Documents.

§ 3.1.3 The Contractor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals required or performed by persons or entities other than the Contractor.

§ 3.2 Review of Contract Documents and Field Conditions by Contractor

§ 3.2.1 Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become generally familiar with local conditions under which the Work is to be performed, and correlated personal observations with requirements of the Contract Documents.

§ 3.2.2 Because the Contract Documents are complementary, the Contractor shall, before starting each portion of the Work, carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 2.3.4, shall take field measurements of any existing conditions related to that portion of the Work, and shall observe any conditions at the site affecting it. These obligations are for the purpose of facilitating coordination and construction by the Contractor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Contractor shall promptly report to the Architect any errors, inconsistencies or omissions discovered by or made known to the Contractor as a request for information in such form as the Architect may require. It is recognized that the Contractor's review is made in the Contractor's

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

capacity as a contractor and not as a licensed design professional, unless otherwise specifically provided in the Contract Documents.

§ 3.2.3 The Contractor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Contractor shall promptly report to the Architect any nonconformity discovered by or made known to the Contractor as a request for information in such form as the Architect may require.

§ 3.2.4 If the Contractor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Contractor's notices or requests for information pursuant to Sections 3.2.2 or 3.2.3, the Contractor shall submit Claims as provided in Article 15. If the Contractor fails to perform the obligations of Sections 3.2.2 or 3.2.3, the Contractor shall pay such costs and damages to the Owner, subject to Section 15.1.7, as would have been avoided if the Contractor had performed such obligations. If the Contractor performs those obligations, the Contractor shall not be liable to the Owner or Architect for damages resulting from errors, inconsistencies or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

§ 3.3 Supervision and Construction Procedures

§ 3.3.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and have control over, construction means, methods, techniques, sequences, and procedures, and for coordinating all portions of the Work under the Contract. If the Contract Documents give specific instructions concerning construction means, methods, techniques, sequences, or procedures, the Contractor shall evaluate the jobsite safety thereof and shall be solely responsible for the jobsite safety of such means, methods, techniques, sequences, or procedures. If the Contractor determines that such means, methods, techniques, sequences or procedures may not be safe, the Contractor shall give timely notice to the Owner and Architect, and shall propose alternative means, methods, techniques, sequences, or procedures. The Architect shall evaluate the proposed alternative solely for conformance with the design intent for the completed construction. Unless the Architect objects to the Contractor's proposed alternative, the Contractor shall perform the Work using its alternative means, methods, techniques, sequences, or procedures.

§ 3.3.2 The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors.

§ 3.3.3 The Contractor shall be responsible for inspection of portions of Work already performed to determine that such portions are in proper condition to receive subsequent Work.

§ 3.4 Labor and Materials

§ 3.4.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

§ 3.4.2 Except in the case of minor changes in the Work approved by the Architect in accordance with Section 3.12.8 or ordered by the Architect in accordance with Section 7.4, the Contractor may make substitutions only with the consent of the Owner, after evaluation by the Architect and in accordance with a Change Order or Construction Change Directive.

§ 3.4.3 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

§ 3.5 Warranty

§ 3.5.1 The Contractor warrants to the Owner and Architect that materials and equipment furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Contractor further warrants that the Work will conform to the requirements of the Contract Documents and will be free from defects, except for those inherent in the quality of the Work the Contract Documents require or permit. Work, materials, or equipment not conforming to these requirements may be considered defective. The Contractor's warranty excludes

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage. If required by the Architect, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

§ 3.5.2 All material, equipment, or other special warranties required by the Contract Documents shall be issued in the name of the Owner, or shall be transferable to the Owner, and shall commence in accordance with Section 9.8.4.

§ 3.6 Taxes

The Contractor shall pay sales, consumer, use and similar taxes for the Work provided by the Contractor that are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

§ 3.7 Permits, Fees, Notices and Compliance with Laws

§ 3.7.1 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for the building permit as well as for other permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or negotiations concluded.

§ 3.7.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work.

§ 3.7.3 If the Contractor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Contractor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.

§ 3.7.4 Concealed or Unknown Conditions

If the Contractor encounters conditions at the site that are (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or (2) unknown physical conditions of an unusual nature that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall promptly provide notice to the Owner and the Architect before conditions are disturbed and in no event later than 14 days after first observance of the conditions. The Architect will promptly investigate such conditions and, if the Architect determines that they differ materially and cause an increase or decrease in the Contractor's cost of, or time required for, performance of any part of the Work, will recommend that an equitable adjustment be made in the Contract Sum or Contract Time, or both. If the Architect determines that the conditions at the site are not materially different from those indicated in the Contract Documents and that no change in the terms of the Contract is justified, the Architect shall promptly notify the Owner and Contractor, stating the reasons. If either party disputes the Architect's determination or recommendation, that party may submit a Claim as provided in Article 15.

§ 3.7.5 If, in the course of the Work, the Contractor encounters human remains or recognizes the existence of burial markers, archaeological sites or wetlands not indicated in the Contract Documents, the Contractor shall immediately suspend any operations that would affect them and shall notify the Owner and Architect. Upon receipt of such notice, the Owner shall promptly take any action necessary to obtain governmental authorization required to resume the operations. The Contractor shall continue to suspend such operations until otherwise instructed by the Owner but shall continue with all other operations that do not affect those remains or features. Requests for adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 15.

§ 3.8 Allowances

§ 3.8.1 The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as the Owner may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

§ 3.8.2 Unless otherwise provided in the Contract Documents,

.1 allowances shall cover the cost to the Contractor of materials and equipment delivered at the site and all required taxes, less applicable trade discounts;

.2 Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit, and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowances; and

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

.3 whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect (1) the difference between actual costs and the allowances under Section 3.8.2.1 and (2) changes in Contractor's costs under Section 3.8.2.2.

§ 3.8.3 Materials and equipment under an allowance shall be selected by the Owner with reasonable promptness.

§ 3.9 Superintendent

§ 3.9.1 The Contractor shall employ a competent superintendent and necessary assistants who shall be in attendance at the Project site during performance of the Work. The superintendent shall represent the Contractor, and communications given to the superintendent shall be as binding as if given to the Contractor.

§ 3.9.2 The Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the name and qualifications of a proposed superintendent. Within 14 days of receipt of the information, the Architect may notify the Contractor, stating whether the Owner or the Architect (1) has reasonable objection to the proposed superintendent or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 3.9.3 The Contractor shall not employ a proposed superintendent to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not change the superintendent without the Owner's consent, which shall not unreasonably be withheld or delayed.

§ 3.10 Contractor's Construction and Submittal Schedules

§ 3.10.1 The Contractor, promptly after being awarded the Contract, shall submit for the Owner's and Architect's information a Contractor's construction schedule for the Work. The schedule shall contain detail appropriate for the Project, including (1) the date of commencement of the Work, interim schedule milestone dates, and the date of Substantial Completion; (2) an apportionment of the Work by construction activity; and (3) the time required for completion of each portion of the Work. The schedule shall provide for the orderly progression of the Work to completion and shall not exceed time limits current under the Contract Documents. The schedule shall be revised at appropriate intervals as required by the conditions of the Work and Project.

§ 3.10.2 The Contractor, promptly after being awarded the Contract and thereafter as necessary to maintain a current submittal schedule, shall submit a submittal schedule for the Architect's approval. The Architect's approval shall not be unreasonably delayed or withheld. The submittal schedule shall (1) be coordinated with the Contractor's construction schedule, and (2) allow the Architect reasonable time to review submittals. If the Contractor fails to submit a submittal schedule, or fails to provide submittals in accordance with the approved submittal schedule, the Contractor shall not be entitled to any increase in Contract Sum or extension of Contract Time based on the time required for review of submittals.

§ 3.10.3 The Contractor shall perform the Work in general accordance with the most recent schedules submitted to the Owner and Architect.

§ 3.11 Documents and Samples at the Site

The Contractor shall make available, at the Project site, the Contract Documents, including Change Orders, Construction Change Directives, and other Modifications, in good order and marked currently to indicate field changes and selections made during construction, and the approved Shop Drawings, Product Data, Samples, and similar required submittals. These shall be in electronic form or paper copy, available to the Architect and Owner, and delivered to the Architect for submittal to the Owner upon completion of the Work as a record of the Work as constructed.

§ 3.12 Shop Drawings, Product Data and Samples

§ 3.12.1 Shop Drawings are drawings, diagrams, schedules, and other data specially prepared for the Work by the Contractor or a Subcontractor, Sub-subcontractor, manufacturer, supplier, or distributor to illustrate some portion of the Work.

§ 3.12.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.

§ 3.12.3 Samples are physical examples that illustrate materials, equipment, or workmanship, and establish standards by which the Work will be judged.

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 3.12.4 Shop Drawings, Product Data, Samples, and similar submittals are not Contract Documents. Their purpose is to demonstrate how the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents for those portions of the Work for which the Contract Documents require submittals. Review by the Architect is subject to the limitations of Section 4.2.7. Informational submittals upon which the Architect is not expected to take responsive action may be so identified in the Contract Documents. Submittals that are not required by the Contract Documents may be returned by the Architect without action.

§ 3.12.5 The Contractor shall review for compliance with the Contract Documents, approve, and submit to the Architect, Shop Drawings, Product Data, Samples, and similar submittals required by the Contract Documents, in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Owner or of Separate Contractors.

§ 3.12.6 By submitting Shop Drawings, Product Data, Samples, and similar submittals, the Contractor represents to the Owner and Architect that the Contractor has (1) reviewed and approved them, (2) determined and verified materials, field measurements and field construction criteria related thereto, or will do so, and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

§ 3.12.7 The Contractor shall perform no portion of the Work for which the Contract Documents require submittal and review of Shop Drawings, Product Data, Samples, or similar submittals, until the respective submittal has been approved by the Architect.

§ 3.12.8 The Work shall be in accordance with approved submittals except that the Contractor shall not be relieved of responsibility for deviations from the requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples, or similar submittals, unless the Contractor has specifically notified the Architect of such deviation at the time of submittal and (1) the Architect has given written approval to the specific deviation as a minor change in the Work, or (2) a Change Order or Construction Change Directive has been issued authorizing the deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals, by the Architect's approval thereof.

§ 3.12.9 The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples, or similar submittals, to revisions other than those requested by the Architect on previous submittals. In the absence of such notice, the Architect's approval of a resubmission shall not apply to such revisions.

§ 3.12.10 The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences, and procedures. The Contractor shall not be required to provide professional services in violation of applicable law.

§ 3.12.10.1 If professional design services or certifications by a design professional related to systems, materials, or equipment are specifically required of the Contractor by the Contract Documents, the Owner and the Architect will specify all performance and design criteria that such services must satisfy. The Contractor shall be entitled to rely upon the adequacy and accuracy of the performance and design criteria provided in the Contract Documents. The Contractor shall cause such services or certifications to be provided by an appropriately licensed design professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings, and other submittals prepared by such professional. Shop Drawings, and other submittals related to the Work, designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to the Architect. The Owner and the Architect shall be entitled to rely upon the adequacy and accuracy of the services, certifications, and approvals performed or provided by such design professionals, provided the Owner and Architect have specified to the Contractor the performance and design criteria that such services must satisfy. Pursuant to this Section 3.12.10, the Architect will review and approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents.

§ 3.12.10.2 If the Contract Documents require the Contractor's design professional to certify that the Work has been performed in accordance with the design criteria, the Contractor shall furnish such certifications to the Architect at the

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

time and in the form specified by the Architect.

§ 3.13 Use of Site

The Contractor shall confine operations at the site to areas permitted by applicable laws, statutes, ordinances, codes, rules and regulations, lawful orders of public authorities, and the Contract Documents and shall not unreasonably encumber the site with materials or equipment.

§ 3.14 Cutting and Patching

§ 3.14.1 The Contractor shall be responsible for cutting, fitting, or patching required to complete the Work or to make its parts fit together properly. All areas requiring cutting, fitting, or patching shall be restored to the condition existing prior to the cutting, fitting, or patching, unless otherwise required by the Contract Documents.

§ 3.14.2 The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or Separate Contractors by cutting, patching, or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter construction by the Owner or a Separate Contractor except with written consent of the Owner and of the Separate Contractor. Consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold, from the Owner or a Separate Contractor, its consent to cutting or otherwise altering the Work.

§ 3.15 Cleaning Up

§ 3.15.1 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials and rubbish caused by operations under the Contract. At completion of the Work, the Contractor shall remove waste materials, rubbish, the Contractor's tools, construction equipment, machinery, and surplus materials from and about the Project.

§ 3.15.2 If the Contractor fails to clean up as provided in the Contract Documents, the Owner may do so and the Owner shall be entitled to reimbursement from the Contractor.

§ 3.16 Access to Work

The Contractor shall provide the Owner and Architect with access to the Work in preparation and progress wherever located.

§ 3.17 Royalties, Patents and Copyrights

The Contractor shall pay all royalties and license fees. The Contractor shall defend suits or claims for infringement of copyrights and patent rights and shall hold the Owner and Architect harmless from loss on account thereof, but shall not be responsible for defense or loss when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents, or where the copyright violations are contained in Drawings, Specifications, or other documents prepared by the Owner or Architect. However, if an infringement of a copyright or patent is discovered by, or made known to, the Contractor, the Contractor shall be responsible for the loss unless the information is promptly furnished to the Architect.

§ 3.18 Indemnification

§ 3.18.1 To the fullest extent permitted by law, the Contractor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Section 3.18.

§ 3.18.2 In claims against any person or entity indemnified under this Section 3.18 by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 3.18.1 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts, or other employee benefit acts.

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

ARTICLE 4 ARCHITECT

§ 4.1 General

§ 4.1.1 The Architect is the person or entity retained by the Owner pursuant to Section 2.3.2 and identified as such in the Agreement.

§ 4.1.2 Duties, responsibilities, and limitations of authority of the Architect as set forth in the Contract Documents shall not be restricted, modified, or extended without written consent of the Owner, Contractor, and Architect. Consent shall not be unreasonably withheld.

§ 4.2 Administration of the Contract

§ 4.2.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during construction until the date the Architect issues the final Certificate for Payment. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents.

§ 4.2.2 The Architect will visit the site at intervals appropriate to the stage of construction, or as otherwise agreed with the Owner, to become generally familiar with the progress and quality of the portion of the Work completed, and to determine in general if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. However, the Architect will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work. The Architect will not have control over, charge of, or responsibility for the construction means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the Work, since these are solely the Contractor's rights and responsibilities under the Contract Documents.

§ 4.2.3 On the basis of the site visits, the Architect will keep the Owner reasonably informed about the progress and quality of the portion of the Work completed, and promptly report to the Owner (1) known deviations from the Contract Documents, (2) known deviations from the most recent construction schedule submitted by the Contractor, and (3) defects and deficiencies observed in the Work. The Architect will not be responsible for the Contractor's failure to perform the Work in accordance with the requirements of the Contract Documents. The Architect will not have control over or charge of, and will not be responsible for acts or omissions of, the Contractor, Subcontractors, or their agents or employees, or any other persons or entities performing portions of the Work.

§ 4.2.4 Communications

The Owner and Contractor shall include the Architect in all communications that relate to or affect the Architect's services or professional responsibilities. The Owner shall promptly notify the Architect of the substance of any direct communications between the Owner and the Contractor otherwise relating to the Project. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with Subcontractors and suppliers shall be through the Contractor. Communications by and with Separate Contractors shall be through the Owner. The Contract Documents may specify other communication protocols.

§ 4.2.5 Based on the Architect's evaluations of the Contractor's Applications for Payment, the Architect will review and certify the amounts due the Contractor and will issue Certificates for Payment in such amounts.

§ 4.2.6 The Architect has authority to reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable, the Architect will have authority to require inspection or testing of the Work in accordance with Sections 13.4.2 and 13.4.3, whether or not the Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, suppliers, their agents or employees, or other persons or entities performing portions of the Work.

§ 4.2.7 The Architect will review and approve, or take other appropriate action upon, the Contractor's submittals such as Shop Drawings, Product Data, and Samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Architect's action will be taken in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness while allowing sufficient time in the Architect's professional judgment to permit adequate review. Review of such submittals is not conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of the Contractor as required by the Contract Documents. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Sections 3.3, 3.5, and 3.12. The Architect's review shall not constitute approval of safety precautions or of any construction means, methods, techniques, sequences, or procedures. The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.

§ 4.2.8 The Architect will prepare Change Orders and Construction Change Directives, and may order minor changes in the Work as provided in Section 7.4. The Architect will investigate and make determinations and recommendations regarding concealed and unknown conditions as provided in Section 3.7.4.

§ 4.2.9 The Architect will conduct inspections to determine the date or dates of Substantial Completion and the date of final completion; issue Certificates of Substantial Completion pursuant to Section 9.8; receive and forward to the Owner, for the Owner's review and records, written warranties and related documents required by the Contract and assembled by the Contractor pursuant to Section 9.10; and issue a final Certificate for Payment pursuant to Section 9.10.

§ 4.2.10 If the Owner and Architect agree, the Architect will provide one or more Project representatives to assist in carrying out the Architect's responsibilities at the site. The Owner shall notify the Contractor of any change in the duties, responsibilities and limitations of authority of the Project representatives.

§ 4.2.11 The Architect will interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness.

§ 4.2.12 Interpretations and decisions of the Architect will be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. When making such interpretations and decisions, the Architect will endeavor to secure faithful performance by both Owner and Contractor, will not show partiality to either, and will not be liable for results of interpretations or decisions rendered in good faith.

§ 4.2.13 The Architect's decisions on matters relating to aesthetic effect will be final if consistent with the intent expressed in the Contract Documents.

§ 4.2.14 The Architect will review and respond to requests for information about the Contract Documents. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information.

ARTICLE 5 SUBCONTRACTORS

§ 5.1 Definitions

§ 5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform a portion of the Work at the site. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or an authorized representative of the Subcontractor. The term "Subcontractor" does not include a Separate Contractor or the subcontractors of a Separate Contractor.

§ 5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform a portion of the Work at the site. The term "Sub-subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Sub-subcontractor or an authorized representative of the Sub-subcontractor.

§ 5.2 Award of Subcontracts and Other Contracts for Portions of the Work

§ 5.2.1 Unless otherwise stated in the Contract Documents, the Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the persons or entities proposed for each principal portion of the Work, including those who are to furnish materials or equipment fabricated to a special design. Within 14 days of receipt of the information, the Architect may notify the Contractor whether the Owner or the Architect (1) has reasonable objection to any such proposed person or entity or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 5.2.2 The Contractor shall not contract with a proposed person or entity to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not be required to contract with anyone to whom the Contractor has made reasonable objection.

§ 5.2.3 If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Contractor shall propose another to whom the Owner or Architect has no reasonable objection. If the proposed but rejected Subcontractor was reasonably capable of performing the Work, the Contract Sum and Contract Time shall be increased or decreased by the difference, if any, occasioned by such change, and an appropriate Change Order shall be issued before commencement of the substitute Subcontractor's Work. However, no increase in the Contract Sum or Contract Time shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.

§ 5.2.4 The Contractor shall not substitute a Subcontractor, person, or entity for one previously selected if the Owner or Architect makes reasonable objection to such substitution.

§ 5.3 Subcontractual Relations

By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work that the Contractor, by these Contract Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the subcontract agreement, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.

§ 5.4 Contingent Assignment of Subcontracts

§ 5.4.1 Each subcontract agreement for a portion of the Work is assigned by the Contractor to the Owner, provided that

.1 assignment is effective only after termination of the Contract by the Owner for cause pursuant to Section 14.2 and only for those subcontract agreements that the Owner accepts by notifying the Subcontractor and Contractor; and

.2 assignment is subject to the prior rights of the surety, if any, obligated under bond relating to the Contract.

When the Owner accepts the assignment of a subcontract agreement, the Owner assumes the Contractor's rights and obligations under the subcontract.

§ 5.4.2 Upon such assignment, if the Work has been suspended for more than 30 days, the Subcontractor's compensation shall be equitably adjusted for increases in cost resulting from the suspension.

§ 5.4.3 Upon assignment to the Owner under this Section 5.4, the Owner may further assign the subcontract to a successor contractor or other entity. If the Owner assigns the subcontract to a successor contractor or other entity, the Owner shall nevertheless remain legally responsible for all of the successor contractor's obligations under the subcontract.

ARTICLE 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

§ 6.1 Owner's Right to Perform Construction and to Award Separate Contracts

§ 6.1.1 The term "Separate Contractor(s)" shall mean other contractors retained by the Owner under separate agreements. The Owner reserves the right to perform construction or operations related to the Project with the Owner's own forces, and with Separate Contractors retained under Conditions of the Contract substantially similar to those of this Contract, including those provisions of the Conditions of the Contract related to insurance and waiver of subrogation.

§ 6.1.2 When separate contracts are awarded for different portions of the Project or other construction or operations on the site, the term "Contractor" in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.

§ 6.1.3 The Owner shall provide for coordination of the activities of the Owner's own forces and of each Separate

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Contractor with the Work of the Contractor, who shall cooperate with them. The Contractor shall participate with any Separate Contractors and the Owner in reviewing their construction schedules. The Contractor shall make any revisions to its construction schedule deemed necessary after a joint review and mutual agreement. The construction schedules shall then constitute the schedules to be used by the Contractor, Separate Contractors, and the Owner until subsequently revised.

§ 6.1.4 Unless otherwise provided in the Contract Documents, when the Owner performs construction or operations related to the Project with the Owner's own forces or with Separate Contractors, the Owner or its Separate Contractors shall have the same obligations and rights that the Contractor has under the Conditions of the Contract, including, without excluding others, those stated in Article 3, this Article 6, and Articles 10, 11, and 12.

§ 6.2 Mutual Responsibility

§ 6.2.1 The Contractor shall afford the Owner and Separate Contractors reasonable opportunity for introduction and storage of their materials and equipment and performance of their activities, and shall connect and coordinate the Contractor's construction and operations with theirs as required by the Contract Documents.

§ 6.2.2 If part of the Contractor's Work depends for proper execution or results upon construction or operations by the Owner or a Separate Contractor, the Contractor shall, prior to proceeding with that portion of the Work, promptly notify the Architect of apparent discrepancies or defects in the construction or operations by the Owner or Separate Contractor that would render it unsuitable for proper execution and results of the Contractor's Work. Failure of the Contractor to notify the Architect of apparent discrepancies or defects prior to proceeding with the Work shall constitute an acknowledgment that the Owner's or Separate Contractor's completed or partially completed construction is fit and proper to receive the Contractor's Work. The Contractor shall not be responsible for discrepancies or defects in the construction or operations by the Owner or Separate Contractor that are not apparent.

§ 6.2.3 The Contractor shall reimburse the Owner for costs the Owner incurs that are payable to a Separate Contractor because of the Contractor's delays, improperly timed activities or defective construction. The Owner shall be responsible to the Contractor for costs the Contractor incurs because of a Separate Contractor's delays, improperly timed activities, damage to the Work or defective construction.

§ 6.2.4 The Contractor shall promptly remedy damage that the Contractor wrongfully causes to completed or partially completed construction or to property of the Owner or Separate Contractor as provided in Section 10.2.5.

§ 6.2.5 The Owner and each Separate Contractor shall have the same responsibilities for cutting and patching as are described for the Contractor in Section 3.14.

§ 6.3 Owner's Right to Clean Up

If a dispute arises among the Contractor, Separate Contractors, and the Owner as to the responsibility under their respective contracts for maintaining the premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 7 CHANGES IN THE WORK

§ 7.1 General

§ 7.1.1 Changes in the Work may be accomplished after execution of the Contract, and without invalidating the Contract, by Change Order, Construction Change Directive or order for a minor change in the Work, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents.

§ 7.1.2 A Change Order shall be based upon agreement among the Owner, Contractor, and Architect. A Construction Change Directive requires agreement by the Owner and Architect and may or may not be agreed to by the Contractor. An order for a minor change in the Work may be issued by the Architect alone.

§ 7.1.3 Changes in the Work shall be performed under applicable provisions of the Contract Documents. The Contractor shall proceed promptly with changes in the Work, unless otherwise provided in the Change Order, Construction Change Directive, or order for a minor change in the Work.

§ 7.2 Change Orders

§ 7.2.1 A Change Order is a written instrument prepared by the Architect and signed by the Owner, Contractor, and Architect stating their agreement upon all of the following:

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

.1 The change in the Work;
.2 The amount of the adjustment, if any, in the Contract Sum; and
.3 The extent of the adjustment, if any, in the Contract Time.

§ 7.3 Construction Change Directives

§ 7.3.1 A Construction Change Directive is a written order prepared by the Architect and signed by the Owner and Architect, directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions, or other revisions, the Contract Sum and Contract Time being adjusted accordingly.

§ 7.3.2 A Construction Change Directive shall be used in the absence of total agreement on the terms of a Change Order.

§ 7.3.3 If the Construction Change Directive provides for an adjustment to the Contract Sum, the adjustment shall be based on one of the following methods:

.1 Mutual acceptance of a lump sum properly itemized and supported by sufficient substantiating data to permit evaluation;
.2 Unit prices stated in the Contract Documents or subsequently agreed upon;
.3 Cost to be determined in a manner agreed upon by the parties and a mutually acceptable fixed or percentage fee; or
.4 As provided in Section 7.3.4.

§ 7.3.4 If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall determine the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in the Agreement, or if no such amount is set forth in the Agreement, a reasonable amount. In such case, and also under Section 7.3.3.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.4 shall be limited to the following:

.1 Costs of labor, including applicable payroll taxes, fringe benefits required by agreement or custom, workers' compensation insurance, and other employee costs approved by the Architect;
.2 Costs of materials, supplies, and equipment, including cost of transportation, whether incorporated or consumed;
.3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others;
.4 Costs of premiums for all bonds and insurance, permit fees, and sales, use, or similar taxes, directly related to the change; and
.5 Costs of supervision and field office personnel directly attributable to the change.

§ 7.3.5 If the Contractor disagrees with the adjustment in the Contract Time, the Contractor may make a Claim in accordance with applicable provisions of Article 15.

§ 7.3.6 Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.

§ 7.3.7 A Construction Change Directive signed by the Contractor indicates the Contractor's agreement therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.

§ 7.3.8 The amount of credit to be allowed by the Contractor to the Owner for a deletion or change that results in a net decrease in the Contract Sum shall be actual net cost as confirmed by the Architect. When both additions and credits covering related Work or substitutions are involved in a change, the allowance for overhead and profit shall be figured on the basis of net increase, if any, with respect to that change.

§ 7.3.9 Pending final determination of the total cost of a Construction Change Directive to the Owner, the Contractor may request payment for Work completed under the Construction Change Directive in Applications for Payment. The

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Architect will make an interim determination for purposes of monthly certification for payment for those costs and certify for payment the amount that the Architect determines, in the Architect's professional judgment, to be reasonably justified. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15.

§ 7.3.10 When the Owner and Contractor agree with a determination made by the Architect concerning the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately and the Architect will prepare a Change Order. Change Orders may be issued for all or any part of a Construction Change Directive.

§ 7.4 Minor Changes in the Work

The Architect may order minor changes in the Work that are consistent with the intent of the Contract Documents and do not involve an adjustment in the Contract Sum or an extension of the Contract Time. The Architect's order for minor changes shall be in writing. If the Contractor believes that the proposed minor change in the Work will affect the Contract Sum or Contract Time, the Contractor shall notify the Architect and shall not proceed to implement the change in the Work. If the Contractor performs the Work set forth in the Architect's order for a minor change without prior notice to the Architect that such change will affect the Contract Sum or Contract Time, the Contractor waives any adjustment to the Contract Sum or extension of the Contract Time.

ARTICLE 8 TIME

§ 8.1 Definitions

§ 8.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for Substantial Completion of the Work.

§ 8.1.2 The date of commencement of the Work is the date established in the Agreement.

§ 8.1.3 The date of Substantial Completion is the date certified by the Architect in accordance with Section 9.8.

§ 8.1.4 The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

§ 8.2 Progress and Completion

§ 8.2.1 Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Agreement, the Contractor confirms that the Contract Time is a reasonable period for performing the Work.

§ 8.2.2 The Contractor shall not knowingly, except by agreement or instruction of the Owner in writing, commence the Work prior to the effective date of insurance required to be furnished by the Contractor and Owner.

§ 8.2.3 The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

§ 8.3 Delays and Extensions of Time

§ 8.3.1 If the Contractor is delayed at any time in the commencement or progress of the Work by (1) an act or neglect of the Owner or Architect, of an employee of either, or of a Separate Contractor; (2) by changes ordered in the Work; (3) by labor disputes, fire, unusual delay in deliveries, unavoidable casualties, adverse weather conditions documented in accordance with Section 15.1.6.2, or other causes beyond the Contractor's control; (4) by delay authorized by the Owner pending mediation and binding dispute resolution; or (5) by other causes that the Contractor asserts, and the Architect determines, justify delay, then the Contract Time shall be extended for such reasonable time as the Architect may determine.

§ 8.3.2 Claims relating to time shall be made in accordance with applicable provisions of Article 15.

§ 8.3.3 This Section 8.3 does not preclude recovery of damages for delay by either party under other provisions of the Contract Documents.

ARTICLE 9 PAYMENTS AND COMPLETION

§ 9.1 Contract Sum

§ 9.1.1 The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

by the Owner to the Contractor for performance of the Work under the Contract Documents.

§ 9.1.2 If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed so that application of such unit prices to the actual quantities causes substantial inequity to the Owner or Contractor, the applicable unit prices shall be equitably adjusted.

§ 9.2 Schedule of Values

Where the Contract is based on a stipulated sum or Guaranteed Maximum Price, the Contractor shall submit a schedule of values to the Architect before the first Application for Payment, allocating the entire Contract Sum to the various portions of the Work. The schedule of values shall be prepared in the form, and supported by the data to substantiate its accuracy, required by the Architect. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. Any changes to the schedule of values shall be submitted to the Architect and supported by such data to substantiate its accuracy as the Architect may require, and unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's subsequent Applications for Payment.

§ 9.3 Applications for Payment

§ 9.3.1 At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2, for completed portions of the Work. The application shall be notarized, if required, and supported by all data substantiating the Contractor's right to payment that the Owner or Architect require, such as copies of requisitions, and releases and waivers of liens from Subcontractors and suppliers, and shall reflect retainage if provided for in the Contract Documents.

§ 9.3.1.1 As provided in Section 7.3.9, such applications may include requests for payment on account of changes in the Work that have been properly authorized by Construction Change Directives, or by interim determinations of the Architect, but not yet included in Change Orders.

§ 9.3.1.2 Applications for Payment shall not include requests for payment for portions of the Work for which the Contractor does not intend to pay a Subcontractor or supplier, unless such Work has been performed by others whom the Contractor intends to pay.

§ 9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the Owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing. Payment for materials and equipment stored on or off the site shall be conditioned upon compliance by the Contractor with procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, and shall include the costs of applicable insurance, storage, and transportation to the site, for such materials and equipment stored off the site.

§ 9.3.3 The Contractor warrants that title to all Work covered by an Application for Payment will pass to the Owner no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment all Work for which Certificates for Payment have been previously issued and payments received from the Owner shall, to the best of the Contractor's knowledge, information, and belief, be free and clear of liens, claims, security interests, or encumbrances, in favor of the Contractor, Subcontractors, suppliers, or other persons or entities that provided labor, materials, and equipment relating to the Work.

§ 9.4 Certificates for Payment

§ 9.4.1 The Architect will, within seven days after receipt of the Contractor's Application for Payment, either (1) issue to the Owner a Certificate for Payment in the full amount of the Application for Payment, with a copy to the Contractor; or (2) issue to the Owner a Certificate for Payment for such amount as the Architect determines is properly due, and notify the Contractor and Owner of the Architect's reasons for withholding certification in part as provided in Section 9.5.1; or (3) withhold certification of the entire Application for Payment, and notify the Contractor and Owner of the Architect's reason for withholding certification in whole as provided in Section 9.5.1.

§ 9.4.2 The issuance of a Certificate for Payment will constitute a representation by the Architect to the Owner, based on the Architect's evaluation of the Work and the data in the Application for Payment, that, to the best of the Architect's knowledge, information, and belief, the Work has progressed to the point indicated, the quality of the Work is in accordance with the Contract Documents, and that the Contractor is entitled to payment in the amount certified. The

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

foregoing representations are subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to results of subsequent tests and inspections, to correction of minor deviations from the Contract Documents prior to completion, and to specific qualifications expressed by the Architect. However, the issuance of a Certificate for Payment will not be a representation that the Architect has (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work; (2) reviewed construction means, methods, techniques, sequences, or procedures; (3) reviewed copies of requisitions received from Subcontractors and suppliers and other data requested by the Owner to substantiate the Contractor's right to payment; or (4) made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

§ 9.5 Decisions to Withhold Certification

§ 9.5.1 The Architect may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the Owner, if in the Architect's opinion the representations to the Owner required by Section 9.4.2 cannot be made. If the Architect is unable to certify payment in the amount of the Application, the Architect will notify the Contractor and Owner as provided in Section 9.4.1. If the Contractor and Architect cannot agree on a revised amount, the Architect will promptly issue a Certificate for Payment for the amount for which the Architect is able to make such representations to the Owner. The Architect may also withhold a Certificate for Payment or, because of subsequently discovered evidence, may nullify the whole or a part of a Certificate for Payment previously issued, to such extent as may be necessary in the Architect's opinion to protect the Owner from loss for which the Contractor is responsible, including loss resulting from acts and omissions described in Section 3.3.2, because of

- .1 defective Work not remedied;
- .2 third party claims filed or reasonable evidence indicating probable filing of such claims, unless security acceptable to the Owner is provided by the Contractor;
- .3 failure of the Contractor to make payments properly to Subcontractors or suppliers for labor, materials or equipment;
- .4 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
- .5 damage to the Owner or a Separate Contractor;
- .6 reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages for the anticipated delay; or
- .7 repeated failure to carry out the Work in accordance with the Contract Documents.

§ 9.5.2 When either party disputes the Architect's decision regarding a Certificate for Payment under Section 9.5.1, in whole or in part, that party may submit a Claim in accordance with Article 15.

§ 9.5.3 When the reasons for withholding certification are removed, certification will be made for amounts previously withheld.

§ 9.5.4 If the Architect withholds certification for payment under Section 9.5.1.3, the Owner may, at its sole option, issue joint checks to the Contractor and to any Subcontractor or supplier to whom the Contractor failed to make payment for Work properly performed or material or equipment suitably delivered. If the Owner makes payments by joint check, the Owner shall notify the Architect and the Contractor shall reflect such payment on its next Application for Payment.

§ 9.6 Progress Payments

§ 9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment in the manner and within the time provided in the Contract Documents, and shall so notify the Architect.

§ 9.6.2 The Contractor shall pay each Subcontractor, no later than seven days after receipt of payment from the Owner, the amount to which the Subcontractor is entitled, reflecting percentages actually retained from payments to the Contractor on account of the Subcontractor's portion of the Work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in a similar manner.

§ 9.6.3 The Architect will, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by the Contractor and action taken thereon by the Architect and Owner on account of portions of the Work done by such Subcontractor.

§ 9.6.4 The Owner has the right to request written evidence from the Contractor that the Contractor has properly paid Subcontractors and suppliers amounts paid by the Owner to the Contractor for subcontracted Work. If the Contractor fails to furnish such evidence within seven days, the Owner shall have the right to contact Subcontractors and suppliers

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

to ascertain whether they have been properly paid. Neither the Owner nor Architect shall have an obligation to pay, or to see to the payment of money to, a Subcontractor or supplier, except as may otherwise be required by law.

§ 9.6.5 The Contractor's payments to suppliers shall be treated in a manner similar to that provided in Sections 9.6.2, 9.6.3 and 9.6.4.

§ 9.6.6 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

§ 9.6.7 Unless the Contractor provides the Owner with a payment bond in the full penal sum of the Contract Sum, payments received by the Contractor for Work properly performed by Subcontractors or provided by suppliers shall be held by the Contractor for those Subcontractors or suppliers who performed Work or furnished materials, or both, under contract with the Contractor for which payment was made by the Owner. Nothing contained herein shall require money to be placed in a separate account and not commingled with money of the Contractor, create any fiduciary liability or tort liability on the part of the Contractor for breach of trust, or entitle any person or entity to an award of punitive damages against the Contractor for breach of the requirements of this provision.

§ 9.6.8 Provided the Owner has fulfilled its payment obligations under the Contract Documents, the Contractor shall defend and indemnify the Owner from all loss, liability, damage or expense, including reasonable attorney's fees and litigation expenses, arising out of any lien claim or other claim for payment by any Subcontractor or supplier of any tier. Upon receipt of notice of a lien claim or other claim for payment, the Owner shall notify the Contractor. If approved by the applicable court, when required, the Contractor may substitute a surety bond for the property against which the lien or other claim for payment has been asserted.

§ 9.7 Failure of Payment

If the Architect does not issue a Certificate for Payment, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the date established in the Contract Documents, the amount certified by the Architect or awarded by binding dispute resolution, then the Contractor may, upon seven additional days' notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided for in the Contract Documents.

§ 9.8 Substantial Completion

§ 9.8.1 Substantial Completion is the stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use.

§ 9.8.2 When the Contractor considers that the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

§ 9.8.3 Upon receipt of the Contractor's list, the Architect will make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion.

§ 9.8.4 When the Work or designated portion thereof is substantially complete, the Architect will prepare a Certificate of Substantial Completion that shall establish the date of Substantial Completion; establish responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work and insurance; and fix the time within which the Contractor shall finish all items on the list accompanying the Certificate. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion.

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 9.8.5 The Certificate of Substantial Completion shall be submitted to the Owner and Contractor for their written acceptance of responsibilities assigned to them in the Certificate. Upon such acceptance, and consent of surety if any, the Owner shall make payment of retainage applying to the Work or designated portion thereof. Such payment shall be adjusted for Work that is incomplete or not in accordance with the requirements of the Contract Documents.

§ 9.9 Partial Occupancy or Use

§ 9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer and authorized by public authorities having jurisdiction over the Project. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner and Contractor or, if no agreement is reached, by decision of the Architect.

§ 9.9.2 Immediately prior to such partial occupancy or use, the Owner, Contractor, and Architect shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

§ 9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

§ 9.10 Final Completion and Final Payment

§ 9.10.1 Upon receipt of the Contractor's notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect will promptly make such inspection. When the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled.

§ 9.10.2 Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect, (3) a written statement that the Contractor knows of no reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment, (5) documentation of any special warranties, such as manufacturers' warranties or specific Subcontractor warranties, and (6) if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts and releases and waivers of liens, claims, security interests, or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner. If a Subcontractor refuses to furnish a release or waiver required by the Owner, the Contractor may furnish a bond satisfactory to the Owner to indemnify the Owner against such lien, claim, security interest, or encumbrance. If a lien, claim, security interest, or encumbrance remains unsatisfied after payments are made, the Contractor shall refund to the Owner all money that the Owner may be compelled to pay in discharging the lien, claim, security interest, or encumbrance, including all costs and reasonable attorneys' fees.

§ 9.10.3 If, after Substantial Completion of the Work, final completion thereof is materially delayed through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed, corrected, and accepted. If the remaining balance for Work not fully completed or corrected is less than retainage stipulated in the Contract Documents, and if bonds have been furnished, the written consent of the surety to payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

constitute a waiver of Claims.

§ 9.10.4 The making of final payment shall constitute a waiver of Claims by the Owner except those arising from

.1 liens, Claims, security interests, or encumbrances arising out of the Contract and unsettled;
.2 failure of the Work to comply with the requirements of the Contract Documents;
.3 terms of special warranties required by the Contract Documents; or
.4 audits performed by the Owner, if permitted by the Contract Documents, after final payment.

§ 9.10.5 Acceptance of final payment by the Contractor, a Subcontractor, or a supplier, shall constitute a waiver of claims by that payee except those previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY

§ 10.1 Safety Precautions and Programs

The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract.

§ 10.2 Safety of Persons and Property

§ 10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury, or loss to

.1 employees on the Work and other persons who may be affected thereby;
.2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor, a Subcontractor, or a Sub-subcontractor; and
.3 other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.

§ 10.2.2 The Contractor shall comply with, and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities, bearing on safety of persons or property or their protection from damage, injury, or loss.

§ 10.2.3 The Contractor shall implement, erect, and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards; promulgating safety regulations; and notifying the owners and users of adjacent sites and utilities of the safeguards.

§ 10.2.4 When use or storage of explosives or other hazardous materials or equipment, or unusual methods are necessary for execution of the Work, the Contractor shall exercise utmost care and carry on such activities under supervision of properly qualified personnel.

§ 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Sections 10.2.1.2 and 10.2.1.3 caused in whole or in part by the Contractor, a Subcontractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Sections 10.2.1.2 and 10.2.1.3. The Contractor may make a Claim for the cost to remedy the damage or loss to the extent such damage or loss is attributable to acts or omissions of the Owner or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Section 3.18.

§ 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner and Architect.

§ 10.2.7 The Contractor shall not permit any part of the construction or site to be loaded so as to cause damage or create an unsafe condition.

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 10.2.8 Injury or Damage to Person or Property

If either party suffers injury or damage to person or property because of an act or omission of the other party, or of others for whose acts such party is legally responsible, notice of the injury or damage, whether or not insured, shall be given to the other party within a reasonable time not exceeding 21 days after discovery. The notice shall provide sufficient detail to enable the other party to investigate the matter.

§ 10.3 Hazardous Materials and Substances

§ 10.3.1 The Contractor is responsible for compliance with any requirements included in the Contract Documents regarding hazardous materials or substances. If the Contractor encounters a hazardous material or substance not addressed in the Contract Documents and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons resulting from a material or substance, including but not limited to asbestos or polychlorinated biphenyl (PCB), encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and notify the Owner and Architect of the condition.

§ 10.3.2 Upon receipt of the Contractor's notice, the Owner shall obtain the services of a licensed laboratory to verify the presence or absence of the material or substance reported by the Contractor and, in the event such material or substance is found to be present, to cause it to be rendered harmless. Unless otherwise required by the Contract Documents, the Owner shall furnish in writing to the Contractor and Architect the names and qualifications of persons or entities who are to perform tests verifying the presence or absence of the material or substance or who are to perform the task of removal or safe containment of the material or substance. The Contractor and the Architect will promptly reply to the Owner in writing stating whether or not either has reasonable objection to the persons or entities proposed by the Owner. If either the Contractor or Architect has an objection to a person or entity proposed by the Owner, the Owner shall propose another to whom the Contractor and the Architect have no reasonable objection. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Contractor. By Change Order, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable additional costs of shutdown, delay, and start-up.

§ 10.3.3 To the fullest extent permitted by law, the Owner shall indemnify and hold harmless the Contractor, Subcontractors, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work in the affected area if in fact the material or substance presents the risk of bodily injury or death as described in Section 10.3.1 and has not been rendered harmless, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), except to the extent that such damage, loss, or expense is due to the fault or negligence of the party seeking indemnity.

§ 10.3.4 The Owner shall not be responsible under this Section 10.3 for hazardous materials or substances the Contractor brings to the site unless such materials or substances are required by the Contract Documents. The Owner shall be responsible for hazardous materials or substances required by the Contract Documents, except to the extent of the Contractor's fault or negligence in the use and handling of such materials or substances.

§ 10.3.5 The Contractor shall reimburse the Owner for the cost and expense the Owner incurs (1) for remediation of hazardous materials or substances the Contractor brings to the site and negligently handles, or (2) where the Contractor fails to perform its obligations under Section 10.3.1, except to the extent that the cost and expense are due to the Owner's fault or negligence.

§ 10.3.6 If, without negligence on the part of the Contractor, the Contractor is held liable by a government agency for the cost of remediation of a hazardous material or substance solely by reason of performing Work as required by the Contract Documents, the Owner shall reimburse the Contractor for all cost and expense thereby incurred.

§ 10.4 Emergencies

In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury, or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 15 and Article 7.

ARTICLE 11 INSURANCE AND BONDS

§ 11.1 Contractor's Insurance and Bonds

§ 11.1.1 The Contractor shall purchase and maintain insurance of the types and limits of liability, containing the

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Contractor shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Owner, Architect, and Architect's consultants shall be named as additional insureds under the Contractor's commercial general liability policy or as otherwise described in the Contract Documents.

§ 11.1.2 The Contractor shall provide surety bonds of the types, for such penal sums, and subject to such terms and conditions as required by the Contract Documents. The Contractor shall purchase and maintain the required bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.

§ 11.1.3 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

§ 11.1.4 Notice of Cancellation or Expiration of Contractor's Required Insurance. Within three (3) business days of the date the Contractor becomes aware of an impending or actual cancellation or expiration of any insurance required by the Contract Documents, the Contractor shall provide notice to the Owner of such impending or actual cancellation or expiration. Upon receipt of notice from the Contractor, the Owner shall, unless the lapse in coverage arises from an act or omission of the Owner, have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by the Contractor. The furnishing of notice by the Contractor shall not relieve the Contractor of any contractual obligation to provide any required coverage.

§ 11.2 Owner's Insurance

§ 11.2.1 The Owner shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Owner shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located.

§ 11.2.2 Failure to Purchase Required Property Insurance. If the Owner fails to purchase and maintain the required property insurance, with all of the coverages and in the amounts described in the Agreement or elsewhere in the Contract Documents, the Owner shall inform the Contractor in writing prior to commencement of the Work. Upon receipt of notice from the Owner, the Contractor may delay commencement of the Work and may obtain insurance that will protect the interests of the Contractor, Subcontractors, and Sub-Subcontractors in the Work. When the failure to provide coverage has been cured or resolved, the Contract Sum and Contract Time shall be equitably adjusted. In the event the Owner fails to procure coverage, the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent the loss to the Owner would have been covered by the insurance to have been procured by the Owner. The cost of the insurance shall be charged to the Owner by a Change Order. If the Owner does not provide written notice, and the Contractor is damaged by the failure or neglect of the Owner to purchase or maintain the required insurance, the Owner shall reimburse the Contractor for all reasonable costs and damages attributable thereto.

§ 11.2.3 Notice of Cancellation or Expiration of Owner's Required Property Insurance. Within three (3) business days of the date the Owner becomes aware of an impending or actual cancellation or expiration of any property insurance required by the Contract Documents, the Owner shall provide notice to the Contractor of such impending or actual cancellation or expiration. Unless the lapse in coverage arises from an act or omission of the Contractor: (1) the Contractor, upon receipt of notice from the Owner, shall have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by either the Owner or the Contractor; (2) the Contract Time and Contract Sum shall be equitably adjusted; and (3) the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent any loss to the Owner would have been covered by the insurance had it not expired or been cancelled. If the Contractor purchases replacement coverage, the cost of the insurance shall be charged to the Owner by an appropriate Change Order. The furnishing of notice by the Owner shall not relieve the Owner of any contractual obligation to provide required insurance.

§ 11.3 Waivers of Subrogation

§ 11.3.1 The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents, and employees, each of the other; (2) the Architect and Architect's consultants; and (3) Separate Contractors, if any, and any of their subcontractors, sub-subcontractors, agents, and employees, for damages caused by fire, or other causes of loss, to the extent those losses are covered by property insurance required by the Agreement or other property insurance applicable to the Project, except such rights as they have to proceeds of such insurance. The

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Owner or Contractor, as appropriate, shall require similar written waivers in favor of the individuals and entities identified above from the Architect, Architect's consultants, Separate Contractors, subcontractors, and sub-subcontractors. The policies of insurance purchased and maintained by each person or entity agreeing to waive claims pursuant to this section 11.3.1 shall not prohibit this waiver of subrogation. This waiver of subrogation shall be effective as to a person or entity (1) even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, (2) even though that person or entity did not pay the insurance premium directly or indirectly, or (3) whether or not the person or entity had an insurable interest in the damaged property.

§ 11.3.2 If during the Project construction period the Owner insures properties, real or personal or both, at or adjacent to the site by property insurance under policies separate from those insuring the Project, or if after final payment property insurance is to be provided on the completed Project through a policy or policies other than those insuring the Project during the construction period, to the extent permissible by such policies, the Owner waives all rights in accordance with the terms of Section 11.3.1 for damages caused by fire or other causes of loss covered by this separate property insurance.

§ 11.4 Loss of Use, Business Interruption, and Delay in Completion Insurance

The Owner, at the Owner's option, may purchase and maintain insurance that will protect the Owner against loss of use of the Owner's property, or the inability to conduct normal operations, due to fire or other causes of loss. The Owner waives all rights of action against the Contractor and Architect for loss of use of the Owner's property, due to fire or other hazards however caused.

§11.5 Adjustment and Settlement of Insured Loss

§ 11.5.1 A loss insured under the property insurance required by the Agreement shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.5.2. The Owner shall pay the Architect and Contractor their just shares of insurance proceeds received by the Owner, and by appropriate agreements the Architect and Contractor shall make payments to their consultants and Subcontractors in similar manner.

§ 11.5.2 Prior to settlement of an insured loss, the Owner shall notify the Contractor of the terms of the proposed settlement as well as the proposed allocation of the insurance proceeds. The Contractor shall have 14 days from receipt of notice to object to the proposed settlement or allocation of the proceeds. If the Contractor does not object, the Owner shall settle the loss and the Contractor shall be bound by the settlement and allocation. Upon receipt, the Owner shall deposit the insurance proceeds in a separate account and make the appropriate distributions. Thereafter, if no other agreement is made or the Owner does not terminate the Contract for convenience, the Owner and Contractor shall execute a Change Order for reconstruction of the damaged or destroyed Work in the amount allocated for that purpose. If the Contractor timely objects to either the terms of the proposed settlement or the allocation of the proceeds, the Owner may proceed to settle the insured loss, and any dispute between the Owner and Contractor arising out of the settlement or allocation of the proceeds shall be resolved pursuant to Article 15. Pending resolution of any dispute, the Owner may issue a Construction Change Directive for the reconstruction of the damaged or destroyed Work.

ARTICLE 12 UNCOVERING AND CORRECTION OF WORK

§ 12.1 Uncovering of Work

§ 12.1.1 If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, it must, if requested in writing by the Architect, be uncovered for the Architect's examination and be replaced at the Contractor's expense without change in the Contract Time.

§ 12.1.2 If a portion of the Work has been covered that the Architect has not specifically requested to examine prior to its being covered, the Architect may request to see such Work and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, the Contractor shall be entitled to an equitable adjustment to the Contract Sum and Contract Time as may be appropriate. If such Work is not in accordance with the Contract Documents, the costs of uncovering the Work, and the cost of correction, shall be at the Contractor's expense.

§ 12.2 Correction of Work

§ 12.2.1 Before Substantial Completion

The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, discovered before Substantial Completion and whether or not fabricated, installed or completed. Costs of correcting such rejected Work, including additional testing and inspections, the cost of uncovering and replacement, and compensation for the Architect's services and expenses made necessary thereby, shall be at the

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

Contractor's expense.

§ 12.2.2 After Substantial Completion

§ 12.2.2.1 In addition to the Contractor's obligations under Section 3.5, if, within one year after the date of Substantial Completion of the Work or designated portion thereof or after the date for commencement of warranties established under Section 9.9.1, or by terms of any applicable special warranty required by the Contract Documents, any of the Work is found to be not in accordance with the requirements of the Contract Documents, the Contractor shall correct it promptly after receipt of notice from the Owner to do so, unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discovery of the condition. During the one-year period for correction of Work, if the Owner fails to notify the Contractor and give the Contractor an opportunity to make the correction, the Owner waives the rights to require correction by the Contractor and to make a claim for breach of warranty. If the Contractor fails to correct nonconforming Work within a reasonable time during that period after receipt of notice from the Owner or Architect, the Owner may correct it in accordance with Section 2.5.

§ 12.2.2.2 The one-year period for correction of Work shall be extended with respect to portions of Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual completion of that portion of the Work.

§ 12.2.2.3 The one-year period for correction of Work shall not be extended by corrective Work performed by the Contractor pursuant to this Section 12.2.

§ 12.2.3 The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.

§ 12.2.4 The Contractor shall bear the cost of correcting destroyed or damaged construction of the Owner or Separate Contractors, whether completed or partially completed, caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents.

§ 12.2.5 Nothing contained in this Section 12.2 shall be construed to establish a period of limitation with respect to other obligations the Contractor has under the Contract Documents. Establishment of the one-year period for correction of Work as described in Section 12.2.2 relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations other than specifically to correct the Work.

§ 12.3 Acceptance of Nonconforming Work

If the Owner prefers to accept Work that is not in accordance with the requirements of the Contract Documents, the Owner may do so instead of requiring its removal and correction, in which case the Contract Sum will be reduced as appropriate and equitable. Such adjustment shall be effected whether or not final payment has been made.

ARTICLE 13 MISCELLANEOUS PROVISIONS

§ 13.1 Governing Law

The Contract shall be governed by the law of the place where the Project is located, excluding that jurisdiction's choice of law rules. If the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4.

§ 13.2 Successors and Assigns

§ 13.2.1 The Owner and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to covenants, agreements, and obligations contained in the Contract Documents. Except as provided in Section 13.2.2, neither party to the Contract shall assign the Contract as a whole without written consent of the other. If either party attempts to make an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

§ 13.2.2 The Owner may, without consent of the Contractor, assign the Contract to a lender providing construction financing for the Project, if the lender assumes the Owner's rights and obligations under the Contract Documents. The Contractor shall execute all consents reasonably required to facilitate the assignment.

SAMPLE

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 13.3 Rights and Remedies

§ 13.3.1 Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

§ 13.3.2 No action or failure to act by the Owner, Architect, or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed upon in writing.

§ 13.4 Tests and Inspections

§ 13.4.1 Tests, inspections, and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules, and regulations or lawful orders of public authorities. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections, and approvals with an independent testing laboratory or entity acceptable to the Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections, and approvals. The Contractor shall give the Architect timely notice of when and where tests and inspections are to be made so that the Architect may be present for such procedures. The Owner shall bear costs of tests, inspections, or approvals that do not become requirements until after bids are received or negotiations concluded. The Owner shall directly arrange and pay for tests, inspections, or approvals where building codes or applicable laws or regulations so require.

§ 13.4.2 If the Architect, Owner, or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection, or approval not included under Section 13.4.1, the Architect will, upon written authorization from the Owner, instruct the Contractor to make arrangements for such additional testing, inspection, or approval, by an entity acceptable to the Owner, and the Contractor shall give timely notice to the Architect of when and where tests and inspections are to be made so that the Architect may be present for such procedures. Such costs, except as provided in Section 13.4.3, shall be at the Owner's expense.

§ 13.4.3 If procedures for testing, inspection, or approval under Sections 13.4.1 and 13.4.2 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, all costs made necessary by such failure, including those of repeated procedures and compensation for the Architect's services and expenses, shall be at the Contractor's expense.

§ 13.4.4 Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor and promptly delivered to the Architect.

§ 13.4.5 If the Architect is to observe tests, inspections, or approvals required by the Contract Documents, the Architect will do so promptly and, where practicable, at the normal place of testing.

§ 13.4.6 Tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.

§ 13.5 Interest

Payments due and unpaid under the Contract Documents shall bear interest from the date payment is due at the rate the parties agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT

§ 14.1 Termination by the Contractor

§ 14.1.1 The Contractor may terminate the Contract if the Work is stopped for a period of 30 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, for any of the following reasons:

.1 Issuance of an order of a court or other public authority having jurisdiction that requires all Work to be stopped;

.2 An act of government, such as a declaration of national emergency, that requires all Work to be stopped;

.3 Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents; or

.4 The Owner has failed to furnish to the Contractor reasonable evidence as required by Section 2.2.

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 14.1.2 The Contractor may terminate the Contract if, through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, repeated suspensions, delays, or interruptions of the entire Work by the Owner as described in Section 14.3, constitute in the aggregate more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less.

§ 14.1.3 If one of the reasons described in Section 14.1.1 or 14.1.2 exists, the Contractor may, upon seven days' notice to the Owner and Architect, terminate the Contract and recover from the Owner payment for Work executed, as well as reasonable overhead and profit on Work not executed, and costs incurred by reason of such termination.

§ 14.1.4 If the Work is stopped for a period of 60 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, or their agents or employees or any other persons or entities performing portions of the Work because the Owner has repeatedly failed to fulfill the Owner's obligations under the Contract Documents with respect to matters important to the progress of the Work, the Contractor may, upon seven additional days' notice to the Owner and the Architect, terminate the Contract and recover from the Owner as provided in Section 14.1.3.

§ 14.2 Termination by the Owner for Cause

§ 14.2.1 The Owner may terminate the Contract if the Contractor

- **.1** repeatedly refuses or fails to supply enough properly skilled workers or proper materials;
- **.2** fails to make payment to Subcontractors or suppliers in accordance with the respective agreements between the Contractor and the Subcontractors or suppliers;
- **.3** repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
- **.4** otherwise is guilty of substantial breach of a provision of the Contract Documents.

§ 14.2.2 When any of the reasons described in Section 14.2.1 exist, and upon certification by the Architect that sufficient cause exists to justify such action, the Owner may, without prejudice to any other rights or remedies of the Owner and after giving the Contractor and the Contractor's surety, if any, seven days' notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:

- **.1** Exclude the Contractor from the site and take possession of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
- **.2** Accept assignment of subcontracts pursuant to Section 5.4; and
- **.3** Finish the Work by whatever reasonable method the Owner may deem expedient. Upon written request of the Contractor, the Owner shall furnish to the Contractor a detailed accounting of the costs incurred by the Owner in finishing the Work.

§ 14.2.3 When the Owner terminates the Contract for one of the reasons stated in Section 14.2.1, the Contractor shall not be entitled to receive further payment until the Work is finished.

§ 14.2.4 If the unpaid balance of the Contract Sum exceeds costs of finishing the Work, including compensation for the Architect's services and expenses made necessary thereby, and other damages incurred by the Owner and not expressly waived, such excess shall be paid to the Contractor. If such costs and damages exceed the unpaid balance, the Contractor shall pay the difference to the Owner. The amount to be paid to the Contractor or Owner, as the case may be, shall be certified by the Initial Decision Maker, upon application, and this obligation for payment shall survive termination of the Contract.

§ 14.3 Suspension by the Owner for Convenience

§ 14.3.1 The Owner may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work, in whole or in part for such period of time as the Owner may determine.

§ 14.3.2 The Contract Sum and Contract Time shall be adjusted for increases in the cost and time caused by suspension, delay, or interruption under Section 14.3.1. Adjustment of the Contract Sum shall include profit. No adjustment shall be made to the extent

- **.1** that performance is, was, or would have been, so suspended, delayed, or interrupted, by another cause for which the Contractor is responsible; or
- **.2** that an equitable adjustment is made or denied under another provision of the Contract.

SAMPLE

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 14.4 Termination by the Owner for Convenience

§ 14.4.1 The Owner may, at any time, terminate the Contract for the Owner's convenience and without cause.

§ 14.4.2 Upon receipt of notice from the Owner of such termination for the Owner's convenience, the Contractor shall

.1 cease operations as directed by the Owner in the notice;

.2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work; and

.3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders.

§ 14.4.3 In case of such termination for the Owner's convenience, the Owner shall pay the Contractor for Work properly executed; costs incurred by reason of the termination, including costs attributable to termination of Subcontracts; and the termination fee, if any, set forth in the Agreement.

ARTICLE 15 CLAIMS AND DISPUTES

§ 15.1 Claims

§ 15.1.1 Definition

A Claim is a demand or assertion by one of the parties seeking, as a matter of right, payment of money, a change in the Contract Time, or other relief with respect to the terms of the Contract. The term "Claim" also includes other disputes and matters in question between the Owner and Contractor arising out of or relating to the Contract. The responsibility to substantiate Claims shall rest with the party making the Claim. This Section 15.1.1 does not require the Owner to file a Claim in order to impose liquidated damages in accordance with the Contract Documents.

§ 15.1.2 Time Limits on Claims

The Owner and Contractor shall commence all Claims and causes of action against the other and arising out of or related to the Contract, whether in contract, tort, breach of warranty or otherwise, in accordance with the requirements of the binding dispute resolution method selected in the Agreement and within the period specified by applicable law, but in any case not more than 10 years after the date of Substantial Completion of the Work. The Owner and Contractor waive all Claims and causes of action not commenced in accordance with this Section 15.1.2.

§ 15.1.3 Notice of Claims

§ 15.1.3.1 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered prior to expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party and to the Initial Decision Maker with a copy sent to the Architect, if the Architect is not serving as the Initial Decision Maker. Claims by either party under this Section 15.1.3.1 shall be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later.

§ 15.1.3.2 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party. In such event, no decision by the Initial Decision Maker is required.

§ 15.1.4 Continuing Contract Performance

§ 15.1.4.1 Pending final resolution of a Claim, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents.

§ 15.1.4.2 The Contract Sum and Contract Time shall be adjusted in accordance with the Initial Decision Maker's decision, subject to the right of either party to proceed in accordance with this Article 15. The Architect will issue Certificates for Payment in accordance with the decision of the Initial Decision Maker.

§ 15.1.5 Claims for Additional Cost

If the Contractor wishes to make a Claim for an increase in the Contract Sum, notice as provided in Section 15.1.3 shall be given before proceeding to execute the portion of the Work that is the subject of the Claim. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

§ 15.1.6 Claims for Additional Time

§ 15.1.6.1 If the Contractor wishes to make a Claim for an increase in the Contract Time, notice as provided in Section

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

15.1.3 shall be given. The Contractor's Claim shall include an estimate of cost and of probable effect of delay on progress of the Work. In the case of a continuing delay, only one Claim is necessary.

§ 15.1.6.2 If adverse weather conditions are the basis for a Claim for additional time, such Claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not have been reasonably anticipated, and had an adverse effect on the scheduled construction.

§ 15.1.7 Waiver of Claims for Consequential Damages

The Contractor and Owner waive Claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes

.1 damages incurred by the Owner for rental expenses, for losses of use, income, profit, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons; and

.2 damages incurred by the Contractor for principal office expenses including the compensation of personnel stationed there, for losses of financing, business and reputation, and for loss of profit, except anticipated profit arising directly from the Work.

This mutual waiver is applicable, without limitation, to all consequential damages due to either party's termination in accordance with Article 14. Nothing contained in this Section 15.1.7 shall be deemed to preclude assessment of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents.

§ 15.2 Initial Decision

§ 15.2.1 Claims, excluding those where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2 or arising under Sections 10.3, 10.4, and 11.5, shall be referred to the Initial Decision Maker for initial decision. The Architect will serve as the Initial Decision Maker, unless otherwise indicated in the Agreement. Except for those Claims excluded by this Section 15.2.1, an initial decision shall be required as a condition precedent to mediation of any Claim. If an initial decision has not been rendered within 30 days after the Claim has been referred to the Initial Decision Maker, the party asserting the Claim may demand mediation and binding dispute resolution without a decision having been rendered. Unless the Initial Decision Maker and all affected parties agree, the Initial Decision Maker will not decide disputes between the Contractor and persons or entities other than the Owner.

§ 15.2.2 The Initial Decision Maker will review Claims and within ten days of the receipt of a Claim take one or more of the following actions: (1) request additional supporting data from the claimant or a response with supporting data from the other party, (2) reject the Claim in whole or in part, (3) approve the Claim, (4) suggest a compromise, or (5) advise the parties that the Initial Decision Maker is unable to resolve the Claim if the Initial Decision Maker lacks sufficient information to evaluate the merits of the Claim or if the Initial Decision Maker concludes that, in the Initial Decision Maker's sole discretion, it would be inappropriate for the Initial Decision Maker to resolve the Claim.

§ 15.2.3 In evaluating Claims, the Initial Decision Maker may, but shall not be obligated to, consult with or seek information from either party or from persons with special knowledge or expertise who may assist the Initial Decision Maker in rendering a decision. The Initial Decision Maker may request the Owner to authorize retention of such persons at the Owner's expense.

§ 15.2.4 If the Initial Decision Maker requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of the request, and shall either (1) provide a response on the requested supporting data, (2) advise the Initial Decision Maker when the response or supporting data will be furnished, or (3) advise the Initial Decision Maker that no supporting data will be furnished. Upon receipt of the response or supporting data, if any, the Initial Decision Maker will either reject or approve the Claim in whole or in part.

§ 15.2.5 The Initial Decision Maker will render an initial decision approving or rejecting the Claim, or indicating that the Initial Decision Maker is unable to resolve the Claim. This initial decision shall (1) be in writing; (2) state the reasons therefor; and (3) notify the parties and the Architect, if the Architect is not serving as the Initial Decision Maker, of any change in the Contract Sum or Contract Time or both. The initial decision shall be final and binding on the parties but subject to mediation and, if the parties fail to resolve their dispute through mediation, to binding dispute resolution.

§ 15.2.6 Either party may file for mediation of an initial decision at any time, subject to the terms of Section 15.2.6.1.

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

§ 15.2.6.1 Either party may, within 30 days from the date of receipt of an initial decision, demand in writing that the other party file for mediation. If such a demand is made and the party receiving the demand fails to file for mediation within 30 days after receipt thereof, then both parties waive their rights to mediate or pursue binding dispute resolution proceedings with respect to the initial decision.

§ 15.2.7 In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

§ 15.2.8 If a Claim relates to or is the subject of a mechanic's lien, the party asserting such Claim may proceed in accordance with applicable law to comply with the lien notice or filing deadlines.

§ 15.3 Mediation

§ 15.3.1 Claims, disputes, or other matters in controversy arising out of or related to the Contract, except those waived as provided for in Sections 9.10.4, 9.10.5, and 15.1.7, shall be subject to mediation as a condition precedent to binding dispute resolution.

§ 15.3.2 The parties shall endeavor to resolve their Claims by mediation which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedures in effect on the date of the Agreement. A request for mediation shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the mediation. The request may be made concurrently with the filing of binding dispute resolution proceedings but, in such event, mediation shall proceed in advance of binding dispute resolution proceedings, which shall be stayed pending mediation for a period of 60 days from the date of filing, unless stayed for a longer period by agreement of the parties or court order. If an arbitration is stayed pursuant to this Section 15.3.2, the parties may nonetheless proceed to the selection of the arbitrator(s) and agree upon a schedule for later proceedings.

§ 15.3.3 Either party may, within 30 days from the date that mediation has been concluded without resolution of the dispute or 60 days after mediation has been demanded without resolution of the dispute, demand in writing that the other party file for binding dispute resolution. If such a demand is made and the party receiving the demand fails to file for binding dispute resolution within 60 days after receipt thereof, then both parties waive their rights to binding dispute resolution proceedings with respect to the initial decision.

§ 15.3.4 The parties shall share the mediator's fee and any filing fees equally. The mediation shall be held in the place where the Project is located, unless another location is mutually agreed upon. Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof.

§ 15.4 Arbitration

§ 15.4.1 If the parties have selected arbitration as the method for binding dispute resolution in the Agreement, any Claim subject to, but not resolved by, mediation shall be subject to arbitration which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Arbitration Rules in effect on the date of the Agreement. The Arbitration shall be conducted in the place where the Project is located, unless another location is mutually agreed upon. A demand for arbitration shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the arbitration. The party filing a notice of demand for arbitration must assert in the demand all Claims then known to that party on which arbitration is permitted to be demanded.

§ 15.4.1.1 A demand for arbitration shall be made no earlier than concurrently with the filing of a request for mediation, but in no event shall it be made after the date when the institution of legal or equitable proceedings based on the Claim would be barred by the applicable statute of limitations. For statute of limitations purposes, receipt of a written demand for arbitration by the person or entity administering the arbitration shall constitute the institution of legal or equitable proceedings based on the Claim.

§ 15.4.2 The award rendered by the arbitrator or arbitrators shall be final, and judgment may be entered upon it in accordance with applicable law in any court having jurisdiction thereof.

§ 15.4.3 The foregoing agreement to arbitrate and other agreements to arbitrate with an additional person or entity duly

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

consented to by parties to the Agreement, shall be specifically enforceable under applicable law in any court having jurisdiction thereof.

§ 15.4.4 Consolidation or Joinder

§ 15.4.4.1 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may consolidate an arbitration conducted under this Agreement with any other arbitration to which it is a party provided that (1) the arbitration agreement governing the other arbitration permits consolidation, (2) the arbitrations to be consolidated substantially involve common questions of law or fact, and (3) the arbitrations employ materially similar procedural rules and methods for selecting arbitrator(s).

§ 15.4.4.2 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may include by joinder persons or entities substantially involved in a common question of law or fact whose presence is required if complete relief is to be accorded in arbitration, provided that the party sought to be joined consents in writing to such joinder. Consent to arbitration involving an additional person or entity shall not constitute consent to arbitration of any claim, dispute or other matter in question not described in the written consent.

§ 15.4.4.3 The Owner and Contractor grant to any person or entity made a party to an arbitration conducted under this Section 15.4, whether by joinder or consolidation, the same rights of joinder and consolidation as those of the Owner and Contractor under this Agreement.

Sample

AIA Document A201® – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. The "American Institute of Architects," "AIA," the AIA Logo, "A201," and "AIA Contract Documents" are registered trademarks and may not be used without permission. To report copyright violations, e-mail copyright@aia.org.

SUPPLEMENTARY GENERAL CONDITIONS A201-2017

The following supplements modify the "General Conditions of the Contract for Construction," AIA Document A201-2017. Where a portion of the General Conditions is modified or deleted by the Supplementary Conditions, the unaltered portions of the General Conditions shall remain in effect.

TABLE OF ARTICLES

1. GENERAL PROVISIONS

2. OWNER

3. CONTRACTOR

4. ADMINISTRATION OF THE CONTRACT

5. SUBCONTRACTORS

6. CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

7. CHANGES IN THE WORK

8. TIME

9. PAYMENTS AND COMPLETION

10. PROTECTION OF PERSONS AND PROPERTY

11. INSURANCE AND BONDS

12. UNCOVERING AND CORRECTION OF WORK

13. MISCELLANEOUS PROVISIONS

14. TERMINATION OR SUSPENSION OF THE CONTRACT

ARTICLE 1: GENERAL PROVISIONS

1.1 BASIC DEFINITIONS

1.1.1 THE CONTRACT DOCUMENTS

Strike the last sentence of Section 1.1.1 in its entirety and replace with the following:

"The Contract Documents also include Advertisement for Bid, Instructions to Bidder, sample forms, the Bid Form, the Contractor's completed Bid and the Award Letter."

Add the following Section:

"1.1.1.1 In the event of conflict or discrepancies among the Contract Documents, the Documents prepared by the Delaware Technical and Community College shall take precedence over all other documents."

1.1.8 INITIAL DECISION MAKER

Strike the last sentence of Section 1.1.8 in its entirety and add the following to the end of the remaining sentence:

" and certify termination of the Agreement under Section14.2.2."

1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

1.2.1.1 Insert "if possible" at the end of the second sentence.

Add the following Sections:

"1.2.4 In the case of an inconsistency between the Drawings and the Specifications, or within either document not clarified by addendum, the better quality or greater quantity of work shall be provided in accordance with the Architect's interpretation."

"1.2.5 The word "PROVIDE" as used in the Contract Documents shall mean "FURNISH AND INSTALL" and shall include, without limitation, all labor, materials, equipment, transportation, services and other items required to complete the Work."

"1.2.6 The word "PRODUCT" as used in the Contract Documents means all materials, systems and equipment."

1.5 OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER INSTRUMENTS OF SERVICE

Strike Section 1.5.1 in its entirety and replace with the following:

"All pre-design studies, drawings, specifications and other documents, including those in electronic form, prepared by the Architect under this Agreement are, and shall remain, the property of the Owner whether the Project for which they are made is executed or not. Such documents may be used by the Owner to construct one or more like Projects without the approval of, or additional compensation to, the Architect. The Contractor, Subcontractors, Sub-subcontractors, and Material or Equipment Suppliers are authorized to use and reproduce applicable portions of the Drawings, Specifications and other documents prepared by the Architect and the Architect's consultants appropriate to and for use in the execution of their Work

under the Contract Documents. They are not to be used by the Contractor or any Subcontractor, Sub-subcontractor or Material and Equipment Supplier on other Projects or for additions to this Project outside the scope of the Work without the specific written consent of the Owner, Architect and Architect's consultants.

The Architect shall not be liable for injury or damage resulting from the re-use of drawings and specifications if the Architect is not involved in the re-use Project. Prior to re-use of construction documents for a Project in which the Architect is not also involved, the Owner will remove from such documents all identification of the original Architect, including name, address and professional seal or stamp."

Strike Section 1.5.2 in its entirety.

1.7 DIGITAL DATA USE AND TRANSMISSION

Strike Section 1.7 in its entirety and replace with the following:

"The parties shall agree upon protocols governing transmission and use of Instruments of Service or any other information or documentation in digital form."

1.8 BUILDING INFORMATION MODELS USE AND RELIANCE

Strike Section 1.8 in its entirety.

ARTICLE 2: OWNER

2.2 EVIDENCE OF THE OWNERS FINANCIAL ARRANGEMENTS

Strike Section 2.2 in its entirety.

2.3 INFORMATION AND SERVICES REQUIRED OF THE OWNER

2.3.3 Strike 2.3.3 in its entirety.

2.3.4 Add the following sentence at the end of the paragraph:

"The Contractor, at their expense shall bear the costs to accurately identify the location of all underground utilities in the area of their excavation and shall bear all cost for any repairs required, out of failure to accurately identify said utilities."

Strike Section 2.3.6 in its entirety and replace with the following:

"2.3.6 The Contractor shall be furnished free of charge (1) electronic set of the Drawings and Project Manuals. Additional sets will be furnished at the cost of reproduction, postage and handling."

2.5 OWNER'S RIGHT TO CARRY OUT THE WORK

Add ", except as outlined in Section 3.15" after the reference to "Article 15" at the end of the last sentence of the Section.

ARTICLE 3: CONTRACTOR

3.2 REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR

3.2.2 Add “and Owner” after “report to the Architect” in the second sentence.

3.2.4 Strike “subject to Section 15.1.7” in the second sentence.

3.2.4 Strike the third sentence.

3.3 SUPERVISION AND CONSTRUCTION PROCEDURES

Add the following Sections:

“3.3.2.1 The Contractor shall immediately remove from the Work, whenever requested to do so by the Owner, any person who is considered by the Owner or Architect to be incompetent or disposed to be so disorderly, or who for any reason is not satisfactory to the Owner, and that person shall not again be employed on the Work without the consent of the Owner or the Architect.”

“3.3.4 The Contractor must provide suitable storage facilities at the Site for the proper protection and safe storage of their materials, or as otherwise identified by the specifications. Consult the Owner and the Architect before storing any materials.”

“3.3.5 When any room is used as a shop, storeroom, office, etc., by the Contractor or Subcontractor(s) during the construction of the Work, the Contractor making use of these areas will be held responsible for any repairs, patching or cleaning arising from such use.”

3.4 LABOR AND MATERIALS

Add the Following Sections:

“3.4.4 Before starting the Work, each Contractor shall carefully examine all preparatory Work that has been executed to receive their Work. Check carefully, by whatever means are required, to insure that its Work and adjacent, related Work, will finish to proper contours, planes and levels. Promptly notify the Architect & Owner of any defects or imperfections in preparatory Work which will in any way affect satisfactory completion of its Work. Absence of such notification will be construed as an acceptance of preparatory Work and later claims of defects will not be recognized.”

“3.4.5 Under no circumstances shall the Contractor’s Work proceed prior to preparatory Work having been completely cured, dried and/or otherwise made satisfactory to receive this Work. Responsibility for timely installation of all materials rests solely with the Contractor responsible for that Work, who shall maintain coordination at all times.”

3.5 WARRANTY

Add the following Sections:

“3.5.3 The Contractor will guarantee all materials and workmanship against original defects, except injury from proper and usual wear when used for the purpose intended, for two years after Acceptance by the Owner, and will maintain all items in perfect condition during the period of warranty.”

"3.5.4 Defects appearing during the period of warranty will be made good by the Contractor at his expense upon demand of the Owner, it being required that all work will be in perfect condition when the period of warranty will have elapsed."

"3.5.5 Upon notification by the Owner of a defect covered by the Contractor's warranty, the Contractor shall respond within 4 hours of the notification."

"3.5.6 In addition to the General Warranty there are other warranties required for certain items for different periods of time than the two years as above, and are particularly so stated in that part of the specifications referring to same. The said warranties will commence at the same time as the General Warranty."

"3.5.7 If the Contractor fails to remedy any failure, defect or damage within a reasonable time after receipt of notice, the Owner will have the right to replace, repair, or otherwise remedy the failure, defect or damage at the Contractor's expense."

3.8 ALLOWANCES

Add the following Section:

"3.8.1.1 For costs to be covered under a project allowance, (included in the schedule of values) the Contractor shall submit a summary of those costs anticipated and an Allowance Access Authorization Form to the Architect and Owner, reflecting the projected costs. The Allowance Access Authorization Form must be signed by the Owner prior to initiating any work associated with the allowance."

3.10 CONTRACTOR'S CONSTRUCTION AND SUBMITTAL SCHEDULES

3.10.1 Add "estimated" after "and the" and before "date of" in the second sentence.

3.10.2 Strike "and thereafter as necessary to maintain a current submittal schedule" in the first sentence.

3.11 DOCUMENTS AND SAMPLES AT THE SITE

Add the following Sections:

"3.11.1 During the course of the Work, the Contractor shall maintain a record set of drawings on which the Contractor shall mark the actual physical location of all piping, valves, equipment, conduit, outlets, access panels, controls, actuators, including all appurtenances that will be concealed once construction is complete, etc., including all invert elevations."

"3.11.2 At the completion of the project, the Contractor shall obtain a set of the conformed contract drawings from the Architect, and neatly transfer all information outlined in 3.11.1 to provide a complete record of the as-built conditions."

"3.11.3 Upon completion of the work noted in 3.11.2 the contractor shall schedule a meeting with the Architect/Engineer and Owner to review the final record drawings and closeout documents prior to submission. After this meeting the Contractor shall make adjustments per the review, and submit one (1) original markup and (2) copies of the red line drawings (as-built conditions, to the Owner and one (1) print to the Architect. In addition, attach one complete set of the as-built documents to each of the Operating and Maintenance Instructions/Manuals. The Contractor will include (2) USB drives, each containing all "red line drawings (as-built) and Closeout Documents properly tabbed in accordance with closeout requirements as defined elsewhere in the contract documents."

3.12 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

3.12.10.2 Strike “If the Contract Documents require” from the beginning of the sentence.

3.12.10.2 Strike “to” between “professional” and certify” and replace with “shall”.

3.17 Insert “indemnify and” between “shall” and “hold” in the second sentence.

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

4.2 ADMINISTRATION OF THE CONTRACT

4.2.7 Strike the first sentence and replace with the following:

“The Architect will review and approve or take other appropriate action upon the Contractor’s submittals such as Shop Drawings, Product Data and Samples for the purpose of checking for conformance with the Contract Documents.”

4.2.7 Strike the second sentence and replace with the following:

“The Architect’s action will be taken with such reasonable promptness as to cause no delay in the Work in the activities of the Owner, Contractor or separate Contractors, while allowing sufficient time in the Owner’s professional judgment to permit adequate review.”

Add the following Section:

“4.2.10.1 There will be no full-time Project Representative provided by the Owner or Architect on this project.”

“4.2.13 Add “and in compliance with all local requirements.” to the end of the sentence.”

ARTICLE 5: SUBCONTRACTORS

5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

5.2.3 Strike Section 5.2.3 in its entirety and replace with the following:

“If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection, subject to the statutory requirements of 29 Delaware Code § 6962(d)(10)b.3 and 4.”

5.2.4 Strike Section 5.2.4 in its entirety and replace with the following:

”The Contractor may not substitute any Subcontractor listed in its Bid unless the Contractor complies with the requirements of 29 Delaware Code § 6962(d)(10)b.3 and 4. Failure to comply with this requirement shall subject the Contractor to a penalty as outlined in Section 5.2 of the Owner’s General Requirements.”

Add the following Section:

“5.2.5 The Contractor shall comply and shall ensure all Subcontractors comply with all requirements for drug testing as set forth in TITLE 19 LABOR

DELAWARE ADMINISTRATIVE CODE 4000 Office of Management and Budget 4100 Division of Facilities Management **4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects."**

ARTICLE 6: CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

6.1 OWNER'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS

6.1.1 Strike "and waiver of subrogation" from the end of the second sentence.

6.1.4 Strike Section 6.1.4 in its entirety.

6.2 MUTUAL RESPONSIBILITY

6.2.3 Strike "shall" and replace with "may" in the second sentence.

ARTICLE 7: CHANGES IN THE WORK

(SEE ARTICLE 7: CHANGES IN WORK IN THE DELAWARE TECHNICAL AND COMMUNITY COLLEGE GENERAL REQUIREMENTS)

7.3.4.1 Strike "and other employee costs approved by the Architect" after "worker's compensation insurance,"

7.3.4.4 Add "work attributable to the" before "change" at the end of the sentence.

7.4 MINOR CHANGES IN WORK
Add "unless such changes are approved" at the end of the third sentence.

ARTICLE 8: TIME

8.2 PROGRESS AND COMPLETION

8.2.1 Add the following Section:

"8.2.1.1 Refer to Project Specifications Section SUMMARY OF WORK for Contract time requirements."

8.2.2 After "by the Contractor" strike "and" and insert "to".

8.2.4 Add the following Section:

"8.2.4 If the Work falls behind the Progress Schedule as submitted by the Contractor, the Contractor shall employ additional labor and/or equipment necessary to bring the Work into compliance with the Progress Schedule at no additional cost to the Owner."

8.3 DELAYS AND EXTENSION OF TIME

8.3.1 Strike "binding dispute resolution" and insert "any and all remedies at law or in equity".

Add the following Section:

"8.3.2.1 The Contractor shall update the status of the suspension, delay, or interruption of the Work with each Application for Payment. (The Contractor shall report the termination of such cause immediately upon the termination thereof.) Failure to comply with this procedure shall constitute a waiver for any claim for adjustment of time or price based upon said cause."

Strike Section 8.3.3 in its entirety and replace with the following:

8.3.3 "Except in the case of a suspension of the Work directed by the Owner, an extension of time under the provisions of Section 8.3.1 shall be the Contractor's sole remedy in the progress of the Work and there shall be no payment or compensation to the Contractor for any expense or damage resulting from the delay."

Add the following Section:

"8.3.4 By permitting the Contractor to work after the expired time for completion of the project, the Owner does not waive their rights under the Contract."

ARTICLE 9: PAYMENTS AND COMPLETION

9.2 SCHEDULE OF VALUES

Add the following Sections:

"9.2.1 The Schedule of Values shall be submitted using AIA Document G703, Continuation Sheet to G702."

"9.2.2 The Schedule of Values is to include a line item for Project Closeout Document Submittal. The value of this item is to be no less than 1.5% of the initial contract amount."

9.3 APPLICATIONS FOR PAYMENT

9.3.1 Strike Section 9.3.1 in its entirety and replace with the following:

"At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values for completed portions of the Work. The application shall be notarized, and supported by all data substantiating the Contractor's right to payment that the Owner or Architect require, such as copies of requisitions, and releases and waivers of liens from Subcontractors and suppliers, and shall reflect retainage."

Add the following Sections:

"9.3.1.3 Application for Payment shall be submitted on AIA Document G702 "Application and Certificate for Payment", supported by AIA Document G703 "Continuation Sheet". Said Applications shall be fully executed and notarized."

"9.3.4 Until Closeout Documents have been received and outstanding items completed the Owner will pay 95% (ninety-five percent) of the amount due the Contractor on account of progress payments."

"9.3.5 The Contractor shall provide a current and updated Progress Schedule to the Architect with each Application for Payment. Failure to provide Schedule will be just cause for rejection of Application for Payment."

9.5 DECISIONS TO WITHHOLD CERTIFICATION

Add the following Subsections to 9.5.1:

.8 failure to provide a current Progress Schedule;
.9 a lien or attachment is filed;
.10 failure to comply with mandatory requirements for maintaining Record Documents.

9.6 PROGRESS PAYMENTS

9.6.1 Strike Section 9.6.1 in its entirety and replace with the following:

"9.6.1 After the Architect has approved and issued a Certificate for Payment, payment shall be made by the Owner within 30 days after Owner's receipt of the Certificate for Payment."

9.6.8 Strike "Provided the Owner has fulfilled its payment obligations under the Contract Documents," in the first sentence.

9.7 FAILURE OF PAYMENT

Strike Section 9.7 in its entirety and replace with the following:

"If the Architect does not issue a Certificate for Payment, through no fault of the Contractor, within fourteen days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within thirty days after the date established in the Contract Documents, the amount certified by the Architect, then the Contractor may, upon thirty additional days' notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided for in the Contract Documents."

9.8 SUBSTANTIAL COMPLETION

9.8.3 At the end of Section 9.8.3, add the following sentence:

"If the Architect is required to make more than 2 inspections of the same portion of work, the Contractor shall be responsible for all costs associated with subsequent inspections including but not limited to any Architect's fees."

9.8.5 Strike "shall" and insert "may" in the second sentence.

9.8.5 Insert "1/2 of the" after "make payment of" in the second sentence.9.9 PARTIAL OCCUPANCY OR USE

9.9.1 Strike the first sentence and replace with the following (the remainder of the Section remains as written):
"The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use authorized by public authorities having jurisdiction over the Project."

9.10.2 Strike “to remain in force after final payment is currently in effect” after “required by the Contract Documents” and replace with “shall remain in force until final payment is completed” in the first sentence.

9.10.4.4 Strike “if permitted by the Contract Documents,”

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

10.1 SAFETY PRECAUTIONS AND PROGRAMS

Add the following Sections:

10.1.1 Each Contractor shall develop a safety program in accordance with the Occupational Safety and Health Act of 1970. A copy of said plan shall be furnished to the Owner and Architect prior to the commencement of that Contractor’s Work.

10.1.2 Each Contractor shall appoint a Safety Representative. Safety Representatives shall be someone who is on site on a full time basis. If deemed necessary by the Owner or Architect, Contractor Safety meetings will be scheduled. The attendance of all Safety Representatives will be required. Minutes will be recorded of said meetings by the Contractor and will be distributed to all parties as well as posted in all job offices/trailers etc.

10.2 SAFETY OF PERSONS AND PROPERTY

Add the following Section:

10.2.4.1 As required in the Hazardous Chemical Act of June 1984, all vendors supplying any material that may be defined as hazardous must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a caution warning on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or in foreseeable emergency situations. Material Safety Data Sheets shall be provided directly to the Owner, along with the shipping slips that include those products.

10.2.5 Strike the second sentence in its entirety.

10.3 HAZARDOUS MATERIALS AND SUBSTANCES

10.3.3 Strike Section 10.3.3 in its entirety.

10.3.4 Insert “hazardous” in the last sentence after “handling of such” .

10.3.6 Strike Section 10.3.6 in its entirety.

ARTICLE 11: INSURANCE AND BONDS

11.1 CONTRACTOR’S INSURANCE AND BONDS

11.1.1 Strike “Owner” from the third sentence .

11.2 OWNER’S LIABILITY INSURANCE

Strike 11.2in its entirety, except that in the case of school projects in which case Section 11.2 shall remain.

11.3 WAIVERS OF SUBROGATION

Delete Section 11.3 in its entirety

11.4 LOSS OF USE, BUSINESS INTERRUPTION, AND DELAY IN COMPLETION INSURANCE

Delete Section 11.4 in its entirety

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

12.2.2 AFTER SUBSTANTIAL COMPLETION

Add the following Section:

"12.2.2.1.1 At any time during the progress of the Work, or in any case where the nature of the defects will be such that it is not expedient to have corrected, the Owner, at its option, will have the right to deduct such sum, or sums, of money from the amount of the Contract as it considers justified to adjust the difference in value between the non-conforming work and that required under contract including any damage to the structure."

12.2.2.1 Strike all references to "one year" or "one-year" and replace with "two years".

12.2.2.2 Strike "one-year" and replace with "two years".

12.2.2.3 Strike "one-year" and replace with "two years".

12.2.5 Strike "one-year" and replaced with "two years".

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.1 GOVERNING LAW

Strike the last sentence.

13.4 TESTS AND INSPECTIONS

13.4.1 Strike the last sentence and replace with the following:

"The Owner shall pay for tests, inspections, or approvals where building codes or applicable laws or regulations prohibit the Owner from delegating their cost to the Contractor."

13.5 INTEREST

Strike "the date payment is due at such rate as the parties may agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located" and replace with "30 days of presentment of the authorized Certificate of Payment at the annual rate of 12% or 1% per month."

Insert the following Section:

"13.6 CONFLICTS WITH FEDERAL STATUTES OR REGULATIONS

13.6.1 If any provision, specifications or requirement of the Contract Documents conflict or is inconsistent with any statute, law or regulation of the government of the United States of America, the Contractor shall notify the Architect and Owner immediately upon discovery."

ARTICLE 14: TERMINATION OR SUSPENSION OF THE CONTRACT

14.1 TERMINATION BY THE CONTRACTOR

14.1.1.4 Insert ", upon the Contractors' request," after "" furnish to the Contractor" .

14.1.3 Strike "and profit on Work not executed, and" after "as well as reasonable overhead" and replace with ", profit, and reasonable"

14.3 SUSPENSION BY OWNER FOR CONVENIENCE

14.3.2 Strike "Adjustment of the Contract Sum shall include profit".

14.4 TERMINATION BY THE OWNER FOR CONVENIENCE

14.4.3 Strike Section 14.4.3 in its entirety and replace with the following:

"In case of such termination for the Owner's convenience, the Contractor shall be entitled to receive payment for Work executed, and reasonable costs incurred by reason of such termination along with reasonable overhead."

ARTICLE 15: CLAIMS AND DISPUTES

15.1 CLAIMS

15.1.2 TIME LIMITS ON CLAIMS

Strike the last sentence.

15.1.3 NOTICE OF CLAIM

Strike all references to "21" and replace with "45".

15.1.5 CLAIMS FOR ADDITIONAL COSTS

Strike the first sentence and replace with the following:

"Contractor shall not proceed to execute any portion of the Work that is subject to the Claim without prior approval of the costs or method of payment for the costs associated with the Claim as determined by the Architect and approved by the Owner."

15.1.7 WAIVER OF CLAIMS FOR CONSEQUENTIAL DAMAGES

Strike Section 15.1.7 in its entirety.

15.2 INITIAL DECISION

15.2.1 Strike “and binding dispute resolution” in the fourth sentence and replace with “or any and all remedies at law or in equity”.

15.2.5 Strike Section 15.2.5 in its entirety and replace with the following:

“The Architect will approve or reject Claims by written decision, which shall state the reasons therefore and shall notify the parties of any change in the Contract Sum or Contract Time or both. The approval or rejection of a Claim by the Architect shall be subject to mediation and any or all remedies at law or in equity.”

15.2.6 Strike Section 15.2.6 and its subsections in their entirety.

15.3 MEDIATION

15.3.1 Strike “binding dispute resolution” and replace with “any or all remedies at law or in equity”.

15.3.2 Strike “, shall be administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedure in effect on the date of the Agreement,” in the first sentence.

15.3.2 Strike all references to “binding dispute resolution” and replace with “any or all remedies at law and in equity”.

15.3.3 Strike Section 15.3.3 in its entirety.

15.4 ARBITRATION

Strike Section 15.4 and its Subsections in their entirety.

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 00 73 46
WAGE DETERMINATION SCHEDULE

1.1 WAGE RATE COVER SHEET AND FEDERAL CONTRACTUAL REQUIREMENTS

1.2 STATE OF DELWARE DEPARTMENT OF LABOR PREVAILING WAGES FOR BUILDING CONSTRUCTION

1.3 FEDERAL DAVIS BACON PREVAILING WAGES FOR BUILDING CONSTRUCTION

PREVAILING WAGES

This project is partially funded with Federal money. Projects with Federal money participation greater than $2000.00 are covered by the Davis-Bacon Act (DBA). The Federal prevailing wage rates are attached and the State of Delaware wage rates are attached. The Contractor shall use the wage rate that is the greatest for this project.

FEDERAL CONTRACTUAL REQUIREMENTS

As this project is partially funded with Federal money, the resulting contract for the awarded contractor must contain certain clauses from the United State Code (USC) and the Code of Federal Regulation (CFR). In 2 CFR, Appendix II to Part 200, is a description of the various USC and CFR language that will be inserted as requirements for the Contractor.

This content is from the eCFR and is authoritative but unofficial.

Displaying title 2, up to date as of 10/14/2026. Title 2 was last amended 8/17/2026.

Title 2 —Federal Financial Assistance
Subtitle A —Office of Management and Budget Guidance for Federal Financial Assistance
Chapter II —Office of Management and Budget Guidance
Part 200 —Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards

Appendix II to Part 200—Contract Provisions for Non-Federal Entity Contracts Under Federal Awards

In addition to other provisions required by the Federal agency or non-Federal entity, all contracts made by the non-Federal entity under the Federal award must contain provisions covering the following, as applicable.

- Contracts for more than the simplified acquisition threshold, which is the inflation adjusted amount determined by the Civilian Agency Acquisition Council and the Defense Acquisition Regulations Council (Councils) as authorized by 41 U.S.C. 1908, must address administrative, contractual, or legal remedies in instances where contractors violate or breach contract terms, and provide for such sanctions and penalties as appropriate.
- All contracts in excess of $10,000 must address termination for cause and for convenience by the non-Federal entity including the manner by which it will be effected and the basis for settlement.
- Equal Employment Opportunity. Except as otherwise provided under 41 CFR Part 60, all contracts that meet the definition of “federally assisted construction contract” in 41 CFR Part 60-1.3 must include the equal opportunity clause provided under 41 CFR 60-1.4(b), in accordance with Executive Order 11246, “Equal Employment Opportunity” (30 FR 12319, 12935, 3 CFR Part, 1964-1965 Comp., p. 339), as amended by Executive Order 11375, “Amending Executive Order 11246 Relating to Equal Employment Opportunity,” and implementing regulations at 41 CFR part 60, “Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor.”
- Davis-Bacon Act, as amended (40 U.S.C. 3141-3148). When required by Federal program legislation, all prime construction contracts in excess of $2,000 awarded by non-Federal entities must include a provision for compliance with the Davis-Bacon Act (40 U.S.C. 3141-3144, and 3146-3148) as supplemented by Department of Labor regulations (29 CFR Part 5, “Labor Standards Provisions Applicable to Contracts Covering Federally Financed and Assisted Construction”). In accordance with the statute, contractors must be required to pay wages to laborers and mechanics at a rate not less than the prevailing wages specified in a wage determination made by the Secretary of Labor. In addition, contractors must be required to pay wages not less than once a week. The non-Federal entity must place a copy of the current prevailing wage determination issued by the Department of Labor in each solicitation. The decision to award a contract or subcontract must be conditioned upon the acceptance of the wage determination. The non-Federal entity must report all suspected or reported violations to the Federal awarding agency. The contracts must also include a provision for compliance with the Copeland “Anti-Kickback” Act (40 U.S.C. 3145), as supplemented by Department of Labor regulations (29 CFR Part 3, “Contractors and Subcontractors on Public Building or Public Work Financed in Whole or in Part by Loans or Grants from the United States”). The Act provides that each contractor or subrecipient must be prohibited from inducing, by any means, any person employed in the construction, completion, or repair of public work, to give up any part of the compensation to which he or she is otherwise entitled. The non-Federal entity must report all suspected or reported violations to the Federal awarding agency.
- Contract Work Hours and Safety Standards Act (40 U.S.C. 3701-3708). Where applicable, all contracts awarded by the non-Federal entity in excess of $100,000 that involve the employment of mechanics or laborers must include a provision for compliance with 40 U.S.C. 3702 and 3704, as supplemented by Department of Labor regulations (29 CFR Part 5). Under 40 U.S.C. 3702 of the Act, each contractor must be required to compute the wages of every mechanic and laborer on the basis of a standard work week of 40 hours. Work in excess of the standard work week is permissible provided that the worker is compensated at a rate of not less than one and a half times the basic rate of pay for all hours worked in excess of 40 hours in the work week. The requirements of 40 U.S.C. 3704 are applicable to construction work and provide that no laborer or mechanic must be required to work in surroundings or under working conditions which are unsanitary, hazardous or dangerous. These requirements do not apply to the purchases of supplies or materials or articles ordinarily available on the open market, or contracts for transportation or transmission of intelligence.
- Rights to Inventions Made Under a Contract or Agreement. If the Federal award meets the definition of “funding agreement” under 37 CFR § 401.2 (a) and the recipient or subrecipient wishes to enter into a contract with a small business firm or nonprofit organization regarding the substitution of parties, assignment or performance of experimental, developmental, or

research work under that "funding agreement," the recipient or subrecipient must comply with the requirements of 37 CFR Part 401, "Rights to Inventions Made by Nonprofit Organizations and Small Business Firms Under Government Grants, Contracts and Cooperative Agreements," and any implementing regulations issued by the awarding agency.

(G) Clean Air Act (42 U.S.C. 7401-7671q.) and the Federal Water Pollution Control Act (33 U.S.C. 1251-1387), as amended—Contracts and subgrants of amounts in excess of $150,000 must contain a provision that requires the non-Federal award to agree to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal awarding agency and the Regional Office of the Environmental Protection Agency (EPA).

(H) Debarment and Suspension (Executive Orders 12549 and 12689)—A contract award (see 2 CFR 180.220) must not be made to parties listed on the governmentwide exclusions in the System for Award Management (SAM), in accordance with the OMB guidelines at 2 CFR 180 that implement Executive Orders 12549 (3 CFR part 1986 Comp., p. 189) and 12689 (3 CFR part 1989 Comp., p. 235), "Debarment and Suspension." SAM Exclusions contains the names of parties debarred, suspended, or otherwise excluded by agencies, as well as parties declared ineligible under statutory or regulatory authority other than Executive Order 12549.

(I) Byrd Anti-Lobbying Amendment (31 U.S.C. 1352)—Contractors that apply or bid for an award exceeding $100,000 must file the required certification. Each tier certifies to the tier above that it will not and has not used Federal appropriated funds to pay any person or organization for influencing or attempting to influence an officer or employee of any agency, a member of Congress, officer or employee of Congress, or an employee of a member of Congress in connection with obtaining any Federal contract, grant or any other award covered by 31 U.S.C. 1352. Each tier must also disclose any lobbying with non-Federal funds that takes place in connection with obtaining any Federal award. Such disclosures are forwarded from tier to tier up to the non-Federal award.

(J) See § 200.323.

(K) See § 200.216.

(L) See § 200.322.

[78 FR 78608, Dec. 26, 2013, as amended at 79 FR 75888, Dec. 19, 2014; 85 FR 49577, Aug. 13, 2020]

This content is from the eCFR and is authoritative but unofficial.

Displaying title 2, up to date as of 10/14/2026. Title 2 was last amended 8/17/2026.

Title 2 —Federal Financial Assistance
Subtitle A —Office of Management and Budget Guidance for Federal Financial Assistance
Chapter II —Office of Management and Budget Guidance
Part 200 —Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards
Subpart D —Post Federal Award Requirements
Procurement Standards

§ 200.323 Procurement of recovered materials.

A recipient or subrecipient that is a State agency or agency of a political subdivision of a State and its contractors must comply with section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act of 1976 as amended, 42 U.S.C. 6962. The requirements of Section 6002 include procuring only items designated in the guidelines of the Environmental Protection Agency (EPA) at 40 CFR part 247 that contain the highest percentage of recovered materials practicable, consistent with maintaining a satisfactory level of competition, where the purchase price of the item exceeds $10,000 or the value of the quantity acquired during the preceding fiscal year exceeded $10,000; procuring solid waste management services in a manner that maximizes energy and resource recovery; and establishing an affirmative procurement program for procurement of recovered materials identified in the EPA guidelines.

The recipient or subrecipient should, to the greatest extent practicable and consistent with law, purchase, acquire, or use products and services that can be reused, refurbished, or recycled; contain recycled content, are biobased, or are energy and water efficient; and are sustainable. This may include purchasing compostable items and other products and services that reduce the use of single-use plastic products. See Executive Order 14057, section 101, Policy.

This content is from the eCFR and is authoritative but unofficial.

Displaying title 2, up to date as of 10/14/2026. Title 2 was last amended 8/17/2026.

Title 2 —Federal Financial Assistance
Subtitle A —Office of Management and Budget Guidance for Federal Financial Assistance
Chapter II —Office of Management and Budget Guidance
Part 200 —Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards
Subpart C —Pre-Federal Award Requirements and Contents of Federal Awards

§ 200.216 Prohibition on certain telecommunications and video surveillance equipment or services.

(a) Recipients and subrecipients are prohibited from obligating or expending loan or grant funds to:

(1) Procure or obtain covered telecommunications equipment or services;

(2) Extend or renew a contract to procure or obtain covered telecommunications equipment or services; or

(3) Enter into a contract (or extend or renew a contract) to procure or obtain covered telecommunications equipment or services.

(b) As described in section 889 of Public Law 115-232, “covered telecommunications equipment or services” means any of the following:

(1) Telecommunications equipment produced by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities);

(2) For the purpose of public safety, security of government facilities, physical security surveillance of critical infrastructure, and other national security purposes, video surveillance and telecommunications equipment produced by Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities);

(3) Telecommunications or video surveillance services provided by such entities or using such equipment;

(4) Telecommunications or video surveillance equipment or services produced or provided by an entity that the Secretary of Defense, in consultation with the Director of the National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of a covered foreign country;

(c) For the purposes of this section, “covered telecommunications equipment or services” also include systems that use covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system.

(d) In implementing the prohibition under section 889 of Public Law 115-232, heads of executive agencies administering loan, grant, or subsidy programs must prioritize available funding and technical support to assist affected businesses, institutions, and organizations as is reasonably necessary for those affected entities to transition from covered telecommunications equipment or services, to procure replacement equipment or services, and to ensure that communications service to users and customers is sustained.

(e) When the recipient or subrecipient accepts a loan or grant, it is certifying that it will comply with the prohibition on covered telecommunications equipment and services in this section. The recipient or subrecipient is not required to certify that funds will not be expended on covered telecommunications equipment or services beyond the certification provided upon accepting the loan or grant and those provided upon submitting payment requests and financial reports.

(f) For additional information, see section 889 of Public Law 115-232 and § 200.471.

This content is from the eCFR and is authoritative but unofficial.

Displaying title 2, up to date as of 10/14/2026. Title 2 was last amended 8/17/2026.

Title 2 —Federal Financial Assistance
Subtitle A —Office of Management and Budget Guidance for Federal Financial Assistance
Chapter II —Office of Management and Budget Guidance
Part 200 —Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards
Subpart D —Post Federal Award Requirements
Procurement Standards

§ 200.322 Domestic preferences for procurements.

The recipient or subrecipient should, to the greatest extent practicable and consistent with law, provide a preference for the purchase, acquisition, or use of goods, products, or materials produced in the United States (including but not limited to iron, aluminum, steel, cement, and other manufactured products). The requirements of this section must be included in all subawards, contracts, and purchase orders under Federal awards.

For purposes of this section:

"Produced in the United States" means, for iron and steel products, that all manufacturing processes, from the initial melting stage through the application of coatings, occurred in the United States.

"Manufactured products" means items and construction materials composed in whole or in part of non-ferrous metals such as aluminum; plastics and polymer-based products such as polyvinyl chloride pipe; aggregates such as concrete; glass, including optical fiber; and lumber.

Federal agencies providing Federal financial assistance for infrastructure projects must implement the Buy America preferences set forth in 2 CFR part 184.

STATE OF DELAWARE
DEPARTMENT OF LABOR
DIVISION OF INDUSTRIAL AFFAIRS
OFFICE OF LABOR LAW ENFORCEMENT
PHONE: (302) 318-2769

Mailing Address:
252 Chapman Road
Suite 210
Newark, DE 19702

Located at:
252 Chapman Road
Suite 210
Newark, DE 19702

PREVAILING WAGES FOR **BUILDING CONSTRUCTION** EFFECTIVE MARCH 13, 2026

CLASSIFICATION	NEW CASTLE	KENT	SUSSEX
ASBESTOS WORKERS	30.70	37.78	55.01
BOILERMAKERS	91.87	46.61	68.52
BRICKLAYERS	68.29	68.29	68.29
CARPENTERS	64.06	64.06	52.30
CEMENT FINISHERS	96.91	68.92	53.44
ELECTRICAL LINE WORKERS	61.02	52.34	39.90
ELECTRICIANS	86.87	86.87	86.87
ELEVATOR CONSTRUCTORS	121.73	86.57	109.37
GLAZIERS	88.42	88.42	76.04
INSULATORS	71.54	71.54	71.54
IRON WORKERS	79.33	79.33	79.33
LABORERS	59.65	59.65	59.65
MILLWRIGHTS	91.00	91.00	73.10
PAINTERS	61.53	61.53	61.53
PILEDRIVERS	93.37	52.83	42.72
PLASTERERS	40.06	40.06	29.69
PLUMBERS/PIPEFITTERS/STEAMFITTERS	82.05	85.29	78.26
POWER EQUIPMENT OPERATORS	85.29	85.29	85.29
ROOFERS-COMPOSITION	36.41	31.28	33.64
ROOFERS-SHINGLE/SLATE/TILE	24.68	29.36	23.08
SHEET METAL WORKERS	87.84	87.84	87.84
SOFT FLOOR LAYERS	63.69	63.69	50.43
SPRINKLER FITTERS	77.63	77.63	77.63
TERRAZZO/MARBLE/TILE FNRS	73.75	73.75	84.10
TERRAZZO/MARBLE/TILE STRS	81.93	81.93	93.27
TRUCK DRIVERS	58.41	36.83	28.66

CERTIFIED: 10/5/2026 BY: Salina Chostad Jr
ADMINISTRATOR, OFFICE OF LABOR LAW ENFORCEMENT

NOTE: THESE RATES ARE PROMULGATED AND ENFORCED PURSUANT TO THE PREVAILING WAGE REGULATIONS ADOPTED BY THE DEPARTMENT OF LABOR ON APRIL 3, 1992.

CLASSIFICATIONS OF WORKERS ARE DETERMINED BY THE DEPARTMENT OF LABOR. FOR ASSISTANCE IN CLASSIFYING WORKERS, OR FOR A COPY OF THE REGULATIONS OR CLASSIFICATIONS, PHONE (302) 318-2769.

NON-REGISTERED APPRENTICES MUST BE PAID THE MECHANIC'S RATE.

PROJECT: C9004020007 Dental Health Center at Owens Campus, Sussex County

PREVAILING WAGE DEBARMENT LIST

The following contractors have been debarred for violations of the prevailing wage law 29Del.C. §6960 or other applicable State statutes.

Therefore, no public construction contract in this State shall be bid on, awarded to, or received by contractors and individuals on this list for a period of (3) three years from the date of the judgment or as deemed by a court of competent jurisdiction.

Contractor	Address	Date of Debarment
Mullen Brothers, Inc. and Daniel Mullen, individually	3375 Garnett Road, Boothwyn, PA 19060	Indefinite/ Civil Contempt
State Contractors Corporation, and Jose Oscar Rivera, individually	13004 Hathaway Drive Silver Spring, MD 20906	Indefinite/ 19 Del.C. 2374(f)
Green Granite and Jason Green, individually	604 Heatherbrooke Court Avondale, PA 19311	Indefinite/ Civil Contempt
Pro Image Landscaping, Inc. and Owner(s) individually	23 Commerce Street Wilmington, DE 19801 and/or 2 Cameo Road Claymont, DE 19703	Indefinite/19 Del.C. §108 & 10 Del.C. 542(c)
Liberty Mechanical, LLC and Owner(s), individually	2032 Duncan Road Wilmington, DE 19801	Indefinite/ 19 Del.C. 2374(f)
Integrated Mechanical and Fire Systems Inc. and Allison Sheldon, individually	4601 Governor Printz Boulevard Wilmington, DE 19809	Indefinite/19 Del.C. §108 & 10 Del.C. 542(c)
ACH 1, INC.	873 Salem Church Road Newark, DE 19702	Indefinite/19 Del.C.6960

Updated: July 6, 2022

"General Decision Number: DE20260009 05/18/2026

State: Delaware

Construction Types: Building

Counties: Delaware Counties of
Sussex

Modification Number	Publication Date
0	01/02/2026
1	05/18/2026

BOIL0013-009 01/01/2025

	Rates	Fringes
BOILERMAKER	$ 55.00	35.48

BRDE0001-001 05/01/2021

	Rates	Fringes
BRICKLAYER	$ 34.19	27.98

CARP0173-011 05/01/2025

	Rates	Fringes
CARPENTER (INCLUDES ACOUSTICAL CEILING INSTALLATION, DRYWALL HANGING, FORM WORK, METAL STUD INSTALLATION, SCAFFOLD BUILDING, EXCLUDES MASONRY/BRICK, AND EXCLUDES SOFT FLOOR LAYER)	$ 32.87	18.98

CARP0251-008 05/01/2025

	Rates	Fringes
SOFT FLOOR LAYER	$ 38.02	25.39

CARP1906-003 05/01/2025

	Rates	Fringes
MILLWRIGHT	$ 51.54	39.26

ELEC0313-002 06/03/2024

	Rates	Fringes

ELECTRICIAN (INCLUDES LOW VOLTAGE WIRING AND INSTALLATION OF ALARMS, HVAC/TEMPERATURE CONTROLS AND SOUND AND COMMUNICATION SYSTEMS).....$ 47.50 35.93

ELEV0005-003 01/01/2025

Rates Fringes
ELEVATOR MECHANIC FOOTNOTES FOR ELEVATOR MECHANICS: A. PAID VACATION: EMPLOYER CONTRIBUTES 8% OF BASIC HOURLY RATE FOR 5 YEARS OR MORE OF SERVICE OR 6% FOR 6 MONTHS TO 5 YEARS OF SERVICE. B. EIGHT PAID HOLIDAYS (PROVIDED EMPLOYEE HAS WORKED 5 CONSECUTIVE DAYS BEFORE AND THE WORKING DAY AFTER THE HOLIDAY): NEW YEARS'S DAY; MEMORIAL DAY; INDEPENDENCE DAY; LABOR DAY; VETERAN'S DAY; THANKSGIVING DAY AND THE FRIDAY AFTER THANKSGIVING DAY, AND CHRISTMAS DAY.....$ 71.85 38.44

ENGI0542-003 05/01/2025

Rates Fringes
POWER EQUIPMENT OPERATOR: FORKLIFT FOOTNOTE: A. PAID HOLIDAYS: NEW YEAR'S DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, THANKSGIVING DAY, CHRISTMAS DAY, AND ELECTION DAY (PROVIDED THE EMPLOYEE WORKS THE SCHEDULED WORK DAY FOLLOWING THE HOLIDAY.).....$ 48.73 32.23

IRON0451-003 07/01/2024

Rates Fringes
IRONWORKER: ORNAMENTAL AND REINFORCING THE FOLLOWING HOLIDAYS SHALL BE OBSERVED, AND WHEN WORK IS PERFORMED THEREON IT SHALL BE PAID FOR AT TWICE THE BASE WAGE RATE: NEW YEAR'S DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, THANKSGIVING DAY AND CHRISTMAS DAY.....$ 41.10 38.23

LABO0199-006 02/01/2024

Rates Fringes
LABORER: BACKFILLER, JACK HAMMER, MASON TENDER - BRICK, PIPELAYER, SCAFFOLD BUILDER (BRICK AND MASONRY), TAMPER (HAND HELD).....$ 29.45 25.70
LABORER (MASON TENDER - CEMENT/CONCRETE).....$ 31.45 25.70

PAIN0252-002 05/01/2025

Rates Fringes
GLAZIER.....$ 49.96 37.56

PLAS0008-006 05/01/2021

Rates Fringes

PLASTERER: FIREPROOFER.....$ 38.37 31.64

PLAS0592-009 05/01/2025

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER	$ 41.69	27.28

PLUM0074-003 09/30/2024

	Rates	Fringes
PIPEFITTER: INDUSTRIAL FOOTNOTE A: PAID HOLIDAYS: NEW YEAR'S DAY, MEMORIAL DAY,INDEPENDENCE DAY, THANKSGIVING DAY,LABOR DAY, CHRISTMAS DAY, AND GENERAL ELECTION DAY	$ 56.43	43.35

PLUM0486-001 12/16/2021

	Rates	Fringes
PIPEFITTER (INCLUDES HVAC PIPE INSTALLATION AND EXCLUDES INDUSTRIAL WORK)	$ 42.62	22.77

SFDE0669-002 04/01/2025

	Rates	Fringes
SPRINKLER FITTER (FIRE SPRINKLERS)	$ 46.47	29.56

SHEE0019-021 07/01/2020

	Rates	Fringes
SHEET METAL WORKER (INCLUDES HVAC DUCT INSTALLATION)	$ 33.63	40.60

SUDE2014-006 01/20/2016

	Rates	Fringes
TILE SETTER	$ 57.98	1.11
TILE FINISHER	$ 35.40	4.31
ROOFER, EXCLUDES INSTALLATION OF METAL ROOFS	$ 27.98	27.90
ROOFER (INSTALLATION OF METAL ROOFS ONLY)	$ 39.09	30.77
PLUMBER	$ 45.40	16.23
PAINTER (BRUSH AND ROLLER)	$ 40.57	0.94
OPERATOR: CRANE	$ 31.59	16.83
OPERATOR: BULLDOZER	$ 25.89	0.00
OPERATOR: BACKHOE/EXCAVATOR/TRACKHOE	$ 36.08	12.02
LABORER: COMMON OR GENERAL	$ 24.45	8.65
IRONWORKER, STRUCTURAL	$ 43.59	7.41

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

==========

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the

Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at https://www.dol.gov/agencies/whd/government-contracts.

Note: Executive Order 13658 generally applies to contracts subject to the Davis-Bacon Act that were awarded on or between January 1, 2015 and January 29, 2022, and that have not been renewed or extended on or after January 30, 2022. Executive Order 13658 does not apply to contracts subject only to the Davis-Bacon Related Acts regardless of when they were awarded. If a contract is subject to Executive Order 13658, the contractor must pay all covered workers at least $13.65 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract from May 11, 2026, through December 31, 2026. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than SU , UAVG , SA , or SC denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council

number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The SU identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

SU wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The SA identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007

01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the SA identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

a) a survey underlying a wage determination
b) an existing published wage determination
c) an initial WHD letter setting forth a position on a wage determination matter
d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an

interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

==========

END OF GENERAL DECISION

"

SECTION 00 81 13

GENERAL REQUIREMENTS

TABLE OF ARTICLES

1. GENERAL
2. OWNER
3. CONTRACTOR
4. ADMINISTRATION OF THE CONTRACT
5. SUBCONTRACTORS
6. CONSTRUCTION BY OWNER OR SEPARATE CONTRACTORS
7. CHANGES IN THE WORK
8. TIME
9. PAYMENTS AND COMPLETION
10. PROTECTION OF PERSONS AND PROPERTY
11. INSURANCE AND BONDS
12. UNCOVERING AND CORRECTION OF WORK
13. MISCELLANEOUS PROVISIONS
14. TERMINATION OR SUSPENSION OF THE CONTRACT

ARTICLE 1: GENERAL

1.1 CONTRACT DOCUMENTS

1.1.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary and what is required by one shall be as binding as if required by all. Performance by the Contractor shall be required to an extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results.

1.1.2 Work including material purchases shall not begin until the Contractor is in receipt of a bonafide State of Delaware Purchase Order. Any work performed or material purchases prior to the issuance of the Purchase Order is done at the Contractor's own risk and cost.

1.2 EQUALITY OF EMPLOYMENT OPPORTUNITY ON PUBLIC WORKS

1.2.1 For Public Works Projects financed in whole or in part by state appropriation the Contractor agrees that during the performance of this contract:

1. The Contractor will not discriminate against any employee or applicant for employment because of race, creed, sex, color, sexual orientation, gender identity or national origin. The Contractor will take positive steps to ensure that applicants are employed and that employees are treated during employment without regard to their race, creed, sex, color, sexual orientation, gender identity or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places available to employees and applicants for employment notices to be provided by the contracting agency setting forth this nondiscrimination clause.

2. The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, creed, sex, color, sexual orientation, gender identity or national origin."

ARTICLE 2: OWNER

(NO ADDITIONAL GENERAL REQUIREMENTS – SEE SUPPLEMENTARY GENERAL CONDITIONS)

ARTICLE 3: CONTRACTOR

3.1 Schedule of Values: The successful Bidder shall within twenty (20) days after receiving notice to proceed with the work, furnish to the Owner a complete schedule of values on the various items comprising the work.

3.2 Subcontracts: Upon approval of Subcontractors, the Contractor shall award their Subcontracts as soon as possible after the signing of their own contract and see that all material, their own and those of their Subcontractors, are promptly ordered so that the work will not be delayed by failure of materials to arrive on time.

3.3 Before commencing any work or construction, the General Contractor is to consult with the Owner as to matters in connection with access to the site and the allocation of Ground Areas for the various features of hauling, storage, etc.

3.4 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for and have control over construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract, unless the Contract Documents give other specific instructions.

3.5 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.

3.6 The Contractor warrants to the Owner that materials and equipment furnished will be new and of good quality, unless otherwise permitted, and that the work will be free from defects and in conformance with the Contract Documents. Work not conforming to these requirements, including substitutions not properly approved, may be considered defective. If required by the Owner, the Contractor shall furnish evidence as to the kind and quality of materials and equipment provided.

3.7 Unless otherwise provided, the Contractor shall pay all sales, consumer, use and other similar taxes, and shall secure and pay for required permits, fees, licenses, and inspections necessary for proper execution of the Work.

3.8 The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on performance of the Work. The Contractor shall promptly notify the Owner if the Drawings and Specifications are observed to be at variance therewith.

3.9 The Contractor shall be responsible to the Owner for the acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons performing portions of the Work under contract with the Contractor.

3.10 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract. At completion of the Work the Contractor shall remove from and about the Project all waste materials, rubbish, the Contractor's tools, construction equipment, machinery and surplus materials. The Contractor shall be responsible for returning all damaged areas to their original conditions.

3.11 STATE LICENSE AND TAX REQUIREMENTS

3.11.1 Each Contractor and Subcontractor shall be licensed to do business in the State of Delaware and shall pay all fees and taxes due under State laws. In conformance with Section 2503, Chapter 25, Title 30, Delaware Code, "the Contractor shall furnish the Delaware Department of Finance within ten (10) days after entering into any contract with a contractor or subcontractor not a resident of this State, a statement of total value of such contract or contracts together with the names and addresses of the contracting parties."

3.12 The Contractor shall comply with all requirements set forth in Section 6962, Chapter 69, Title 29 of the Delaware Code.

3.13 During the contract Work, the Contractor and each Subcontractor, shall implement an Employee Drug Testing Program in accordance with OMB Regulation 4104 -

"Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on "Large Public Works Projects". "Large Public Works" is based upon the current threshold required for bidding Public Works as set by the Purchasing and Contracting Advisory Council.

ARTICLE 4: ADMINISTRATION OF THE CONTRACT

4.1 CONTRACT SURETY

4.1.1 PERFORMANCE BOND AND LABOR AND MATERIAL PAYMENT BOND

4.1.2 All bonds will be required as follows unless specifically waived elsewhere in the Bidding Documents.

4.1.3 Contents of Performance Bonds – The bond shall be in the form approved by the Office of Management and Budget. The bond shall be conditioned upon the faithful compliance and performance by the successful bidder of each and every term and condition of the contract and the proposal, plans, specifications, and bid documents thereof. Each term and condition shall be met at the time and in the manner prescribed by the Contract, Bid documents and the specifications, including the payment in full to every person furnishing materiel or performing labor in the performance of the Contract, of all sums of money due the person for such labor and materiel. (The bond shall also contain the successful bidder's guarantee to indemnify and save harmless the State and the agency from all costs, damages and expenses growing out of or by reason of the Contract in accordance with the Contract.)

4.1.4 Invoking a Performance Bond – The agency may, when it considers that the interest of the State so requires, cause judgement to be confessed upon the bond.

4.1.5 Within twenty (20) days after the date of notice of award of contract, the Bidder to whom the award is made shall furnish a Performance Bond and Labor and Material Payment Bond, each equal to the full amount of the Contract price to guarantee the faithful performance of all terms, covenants and conditions of the same. The bonds are to be issued by an acceptable Bonding Company licensed to do business in the State of Delaware and shall be issued in duplicate.

4.1.6 Performance and Payment Bonds shall be maintained in full force (warranty bond) for a period of two (2) years after the date of the Certificate for Final Payment. The Performance Bond shall guarantee the satisfactory completion of the Project and that the Contractor will make good any faults or defects in his work which may develop during the period of said guarantees as a result of improper or defective workmanship, material or apparatus, whether furnished by themselves or their Sub-Contractors. The Payment Bond shall guarantee that the Contractor shall pay in full all persons, firms or corporations who furnish labor or material or both labor and material for, or on account of, the work included herein. The bonds shall be paid for by this Contractor. The Owner shall have the right to demand that the proof parties signing the bonds are duly authorized to do so.

4.2 FAILURE TO COMPLY WITH CONTRACT

4.2.1 If any firm entering into a contract with the State, or Agency that neglects or refuses to perform or fails to comply with the terms thereof, the Agency which signed the Contract may terminate the Contract and proceed to award a new contract in accordance with this Chapter 69, Title 29 of the Delaware Code or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond.

Nothing herein shall preclude the Agency from pursing additional remedies as otherwise provided by law.

4.3 CONTRACT INSURANCE AND CONTRACT LIABILITY

4.3.1 In addition to the bond requirements stated in the Bid Documents, each successful Bidder shall purchase adequate insurance for the performance of the Contract and, by submission of a Bid, agrees to indemnify and save harmless and to defend all legal or equitable actions brought against the State, any Agency, officer and/or employee of the State, for and from all claims of liability which is or may be the result of the successful Bidder's actions during the performance of the Contract.

4.3.2 The purchase or nonpurchase of such insurance or the involvement of the successful Bidder in any legal or equitable defense of any action brought against the successful Bidder based upon work performed pursuant to the Contract will not waive any defense which the State, its agencies and their respective officers, employees and agents might otherwise have against such claims, specifically including the defense of sovereign immunity, where applicable, and by the terms of this section, the State and all agencies, officers and employees thereof shall not be financially responsible for the consequences of work performed, pursuant to said contract.

4.4 RIGHT TO AUDIT RECORDS

4.4.1 The Owner shall have the right to audit the books and records of a Contractor or any Subcontractor under any Contract or Subcontract to the extent that the books and records relate to the performance of the Contract or Subcontract.

4.4.2 Said books and records shall be maintained by the Contractor for a period of seven (7) years from the date of final payment under the Prime Contract and by the Subcontractor for a period of seven (7) years from the date of final payment under the Subcontract.

ARTICLE 5: SUBCONTRACTORS

5.1 SUBCONTRACTING REQUIREMENTS

5.1.1 All contracts for the construction, reconstruction, alteration or repair of any public building (not a road, street or highway) shall be subject to the following provisions:

1. A contract shall be awarded only to a Bidder whose Bid is accompanied by a statement containing, for each Subcontractor category, the name and address (city or town and State only – street number and P.O. Box addresses not required) of the subcontractor whose services the Bidder intends to use in performing the Work and providing the material for such Subcontractor category.

2. A Bid will not be accepted nor will an award of any Contract be made to any Bidder which, as the Prime Contractor, has listed itself as the Subcontractor for any Subcontractor unless:

   A. It has been established to the satisfaction of the awarding Agency that the Bidder has customarily performed the specialty work of such Subcontractor category by artisans regularly employed by the Bidder's firm;

B. That the Bidder is duly licensed by the State to engage in such specialty work, if the State requires licenses; and

C. That the Bidder is recognized in the industry as a bona fide Subcontractor or Contractor in such specialty work and Subcontractor category.

5.1.2 The decision of the awarding Agency as to whether a Bidder who list itself as the Subcontractor for a Subcontractor category shall be final and binding upon all Bidders, and no action of any nature shall lie against any awarding agency or its employees or officers because of its decision in this regard.

5.1.3 After such a Contract has been awarded, the successful Bidder shall not substitute another Subcontractor for any Subcontractor whose name was set forth in the statement which accompanied the Bid without the written consent of the awarding Agency.

5.1.4 No Agency shall consent to any substitution of Subcontractors unless the Agency is satisfied that the Subcontractor whose name is on the Bidders accompanying statement:

A. Is unqualified to perform the work required;

B. Has failed to execute a timely reasonable Subcontract;

C. Has defaulted in the performance on the portion of the work covered by the Subcontract; or

D. Is no longer engaged in such business.

5.1.5 Should a Bidder be awarded a contract, such successful Bidder shall provide to the agency the taxpayer identification license numbers of such subcontractors. Such numbers shall be provided on the later of the date on which such subcontractor is required to be identified or the time the contract is executed. The successful Bidder shall provide to the agency to which it is contracting, within 30 days of entering into such public works contract, copies of all Delaware Business licenses of subcontractors and/or independent contractors that will perform work for such public works contract. However, if a subcontractor or independent contractor is hired or contracted more than 20 days after the Bidder entered the public works contract the Delaware Business license of such subcontractor or independent contractor shall be provided to the agency within 10 days of being contracted or hired.

5.1.6 The Contractor may employ additional Subcontractors on the jobsite only after submitting a copy of the Subcontractor's Employee Drug Testing Program to the Owner for approval. A Contractor or Subcontractor shall not commence work until the Owner has concluded its review and determined that the submitted Employee Drug Testing Program complies with OMB Regulation 4104.

5.2 PENALTY FOR SUBSTITUTION OF SUBCONTRACTORS

5.2.1 Should the Contractor fail to utilize any or all of the Subcontractors in the Contractor's Bid statement in the performance of the Work on the public bidding, the Contractor shall be penalized in the amount of (project specific amount*). The Agency may determine to deduct payments of the penalty from the Contractor or have the amount paid directly to the Agency. Any penalty amount assessed against the Contractor may be remitted or refunded, in whole or in part, by the Agency awarding the Contract, only if it is established to the satisfaction of the Agency that the Subcontractor in question has defaulted or is no longer engaged in such business. No claim for the remission or refund of any penalty shall be granted unless an

application is filed within one year after the liability of the successful Bidder accrues. All penalty amounts assessed and not refunded or remitted to the contractor shall be reverted to the State.

*one (1) percent of contract amount not to exceed $10,000

5.3 ASBESTOS ABATEMENT

5.3.1 The selection of any Contractor to perform asbestos abatement for State-funded projects shall be approved by the Office of Management and Budget, Division of Facilities Management pursuant to Chapter 78 of Title 16.

5.4 STANDARDS OF CONSTRUCTION FOR THE PROTECTION OF THE PHYSICALLY HANDICAPPED

5.4.1 All Contracts shall conform with the standard established by the Delaware Architectural Accessibility Board unless otherwise exempted by the Board.

5.5 CONTRACT PERFORMANCE

5.5.1 Any firm entering into a Public Works Contract that neglects or refuses to perform or fails to comply with its terms, the Agency may terminate the Contract and proceed to award a new Contract or may require the Surety on the Performance Bond to complete the Contract in accordance with the terms of the Performance Bond.

ARTICLE 6: CONSTRUCTION BY OWNER OR SEPARATE CONTRACTORS

6.1 The Owner reserves the right to simultaneously perform other construction or operations related to the Project with the Owner's own forces, and to award separate contracts in connection with other portions of the Project or other Projects at the same site.

6.2 The Contractor shall afford the Owner and other Contractors reasonable opportunity for access and storage of materials and equipment, and for the performance of their activities, and shall connect and coordinate their activities with other forces as required by the Contract Documents.

ARTICLE 7: CHANGES IN THE WORK

7.1 The Owner, without invalidating the Contract, may order changes in the Work consisting of Additions, Deletions, Modifications or Substitutions, with the Contract Sum and Contract completion date being adjusted accordingly. Such changes in the Work shall be authorized by written Change Order signed by the Professional, as the duly authorized agent, the Contractor and the Owner.

7.2 The Contract Sum and Contract Completion Date shall be adjusted only by a fully executed Change Order.

7.3 The additional cost, or credit to the Owner resulting from a change in the Work shall be by mutual agreement of the Owner, Contractor and the Architect. In all cases, this cost or credit shall be based on the ‘DPE’ wages required and the “invoice price” of the materials/equipment needed.

7.3.1 "DPE" shall be defined to mean "direct personnel expense". Direct payroll expense includes prevailing wage rates plus a maximum multiplier of 1.35 times DPE. For example, if the prevailing wage rate is $50/hour, the DPE would be $67.50/hour (50 x 1.35).

7.3.2 "Invoice price" of materials/equipment shall be defined to mean the actual cost of materials and/or equipment that is paid by the Contractor, (or subcontractor), to a material distributor, direct factory vendor, store, material provider, or equipment leasing entity. Rates for equipment that is leased and/or owned by the Contractor or subcontractor(s) shall not exceed those listed in the latest version of the "Means Building Construction Cost Data" publication.

7.3.3 In addition to the above:

7.3.3.1 The General Contractor is allowed a fifteen percent (15%) markup for overhead and profit for additional work performed by the General Contractor's own forces.

7.3.3.2 For additional subcontractor work, the Subcontractor is allowed a fifteen (15) percent overhead and profit on change order work above and beyond the direct costs stated previously. To this amount, the General Contractor will be allowed a mark-up not exceeding seven- and one-half percent (7.5%) on the subcontractor's work.

7.3.3.3 Where the Third Tier Contractor is going to be completing the additional work, the Third-Tier contractor will be allowed a markup of fifteen percent (15%) overhead and profit on changes order work above and beyond the direct costs stated previously. To this amount, the Subcontractor will be allowed a markup not to exceed seven and one-half percent (7.5%) on the Third-Tier Contractor's work and the General Contractor will be allowed a markup not to exceed seven and one-half percent (7.5%) of the amount of the Subcontractor's markup.

7.3.3.4 No additional costs shall be allowed for changes related to the Contractor's onsite superintendent/staff, or project manager, unless a change in the work changes the project duration and is identified by the CPM schedule. There will be no other costs associated with the change order.

7.3.3.5 These markups shall include all costs including, but not limited to: overhead, profit, bonds, insurance, supervision, etc.

ARTICLE 8: TIME

8.1 Time limits, if any, are as stated in the Project Manual. By executing the Agreement, the Contractor confirms that the stipulated limits are reasonable, and that the Work will be completed within the anticipated time frame.

8.2 If progress of the Work is delayed at any time by changes ordered by the Owner, by labor disputes, fire, unusual delay in deliveries, abnormal adverse weather conditions, unavoidable casualties or other causes beyond the Contractor's control, the Contract Time shall be extended for such reasonable time as the Owner may determine.

8.3 Any extension of time beyond the date fixed for completion of the construction and acceptance of any part of the Work called for by the Contract, or the occupancy of the building by the Owner, in whole or in part, previous to the completion shall not be deemed a waiver by the Owner of his right to annul or terminate the Contract for abandonment or delay in the matter provided for, nor relieve the Contractor of full responsibility

8.4 SUSPENSION AND DEBARMENT

8.4.1 Per Section 6962(d)(14), Title 29, Delaware Code, “Any Contractor who fails to perform a public works contract or complete a public works project within the time schedule established by the Agency in the Invitation To Bid, may be subject to Suspension or Debarment for one or more of the following reasons: a) failure to supply the adequate labor supply ratio for the project; b) inadequate financial resources; or, c) poor performance on the Project.”

8.4.2 “Upon such failure for any of the above stated reasons, the Agency that contracted for the public works project may petition the Director of the Office of Management and Budget for Suspension or Debarment of the Contractor. The Agency shall send a copy of the petition to the Contractor within three (3) working days of filing with the Director. If the Director concludes that the petition has merit, the Director shall schedule and hold a hearing to determine whether to suspend the Contractor, debar the Contractor or deny the petition. The Agency shall have the burden of proving, by a preponderance of the evidence, that the Contractor failed to perform or complete the public works project within the time schedule established by the Agency and failed to do so for one or more of the following reasons: a) failure to supply the adequate labor supply ratio for the project; b) inadequate financial resources; or, c) poor performance on the project. Upon a finding in favor of the Agency, the Director may suspend a Contractor from Bidding on any project funded, in whole or in part, with public funds for up to 1 year for a first offense, up to 3 years for a second offense and permanently debar the Contractor for a third offense. The Director shall issue a written decision and shall send a copy to the Contractor and the Agency. Such decision may be appealed to the Superior Court within thirty (30) days for a review on the record.”

8.5 RETAINAGE

8.5.1 Per Section 6962(d)(5) a.3, Title 29, Delaware Code: The Agency may at the beginning of each public works project establish a time schedule for the completion of the project. If the project is delayed beyond the completion date due to the Contractor’s failure to meet their responsibilities, the Agency may forfeit, at its discretion, all or part of the Contractor’s retainage.

8.5.2 This forfeiture of retainage also applies to the timely completion of the punchlist. A punchlist will only be prepared upon the mutual agreement of the Owner, Architect and Contractor. Once the punchlist is prepared, all three parties will by mutual agreement, establish a schedule for its completion. Should completion of the punchlist be delayed beyond the established date due to the Contractor’s failure to meet their responsibilities, the Agency may hold permanently, at its discretion, all or part of the Contractor’s retainage.

ARTICLE 9: PAYMENTS AND COMPLETION

9.1 APPLICATION FOR PAYMENT

9.1.1 Applications for payment shall be made upon AIA Document G702. There will be a five percent (5%) retainage on all Contractor's monthly invoices until completion of the project. This retainage may become payable upon receipt of all required closeout documentation, provided all other requirements of the Contract Documents have been met.

9.1.2 A date will be fixed for the taking of the monthly account of work done. Upon receipt of Contractor's itemized application for payment, such application will be audited, modified, if found necessary, and approved for the amount. Statement shall be submitted to the Owner.

9.1.3 Section 6516, Title 29 of the Delaware Code annualized interest is not to exceed 12% per annum beginning thirty (30) days after the “presentment” (as opposed to the date) of the invoice.

9.2 PARTIAL PAYMENTS

9.2.1 Any public works Contract executed by any Agency may provide for partial payments at the option of the Owner with respect to materials placed along or upon the sites or stored at secured locations, which are suitable for use in the performance of the contract.

9.2.2 When approved by the agency, partial payment may include the values of tested and acceptable materials of a nonperishable or noncontaminative nature which have been produced or furnished for incorporation as a permanent part of the work yet to be completed, provided acceptable provisions have been made for storage.

9.2.2.1 Any allowance made for materials on hand will not exceed the delivered cost of the materials as verified by invoices furnished by the Contractor, nor will it exceed the contract bid price for the material complete in place.

9.2.3 If requested by the Agency, receipted bills from all Contractors, Subcontractors, and material, men, etc., for the previous payment must accompany each application for payment. Following such a request, no payment will be made until these receipted bills have been received by the Owner.

9.3 SUBSTANTIAL COMPLETION

9.3.1 When the building has been made suitable for occupancy, but still requires small items of miscellaneous work, the Owner will determine the date when the project has been substantially completed.

9.3.2 If, after the Work has been substantially completed, full completion thereof is materially delayed through no fault of the Contractor, and without terminating the Contract, the Owner may make payment of the balance due for the portion of the Work fully completed and accepted. Such payment shall be made under the terms and conditions governing final payment that it shall not constitute a waiver of claims.

9.3.3 On projects where commissioning is included, the commissioning work as defined in the specifications must be complete prior to the issuance of substantial completion.

9.4 FINAL PAYMENT

9.4.1 Final payment, including the five percent (5%) retainage if determined appropriate, shall be made within thirty (30) days after the Work is fully completed and the Contract fully performed and provided that the Contractor has submitted the following closeout documentation (in addition to any other documentation required elsewhere in the Contract Documents):

9.4.1.1 Evidence satisfactory to the Owner that all payrolls, material bills, and other indebtedness connected with the work have been paid,

9.4.1.2 An acceptable RELEASE OF LIENS,

9.4.1.3 Copies of all applicable warranties,

9.4.1.4 As-built drawings,

9.4.1.5 Operations and Maintenance Manuals,

9.4.1.6 Instruction Manuals,

9.4.1.7 Consent of Surety to final payment.

9.4.1.8 The Owner reserves the right to retain payments, or parts thereof, for its protection until the foregoing conditions have been complied with, defective work corrected and all unsatisfactory conditions remedied.

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

10.1 The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract. The Contractor shall take all reasonable precautions to prevent damage, injury or loss to: workers, persons nearby who may be affected, the Work, materials and equipment to be incorporated, and existing property at the site or adjacent thereto. The Contractor shall give notices and comply with applicable laws ordinances, rules regulations, and lawful orders of public authorities bearing on the safety of persons and property and their protection from injury, damage, or loss. The Contractor shall promptly remedy damage and loss to property at the site caused in whole or in part by the Contractor, a Subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable.

10.2 The Contractor shall notify the Owner in the event any previously unknown hazardous material such as PCBs, asbestos, etc. is encountered on the project. The Owner will arrange with a qualified specialist for the identification, testing, removal, handling and protection against exposure or environmental pollution, to comply with applicable regulation laws and ordinances. The Contractor and Architect will not be required to participate in or to perform this operation. Upon completion of this work, the Owner will notify the Contractor and Architect in writing the area has been cleared and approved by the authorities in order for the work to proceed. The Contractor shall attach documentation from the authorities of said approval to the closeout documents to be submitted at the end of the project.

10.2.1 Any activities with the potential to disturb lead-based materials should be performed by the Contractor in accordance with OSHA regulations pertaining to Lead in Construction, 29 CFR 1926.62, Lead.

10.2.1.1 The Contractor shall notify the Owner in the event they encounter previously unknown material that they suspect may contain “lead”. The Owner will arrange with a qualified specialist for identification and testing and advise the Contractor of the results. In the case that testing identifies potential lead based materials, the contractor shall continue performance of the work that has the potential to disturb associated in accordance with OSHA regulations pertaining to Lead in Construction, 29 CFR 1926.62, Lead.

10.3 As required in the Hazardous Chemical Information Act of June 1984, all vendors supplying any materials that may be defined as hazardous, must provide Material Safety Data Sheets for those products. Any chemical product should be considered hazardous if it has a warning caution on the label relating to a potential physical or health hazard, if it is known to be present in the work place, and if employees may be exposed under normal conditions or

in any foreseeable emergency situation. Material Safety Data Sheets must be provided directly to the Owner along with the shipping slips that include those products.

10.4 The Contractor shall certify to the Owner that materials incorporated into the Work are free of all asbestos. This certification may be in the form of Material Safety Data Sheet (MSDS) provided by the product manufacturer for the materials used in construction, as specified or as provided by the Contractor.

ARTICLE 11: INSURANCE AND BONDS

11.1 The Contractor shall carry all insurance required by law, such as Unemployment Insurance, etc. The Contractor shall carry such insurance coverage as they desire on their own property such as a field office, storage sheds or other structures erected upon the project site that belong to them and for their own use. The Subcontractors involved with this project shall carry whatever insurance protection they consider necessary to cover the loss of any of their personal property, etc.

11.2 Upon being awarded the Contract, the Contractor shall obtain a minimum of two (2) copies of all required insurance certificates called for herein, and submit one (1) copy of each certificate, to the Owner, within 20 days of contract award.

11.3 Bodily Injury Liability and Property Damage Liability Insurance shall, in addition to the coverage included herein, include coverage for injury to or destruction of any property arising out of the collapse of or structural injury to any building or structure due to demolition work and evidence of these coverages shall be filed with and approved by the Owner.

11.4 The Contractor's Property Damage Liability Insurance shall, in addition to the coverage noted herein, include coverage on all real and personal property in their care, custody and control damaged in any way by the Contractor or their Subcontractors during the entire construction period on this project.

11.5 Builders Risk (including Standard Extended Coverage Insurance) on the existing building during the entire construction period, may be provided by the Contractor under this contract. The Owner shall insure the existing building and all of its contents and all this new alteration work under this contract during entire construction period for the full insurable value of the entire work at the site. Note, however, that the Contractor and their Subcontractors shall be responsible for insuring building materials (installed and stored) and their tools and equipment whenever in use on the project, against fire damage, theft, vandalism, etc.

11.6 Certificates of the insurance company or companies stating the amount and type of coverage, terms of policies, etc., shall be furnished to the Owner, within 20 days of contract award.

11.7 The Contractor shall, at their own expense, (in addition to the above) carry the following forms of insurance:

11.7.1 Contractor's Contractual Liability Insurance

Minimum coverage to be:

Bodily Injury

$1,000,000 for each occurrence

	$3,000,000	aggregate
Property Damage	$1,000,000	for each occurrence
	$3,000,000	aggregate

11.7.2 Contractor's Protective Liability Insurance

Minimum coverage to be:

Bodily Injury		
	$1,000,000	for each occurrence
	$3,000,000	aggregate
Property Damage	$1,000,000	for each occurrence
	$3,000,000	aggregate

11.7.3 Automobile Liability Insurance

Minimum coverage to be:

Bodily Injury	$1,000,000	for each person
	$1,000,000	for each occurrence
Property Damage	$500,000	per accident

11.7.4 Prime Contractor's and Subcontractors' policies shall include contingent and contractual liability coverage in the same minimum amounts as 11.7.1 above.

11.7.5 Workmen's Compensation (including Employer's Liability):

11.7.5.1 Minimum Limit on employer's liability to be as required by law.

11.7.5.2 Minimum Limit for all employees working at one site.

11.7.6 Certificates of Insurance must be filed with the Owner guaranteeing fifteen (15) days prior notice of cancellation, non-renewal, or any change in coverages and limits of liability shown as included on certificates.

11.7.7 Social Security Liability

11.7.7.1 With respect to all persons at any time employed by or on the payroll of the Contractor or performing any work for or on their behalf, or in connection with or arising out of the Contractor’s business, the Contractor shall accept full and exclusive liability for the payment of any and all contributions or taxes or unemployment insurance, or old age retirement benefits, pensions or annuities now or hereafter imposed by the Government of the United States and the State or political subdivision thereof, whether the same be measured by wages, salaries or other remuneration paid to such persons or otherwise.

11.7.7.2 Upon request, the Contractor shall furnish Owner such information on payrolls or employment records as may be necessary to enable it to fully comply with the law imposing the aforesaid contributions or taxes.

11.7.7.3 If the Owner is required by law to and does pay any and/or all of the aforesaid contributions or taxes, the Contractor shall forthwith reimburse the Owner for the entire amount so paid by the Owner.

ARTICLE 12: UNCOVERING AND CORRECTION OF WORK

12.1 The Contractor shall promptly correct Work rejected by the Owner or failing to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed or completed, and shall correct any Work found to be not in accordance with the requirements of the Contract Documents within a period of two years from the date of Substantial Completion, or by terms of an applicable special warranty required by the Contract Documents. The provisions of this Article apply to work done by Subcontractors as well as to Work done by direct employees of the Contractor.

12.2 At any time during the progress of the work, or in any case where the nature of the defects shall be such that it is not expedient to have them corrected, the Owner, at their option, shall have the right to deduct such sum, or sums, of money from the amount of the contract as they consider justified to adjust the difference in value between the defective work and that required under contract including any damage to the structure.

ARTICLE 13: MISCELLANEOUS PROVISIONS

13.1 CUTTING AND PATCHING

13.1.1 The Contractor shall be responsible for all cutting and patching. The Contractor shall coordinate the work of the various trades involved.

13.2 DIMENSIONS

13.2.1 All dimensions shown shall be verified by the Contractor by actual measurements at the project site. Any discrepancies between the drawings and specifications and the existing conditions shall be referred to the Owner for adjustment before any work affected thereby has been performed.

13.3 LABORATORY TESTS

13.3.1 Any specified laboratory tests of material and finished articles to be incorporated in the work shall be made by bureaus, laboratories or agencies approved by the Owner and reports of such tests shall be submitted to the Owner. The cost of the testing shall be paid for by the Contractor.

13.3.2 The Contractor shall furnish all sample materials required for these tests and shall deliver same without charge to the testing laboratory or other designated agency when and where directed by the Owner.

13.4 ARCHAEOLOGICAL EVIDENCE

13.4.1 Whenever, in the course of construction, any archaeological evidence is encountered on the surface or below the surface of the ground, the Contractor shall notify the authorities of the State Historic Preservation Office and suspend work in the immediate area for a reasonable time to permit those authorities, or persons designated by them, to examine the area and ensure the proper removal of the archaeological evidence for suitable preservation by the Division of Historical and Cultural Affairs.

13.5 GLASS REPLACEMENT AND CLEANING

13.5.1 The General Contractor shall replace without expense to the Owner all glass broken during the construction of the project. If job conditions warrant, at completion of the job the General Contractor shall have all glass cleaned and polished.

13.6 WARRANTY

13.6.1 For a period of two (2) years from the date of substantial completion, as evidenced by the date of final acceptance of the work, the contractor warrants that work performed under this contract conforms to the contract requirements and is free of any defect of equipment, material or workmanship performed by the contractor or any of his subcontractors or suppliers. However, manufacturer's warranties and guarantees, if for a period longer than two (2) years, shall take precedence over the above warranties. The contractor shall remedy, at his own expense, any such failure to conform or any such defect. The protection of this warranty shall be included in the Contractor's Performance Bond.

ARTICLE 14: TERMINATION OR SUSPENSION OF THE CONTRACT

14.1 If the Contractor defaults or persistently fails or neglects to carry out the Work in accordance with the Contract Documents or fails to perform a provision of the Contract, the Owner, after seven days written notice to the Contractor, may make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor. Alternatively, at the Owner's option, and the Owner may terminate the Contract and take possession of the site and of all materials, equipment, tools, and machinery thereon owned by the Contractor and may finish the Work by whatever method the Owner may deem expedient. If the costs of finishing the Work exceed any unpaid compensation due the Contractor, the Contractor shall pay the difference to the Owner.

14.2 “If the continuation of this Agreement is contingent upon the appropriation of adequate state, or federal funds, this Agreement may be terminated on the date beginning on the first fiscal year for which funds are not appropriated or at the exhaustion of the appropriation. The Owner may terminate this Agreement by providing written notice to the parties of such non-appropriation. All payment obligations of the Owner will cease upon the date of termination. Notwithstanding the foregoing, the Owner agrees that it will use its best efforts to obtain approval of necessary funds to continue the Agreement by taking appropriate action to request adequate funds to continue the Agreement.”

END OF SECTION

PAGE LEFT INTENTIONALLY BLANK

EMPLOYEE DRUG TESTING REPORT FORM
Period Ending:_____

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors who work on Large Public Works Contracts funded all or in part with public funds maintain testing data that includes but is not limited to the data elements below.

Project Number: _____

Project Name: _____

Contractor/Subcontractor Name: _____

Contractor/Subcontractor Address: _____
_____
_____

Number of employees who worked on the jobsite during the report period: _____

Number of employees subject to random testing during the report period: _____

Number of Negative Results _____ Number of Positive Results _____

Action taken on employee(s) in response to a failed or positive random test:
_____
_____
_____

Date: _____

This form is not required to be submitted to the Owner. Included as a reference to show information required to be maintained by the Contractor. The Owner shall have the right to periodically audit all Contractor and Subcontractor test results at the Contractor's or Subcontractor's offices (or by other means to make the data available for inspection by the Owner).

EMPLOYEE DRUG TESTING
REPORT OF POSITIVE RESULTS

4104 Regulations for the Drug Testing of Contractor and Subcontractor Employees Working on Large Public Works Projects requires that Contractors and Subcontractors who work on Large Public Works Contracts funded all or in part with public funds to notify the Owner in writing of a positive random drug test.

Project Number: _____

Project Name: _____

Contractor/Subcontractor Name: _____

Contractor/Subcontractor Address: _____
_____
_____

Name of employee with positive test result: _____

Last 4 digits of employee SSN: _____

Date test results received: _____

Action taken on employee in response to a positive test result:
_____
_____
_____

Authorized Representative of Contractor/Subcontractor: _____
(typed or printed)

Authorized Representative of Contractor/Subcontractor: _____
(signature)

Date: _____

This form shall be sent by mail to the Owner within 24 hours of receipt of test results. Enclose this test results form in a sealed envelope with the notation "Drug Testing Form – DO NOT OPEN" on the face thereof and place in a separate mailing envelope.

END OF SECTIOND

DELAWARE TECHNICAL COMMUNITY COLLEGE
#DTCC C9004020007

AFFIDAVIT OF CRAFT TRAINING COMPLIANCE

We, the contractor, hereby certify that we and all applicable subcontractors will abide by the contractor and subcontractor craft training requirements outlined below for the duration of the contract. Craft training must be provided by a contractor and/or subcontractor for each craft on a project for which there are Delaware Department of Labor approved and registered training programs. A list of crafts for which there are approved and registered training programs is maintained by the Delaware Department of Labor and can be found at https://laborfiles.delaware.gov/main/det/apprenticeship/DE%20Craft%20Training%20Occupation%20List%20Effective%20March%201%202022.pdf. If you have questions regarding craft training programs, please submit them in writing to the Delaware Department of Labor at: apprenticeship@delaware.gov. The Craft Training Compliance Affidavit must be submitted prior to contract execution.

In accordance with Title 29, Chapter 69, Section 6962(c)(13) of the Delaware Code, contractors and subcontractors must provide craft training for journeyman and apprentice levels if **all** of the following apply:

A. A project meets the prevailing wage requirement under Title 29, Chapter 69, Section 6960 of the Delaware Code.
B. The contractor employs 10 or more total employees.
C. The project is not a federal highway project

Failure to provide required craft training on the project may subject the successful contractor and/or subcontractor(s) to penalties as outlined in Title 29, Chapter 69, Section 6962(c)(13) of the Delaware Code.

Craft(s)

_____

Contractor Name: _____

Contractor Address: _____

_____

_____

Contractor Program Registration Number(s) _____
On this line also indicate whether DE, Other State (identify) or US Registration Number

Or

☐ **Craft Training requirements are not applicable because:** _____

Authorized Representative (typed or printed): _____

Authorized Representative (signature): _____

Title: _____

Sworn to and Subscribed before me this _____day of _____ 20____.

My Commission expires _____. NOTARY PUBLIC _____ _____.

THIS PAGE MUST BE SIGNED AND NOTARIZED TO BE CONSIDERED.

END OF SECTION

SECTION 01 10 00
SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Phased construction.
4. Work performed by Owner.
5. Owner's product purchase contracts.
6. Owner-furnished/Contractor-installed (OFCI) products.
7. Owner-furnished/Owner-installed (OFOI) products.
8. Contractor-furnished/Owner-installed (CFOI) products.
9. Contractor's use of site and premises.
10. Coordination with occupants.
11. Work restrictions.
12. Specification and Drawing conventions.
13. Miscellaneous provisions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.
2. Section 017300 "Execution" for coordination of Owner-installed products.

1.2 DEFINITIONS

A. Work Package: A group of specifications, drawings, and schedules prepared by the design team to describe a portion of the Project Work for pricing, permitting, and construction.

1.3 PROJECT INFORMATION

A. Project Identification: Dental Health Center At Carter Partnership Center Georgetown Campus.

1. Project Location: 21225 College Drive, Georgetown, DE 19947.

B. Owner: Delaware Technical Community College.

1. Owner's Representative: Mark DeVore.

2. Owner Address: 21179 College Drive, Georgetown, DE 19947

C. Architect: Tevebaugh Architecture.

D. Architect's Consultants: Architect has retained the following design professionals, who have prepared designated portions of the Contract Documents:

1. Mechanical & Electrical: Gipe Engineering.

2. Structural Engineering: DCI Engineers

E. Web-Based Project Software: Project software will be used for purposes of managing communication and documents during the construction stage.

1. See Section 013100 "Project Management and Coordination" for requirements for using web-based Project software.

1.4 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of Project is defined by the Contract Documents and includes, but is not limited to, the following:

Comprehensive interior and exterior improvements, including new architectural finishes, millwork and carpentry, mechanical and electrical upgrades, concrete trenching and patching, limited roofing repairs, minor structural modifications to support the new program requirements, and other Work indicated in the Contract Documents.

B. Type of Contract:

1. Project will be constructed under a single prime contract.

1.5 WORK UNDER OWNER'S SEPARATE CONTRACTS

A. Work with Separate Contractors: Cooperate fully with Owner's separate contractors, so work on those contracts may be carried out smoothly, without interfering with or delaying Work under this Contract or other contracts. Coordinate the Work of this Contract with work performed under Owner's separate contracts.

B. Concurrent Work: Owner will award separate contract(s) for the following construction operations at Project site. Those operations will be conducted simultaneously with Work under this Contract.

1. Security and access control supplier and installer: Work to completed simultaneously with work under this contract.

1.6 OWNER-FURNISHED/CONTRACTOR-INSTALLED (OFCI) PRODUCTS

A. Owner's Responsibilities: Owner will furnish products indicated and perform the following, as applicable:

1. Provide to Contractor Owner-reviewed Product Data, Shop Drawings, and Samples.
2. Provide for delivery of Owner-furnished products to Project site.
3. Upon delivery, inspect, with Contractor present, delivered items.

a. If Owner-furnished products are damaged, defective, or missing, arrange for replacement.

4. Obtain manufacturer's inspections, service, and warranties.
5. Inform Contractor of earliest available delivery date for Owner-furnished products.

B. Contractor's Responsibilities: The Work includes the following, as applicable:

1. Designate delivery dates of Owner-furnished products in Contractor's construction schedule, utilizing Owner-furnished earliest available delivery dates.
2. Review Owner-reviewed Product Data, Shop Drawings, and Samples, noting discrepancies and other issues in providing for Owner-furnished products in the Work.
3. Receive, unload, handle, store, protect, and install Owner-furnished products.
4. Make building services connections for Owner-furnished products.
5. Protect Owner-furnished products from damage during storage, handling, and installation and prior to Substantial Completion.
6. Repair or replace Owner-furnished products damaged following receipt.

C. Owner-Furnished/Contractor-Installed (OFCI) Products:

1. Wall mounted dispensers and glove box holders.

1.7 OWNER-FURNISHED/OWNER-INSTALLED (OFOI) PRODUCTS

A. The Owner will furnish and install products indicated on the contract documents.

B. Owner-Furnished/Owner-Installed (OFOI) Products:

1. Dental and healthcare equipment.
2. Furniture.

1.8 CONTRACTOR'S USE OF SITE AND PREMISES

A. Unrestricted Use of Site: Contractor shall have full use of Project site for construction operations during construction period. Contractor's use of Project

site is limited only by Owner's right to perform work or to retain other contractors on portions of Project.

B. Limits on Use of Site: Limit use of Project site to areas within the Contract limits indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1. Driveways, Walkways and Entrances: Keep driveways loading areas, and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or for storage of materials.

a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.

C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

D. Condition of Existing Grounds: Maintain portions of existing grounds, landscaping, and hardscaping affected by construction operations throughout construction period. Repair damage caused by construction operations.

1.9 COORDINATION WITH OCCUPANTS

A. Partial Owner Occupancy: Owner will occupy the premises during entire construction period, with the exception of areas under construction. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's operations. Maintain existing exits unless otherwise indicated.

1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and authorities having jurisdiction.
2. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.

1.10 WORK RESTRICTIONS

A. Comply with restrictions on construction operations.

1. Comply with limitations on use of public streets, work on public streets, rights of way, and other requirements of authorities having jurisdiction.

B. On-Site Work Hours: Limit work to between 7 a.m. to 4 p.m., Monday through Friday, unless otherwise indicated. Work hours may be modified to meet Project

requirements if approved by Owner and authorities having jurisdiction.

1. Hours for Utility Shutdowns: Shall be limited to off hours.

C. On-Site Work Day Restrictions: Do not perform work resulting in utility shutdowns or resulting in noisy activity on-site during work black-out days indicated in Document 003113 "Preliminary Schedules."

D. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging for temporary utility services according to requirements indicated:

1. Notify Owner not less than Insert number days in advance of proposed utility interruptions.
2. Obtain Owner's written permission before proceeding with utility interruptions.

E. Noise, Vibration, Dust, and Odors: Coordinate operations that may result in high levels of noise and vibration, dust, odors, or other disruption to Owner occupancy with Owner.

1. Notify Owner not less than two days in advance of proposed disruptive operations.
2. Obtain Owner's written permission before proceeding with disruptive operations.

F. Smoking and Controlled Substance Restrictions: Use of tobacco products , alcoholic beverages, and other controlled substances on Owner's property is not permitted.

G. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.

H. Employee Screening: Comply with Owner's requirements for drug and background screening of Contractor personnel working on Project site.

1. Maintain list of approved screened personnel with Owner's representative.

1.11 SPECIFICATION AND DRAWING CONVENTIONS

A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
2. Text Color: Text used in the Specifications, including units of measure, manufacturer and product names, and other text may appear in multiple

colors or underlined as part of a hyperlink; no emphasis is implied by text with these characteristics.

3. Hypertext: Text used in the Specifications may contain hyperlinks. Hyperlinks may allow for access to linked information that is not residing in the Specifications. Unless otherwise indicated, linked information is not part of the Contract Documents.
4. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

B. Division 00 Contracting Requirements: General provisions of the Contract, including General and Supplementary Conditions, apply to all Sections of the Specifications.

C. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

D. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:

1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
2. Abbreviations: Materials and products are identified by abbreviations scheduled on Drawings and published as part of the U.S. National CAD Standard.
3. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 10 00

SECTION 01 21 00
ALLOWANCES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements governing allowances.

B. Types of allowances include the following:

1. Contingency allowances.

C. Related Requirements:

1. Section 012600 "Contract Modification Procedures" for procedures for submitting and handling Change Orders.

1.2 DEFINITIONS

A. Allowance: A quantity of work or dollar amount included in the Contract, established in lieu of additional requirements, used to defer selection of actual materials and equipment to a later date when direction will be provided to Contractor. If necessary, additional requirements will be issued by Change Order.

1.3 SELECTION AND PURCHASE

A. At the earliest practical date after award of the Contract, advise Architect of the date when final selection, or purchase and delivery, of each product or system described by an allowance must be completed by the Owner to avoid delaying the Work.

B. At Architect's request, obtain proposals for each allowance for use in making final selections. Include recommendations that are relevant to performing the Work.

C. Purchase products and systems selected by Architect from the designated supplier.

1.4 ACTION SUBMITTALS

A. Submit proposals for purchase of products or systems included in allowances in the form specified for Change Orders.

1.5 INFORMATIONAL SUBMITTALS

A. Submit invoices or delivery slips to show actual quantities of materials delivered to the site for use in fulfillment of each allowance.

B. Submit time sheets and other documentation to show labor time and cost for installation of allowance items that include installation as part of the allowance.

C. Coordinate and process submittals for allowance items in same manner as for other portions of the Work.

1.6 CONTINGENCY ALLOWANCES

A. Use the contingency allowance only as directed by Architect for Owner's purposes and only by Change Orders that indicate amounts to be charged to the allowance.

B. Contractor's overhead, profit, and related costs for products and equipment ordered by Owner under the contingency allowance are included in the allowance and are not part of the Contract Sum. These costs include delivery, installation, taxes, insurance, equipment rental, and similar costs.

C. Change Orders authorizing use of funds from the contingency allowance will include Contractor's related costs and reasonable overhead and profit.

D. At Project closeout, credit unused amounts remaining in the contingency allowance to Owner by Change Order.

1.7 ADJUSTMENT OF ALLOWANCES

A. Allowance Adjustment: To adjust allowance amounts, prepare a Change Order proposal based on the difference between purchase amount and the allowance, multiplied by final measurement of work-in-place where applicable. If applicable, include reasonable allowances for cutting losses, tolerances, mixing wastes, normal product imperfections, required maintenance materials, and similar margins.

1. Include installation costs in purchase amount only where indicated as part of the allowance.
2. If requested, prepare explanation and documentation to substantiate distribution of overhead costs and other markups.
3. Submit substantiation of a change in scope of Work, if any, claimed in Change Orders related to unit-cost allowances.
4. Owner reserves the right to establish the quantity of work-in-place by independent quantity survey, measure, or count.

B. Submit claims for increased costs due to a change in the scope or nature of the allowance described in the Contract Documents, whether for the purchase order amount or Contractor's handling, labor, installation, overhead, and profit.

1. Do not include Contractor's or subcontractor's indirect expense in the Change Order cost amount unless it is clearly shown that the nature or extent of Work has changed from what could have been foreseen from information in the Contract Documents.
2. No change to Contractor's indirect expense is permitted for selection of higher- or lower-priced materials or systems of the same scope and nature as originally indicated.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

3.2 PREPARATION

A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

A. Allowance No. 1: Contingency Allowance: Include a contingency allowance of $20,000.00 for use according to Owner's written instructions.

END OF SECTION 01 21 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 01 21 16
ALLOWANCE AUTHORIZATION FORM

Project: Delaware Technical Community College Owen Campus Dental Health Center at the Carter Partnership Building

Architect: Tevebaugh Architecture Project No. DTCC C90040020007

Contractor: _____

AAA No.: _____ Initiation Date: _____

The Allowance is allocated as follows:

Bidders to carry contingency allowance $20,000 for unforeseen conditions.

Total original Contract Allowance was:	$ 20,000
Amount of Contract Allowance Access previously authorized:	$ _____
Adjusted Contract Allowance prior to this authorization is:	$ _____
The amount of available Allowance will Decrease by this Access Authorization:	$ _____
The remaining Contract Allowance, after this Access Authorization will be:	$ _____

Recommended by:
Architect

By (Signature): _____

Date: _____

Accepted by:
Contractor

By (Signature): _____

Date: _____

Approved by:
Owner

By (Signature): _____

Date: _____

END OF SECTION

THIS PAGE LEFT INTENTIONALLY BLANK

SECTION 01 23 00
ALTERNATES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for alternates.

1.2 DEFINITIONS

A. Alternate: An amount proposed by bidders and stated on the Bid Form for certain work defined in the bidding requirements that may be added to or deducted from the base bid amount if the Owner decides to accept a corresponding change either in the amount of construction to be completed or in the products, materials, equipment, systems, or installation methods described in the Contract Documents.

1. Alternates described in this Section are part of the Work only if enumerated in the Agreement.
2. The cost or credit for each alternate is the net addition to or deduction from the Contract Sum to incorporate alternates into the Work. No other adjustments are made to the Contract Sum.

1.3 PROCEDURES

A. Coordination: Revise or adjust affected adjacent work as necessary to completely integrate work of the alternate into Project.

1. Include, as part of each alternate, miscellaneous devices, accessory objects, and similar items incidental to or required for a complete installation, whether or not indicated as part of alternate.

B. Execute accepted alternates under the same conditions as other Work of the Contract.

C. Schedule: A Part 3 "Schedule of Alternates" Article is included at the end of this Section. Specification Sections referenced in schedule contain requirements for materials necessary to achieve the work described under each alternate.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION

3.1 SCHEDULE OF ALTERNATES

A. Alternate No. 1: ATC System by Siemens Controls.

1. Base Bid: **Provide ATC system and integration by any listed ATC vendor/manufacturer** as as specified in Section 230900 " Instrumentation and Controls of HVAC and Plumbing Systems."Base Bid ATC Vendor _____.
2. Alternate: Provide additional costs, if any, for ATC system by Siemens Controls as specified in Section 230900 " Instrumentation and Controls of HVAC and Plumbing Systems" and integrate/upgrade existing ATC system. If Siemens Controls is the low ATC subcontractor then the alternate value on the bid form shall be listed as zero ($0) dollars.

END OF SECTION 01 23 00

SECTION 01 25 00
SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of This Section Includes: Administrative and procedural requirements for substitutions.

B. Related Requirements:

1. Document 002600 "Procurement Substitution Procedures" for requirements for substitution requests prior to award of Contract.
2. Section 012100 "Allowances" for products selected under an allowance.
3. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents.

1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required to meet other Project requirements but may offer advantage to Contractor or Owner.

1.3 ACTION SUBMITTALS

A. Substitution Requests: Submit documentation identifying product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Substitution Request Form: Use form acceptable to Architect.
2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:

a. Statement indicating why specified product or fabrication or installation method cannot be provided, if applicable.
b. Coordination of information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to

accommodate proposed substitution.

c. Detailed comparison of significant qualities of proposed substitutions with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes, such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
e. Samples, where applicable or requested.
f. Certificates and qualification data, where applicable or requested.
g. List of similar installations for completed projects, with project names and addresses as well as names and addresses of architects and owners.
h. Material test reports from a qualified testing agency, indicating and interpreting test results for compliance with requirements indicated.
i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
j. Detailed comparison of Contractor's construction schedule using proposed substitutions with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
k. Cost information, including a proposal of change, if any, in the Contract Sum.
l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents, except as indicated in substitution request, is compatible with related materials and is appropriate for applications indicated.
m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.

3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor [**through Construction Manager**] of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

   a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
   b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.5 PROCEDURES

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

1.6 SUBSTITUTIONS

A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.

1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:

a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
b. Requested substitution provides sustainable design characteristics that specified product provided for compliance with LEED requirements.
c. Requested substitution provides sustainable design characteristics that specified product provided for compliance with IgCC requirements.
d. Requested substitution provides sustainable design characteristics that specified product provided for compliance with Green Globes requirements.
e. Substitution request is fully documented and properly submitted.
f. Requested substitution will not adversely affect Contractor's construction schedule.
g. Requested substitution has received necessary approvals from authorities having jurisdiction.
h. Requested substitution is compatible with other portions of the Work.
i. Requested substitution has been coordinated with other portions of the Work.
j. Requested substitution provides specified warranty.
k. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

B. Substitutions for Convenience:

1. Not allowed unless otherwise indicated.
2. Architect will consider requests for substitution if received within 60 days after the Notice to Proceed. Requests received after that time may be considered or rejected at discretion of Architect.

    a. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:

        1) Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
        2) Requested substitution does not require extensive revisions to the Contract Documents.
        3) Requested substitution is consistent with the Contract Documents and will produce indicated results.
        4) Requested substitution provides sustainable design characteristics that specified product provided for compliance with LEED requirements.
        5) Substitution request is fully documented and properly submitted.
        6) Requested substitution will not adversely affect Contractor's construction schedule.
        7) Requested substitution has received necessary approvals from authorities having jurisdiction.
        8) Requested substitution is compatible with other portions of the Work.
        9) Requested substitution has been coordinated with other portions of the Work.
        10) Requested substitution provides specified warranty.
        11) If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 25 00

SECTION 01 26 00
CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

B. Related Requirements:

1. Section 012500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.

1.2 MINOR CHANGES IN THE WORK

A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on form included in Project Manual.

1.3 PROPOSAL REQUESTS

A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.

1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
2. Within time specified in Proposal Request or 20 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.

a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
c. Include costs of labor and supervision directly attributable to the change.
d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract

Time.

e. Quotation Form: Use forms acceptable to Architect.

B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.

1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
7. Proposal Request Form: Use form acceptable to Architect.

1.4 ADMINISTRATIVE CHANGE ORDERS

A. Allowance Adjustment: See Section 012100 "Allowances" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect actual costs of allowances.

1.5 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Change Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 26 00

SECTION 01 29 00
PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Requirements:

1. Document 004373 "Proposed Schedule of Values Form" for requirements for furnishing proposed schedule of values with bid.
2. Section 012100 "Allowances" for procedural requirements governing the handling and processing of allowances.
3. Section 012200 "Unit Prices" for administrative requirements governing the use of unit prices.
4. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
5. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.3 SCHEDULE OF VALUES

A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.

1. Coordinate line items in the schedule of values with items required to be indicated as separate activities in Contractor's construction schedule.
2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.

3. Subschedules for Separate Elements of Work: Where the Contractor's construction schedule defines separate elements of the Work, provide subschedules showing values coordinated with each element.

B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.

1. Identification: Include the following Project identification on the schedule of values:

    a. Project name and location.
    b. Owner's name.
    c. Owner's Project number.
    d. Name of Architect.
    e. Architect's Project number.
    f. Contractor's name and address.
    g. Date of submittal.

2. Arrange schedule of values consistent with format of AIA Document G703.
3. Arrange the schedule of values in tabular form, with separate columns to indicate the following for each item listed:

    a. Related Specification Section or division.
    b. Description of the Work.
    c. Name of subcontractor.
    d. Name of manufacturer or fabricator.
    e. Name of supplier.
    f. Change Orders (numbers) that affect value.
    g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent. Round dollar amounts to whole dollars, with total equal to Contract Sum.

        1) Labor.
        2) Materials.
        3) Equipment.

4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
5. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.

    a. Differentiate between items stored on-site and items stored off-site.

6. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.

7. Overhead Costs, Proportional Distribution: Include total cost and proportionate share of general overhead and profit for each line item.
8. Overhead Costs, Separate Line Items: Show cost of temporary facilities

and other major cost items that are not direct cost of actual work-in-place as separate line items.

9. Temporary Facilities: Show cost of temporary facilities and other major cost items that are not direct cost of actual work-in-place as separate line items.
10. Closeout Costs. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
11. Schedule of Values Revisions: Revise the schedule of values when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive.

1.4 APPLICATIONS FOR PAYMENT

A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments, as certified by Architect and paid for by Owner.

B. Payment Application Times: The date for each progress payment is indicated in the Owner/Contractor Agreement. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.

C. Payment Application Times: Submit Application for Payment to Architect by the 5 of the month. The period covered by each Application for Payment is one month, ending on the last day of the month.

1. Submit draft copy of Application for Payment seven days prior to due date for review by Architect.

D. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.

E. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.

F. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.

1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment for stored materials.
2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
3. Provide summary documentation for stored materials indicating the following:

    a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
    b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
    c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.

G. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.

1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.

H. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.

1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
2. When an application shows completion of an item, submit conditional final or full waivers.
3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
5. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.

I. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:

1. List of subcontractors.
2. Schedule of values.
3. Contractor's construction schedule (preliminary if not final).
4. Combined Contractor's construction schedule (preliminary if not final) incorporating Work of multiple contracts, with indication of acceptance of schedule by each Contractor.
5. Products list (preliminary if not final).

6. Sustainable design action plans, including preliminary project materials cost data.
7. Schedule of unit prices.
8. Submittal schedule (preliminary if not final).
9. List of Contractor's staff assignments.
10. List of Contractor's principal consultants.
11. Copies of building permits.
12. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
13. Initial progress report.
14. Report of preconstruction conference.
15. Certificates of insurance and insurance policies.
16. Performance and payment bonds.
17. Data needed to acquire Owner's insurance.

J. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.

    a. Complete administrative actions, submittals, and Work preceding this application, as described in Section 017700 "Closeout Procedures."

2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

K. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:

1. Evidence of completion of Project closeout requirements.
2. Certification of completion of final punch list items.
3. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
4. Updated final statement, accounting for final changes to the Contract Sum.
5. AIA Document G706.
6. AIA Document G706A.
7. AIA Document G707.
8. Evidence that claims have been settled.
9. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
10. Final liquidated damages settlement statement.
11. Proof that taxes, fees, and similar obligations are paid.

12. Waivers and releases.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 29 00

SECTION 01 32 00
CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:

1. Contractor's Construction Schedule.
2. Site condition reports.
3. Unusual event reports.

B. Related Requirements:

1. Section 012900 "Payment Procedures" for schedule of values and requirements for use of cost-loaded schedule for Applications for Payment.
2. Section 014000 "Quality Requirements" for schedule of tests and inspections.

1.2 DEFINITIONS

A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction Project. Activities included in a construction schedule consume time and resources.

1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
2. Predecessor Activity: An activity that precedes another activity in the network.
3. Successor Activity: An activity that follows another activity in the network.

B. Cost Loading: The allocation of the schedule of values for completing an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum.

C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine the critical path of Project and when activities can be performed.

D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.

E. Event: The starting or ending point of an activity.

F. Float: The measure of leeway in starting and completing an activity.

1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

G. Resource Loading: The allocation of labor and equipment necessary for completing an activity as scheduled.

1.3 INFORMATIONAL SUBMITTALS

A. Format for Submittals: Submit required submittals in the following format:

1. Working electronic copy of schedule file.
2. PDF file.

B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.

1. Submit a working digital copy of schedule, using software indicated, and labeled to comply with requirements for submittals.

C. Construction Schedule Updating Reports: Submit with Applications for Payment.

D. Daily Construction Reports: Submit at weekly intervals.

E. Site Condition Reports: Submit at time of discovery of differing conditions.

F. Unusual Event Reports: Submit at time of unusual event.

G. Qualification Data: For scheduling consultant.

1.4 QUALITY ASSURANCE

A. Scheduling Consultant Qualifications: An experienced specialist in CPM scheduling and reporting, with capability of producing CPM reports and diagrams within 24 hours of Architect's request.

B. Prescheduling Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to the preliminary construction schedule and Contractor's Construction Schedule, including, but not limited to,

the following:

1. Review software limitations and content and format for reports.
2. Verify availability of qualified personnel needed to develop and update schedule.
3. Review delivery dates for Owner-furnished products.
4. Review schedule for work of Owner's separate contracts.
5. Review submittal requirements and procedures.
6. Review time required for review of submittals and resubmittals.
7. Review requirements for tests and inspections by independent testing and inspecting agencies.
8. Review time required for Project closeout and Owner startup procedures, including commissioning activities.
9. Review and finalize list of construction activities to be included in schedule.
10. Review procedures for updating schedule.

1.5 COORDINATION

A. Coordinate Contractor's Construction Schedule with the schedule of values, list of subcontracts, submittal schedule, progress reports, payment requests, and other required schedules and reports.

1. Secure time commitments for performing critical elements of the Work from entities involved.
2. Coordinate each construction activity in the network with other activities, and schedule them in proper sequence.

1.6 CONTRACTOR'S CONSTRUCTION SCHEDULE

A. Computer Scheduling Software: Prepare schedules using current version of a program that is capable of managing construction schedules.

B. Time Frame: Extend schedule from date established for the Notice of Award to date of Final Completion.

1. Contract completion date to not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.

C. Activities: Treat each floor or separate area as a separate numbered activity for each main element of the Work. Comply with the following:

1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
2. Temporary Facilities: Indicate start and completion dates for the following as applicable:

a. Securing of approvals and permits required for performance of the

Work.
b. Temporary facilities.
c. Construction of mock-ups, prototypes and samples.
d. Owner interfaces and furnishing of items.
e. Interfaces with Separate Contracts.
f. Regulatory agency approvals.
g. Punch list.

3. Procurement Activities: Include procurement process activities for the following long lead-time items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.

4. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's Construction Schedule with submittal schedule.
5. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
6. Commissioning Time: Include no fewer than 15 days for commissioning.
7. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
8. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and Final Completion.

D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Phasing: Arrange list of activities on schedule by phase.

2. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
3. Products Ordered in Advance: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
4. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Section 011000 "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
5. Work Restrictions: Show the effect of the following items on the schedule:

a. Coordination with existing construction.
b. Limitations of continued occupancies.
c. Uninterruptible services.
d. Partial occupancy before Substantial Completion.
e. Use-of-premises restrictions.
f. Provisions for future construction.
g. Seasonal variations.
h. Environmental control.

6. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:

    a. Subcontract awards.
    b. Submittals.
    c. Purchases.
    d. Mockups.
    e. Fabrication.
    f. Sample testing.
    g. Deliveries.
    h. Installation.
    i. Tests and inspections.
    j. Adjusting.
    k. Curing.
    l. Building flush-out.
    m. Startup and placement into final use and operation.
    n. Commissioning.

7. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:

    a. Structural completion.
    b. Temporary enclosure and space conditioning.
    c. Permanent space enclosure.
    d. Completion of mechanical installation.
    e. Completion of electrical installation.
    f. Substantial Completion.

E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and Final Completion, and the following interim milestones:

F. Cost Correlation: Superimpose a cost correlation timeline, indicating planned and actual costs. On the line, show planned and actual dollar volume of the Work performed as of planned and actual dates used for preparation of payment requests.

1. See Section 012900 "Payment Procedures" for cost reporting and payment procedures.

G. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:

1. Unresolved issues.
2. Unanswered Requests for Information.
3. Rejected or unreturned submittals.
4. Notations on returned submittals.
5. Pending modifications affecting the Work and the Contract Time.

H. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.

1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
3. As the Work progresses, indicate Final Completion percentage for each activity.

I. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, equipment required to achieve compliance, and date by which recovery will be accomplished.

J. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.

1. Post copies in Project meeting rooms and temporary field offices.
2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

1.7 STARTUP CONSTRUCTION SCHEDULE

A. Gantt-Chart Schedule: Submit startup, horizontal, Gantt-chart-type construction schedule within seven days of date established for the Notice of Award.

B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line. Outline significant construction activities for first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

1.8 GANTT-CHART SCHEDULE REQUIREMENTS

A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal, Gantt-chart-type, Contractor's Construction Schedule within 30 days of date established for the Notice of Award.

1. Base schedule on the startup construction schedule and additional information received since the start of Project.

B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.

1. For construction activities that require three months or longer to complete, indicate an estimated completion percentage in 10 percent increments within time bar.

1.9 REPORTS

A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:

1. List of subcontractors at Project site.
2. List of separate contractors at Project site.
3. Approximate count of personnel at Project site.
4. Equipment at Project site.
5. Material deliveries.
6. High and low temperatures and general weather conditions, including presence of rain or snow.
7. Testing and inspection.
8. Accidents.
9. Meetings and significant decisions.
10. Unusual events.
11. Stoppages, delays, shortages, and losses.
12. Meter readings and similar recordings.
13. Emergency procedures.
14. Orders and requests of authorities having jurisdiction.
15. Change Orders received and implemented.
16. Construction Change Directives received and implemented.
17. Services connected and disconnected.
18. Equipment or system tests and startups.
19. Partial completions and occupancies.
20. Substantial Completions authorized.

B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

C. Unusual Event Reports: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, responses by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

1. Submit unusual event reports directly to Owner within one day(s) of an occurrence. Distribute copies of report to parties affected by the occurrence.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 32 00

SECTION 01 33 00
SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Submittal schedule requirements.
2. Administrative and procedural requirements for submittals.

B. Related Requirements:

1. Section 012900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.

2. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.

3. Section 014000 "Quality Requirements" for submitting test and inspection reports, and schedule of tests and inspections.
4. Section 017700 "Closeout Procedures" for submitting closeout submittals and maintenance material submittals.
5. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
6. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
7. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

1.2 DEFINITIONS

A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."

B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."

1.3 SUBMITTAL SCHEDULE

A. Submittal Schedule: Submit, as an action submittal, a list of submittals, arranged

in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
2. Initial Submittal Schedule: Submit concurrently with startup construction schedule. Include submittals required during the first 60 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
3. Final Submittal Schedule: Submit concurrently with the first complete submittal of Contractor's construction schedule.

    a. Submit revised submittal schedule as required to reflect changes in current status and timing for submittals.

4. Format: Arrange the following information in a tabular format:

    a. Scheduled date for first submittal.
    b. Specification Section number and title.
    c. Submittal Category: Action; informational.
    d. Name of subcontractor.
    e. Description of the Work covered.
    f. Scheduled date for Architect's final release or approval.
    g. Scheduled dates for purchasing.
    h. Scheduled date of fabrication.
    i. Scheduled dates for installation.
    j. Activity or event number.

1.4 SUBMITTAL FORMATS

A. Submittal Information: Include the following information in each submittal:

1. Project name.
2. Date.
3. Name of Architect.
4. Name of Construction Manager.
5. Name of Contractor.
6. Name of firm or entity that prepared submittal.
7. Names of subcontractor, manufacturer, and supplier.
8. Unique submittal number, including revision identifier. Include Specification Section number with sequential alphanumeric identifier and alphanumeric suffix for resubmittals.
9. Category and type of submittal.
10. Submittal purpose and description.
11. Number and title of Specification Section, with paragraph number and generic name for each of multiple items.

12. Drawing number and detail references, as appropriate.
13. Indication of full or partial submittal.
14. Location(s) where product is to be installed, as appropriate.
15. Other necessary identification.
16. Remarks.
17. Signature of transmitter.

B. Options: Identify options requiring selection by Architect.

C. Deviations and Additional Information: On each submittal, clearly indicate deviations from requirements in the Contract Documents, including minor variations and limitations; include relevant additional information and revisions, other than those requested by Architect on previous submittals. Indicate by highlighting on each submittal or noting on attached separate sheet.

D. Paper Submittals:

1. Place a permanent label or title block on each submittal item for identification; include name of firm or entity that prepared submittal.
2. Provide a space approximately 6 by 8 inches on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
3. Action Submittals: Submit one paper copies of each submittal unless otherwise indicated. Architect, through Construction Manager, will return two one copies.
4. Informational Submittals: Submit two paper copies of each submittal unless otherwise indicated. Architect will not return copies.
5. Additional Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.
6. Transmittal for Submittals: Assemble each submittal individually and appropriately for transmittal and handling. Transmit each submittal using facsimile of sample form included in Project Manual transmittal form.

E. Electronic Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file. Name PDF file with submittal number.

F. Submittals Utilizing Web-Based Project Software: Prepare submittals as PDF files or other format indicated by Project management software.

1.5 SUBMITTAL PROCEDURES

A. Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.

1. Email: Prepare submittals as PDF package and transmit to Architect by sending via email. Include PDF transmittal form. Include information in email subject line as requested by Architect.

a. Architect will return annotated file. Annotate and retain one copy of

file as a digital Project Record Document file.

2. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project management software website. Enter required data in web-based software site to fully identify submittal.
3. Paper: Prepare submittals in paper form and deliver to Architect.

B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.

1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
4. Coordinate transmittal of submittals for related parts of the Work specified in different Sections, so processing will not be delayed because of need to review submittals concurrently for coordination.

    a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.

1. Initial Review: Allow Insert number days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
3. Resubmittal Review: Allow 15 days for review of each resubmittal.
4. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 days for initial review of each submittal.

5. Concurrent Consultant Review: Where the Contract Documents indicate that submittals may be transmitted simultaneously to Architect and to Architect's consultants, allow 15 days for review of each submittal. Submittal will be returned to Architect before being returned to Contractor.

    a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect and Construction Manager.

D. Resubmittals: Make resubmittals in same form and number of copies as initial

submittal.

1. Note date and content of previous submittal.
2. Note date and content of revision in label or title block, and clearly indicate extent of revision.
3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.

E. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.

F. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

1.6 SUBMITTAL REQUIREMENTS

A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard published data are unsuitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each copy of each submittal to show which products and options are applicable.
3. Include the following information, as applicable:

    a. Manufacturer's catalog cuts.
    b. Manufacturer's product specifications.
    c. Standard color charts.
    d. Statement of compliance with specified referenced standards.
    e. Testing by recognized testing agency.
    f. Application of testing agency labels and seals.
    g. Notation of coordination requirements.
    h. Availability and delivery time information.

4. For equipment, include the following in addition to the above, as applicable:

    a. Wiring diagrams that show factory-installed wiring.
    b. Printed performance curves.
    c. Operational range diagrams.
    d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before Shop Drawings, and before or concurrently with Samples.

B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale.

Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data unless submittal based on Architect's digital data drawing files is otherwise permitted.

1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:

    a. Identification of products.
    b. Schedules.
    c. Compliance with specified standards.
    d. Notation of coordination requirements.
    e. Notation of dimensions established by field measurement.
    f. Relationship and attachment to adjoining construction clearly indicated.
    g. Seal and signature of professional engineer if specified.

2. Paper Sheet Size: Except for templates, patterns, and similar full-size Drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches, but no larger than 30 by 42 inches.

    a. Two opaque (bond) copies of each submittal. Architect will return one copy(ies).

C. Samples: Submit Samples for review of type, color, pattern, and texture for a check of these characteristics with other materials.

1. Transmit Samples that contain multiple, related components, such as accessories together in one submittal package.
2. Identification: Permanently attach label on unexposed side of Samples that includes the following:

    a. Project name and submittal number.
    b. Generic description of Sample.
    c. Product name and name of manufacturer.
    d. Sample source.
    e. Number and title of applicable Specification Section.
    f. Specification paragraph number and generic name of each item.

3. Email Transmittal: Provide PDF transmittal. Include digital image file illustrating Sample characteristics and identification information for record.
4. Web-Based Project Management Software: Prepare submittals in PDF form, and upload to web-based Project software website. Enter required data in web-based software site to fully identify submittal.
5. Paper Transmittal: Include paper transmittal, including complete submittal information indicated.
6. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.

    a. Samples that may be incorporated into the Work are indicated in

individual Specification Sections. Such Samples must be in an undamaged condition at time of use.

b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.

7. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units, showing the full range of colors, textures, and patterns available.

   a. Number of Samples: Submit one full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.

8. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.

   a. Number of Samples: Submit one sets of Samples. Architect will retain Sample sets; remainder will be returned.

      1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
      2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.

D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:

1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
2. Manufacturer and product name, and model number if applicable.
3. Number and name of room or space.
4. Location within room or space.

E. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.

F. Design Data: Prepare and submit written and graphic information indicating

compliance with indicated performance and design criteria in individual Specification Sections. Include list of assumptions and summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Number each page of submittal.

G. Certificates:

1. Certificates and Certifications Submittals: Submit a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity. Provide a notarized signature where indicated.
2. Installer Certificates: Submit written statements on manufacturer's letterhead, certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
3. Manufacturer Certificates: Submit written statements on manufacturer's letterhead, certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
4. Material Certificates: Submit written statements on manufacturer's letterhead, certifying that material complies with requirements in the Contract Documents.
5. Product Certificates: Submit written statements on manufacturer's letterhead, certifying that product complies with requirements in the Contract Documents.
6. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of AWS B2.1/B2.1M on AWS forms. Include names of firms and personnel certified.

H. Test and Research Reports:

1. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for substrate preparation and primers required.
2. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
3. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
4. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
5. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract

Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.

6. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:

    a. Name of evaluation organization.
    b. Date of evaluation.
    c. Time period when report is in effect.
    d. Product and manufacturers' names.
    e. Description of product.
    f. Test procedures and results.
    g. Limitations of use.

1.7 DELEGATED DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

    1. If criteria indicated are insufficient to perform services or certification required, submit a written request for additional information to Architect.

B. Delegated Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF file paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.

    1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

1.8 CONTRACTOR'S REVIEW

A. Action Submittals and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.

B. Contractor's Approval: Indicate Contractor's approval for each submittal with a uniform approval stamp. Include name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

    1. Architect and Construction Manager will not review submittals received

from Contractor that do not have Contractor's review and approval.

1.9 ARCHITECT'S REVIEW

A. Action Submittals: Architect will review each submittal, indicate corrections or revisions required, and return.

1. PDF Submittals: Architect will indicate, via markup on each submittal, the appropriate action.

2. Paper Submittals: Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.

3. Submittals by Web-Based Project Management Software: Architect will indicate, on Project management software website, the appropriate action.

B. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.

C. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.

D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

E. Architect will return without review submittals received from sources other than Contractor.

F. Submittals not required by the Contract Documents will be returned by Architect without action.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 33 00

SECTION 01 40 00
QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for quality assurance and quality control.

B. Testing and inspection services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.

1. Specific quality-assurance and quality-control requirements for individual work results are specified in their respective Specification Sections. Requirements in individual Sections may also cover production of standard products.
2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and quality-control procedures that facilitate compliance with the Contract Document requirements.
3. Requirements for Contractor to provide quality-assurance and quality-control services required by Architect, Owner, Commissioning Authority, or authorities having jurisdiction are not limited by provisions of this Section.

1.2 DEFINITIONS

A. Experienced: When used with an entity or individual, "experienced," unless otherwise further described, means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

B. Field Quality-Control Tests and Inspections: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

C. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, subcontractor, or sub-subcontractor, to perform a particular construction operation, including installation, erection, application, assembly, and similar operations.

1. Use of trade-specific terminology in referring to a Work result does not require that certain construction activities specified apply exclusively to specific trade(s).

D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify

performance or compliance with specified criteria. Unless otherwise indicated, copies of reports of tests or inspections performed for other than the Project do not meet this definition.

E. Product Tests: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) in accordance with 29 CFR 1910.7, by a testing agency accredited in accordance with NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or by a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.

F. Source Quality-Control Tests and Inspections: Tests and inspections that are performed at the source (e.g., plant, mill, factory, or shop).

G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. The term "testing laboratory" has the same meaning as the term "testing agency."

H. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work, to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.

I. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work, to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Contractor's quality-control services do not include contract administration activities performed by Architect.

1.3 DELEGATED DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.

B. Delegated Design Services Statement: Submit a statement signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.

1.4 CONFLICTING REQUIREMENTS

A. Conflicting Standards and Other Requirements: If compliance with two or more

standards or requirements is specified and the standards or requirements establish different or conflicting requirements for minimum quantities or quality levels, inform the Architect regarding the conflict and obtain clarification prior to proceeding with the Work. Refer conflicting requirements that are different, but apparently equal, to Architect for clarification before proceeding.

B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified is the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 INFORMATIONAL SUBMITTALS

A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.

B. Qualification Data: For Contractor's quality-control personnel.

C. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility submitted to authorities having jurisdiction before starting work on the following systems:

1. Seismic-force-resisting system, designated seismic system, or component listed in the Statement of Special Inspections.
2. Primary wind-force-resisting system or a wind-resisting component listed in the Statement of Special Inspections.

D. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

E. Schedule of Tests and Inspections: Prepare in tabular form and include the following:

1. Specification Section number and title.
2. Entity responsible for performing tests and inspections.
3. Description of test and inspection.
4. Identification of applicable standards.
5. Identification of test and inspection methods.
6. Number of tests and inspections required.
7. Time schedule or time span for tests and inspections.
8. Requirements for obtaining samples.
9. Unique characteristics of each quality-control service.

F. Reports: Prepare and submit certified written reports and documents as specified.

G. Permits, Licenses, and Certificates: For Owner's record, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents established for compliance with standards and regulations bearing on performance of the Work.

1.6 CONTRACTOR'S QUALITY-CONTROL PLAN

A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities and to coordinate Owner's quality-assurance and quality-control activities. Coordinate with Contractor's Construction Schedule.

B. Quality-Control Personnel Qualifications: Engage qualified personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.

C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.

D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:

1. Contractor-performed tests and inspections, including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections. Distinguish source quality-control tests and inspections from field quality-control tests and inspections.
2. Special inspections required by authorities having jurisdiction and indicated on the Statement of Special Inspections.
3. Owner-performed tests and inspections indicated in the Contract Documents, including tests and inspections indicated to be performed by Commissioning Authority.

E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring the Work into compliance with standards of workmanship established by Contract requirements and approved mockups.

F. Monitoring and Documentation: Maintain testing and inspection reports, including log of approved and rejected results. Include Work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming Work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

1.7 REPORTS AND DOCUMENTS

A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:

1. Date of issue.
2. Project title and number.
3. Name, address, telephone number, and email address of testing agency.
4. Dates and locations of samples and tests or inspections.
5. Names of individuals making tests and inspections.
6. Description of the Work and test and inspection method.
7. Identification of product and Specification Section.
8. Complete test or inspection data.
9. Test and inspection results and an interpretation of test results.
10. Record of temperature and weather conditions at time of sample-taking and testing and inspection.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and reinspecting.

B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:

1. Name, address, telephone number, and email address of technical representative making report.
2. Statement on condition of substrates and their acceptability for installation of product.
3. Statement that products at Project site comply with requirements.
4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
6. Statement of whether conditions, products, and installation will affect warranty.
7. Other required items indicated in individual Specification Sections.

C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:

1. Name, address, telephone number, and email address of factory-authorized service representative making report.
2. Statement that equipment complies with requirements.
3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
4. Statement of whether conditions, products, and installation will affect warranty.
5. Other required items indicated in individual Specification Sections.

1.8 QUALITY ASSURANCE

A. Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units. As applicable, procure products from manufacturers able to meet qualification requirements, warranty requirements, and technical or factory-authorized service representative requirements.

C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Installer Qualifications: A firm or individual experienced in installing, erecting, applying, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that is similar in material, design, and extent to those indicated for this Project.

F. Testing and Inspecting Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspection indicated, as documented in accordance with ASTM E329, and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.

G. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

H. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect, demonstrate, repair, and perform service on installations of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

1.9 QUALITY CONTROL

A. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities, whether specified or not, to verify and document that the Work

complies with requirements.

1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
2. Engage a qualified testing agency to perform quality-control services.
    a. Contractor will not employ same entity engaged by Owner, unless agreed to in writing by Owner.
3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspection will be performed.
4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
5. Testing and inspection requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.

B. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.

C. Testing Agency Responsibilities: Cooperate with Architect, Commissioning Authority and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.

1. Notify Architect, Commissioning Authority, and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
2. Determine the locations from which test samples will be taken and in which in-situ tests are conducted.
3. Conduct and interpret tests and inspections, and state in each report whether tested and inspected Work complies with or deviates from requirements.
4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
6. Do not perform duties of Contractor.

D. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Section 013300 "Submittal Procedures."

E. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation

conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.

F. Contractor's Associated Requirements and Services: Cooperate with agencies and representatives performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.
3. Adequate quantities of representative samples of materials that require testing and inspection. Assist agency in obtaining samples.
4. Facilities for storage and field curing of test samples.
5. Delivery of samples to testing agencies.
6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
7. Security and protection for samples and for testing and inspection equipment at Project site.

G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspection.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

H. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents as a component of Contractor's quality-control plan. Coordinate and submit concurrently with Contractor's Construction Schedule. Update and submit with each Application for Payment.

1. Schedule Contents: Include tests, inspections, and quality-control services, including Contractor- and Owner-retained services, commissioning activities, and other Project-required services paid for by other entities.
2. Distribution: Distribute schedule to Owner, Architect, Commissioning Authority, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
2. Description of the Work tested or inspected.
3. Date test or inspection results were transmitted to Architect.
4. Identification of testing agency or special inspector conducting test or inspection.

B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's, Commissioning Authority's, and reference during normal working hours.

1. Submit log at Project closeout as part of Project Record Documents.

3.2 REPAIR AND PROTECTION

A. General: On completion of testing, inspection, sample-taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 01 40 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 01 42 00
REFERENCES

PART 1 - GENERAL

1.1 DEFINITIONS

A. General: Basic Contract definitions are included in the Conditions of the Contract.

B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.

C. "Directed": A command or instruction by Architect. Other terms, including "requested," "authorized," "selected," "required," and "permitted," have the same meaning as "directed."

D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms, including "shown," "noted," "scheduled," and "specified," have the same meaning as "indicated."

E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.

F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.

G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.

H. "Provide": Furnish and install, complete and ready for the intended use.

I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.2 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

1. For standards referenced by applicable building codes, comply with dates of standards as listed in building codes.

C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.3 ABBREVIATIONS AND ACRONYMS

A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."

B. Industry Organizations, List: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities in the following list. Abbreviations and acronyms not included in this list are to mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States." The information in this list is subject to change and is believed to be accurate as of the date of the Contract Documents.

1. AABC - Associated Air Balance Council; www.aabc.com.
2. AAMA - American Architectural Manufacturers Association; (see FGIA).
3. AASHTO - American Association of State Highway and Transportation Officials; www.transportation.org.
4. AATCC - American Association of Textile Chemists and Colorists; www.aatcc.org.
5. ABMA - American Bearing Manufacturers Association; www.americanbearings.org.
6. ACI - American Concrete Institute; www.concrete.org.
7. ACPA - American Concrete Pipe Association; www.concretepipe.org.
8. AEIC - Association of Edison Illuminating Companies, Inc. (The); www.aeic.org.
9. AF&PA - American Forest & Paper Association; www.afandpa.org.
10. AGA - American Gas Association; www.aga.org.
11. AHRI - Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.

12. AI - Asphalt Institute; www.asphaltinstitute.org.
13. AIA - American Institute of Architects (The); www.aia.org.
14. AISC - American Institute of Steel Construction; www.aisc.org.
15. AISI - American Iron and Steel Institute; www.steel.org.

16. AMCA - Air Movement and Control Association International, Inc.; www.amca.org.
17. AMPP - Association for Materials Protection and Performance; www.ampp.org.
18. ANSI - American National Standards Institute; www.ansi.org.

19. ARMA - Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.

20. ASCE - American Society of Civil Engineers; www.asce.org.
21. ASCE/SEI - American Society of Civil Engineers/Structural Engineering Institute; (see ASCE).
22. ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers; www.ashrae.org.
23. ASME - ASME International; American Society of Mechanical Engineers (The); www.asme.org.

24. ASTM - ASTM International; www.astm.org.
25. ATIS - Alliance for Telecommunications Industry Solutions; www.atis.org.

26. AWI - Architectural Woodwork Institute; www.awinet.org.

27. AWPA - American Wood Protection Association; www.awpa.com.
28. AWS - American Welding Society; www.aws.org.
29. AWWA - American Water Works Association; www.awwa.org.
30. BHMA - Builders Hardware Manufacturers Association; www.buildershardware.com.

31. BICSI - BICSI, Inc.; www.bicsi.org.
32. BIFMA - Business and Institutional Furniture Manufacturer's Association; www.bifma.org.

33. CARB - California Air Resources Board; www.arb.ca.gov.
34. CDA - Copper Development Association Inc.; www.copper.org.

35. CFSEI - Cold-Formed Steel Engineers Institute; www.cfsei.org.

36. CIMA - Cellulose Insulation Manufacturers Association; www.cellulose.org.
37. CISCA - Ceilings & Interior Systems Construction Association; www.cisca.org.
38. CISPI - Cast Iron Soil Pipe Institute; www.cispi.org.

39. CRI - Carpet and Rug Institute (The); www.carpet-rug.org.

40. CRSI - Concrete Reinforcing Steel Institute; www.crsi.org.
41. CSA - CSA Group; www.csagroup.org.

42. CSI - Construction Specifications Institute (The); www.csiresources.org.

43. CTI - Cooling Technology Institute; www.coolingtechnology.org.

44. DHI - Door and Hardware Institute; www.dhi.org.
45. ECIA - Electronic Components Industry Association; www.ecianow.org.

46. EJMA - Expansion Joint Manufacturers Association, Inc.; www.ejma.org.

47. FGIA - Fenestration and Glazing Industry Alliance; https://fgiaonline.org.

48. FM Approvals - FM Approvals LLC; www.fmapprovals.com.
49. FM Global - FM Global; www.fmglobal.com.

50. FSC - Forest Stewardship Council U.S.; www.fscus.org.
51. GA - Gypsum Association; www.gypsum.org.

52. HMMA - Hollow Metal Manufacturers Association; (see NAAMM).
53. IAPSC - International Association of Professional Security Consultants; www.iapsc.org.
54. IAS - International Accreditation Service; www.iasonline.org.
55. ICC - International Code Council; www.iccsafe.org.

56. ICRI - International Concrete Repair Institute, Inc.; www.icri.org.

57. IEEE SA - IEEE Standards Association; https://standards.ieee.org.

58. Intertek - Intertek Group; www.intertek.com.
59. ISA - International Society of Automation (The); www.isa.org.

60. ISO - International Organization for Standardization; www.iso.org.

61. MCA - Metal Construction Association; www.metalconstruction.org.

62. MFMA - Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.

63. MMPA - Moulding & Millwork Producers Association; www.wmmpa.com.
64. MPI - Master Painters Institute; www.paintinfo.com.

65. NAAMM - National Association of Architectural Metal Manufacturers; www.naamm.org.
66. NACE - NACE International; (National Association of Corrosion Engineers International); (see AMPP).

67. NAIMA - North American Insulation Manufacturers Association; www.insulationinstitute.org.

68. NBGQA - National Building Granite Quarries Association, Inc.; www.nbgqa.com.
69. NBI - New Buildings Institute; www.newbuildings.org.

70. NEMA - National Electrical Manufacturers Association; www.nema.org.

71. NFPA - National Fire Protection Association; www.nfpa.org.
72. NFPA - NFPA International; (see NFPA).

73. NHLA - National Hardwood Lumber Association; www.nhla.com.
74. NLGA - National Lumber Grades Authority; www.nlga.org.

75. NRMCA - National Ready Mixed Concrete Association; www.nrmca.org.
76. NSF - NSF International; www.nsf.org.

77. RCSC - Research Council on Structural Connections; www.boltcouncil.org.
78. RFCI - Resilient Floor Covering Institute; www.rfci.com.
79. RIS - Redwood Inspection Service; (see WWPA).
80. SAE - SAE International; www.sae.org.

81. SDI - Steel Deck Institute; www.sdi.org.
82. SDI - Steel Door Institute; www.steeldoor.org.

83. SEI/ASCE - Structural Engineering Institute/American Society of Civil Engineers; (see ASCE).

84. SMACNA - Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
85. SMPTE - Society of Motion Picture and Television Engineers; www.smpte.org.
86. SPFA - Spray Polyurethane Foam Alliance; www.sprayfoam.org.
87. SPIB - Southern Pine Inspection Bureau; www.spib.org.
88. SPRI - Single Ply Roofing Industry; www.spri.org.

89. SSINA - Specialty Steel Industry of North America; www.ssina.com.

90. STI/SPFA - Steel Tank Institute/Steel Plate Fabricators Association; www.steeltank.com.
91. SWI - Steel Window Institute; www.steelwindows.com.

92. UL - UL Solutions Inc.; www.ul.com.

93. USGBC - U.S. Green Building Council; www.usgbc.org.

94. WA - Wallcoverings Association; www.wallcoverings.org.

95. WDMA - Window & Door Manufacturers Association; www.wdma.com.
96. WI - Woodwork Institute; www.woodworkinstitute.com.

C. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they are to mean the recognized name of the entities in the following list. This information is believed to be accurate as of the date of the Contract Documents.

1. IAPMO - International Association of Plumbing and Mechanical Officials;

www.iapmo.org.
2. ICC - International Code Council; www.iccsafe.org.
3. ICC-ES - ICC Evaluation Service, LLC; www.icc-es.org.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 42 00

SECTION 01 50 00
TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Section 011000 "Summary" for work restrictions and limitations on utility interruptions.

1.2 USE CHARGES

A. Installation, removal, and use charges for temporary facilities to be included in the Contract Sum unless otherwise indicated. Allow other entities engaged in the Project to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.

B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

1.3 INFORMATIONAL SUBMITTALS

A. Site Utilization Plan: Show temporary facilities, temporary utility lines and connections, staging areas, construction site entrances, vehicle circulation, and parking areas for construction personnel.

B. Implementation and Termination Schedule: Within 15 days of date established for commencement of the Work, submit schedule indicating implementation and termination dates of each temporary utility.

C. Project Identification and Temporary Signs: Show fabrication and installation details, including plans, elevations, details, layouts, typestyles, graphic elements, and message content.

D. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.

E. Moisture- and Mold-Protection Plan: Describe procedures and controls for protecting materials and construction from water absorption and damage and mold. Describe delivery, handling, storage, installation, and protection provisions for materials subject to water absorption or water damage.

1. Indicate procedures for discarding water-damaged materials, protocols for mitigating water intrusion into completed Work, and requirements for replacing water-damaged Work.
2. Indicate sequencing of work that requires water, such as sprayed fire-resistive materials, plastering, and terrazzo grinding, and describe plans for dealing with water from these operations. Show procedures for verifying that wet construction has dried sufficiently to permit installation of finish materials.
3. Indicate methods to be used to avoid trapping water in finished work.

F. Dust- and HVAC-Control Plan: Submit coordination drawing and narrative that indicates the dust- and HVAC-control measures proposed for use, proposed locations, and proposed time frame for their operation. Include the following:

1. Locations of dust-control partitions at each phase of work.
2. HVAC system isolation schematic drawing.
3. Location of proposed air-filtration system discharge.
4. Waste-handling procedures.
5. Other dust-control measures.

G. Noise and Vibration Control Plan: Identify construction activities that may impact the occupancy and use of existing spaces within the building or adjacent existing buildings, whether occupied by others, or occupied by Owner. Include the following:

1. Methods used to meet the goals and requirements of Owner.
2. Concrete cutting method(s) to be used.
3. Location of construction devices on the site.
4. Show compliance with the use and maintenance of quieted construction devices for the duration of the Project.
5. Indicate activities that may disturb building occupants and that are planned to be performed during non-standard working hours as coordinated with Owner.
6. Indicate locations of sensitive areas or other areas requiring special attention as identified by Owner. Indicate means for complying with Owner's requirements.

1.4 QUALITY ASSURANCE

A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.

B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

C. Accessible Temporary Egress: Comply with applicable provisions in the DOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.

1.5 PROJECT CONDITIONS

A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Chain-Link Fencing: Minimum **2-inch**, **0.148-inch-** thick, galvanized-steel, chain-link fabric fencing; minimum **6 feet** high with galvanized-steel pipe posts; minimum **2-3/8-inch-** OD line posts and **2-7/8-inch-** OD corner and pull posts, with 1-5/8-inch- OD top rails.

B. Portable Chain-Link Fencing: Minimum **2-inch**, **0.148-inch-** thick, galvanized-steel, chain-link fabric fencing; minimum **6 feet** high with galvanized-steel pipe posts; minimum **2-3/8-inch-** OD line posts and **2-7/8-inch-** OD corner and pull posts, with **1-5/8-inch-** OD top and bottom rails. Provide concrete bases for supporting posts.

C. Fencing Windscreen Privacy Screen: Polyester fabric scrim with grommets for attachment to chain-link fence, sized to height of fence, in color selected by Architect from manufacturer's standard colors.

D. Polyethylene Sheet: Reinforced, fire-resistive sheet, **10-mil** minimum thickness, with flame-spread rating of 15 or less in accordance with ASTM E84 and passing NFPA 701 Test Method 2.

E. Dust-Control Adhesive-Surface Walk-Off Mats: Provide mats, minimum **36 by 60 inches**.

F. Insulation: Unfaced mineral-fiber blanket, manufactured from glass, slag wool, or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively.

2.2 TEMPORARY FACILITIES

A. Field Offices:

1. Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.

B. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.

1. Store combustible materials apart from building.

2.3 EQUIPMENT

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.

1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
2. Heating, Cooling, and Dehumidifying Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.

C. Air-Filtration Units: Primary and secondary HEPA-filter-equipped portable units with four-stage filtration. Provide single switch for emergency shutoff. Configure to run continuously.

PART 3 - EXECUTION

3.1 TEMPORARY FACILITIES, GENERAL

A. Conservation: Coordinate construction and use of temporary facilities with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. See other Sections for disposition of salvaged materials that are designated as Owner's property.

3.2 INSTALLATION, GENERAL

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

1. Locate facilities to limit site disturbance as specified in Section 011000

"Summary."

B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

C. Isolation of Work Areas in Occupied Facilities: Prevent dust, fumes, and odors from entering occupied areas.

1. Prior to commencing work, isolate the HVAC system in area where work is to be performed in accordance with coordination drawings.

a. Disconnect supply and return ductwork in work area from HVAC systems servicing occupied areas.
b. Maintain negative air pressure within work area, using HEPA-equipped air-filtration units, starting with commencement of temporary partition construction, and continuing until removal of temporary partitions is complete.

2. Maintain dust partitions during the Work. Use vacuum collection attachments on dust-producing equipment. Isolate limited work within occupied areas using portable dust-containment devices.
3. Perform daily construction cleanup and final cleanup using approved, HEPA-filter-equipped vacuum equipment.

3.3 TEMPORARY UTILITY INSTALLATION

A. General: Install temporary service or connect to existing service.

1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.

B. Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.

1. Connect temporary sewers to municipal system as directed by authorities having jurisdiction.

C. Water Service:

1. Install water service and distribution piping in sizes and pressures adequate for construction.
2. Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.

D. Sanitary Facilities: Provide temporary toilets, wash facilities, safety shower and eyewash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.

1. Use of Permanent Toilets: Use of Owner's existing or new toilet facilities is not permitted.

E. Temporary Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

1. Provide temporary dehumidification systems when required to reduce ambient and substrate moisture levels to level required to allow installation or application of finishes and their proper curing or drying.

F. Electric Power Service:

1. Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.
2. Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.

a. Connect temporary service to Owner's existing power source, as directed by Owner.

G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

H. Telephone Service: Provide temporary telephone service in common-use facilities for use by all construction personnel. Install WiFi cell phone access equipment land-based telephone line(s) for each field office.

1. Provide additional telephone lines for the following:

2. At each telephone, post a list of important telephone numbers.

a. Police and fire departments.
b. Ambulance service.
c. Contractor's home office.
d. Contractor's emergency after-hours telephone number.
e. Architect's office.

f. Engineers' offices.
g. Owner's office.
h. Principal subcontractors' field and home offices.

I. Electronic Communication Service: Provide secure WiFi wireless connection to internet with provisions for access by Architect and Owner.

3.4 SUPPORT FACILITIES INSTALLATION

A. Comply with the following:

1. Provide construction for temporary field offices, shops, and sheds located within construction area or within **30 feet** of building lines that is noncombustible in accordance with ASTM E136. Comply with NFPA 241.
2. Utilize designated area within existing building for temporary field offices.
3. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

B. Traffic Controls: Comply with requirements of authorities having jurisdiction.

1. Protect existing site improvements to remain, including curbs, pavement, and utilities.
2. Maintain access for fire-fighting equipment and access to fire hydrants.

C. Parking: Use designated areas of Owner's existing parking areas for construction personnel.

D. Storage and Staging: Use designated areas of Project site for storage and staging needs.

E. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.

1. Identification Signs: Provide Project identification signs as indicated on Drawings.
2. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.

    a. Provide temporary, directional signs for construction personnel and visitors.

3. Maintain and touch up signs, so they are legible at all times.

F. Waste Disposal Facilities:

1. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."
2. Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 017300 "Execution."

G. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.

1. Truck cranes and similar devices used for hoisting materials are

considered "tools and equipment" and not temporary facilities.

H. Temporary Use of Permanent Stairs: Use of new stairs for construction traffic will be permitted, provided stairs are protected and finishes restored to new condition at time of Substantial Completion.

3.5 SECURITY AND PROTECTION FACILITIES INSTALLATION

A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.

1. Where access to adjacent properties is required in order to affect protection of existing facilities, obtain written permission from adjacent property owner to access property for that purpose.

B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

1. Comply with work restrictions specified in Section 011000 "Summary."

C. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.

D. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals, so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using materials approved by authorities having jurisdiction.

E. Site Enclosure Fence: Before construction operations begin, furnish and install site enclosure fence in a manner that will prevent people from easily entering site except by entrance gates.

1. Extent of Fence: As required to enclose entire Project site or portion determined sufficient to accommodate construction operations.
2. Maintain security by limiting number of keys and restricting distribution to authorized personnel. Furnish one set of keys to Owner.

F. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each workday.

G. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including

warning signs and lighting.

H. Temporary Egress: Provide temporary egress from existing occupied facilities as indicated and as required by authorities having jurisdiction. Provide signage directing occupants to temporary egress.

I. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.

1. Where heating or cooling is needed and permanent enclosure is incomplete, insulate temporary enclosures.

J. Temporary Partitions: Provide floor-to-ceiling dustproof partitions to limit dust and dirt migration and to separate areas occupied by Owner from fumes and noise.

1. Construct dustproof partitions with gypsum wallboard, with joints taped on occupied side, and fire-retardant-treated plywood on construction operations side.
2. Construct dustproof partitions with two layers of **6-mil** polyethylene sheet on each side. Cover floor with two layers of **6-mil** polyethylene sheet, extending sheets **18 inches** up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant-treated plywood.

    a. Construct vestibule and airlock at each entrance through temporary partition with not less than **48 inches** between doors. Maintain water-dampened foot mats in vestibule.

3. Where fire-resistance-rated temporary partitions are indicated or are required by authorities having jurisdiction, construct partitions according to the rated assemblies.
4. Insulate partitions to control noise transmission to occupied areas.
5. Seal joints and perimeter. Equip partitions with gasketed dustproof doors and security locks where openings are required.
6. Protect air-handling equipment.
7. Provide walk-off mats at each entrance through temporary partition.

K. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.

1. Prohibit smoking in construction areas. Comply with additional limits on smoking specified in other Sections.
2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition in accordance with requirements of authorities having jurisdiction.
3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and

procedures. Post warnings and information.

4. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign, stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

3.6 MOISTURE AND MOLD CONTROL

A. Moisture and Mold Protection: Protect stored materials and installed Work in accordance with Moisture and Mold Protection Plan.

B. Exposed Construction Period: Before installation of weather barriers, when materials are subject to wetting and exposure and to airborne mold spores, protect as follows:

1. Protect porous materials from water damage.
2. Protect stored and installed material from flowing or standing water.
3. Keep porous and organic materials from coming into prolonged contact with concrete.
4. Remove standing water from decks.
5. Keep deck openings covered or dammed.

C. Partially Enclosed Construction Period: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:

1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
2. Keep interior spaces reasonably clean and protected from water damage.
3. Periodically collect and remove waste containing cellulose or other organic matter.
4. Discard or replace water-damaged material.
5. Do not install material that is wet.
6. Discard and replace stored or installed material that begins to grow mold.
7. Perform work in a sequence that allows wet materials adequate time to dry before enclosing the material in gypsum board or other interior finishes.

D. Controlled Construction Period: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:

1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
2. Use temporary or permanent HVAC system to control humidity within ranges specified for installed and stored materials.
3. Comply with manufacturer's written instructions for temperature, relative humidity, and exposure to water limits.

    a. Hygroscopic materials that may support mold growth, including wood

and gypsum-based products, that become wet during the course of construction and remain wet for 48 hours are considered defective and require replacing.

b. Measure moisture content of materials that have been exposed to moisture during construction operations or after installation. Record readings beginning at time of exposure and continuing daily for 48 hours. Identify materials containing moisture levels higher than allowed. Report findings in writing to Architect.

c. Remove and replace materials that cannot be completely restored to their manufactured moisture level within 48 hours.

3.7 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
2. Remove temporary roads and paved areas not intended for or acceptable for integration into permanent construction. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
3. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION 01 50 00

SECTION 01 60 00
PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of This Section Includes: Administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

1. Section 011000 "Summary" for Contractor requirements related to Owner-furnished products.

2. Section 012500 "Substitution Procedures" for requests for substitutions.
3. Section 014200 "References" for applicable industry standards for products specified.
4. Section 017700 "Closeout Procedures" for submitting warranties.

1.2 DEFINITIONS

A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.

1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
2. New Products: Items that have not previously been incorporated into another project or facility. Salvaged items or items reused from other projects are not considered new products. Items that are manufactured or fabricated to include recycled content materials are considered new products unless otherwise indicated.
3. Comparable Product: Product by named manufacturer that is demonstrated and approved through the comparable product submittal process described in "Comparable Products" Article, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation.

Published attributes and characteristics of basis-of-design product establish salient characteristics of products.

1. Evaluating Comparable Products: In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification. Manufacturer's published attributes and characteristics of basis-of-design product also establish salient characteristics of products for purposes of evaluating comparable products.

C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications; submit a comparable product request or substitution request, if applicable.

D. Comparable Product Request Submittal: An action submittal requesting consideration of a comparable product, including the following information:

1. Identification of basis-of-design product or fabrication or installation method to be replaced, including Specification Section number and title and Drawing numbers and titles.
2. Data indicating compliance with the requirements specified in "Comparable Products" Article.

E. Basis-of-Design Product Specification Submittal: An action submittal complying with requirements in Section 013300 "Submittal Procedures."

F. Substitution: Refer to Section 012500 "Substitution Procedures" for definition and limitations on substitutions.

1.3 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

1. Resolution of Compatibility Disputes between Multiple Contractors:

a. Contractors are responsible for providing products and construction methods compatible with products and construction methods of other contractors.
b. If a dispute arises between the multiple contractors over concurrently selectable but incompatible products, Architect will determine which

products will be used.

B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.

1. Labels: Locate required product labels and stamps on a concealed surface, or, where required for observation following installation, on a visually accessible surface that is inconspicuous.
2. Equipment Nameplates: Provide a permanent nameplate on each item of service- or power-operated equipment. Locate on a visually accessible but inconspicuous surface. Include information essential for operation, including the following:

    a. Name of product and manufacturer.
    b. Model and serial number.
    c. Capacity.
    d. Speed.
    e. Ratings.

3. See individual identification Sections in Divisions 21, 22, 23, and 26 for additional equipment identification requirements.

1.4 COORDINATION

A. Modify or adjust affected work as necessary to integrate work of approved comparable products and approved substitutions.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products, using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
4. Inspect products on delivery to determine compliance with the Contract Documents and that products are undamaged and properly protected.

C. Storage:

1. Provide a secure location and enclosure at Project site for storage of materials and equipment.
2. Store products to allow for inspection and measurement of quantity or counting of units.
3. Store materials in a manner that will not endanger Project structure.
4. Store products that are subject to damage by the elements under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation and with adequate protection from wind.
5. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
7. Protect stored products from damage and liquids from freezing.
8. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.6 PRODUCT WARRANTIES

A. Warranties specified in other Sections are to be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

1. Manufacturer's Warranty: Written standard warranty form furnished by individual manufacturer for a particular product and issued in the name of Owner or endorsed by manufacturer to Owner.
2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner and issued in the name of Owner or endorsed by manufacturer to Owner.

B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.

1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
2. Specified Form: When specified forms are included in the Project Manual, prepare a written document, using indicated form properly executed.
3. See other Sections for specific content requirements and particular requirements for submitting special warranties.

C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
3. Owner reserves the right to limit selection to products with warranties meeting requirements of the Contract Documents.
4. Where products are accompanied by the term "as selected," Architect will make selection.
5. Descriptive, performance, and reference standard requirements in Specifications establish salient characteristics of products.
6. Or Equal: For products specified by name and accompanied by the term "or equal," "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.

    a. Submit additional documentation required by Architect in order to establish equivalency of proposed products. Unless otherwise indicated, evaluation of "or equal" product status is by Architect, whose determination is final.

B. Product Selection Procedures:

1. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will be considered unless otherwise indicated.

    a. Limited list of products may be indicated by the phrase "Subject to compliance with requirements, provide one of the following."

2. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed or an unnamed product that complies with requirements.

    a. Non-limited list of products is indicated by the phrase "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following."
    b. Provision of an unnamed product is not considered a substitution, if the product complies with requirements.

3. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will be considered unless otherwise indicated.

    a. Limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, provide products by one of the following."

4. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed or a product by an unnamed manufacturer that complies with requirements.

    a. Non-limited list of manufacturers is indicated by the phrase "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following."
    b. Provision of products of an unnamed manufacturer is not considered a substitution, if the product complies with requirements.

5. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications may additionally indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.

    a. For approval of products by unnamed manufacturers, comply with requirements in Section 012500 "Substitution Procedures" for substitutions for convenience.

C. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or a similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with the following requirements:

    1. Evidence that proposed product does not require revisions to the Contract

Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work.

2. Detailed comparison of significant qualities of proposed product with those of the named basis-of-design product. Significant product qualities include attributes such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
3. Evidence that proposed product provides specified warranty.
4. List of similar installations for completed projects, with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

B. Submittal Requirements, Two-Step Process: Approval by Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.

C. Submittal Requirements, Single-Step Process: When acceptable to Architect, incorporate specified submittal requirements of individual Specification Section in combined submittal for comparable products. Approval by Architect of Contractor's request for use of comparable product and of individual submittal requirements will also satisfy other submittal requirements.

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 60 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 01 74 19
CONSTRUCTION WASTE MANAGEMENT

PART 1 – GENERAL

1.1 SUMMARY

A. Section includes: Administrative and procedural requirements for construction waste management activities.

1.2 DEFINITIONS

A. Construction, Demolition, and Land clearing (CDL) Waste: Includes all non-hazardous solid wastes resulting from construction, remodeling, alterations, repair, demolition and land clearing. Includes material that is recycled, reused, salvaged or disposed as garbage.

B. Salvage: Recovery of materials for on-site reuse, sale or donation to a third party.

C. Reuse: Making use of a material without altering its form. Materials can be reused on-site or reused on other projects off-site. Examples include, but are not limited to the following: Crushing or grinding of concrete for use as sub-base material. Chipping of land clearing debris for use as mulch.

D. Recycling: The process of sorting, cleaning, treating, and reconstituting materials for the purpose of using the material in the manufacture of a new product.

E. Source-Separated CDL Recycling: The process of separating recyclable materials in separate containers as they are generated on the job-site. The separated materials are hauled directly to a recycling facility or transfer station.

F. Co-mingled CDL Recycling: The process of collecting mixed recyclable materials in one container on-site. The container is taken to a material recovery facility where materials are separated for recycling.

G. Approved Recycling Facility: Any of the following:

1. A facility that can legally accept CDL waste materials for the purpose of processing the materials into an altered form for the manufacture of a new product.

2. Material Recovery Facility: A general term used to describe a waste-sorting facility. Mechanical, hand-separation, or a combination of both procedures, are used to recover recyclable materials.

H. Universal waste components (UWC) are as follows: electric motors, PCB ballasts, non PCB ballasts, capacitors, contactors, circuit breakers, elemental and liquid mercury containing articles, transformers, lead acid batteries, fluorescent light bulbs, and all HID light bulbs.

1.3 SUBMITTALS

A. Contractor shall develop a Waste Management Plan: Submit 3 copies of plan within 14 days of date established for the **Notice to Proceed**.

B. Contractor shall provide Waste Management Report: Concurrent with each Application for Payment, submit **3** copies of report.

1.4 PERFORMANCE REQUIREMENTS

A. General: Divert a minimum of **75%** CDL waste, by weight, from the landfill by one, or a combination of the following activities:

1. Salvage
2. Reuse
3. Source-Separated CDL Recycling
4. Co-mingled CDL Recycling

B. CDL waste materials that can be salvaged, reused or recycled include, but are not limited to, the following:

1. Acoustical ceiling tiles
2. Asphalt
3. Asphalt shingles
4. Cardboard packaging
5. Carpet and carpet pad
6. Concrete
7. Drywall
8. Fluorescent lights and ballasts
9. Land clearing debris (vegetation, stumpage, dirt)
10. Metals
11. Paint (through hazardous waste outlets)
12. Wood
13. Plastic film (sheeting, shrink wrap, packaging)
14. Window glass
15. Wood
16. Field office waste, including office paper, aluminum cans, glass, plastic, and office cardboard.

1.5 QUALITY ASSURANCE

A. Waste Management Coordinator Qualifications: Experienced firm, with a record of successful waste management coordination of projects with similar requirements, that employs a LEED Accredited Professional, certified by the USGBC as waste management coordinator.

B. Refrigerant Recovery Technician Qualifications: Certified by EPA-approved certification program.

C. Regulatory Requirements: Conduct construction waste management activities in accordance with hauling and disposal regulations of all authorities having jurisdiction and all other applicable laws and ordinances.

D. Preconstruction Conference: Schedule and conduct meeting at Project site prior to construction activities.

1. Attendees: Inform the following individuals, whose presence is required, of date and time of meeting.

a. Owner
b. Architect
c. Contractor's superintendent
d. Major subcontractors
e. Waste Management Coordinator
f. Other concerned parties.

2. Agenda Items: Review methods and procedures related to waste management including, but not limited to, the following:

a. Review and discuss waste management plan including responsibilities of Waste Management Coordinator.
b. Review requirements for documenting quantities of each type of waste and its disposition.
c. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.
d. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
e. Review waste management requirements for each trade.

3. Minutes: Record discussion. Distribute meeting minutes to all participants.
Note: If there is a Project Architect, they will perform this role.

1.6 WASTE MANAGEMENT PLAN – Contactor shall develop and document the following:

A. Develop a plan to meet the requirements listed in this section at a minimum. Plan shall consist of waste identification, waste reduction plan and cost/revenue analysis. Distinguish between demolition and construction waste. Indicate quantities by weight throughout the plan.

B. Indicate anticipated types and quantities of demolition, site-cleaning and construction waste generated by the project. List all assumptions made for the quantities estimates.

C. List each type of waste and whether it will be salvaged, recycled, or disposed of in an landfill. The plan should included the following information:

1. Types and estimated quantities, by weight, of CDL waste expected to be generated during demolition and construction.

2. Proposed methods for CDL waste salvage, reuse, recycling and disposal during demolition including, but not limited to, one or more of the following:

    a. Contracting with a deconstruction specialist to salvage materials generated,
    b. Selective salvage as part of demolition contractor's work,
    c. Reuse of materials on-site or sale or donation to a third party.

3. Proposed methods for salvage, reuse, recycling and disposal during construction including, but not limited to, one or more of the following:

    a. Requiring subcontractors to take their CDL waste to a recycling facility;
    b. Contracting with a recycling hauler to haul recyclable CDL waste to an approved recycling or material recovery facility;
    c. Processing and reusing materials on-site;
    d. Self-hauling to a recycling or material recovery facility.

4. Name of recycling or material recovery facility receiving the CDL wastes.

5. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location on project site where materials separation will be located.

D. Cost/Revenue Analysis: Indicate total cost of waste disposal as if there was no waste management plan and net additional cost or net savings resulting from implementing waste management plan. Include the following:

1. Total quantity of waste.
2. Estimated cost of disposal (cost per unit). Include hauling and tipping fees and cost of collection containers for each type of waste.
3. Total cost of disposal (with no waste management).
4. Revenue from salvaged materials.
5. Revenue from recycled materials.
6. Savings in hauling and tipping fees by donating materials.
7. Savings in hauling and tipping fees that are avoided.
8. Handling and transportation costs. Including cost of collection containers for each type of waste.
9. Net additional cost or net savings from waste management plan.

PART 2 - PRODUCTS (Not Used)

PART 3 – EXECUTION

3.1 CONSTRUCTION WASTE MANAGEMENT, GENERAL

A. Provide containers for CDL waste that is to be recycled clearly labeled as such with a list of acceptable and unacceptable materials. The list of acceptable materials must be the same as the materials recycled at the receiving material recovery facility or recycling processor.

B. The collection containers for recyclable CDL waste must contain no more than 10% non-recyclable material, by volume.

C. Provide containers for CDL waste that is disposed in a landfill clearly labeled as such.

D. Use detailed material estimates to reduce risk of unplanned and potentially wasteful cuts.

E. To the greatest extent possible, include in material purchasing agreements a waste reduction provision requesting that materials and equipment be delivered in packaging made of recyclable material, that they reduce the amount of packaging, that packaging be taken back for reuse or recycling, and to take back all unused product. Insure that subcontractors require the same provisions in their purchase agreements.

F. Conduct regular visual inspections of dumpsters and recycling bins to remove contaminants.

3.2 SOURCE SEPARATION

A. General: Contractor shall separate recyclable materials from CDL waste to the maximum extent possible.

Separate recyclable materials by type.

1. Provide containers, clearly labeled, by type of separated materials or provide other storage method for managing recyclable materials until they are removed from Project site.
2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water and to minimize pest attraction. Cover to prevent windblown dust.
3. Stockpile materials away from demolition area. Do not store within drip line of remaining trees.
4. Store components off the ground and protect from weather.

3.3 CO-MINGLED RECYCLING

A. General: Do not put CDL waste that will be disposed in a landfill into a co-mingled CDL waste recycling container.

3.4 REMOVAL OF CONSTRUCTION WASTE MATERIALS

A. Remove CDL waste materials from project site on a regular basis. Do not allow CDL waste to accumulate on-site.

B. Transport CDL waste materials off Owner's property and legally dispose of them.

C. Burning of CDL waste is not permitted.

3.5 UNIVERSAL WASTE DIVERSION

A. Remove all universal waste from fixtures, panels, and related devices for proper diversion and reclamation.

B. Store all universal waste in containers provided by contact person within facilities operations.

C. Store all universal waste in a secured location and request periodic removal from assigned contact person.

D. Exemption: electric motors, circuit breakers, transformers and lighting contactors are exempt
from this provision provided the contractor chooses to salvage or reuse the components.

E. No identified universal waste will be discarded into the waste stream.

END OF SECTION

WASTE MANAGEMENT PROGRESS REPORT				
	DISPOSED IN MUNICIPAL SOLID WASTE LANDFILL	**DIVERTED FROM LANDFILL BY RECYCLING, SALVAGE OR REUSE**		
MATERIAL CATEGORY		Recycled	Salvaged	Reused
1. Acoustical Ceiling Tiles				
2. Asphalt				
3. Asphalt Shingles				
4. Cardboard Packaging				
5. Carpet and Carpet Pad				
6. Concrete				
7. Drywall				
8. Fluorescent Lights and Ballasts				
9. Land Clearing Debris (vegetation, stumpage, dirt)				
10. Metals				
11. Paint (through hazardous waste outlets)				
12. Wood				
13. Plastic Film (sheeting, shrink wrap, packaging)				
14. Window Glass				
15. Field Office Waste (office paper, aluminum cans, glass, plastic, and coffee cardboard)				
16. Other (insert description)				
17. Other (insert description)				
Total (In Weight)		(TOTAL OF ALL ABOVE VALUES – IN WEIGHT)		
	Percentage of Waste Diverted	(TOTAL WASTE DIVIDED BY TOTAL DIVERTED)		

PAGE LEFT INTENTIONALLY BLANK

SECTION 01 77 00
CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for Contract closeout, including, but not limited to, the following:

1. Substantial Completion procedures.
2. Final Completion procedures.
3. List of incomplete items.
4. Submittal of Project warranties.
5. Final cleaning.

B. Related Requirements:

1. Section 012900 "Payment Procedures" for requirements for Applications for Payment for Substantial Completion and Final Completion.

2. Section 017823 "Operation and Maintenance Data" for additional operation and maintenance manual requirements.
3. Section 017839 "Project Record Documents" for submitting Record Drawings, Record Specifications, and Record Product Data.
4. Section 017900 "Demonstration and Training" for requirements to train Owner's maintenance personnel to adjust, operate, and maintain products, equipment, and systems.

1.2 DEFINITIONS

A. List of Incomplete Items: Contractor-prepared list of items to be completed or corrected, prepared for the Architect's use prior to Architect's inspection, to determine if the Work is substantially complete.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of cleaning agent.

B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.

C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.4 CLOSEOUT SUBMITTALS

A. Certificates of Release: From authorities having jurisdiction.

B. Certificate of Insurance: For continuing coverage.

C. Field Report: For pest-control inspection.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Schedule of Maintenance Material Items: For maintenance material submittal items required by other Sections.

1.6 SUBSTANTIAL COMPLETION PROCEDURES

A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's "punch list"), indicating the value of each item on the list and reasons why the Work is incomplete.

B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction, permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
2. Submit closeout submittals specified in other Division 01 Sections, including Project Record Documents, operation and maintenance manuals, damage or settlement surveys, property surveys, and similar final record information.
3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number.

    a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's signature for receipt of submittals.

5. Submit testing, adjusting, and balancing records.
6. Submit sustainable design submittals not previously submitted.
7. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.

C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Advise Owner of pending insurance changeover requirements.
2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
3. Complete startup and testing of systems and equipment.
4. Perform preventive maintenance on equipment used prior to Substantial Completion.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
6. Advise Owner of changeover in utility services.
7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
9. Complete final cleaning requirements.
10. Touch up paint and otherwise repair and restore marred exposed finishes to eliminate visual defects.

D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for Final Completion.

1.7 FINAL COMPLETION PROCEDURES

A. Submittals Prior to Final Completion: Before requesting final inspection for determining Final Completion, complete the following:

1. Submit a final Application for Payment in accordance with Section 012900 "Payment Procedures."
2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list will state that each item has been completed or otherwise resolved for acceptance.
3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.

4. Submit pest-control final inspection report.
5. Submit Final Completion photographic documentation.

B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the Work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.8 LIST OF INCOMPLETE ITEMS

A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.

1. Organize list of spaces in sequential order, starting with exterior areas first, listed by room or space number.
2. Organize items applying to each space by major element, including categories for ceilings, individual walls, floors, equipment, and building systems.
3. Include the following information at the top of each page:

    a. Project name.
    b. Date.
    c. Name of Architect.
    d. Name of Contractor.
    e. Page number.

4. Submit list of incomplete items in the following format:

    a. MS Excel Electronic File: Architect will return annotated file.
    b. PDF Electronic File: Architect will return annotated file.
    c. Web-Based Project Software Upload: Utilize software feature for creating and updating list of incomplete items (punch list).
    d. Three Paper Copies: Architect will return two copies.

1.9 SUBMITTAL OF PROJECT WARRANTIES

A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where warranties are indicated to commence on dates other than date of Substantial Completion, or when delay in submittal of warranties might limit Owner's rights under warranty.

B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.

C. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.

D. Warranty Electronic File: Provide warranties and bonds in PDF format. Assemble complete warranty and bond submittal package into a single electronic PDF file with bookmarks enabling navigation to each item. Provide bookmarked table of contents at beginning of document.

1. Submit on digital media acceptable to Architect.

E. Warranties in Paper Form:

1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive **8-1/2-by-11-inch** paper.
2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

F. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.

1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:

a. Clean Project site of rubbish, waste material, litter, and other foreign substances.
b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
c. Rake grounds that are not planted, mulched, or paved to a smooth, even-textured surface.
d. Remove tools, construction equipment, machinery, and surplus material from Project site.
e. Remove snow and ice to provide safe access to building.
f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
g. Remove debris and surface dust from limited-access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
h. Clean flooring, removing debris, dirt, and staining; clean in accordance with manufacturer's instructions.
i. Vacuum and mop concrete.
j. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean in accordance with manufacturer's instructions if visible soil or stains remain.
k. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
l. Remove labels that are not permanent.
m. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
n. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
o. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
p. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.

1) Clean HVAC system in compliance with NADCA ACR. Provide written report on completion of cleaning.

q. Clean luminaires, lamps, globes, and reflectors to function with full

efficiency.

r. Clean strainers.

s. Leave Project clean and ready for occupancy.

C. Pest Control: Comply with pest control requirements in Section 015000 "Temporary Facilities and Controls." Prepare written report.

D. Construction Waste Disposal: Comply with waste-disposal requirements in Section 017419 "Construction Waste Management and Disposal."

3.2 CORRECTION OF THE WORK

A. Complete repair and restoration operations required by "Correction of the Work" Article in Section 017300 "Execution" before requesting inspection for determination of Substantial Completion.

END OF SECTION 01 77 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 01 78 23
OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Administrative and procedural requirements for preparing operation and maintenance manuals, including the following:

1. Operation and maintenance documentation directory manuals.

2. Systems and equipment operation manuals.
3. Systems and equipment maintenance manuals.
4. Product maintenance manuals.

B. Related Requirements:

1. Section 013300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.

1.2 DEFINITIONS

A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.

B. Subsystem: A portion of a system with characteristics similar to a system.

1.3 CLOSEOUT SUBMITTALS

A. Submit operation and maintenance manuals indicated. Provide content for each manual as specified in individual Specification Sections, and as reviewed and approved at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.

1. Architect and Commissioning Authority will comment on whether content of operation and maintenance submittals is acceptable.
2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.

B. Format: Submit operation and maintenance manuals in the following format:

1. Submit on digital media acceptable to Architect. Enable reviewer comments on draft submittals.
2. Submit three paper copies. Architect, will return two copies.

C. Initial Manual Submittal: Submit draft copy of each manual at least 30 days before commencing demonstration and training. Architect will comment on whether general scope and content of manual are acceptable.

D. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.

1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.

E. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

1.4 FORMAT OF OPERATION AND MAINTENANCE MANUALS

A. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.

1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
2. File Names and Bookmarks: Bookmark individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

B. Manuals, Paper Copy: Submit manuals in the form of hard-copy, bound and labeled volumes.

1. Binders: Heavy-duty, three-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold **8-1/2-by-11-inch** paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.

a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
b. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, subject matter of contents, and indicate Specification Section number on bottom of spine. Indicate volume number for multiple-volume sets.

2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software storage media for computerized electronic equipment. Enclose title pages and directories in clear plastic sleeves.
4. Supplementary Text: Prepared on **8-1/2-by-11-inch** white bond paper.
5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.

    a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
    b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

1.5 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

A. Organization of Manuals: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual to contain the following materials, in the order listed:

1. Title page.
2. Table of contents.
3. Manual contents.

B. Title Page: Include the following information:

1. Subject matter included in manual.
2. Name and address of Project.
3. Name and address of Owner.
4. Date of submittal.
5. Name and contact information for Contractor.
6. Name and contact information for Construction Manager.
7. Name and contact information for Architect.
8. Name and contact information for Commissioning Authority.
9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
10. Cross-reference to related systems in other operation and maintenance manuals.

C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.

D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.

E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation in accordance with ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

1.6 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY MANUAL

A. Operation and Maintenance Documentation Directory: Prepare a separate manual that provides an organized reference to emergency, operation, and maintenance manuals. List items and their location to facilitate ready access to desired information. Include the following:

1. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
2. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
3. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.

1.7 SYSTEMS AND EQUIPMENT OPERATION MANUALS

A. Systems and Equipment Operation Manual: Assemble a complete set of data indicating operation of each system, subsystem, and piece of equipment not part of a system. Include information required for daily operation and management, operating standards, and routine and special operating procedures.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.

B. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:

1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.

2. Performance and design criteria if Contractor has delegated design responsibility.
3. Operating standards.
4. Operating procedures.
5. Operating logs.
6. Wiring diagrams.
7. Control diagrams.
8. Piped system diagrams.
9. Precautions against improper use.
10. License requirements including inspection and renewal dates.

C. Descriptions: Include the following:

1. Product name and model number. Use designations for products indicated on Contract Documents.
2. Manufacturer's name.
3. Equipment identification with serial number of each component.
4. Equipment function.
5. Operating characteristics.
6. Limiting conditions.
7. Performance curves.
8. Engineering data and tests.
9. Complete nomenclature and number of replacement parts.

D. Operating Procedures: Include the following, as applicable:

1. Startup procedures.
2. Equipment or system break-in procedures.
3. Routine and normal operating instructions.
4. Regulation and control procedures.
5. Instructions on stopping.
6. Normal shutdown instructions.
7. Seasonal and weekend operating instructions.
8. Required sequences for electric or electronic systems.
9. Special operating instructions and procedures.

E. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

F. Piped Systems: Diagram piping as installed, and identify color coding where required for identification.

1.8 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

A. Systems and Equipment Maintenance Manuals: Assemble a complete set of data indicating maintenance of each system, subsystem, and piece of equipment not part of a system. Include manufacturers' maintenance documentation, preventive maintenance procedures and frequency, repair procedures, wiring and systems diagrams, lists of spare parts, and warranty information.

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.

B. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranties and bonds as described below.

C. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

D. Manufacturers' Maintenance Documentation: Include the following information for each component part or piece of equipment:

1. Standard maintenance instructions and bulletins; include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.

    a. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.

2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
3. Identification and nomenclature of parts and components.
4. List of items recommended to be stocked as spare parts.

E. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:

1. Test and inspection instructions.
2. Troubleshooting guide.
3. Precautions against improper maintenance.
4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
5. Aligning, adjusting, and checking instructions.
6. Demonstration and training video recording, if available.

F. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules

for preventive and routine maintenance and service with standard time allotment.

1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.

G. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.

H. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.

I. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

J. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.

1. Do not use original project record documents as part of maintenance manuals.

1.9 PRODUCT MAINTENANCE MANUALS

A. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.

B. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.

C. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

D. Product Information: Include the following, as applicable:

1. Product name and model number.
2. Manufacturer's name.

3. Color, pattern, and texture.
4. Material and chemical composition.
5. Reordering information for specially manufactured products.

E. Maintenance Procedures: Include manufacturer's written recommendations and the following:

1. Inspection procedures.
2. Types of cleaning agents to be used and methods of cleaning.
3. List of cleaning agents and methods of cleaning detrimental to product.
4. Schedule for routine cleaning and maintenance.
5. Repair instructions.

F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 78 23

SECTION 01 78 39
PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for Project Record Documents, including the following:

1. Record Drawings.
2. Record specifications.
3. Record Product Data.
4. Miscellaneous record submittals.

B. Related Requirements:

1. Section 017300 "Execution" for final property survey.
2. Section 017700 "Closeout Procedures" for general closeout procedures.
3. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.2 CLOSEOUT SUBMITTALS

A. Record Drawings: Comply with the following:

1. Number of Copies: Submit one set(s) of marked-up record prints.
2. Number of Copies: Submit copies of Record Drawings as follows:

a. Initial Submittal:

1) Submit one paper-copy set(s) of marked-up record prints.
2) Submit PDF electronic files of scanned record prints and one set(s) of file prints.
3) Submit Record Digital Data Files and one set(s) of plots.
4) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.

b. Final Submittal:

1) Submit one paper-copy set(s) of marked-up record prints.
2) Submit Record Digital Data Files and set of Record Digital Data File plots.
3) Plot each drawing file, whether or not changes and additional information were recorded.

B. Record Specifications: Submit annotated PDF electronic files and paper copies of Project's Specifications, including addenda and Contract modifications.

C. Record Product Data: Submit annotated PDF electronic files and directories and paper copies of each submittal.

1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.

D. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories and paper copies of each submittal.

E. Reports: Submit written report weekly indicating items incorporated into Project Record Documents concurrent with progress of the Work, including revisions, concealed conditions, field changes, product selections, and other notations incorporated.

1.3 RECORD DRAWINGS

A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.

1. Preparation: Mark record prints to show the actual installation, where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.

a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
b. Accurately record information in an acceptable drawing technique.
c. Record data as soon as possible after obtaining it.
d. Record and check the markup before enclosing concealed installations.
e. Cross-reference record prints to corresponding photographic documentation.

2. Content: Types of items requiring marking include, but are not limited to, the following:

a. Dimensional changes to Drawings.
b. Revisions to details shown on Drawings.
c. Depths of foundations.
d. Locations and depths of underground utilities.
e. Revisions to routing of piping and conduits.
f. Revisions to electrical circuitry.

g. Actual equipment locations.
h. Duct size and routing.
i. Locations of concealed internal utilities.
j. Changes made by Change Order or Construction Change Directive.
k. Changes made following Architect's written orders.
l. Details not on the original Contract Drawings.
m. Field records for variable and concealed conditions.
n. Record information on the Work that is shown only schematically.

3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
4. Mark record prints with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
5. Mark important additional information that was either shown schematically or omitted from original Drawings.
6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:

1. Format: Same digital data software program, version, and operating system as for the original Contract Drawings.
2. Format: DWG.
3. Format: Annotated PDF electronic file with comment function enabled.
4. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
5. Refer instances of uncertainty to Architect for resolution.
6. Architect will furnish Contractor with one set of digital data files of the Contract Drawings for use in recording information.

a. See Section 013100 "Project Management and Coordination" for requirements related to use of Architect's digital data files.
b. Architect will provide data file layer information. Record markups in separate layers.

C. Format: Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

1. Record Prints: Organize record prints into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
2. Format: Annotated PDF electronic file with comment function enabled.
3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.

4. Identification: As follows:

    a. Project name.
    b. Date.
    c. Designation "PROJECT RECORD DRAWINGS."
    d. Name of Architect.
    e. Name of Contractor.

1.4 RECORD SPECIFICATIONS

A. Preparation: Mark Specifications to indicate the actual product installation, where installation varies from that indicated in Specifications, addenda, and Contract modifications.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
4. For each principal product, indicate whether Record Product Data has been submitted in operation and maintenance manuals instead of submitted as Record Product Data.
5. Note related Change Orders , Record Product Data, and Record Drawings where applicable.

B. Format: Submit record specifications as annotated PDF electronic file or scanned PDF electronic file(s) of marked-up paper copy of Specifications.

1.5 RECORD PRODUCT DATA

A. Recording: Maintain one copy of each submittal during the construction period for Project Record Document purposes. Post changes and revisions to Project Record Documents as they occur; do not wait until end of Project.

B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
3. Note related Change Orders , Record Specifications, and Record Drawings where applicable.

C. Format: Submit Record Product Data as annotated PDF electronic file.

1. Include Record Product Data directory organized by Specification Section

number and title, electronically linked to each item of Record Product Data.

1.6 MISCELLANEOUS RECORD SUBMITTALS

A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

B. Format: Submit miscellaneous record submittals as PDF electronic file or scanned PDF electronic file(s) of marked-up miscellaneous record submittals.

1. Include miscellaneous record submittals directory organized by Specification Section number and title, electronically linked to each item of miscellaneous record submittals.

1.7 MAINTENANCE OF RECORD DOCUMENTS

A. Maintenance of Record Documents: Store Record Documents in the field office apart from the Contract Documents used for construction. Do not use Project Record Documents for construction purposes. Maintain Record Documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to Project Record Documents for Architect'sreference during normal working hours.

PART 2 - PRODUCTS (Not Used)
PART 3 - EXECUTION (Not Used)

END OF SECTION 01 78 39

PAGE LEFT INTENTIONALLY BLANK

SECTION 019113 – GENERAL COMMISSIONING REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes general requirements that apply to implementation of commissioning without regard to systems, subsystems, and equipment being commissioned.

B. Related Sections include the following:

1. Division 01 Section "HVAC Commissioning Requirements**"** for specific requirements for commissioning HVAC systems.
2. Division 26 Section "Commissioning of Electrical Systems" for specific requirements for commissioning electrical systems.
3. Division 01 Section "Contract Closeout" for specific requirements for closeout at substantial and final completion.
4. Division 01 Section "Contract Closeout" for Specific Requirements for training and demonstration of systems to Owner.
5. Division 01 Section "Contract Closeout" for Specific Requirements related to the Preparation of systems operation and maintenance manuals.

1.3 DEFINITIONS

A. CxA: Commissioning Authority.

B. OPR: Owner's Project Requirements.

C. Systems, Subsystems, and Equipment: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, and equipment.

D. TAB: Testing, Adjusting, and Balancing.

1.4 COMMISSIONING TEAM

A. Members Appointed by Contractor(s): Individuals, each having authority to act on behalf of the entity he or she represents, explicitly organized to implement the commissioning process through coordinated actions. The commissioning team

shall consist of, but not be limited to, representatives of Contractor, including Project superintendent and subcontractors, installers, suppliers, and specialists deemed appropriate by the CxA.

B. Members Appointed by Owner:

1. CxA: The designated person, company, or entity that plans, schedules, and coordinates the commissioning team to implement the commissioning process. Owner will engage the CxA under a separate contract.
2. All contractor commissioning requirements and costs associated with commissioning the project shall be included in the base bid.
3. Representatives of the facility user and operation and maintenance personnel.
4. Architect and Engineering design professionals.

1.5 OWNER'S RESPONSIBILITIES

A. Assign operation and maintenance personnel and schedule them to participate in commissioning team activities including, but not limited to, the following:

1. Coordination meetings.
2. Training in operation and maintenance of systems, subsystems, and equipment.
3. Testing meetings.
4. Demonstration of operation of systems, subsystems, and equipment.

1.6 CONTRACTOR'S RESPONSIBILITIES

A. Provide utility services required for the commissioning process.

B. Contractor shall assign representatives with expertise and authority to act on behalf of the Contractor and schedule them to participate in and perform commissioning team activities including, but not limited to, the following:

1. Participate in commissioning and construction-phase coordination meetings.
2. Participate in maintenance orientation and inspection.
3. Participate in operation and maintenance training sessions.
4. Participate in final review at acceptance meeting.
5. Certify that Work is complete and systems are operational according to the Contract Documents, including calibration of instrumentation and controls.
6. Evaluate performance deficiencies identified in test reports and, in collaboration with entity responsible for system and equipment installation, recommend corrective action.
7. Review and approve final commissioning documentation.
8. Certify that all pre-test work and pre-testing of functional performance tests are complete and operational prior to scheduling performed testing by CxA. Submit completed functional performance test forms with data from pre-

testing.

9. During functional performance testing, a representative from the mechanical contractor, controls contractor, and test/balance engineer must be present and participate in testing.

C. Subcontractors shall assign representatives with expertise and authority to act on behalf of subcontractors and schedule them to participate in and perform commissioning team activities including, but not limited to, the following:

1. Pre-test all systems/equipment prior to engaging CxA for Functional Performance Testing.
2. Participate in commissioning and construction-phase coordination meetings.
3. Participate in maintenance orientation and inspection.
4. Participate in procedures meeting for testing.
5. Participate in final review at acceptance meeting.
6. Provide schedule for operation and maintenance data submittals, equipment startup, and testing to CxA for incorporation into the commissioning plan. Update schedule on a weekly basis throughout the construction period.
7. Provide information to the CxA for developing construction-phase commissioning plan.
8. Participate in training sessions for Owner's operation and maintenance personnel.
9. Provide updated Project Record Documents to the CxA on a daily basis.
10. Gather and submit operation and maintenance data for systems, subsystems, and equipment to the CxA, as specified in Division 01 Section "Operation and Maintenance Data."
11. Provide technicians who are familiar with the construction and operation of installed systems and who shall develop specific test procedures and participate in testing of installed systems, subsystems, and equipment.
12. The test/balance subcontractor, mechanical contractor, and automatic temperature controls subcontractor must be on-site and provide assistance during all functional performance testing.

D. Contractors and subcontractors must pre-inspect and pre-test all equipment and systems prior to requesting functional performance testing by the CxA. All pre-start/start-up checklists and functional performance test forms must be completed and submitted to Engineer prior to scheduling formal functional performance testing.

1.7 CXA'S RESPONSIBILITIES

A. Organize and lead the commissioning team.

B. Prepare a construction-phase commissioning plan. Collaborate with Contractor and with subcontractors to develop test and inspection procedures. Include design changes and scheduled commissioning activities coordinated with overall Project schedule. Identify commissioning team member responsibilities, by name, firm,

and trade specialty, for performance of each commissioning task.

C. Convene commissioning team meetings for the purpose of coordination, communication, and conflict resolution; discuss progress of the commissioning processes. Responsibilities include arranging for facilities, preparing agenda and attendance lists, and notifying participants. The CxA shall prepare and distribute minutes to commissioning team members and attendees within five workdays of the commissioning meeting.

D. At a mutually agreed upon time, conduct an initial construction-phase coordination meeting for the purpose of reviewing the commissioning activities and establishing tentative schedules for operation and maintenance submittals; operation and maintenance training sessions; TAB Work; and Project completion.

E. Observe and inspect construction and report progress and deficiencies. In addition to compliance with the Contract Documents, inspect systems and equipment installation for adequate accessibility for maintenance and component replacement or repair.

F. Prepare Project-specific test and inspection procedures and checklists.

G. Schedule, direct, witness, and document tests, inspections, and systems startup.

H. Compile test data, inspection reports, and certificates and include them in the systems manual and commissioning report.

I. Certify date of acceptance and startup for each item of equipment for start of warranty periods.

J. Review Project Record Documents for accuracy. Request revisions from Contractor to achieve accuracy. Project Record Documents requirements are specified in Division 01 Section "Project Record Documents."

K. Review and comment on operation and maintenance documentation and systems manual outline for compliance with the Contract Documents. Operation and maintenance documentation requirements are specified in Division 01 Section

L. Assemble the final commissioning documentation, including the commissioning report and Project Record Documents.

1.8 COMMISSIONING DOCUMENTATION

A. Commissioning Plan: A document, prepared by CxA, that outlines the schedule, allocation of resources, and documentation requirements of the commissioning process, and shall include, but is not limited to the following:

1. Plan for delivery and review of submittals, systems manuals, and other documents and reports. Identification of the relationship of these documents to other functions and a detailed description of submittals that are required to support the commissioning processes. Submittal dates

shall include the latest date approved submittals must be received without adversely affecting commissioning plan.

2. Description of the organization, layout, and content of commissioning documentation (including systems manual) and a detailed description of documents to be provided along with identification of responsible parties.
3. Identification of systems and equipment to be commissioned.
4. Description of schedules for testing procedures along with identification of parties involved in performing and verifying tests.
5. Identification of items that must be completed before the next operation can proceed.
6. Description of responsibilities of commissioning team members.
7. Description of observations to be made.
8. Description of requirements for operation and maintenance training, including required training materials.
9. Description of expected performance for systems, subsystems, equipment, and controls.
10. Schedule for commissioning activities with specific dates coordinated with overall construction schedule.
11. Identification of installed systems, subsystems, and equipment, including design changes that occurred during the construction phase.
12. Process and schedule for documenting changes on a continuous basis to appear in Project Record Documents.
13. Process and schedule for completing prestart and startup checklists for systems, subsystems, and equipment to be verified and tested.
14. Step-by-step procedures for testing systems, subsystems, and equipment with descriptions for methods of verifying relevant data, recording the results obtained, and listing parties involved in performing and verifying tests.

B. Test Checklists: CxA, with assistance of Contractor and Subcontractors, shall develop test checklists for each system, subsystem, or equipment including interfaces and interlocks, and include a separate entry, with space for comments, for each item to be tested. Prepare separate checklists for each mode of operation and provide space to indicate whether the mode under test responded as required. Provide space for testing personnel to sign off on each checklist. Specific checklist content requirements are specified in Division 01 Section "HVAC Commissioning Requirements" and Division 26 Section "Commissioning of Electrical Systems". Test checklists will be jointly developed as the project progresses. Each checklist, regardless of system, subsystem, or equipment being tested, shall include, but not be limited to, the following:

1. Name and identification code of tested item.
2. Test number.
3. Time and date of test.
4. Indication of whether the record is for a first test or retest following correction of a problem or issue.
5. Dated signatures of the person performing test and of the witness, if applicable.
6. Individuals present for test.
7. Deficiencies.

8. Issue number, if any, generated as the result of test.

C. Certificate of Readiness: Certificate of Readiness shall be signed by Contractor, Subcontractor(s), Installer(s), and CxA certifying that systems, subsystems, equipment, and associated controls are ready for testing. Completed test checklists signed by the responsible parties shall accompany this certificate.

D. Test and Inspection Reports: CxA shall record test data, observations, and measurements on test checklists. Photographs, forms, and other means appropriate for the application shall be included with data. CxA shall compile test and inspection reports and test and inspection certificates and include them in systems manual and commissioning report.

E. Corrective Action Documents: CxA shall document corrective action taken for systems and equipment that fail tests. Include required modifications to systems and equipment and revisions to test procedures, if any. Retest systems and equipment requiring corrective action and document retest results.

F. Issues Log: CxA shall prepare and maintain an issues log that describes design, installation, and performance issues that are at variance with the Contract Documents. Identify and track issues as they are encountered, documenting the status of unresolved and resolved issues.

1. Creating an Issues Log Entry:

   a. Identify the issue with unique numeric or alphanumeric identifier by which the issue may be tracked.
   b. Assign a descriptive title of the issue.
   c. Identify date and time of the issue.
   d. Identify test number of test being performed at the time of the observation, if applicable, for cross-reference.
   e. Identify system, subsystem, and equipment to which the issue applies.
   f. Identify location of system, subsystem, and equipment.
   g. Include information that may be helpful in diagnosing or evaluating the issue.
   h. Note recommended corrective action.
   i. Identify commissioning team member responsible for corrective action.
   j. Identify expected date of correction.
   k. Identify person documenting the issue.

2. Documenting Issue Resolution:

   a. Log date correction is completed or the issue is resolved.
   b. Describe corrective action or resolution taken. Include description of diagnostic steps taken to determine root cause of the issue, if any.
   c. Identify changes to the Contract Documents that may require action.

d. State that correction was completed and system, subsystem, and equipment is ready for retest, if applicable.
e. Identify person(s) who corrected or resolved the issue.
f. Identify person(s) documenting the issue resolution.

3. Issues Log Report: On a periodic basis, but not less than for each commissioning team meeting, CxA shall prepare a written narrative for review of outstanding issues and a status update of the issues log. As a minimum, CxA shall include the following information in the issues log and expand it in the narrative:

a. Issue number and title.
b. Date of the identification of the issue.
c. Name of the commissioning team member assigned responsibility for resolution.
d. Expected date of correction.

G. Commissioning Report: CxA shall document results of the commissioning process including unresolved issues and performance of systems, subsystems, and equipment. The commissioning report shall indicate whether systems, subsystems, and equipment have been completed and are performing according to the Contract Documents. The commissioning report shall include, but is not limited to, the following:

1. Lists and explanations of substitutions; compromises; variances in the Contract Documents; record of conditions; and, if appropriate, recommendations for resolution. This report shall be used to evaluate systems, subsystems, and equipment and shall serve as a future reference document during Owner occupancy and operation. It shall describe components and performance that exceed requirements of the Contract Documents and those that do not meet requirements of the Contract Documents. It may also include a recommendation for accepting or rejecting systems, subsystems, and equipment.
2. Commissioning plan.
3. Testing plans and reports.
4. Corrective modification documentation.
5. Issues log.
6. Completed test checklists.
7. Punch Lists.
8. Test/Balance Reports.
9. Listing of off-season test(s) not performed and a schedule for their completion.
10. All commissioning documents must be submitted to the building Owner within 90 days of the date of receipt of the Certificate of Occupancy.

H. Systems Manual: CxA shall gather required information and compile systems manual. Systems manual shall include, but is not limited to, the following:

1. Project Record Documents as specified in Division 01 Section "Project Record Documents."

2. Final commissioning plan.
3. Commissioning report.
4. Operation and maintenance data as specified in Division 01 Section "Operation and Maintenance Data."

1.9 SUBMITTALS

A. Test Checklists and Report Forms: CxA shall submit sample checklists and forms to Contractor quality-control manager and subcontractors for review and comment. Submit two copies of each checklist and report form.

B. Test and Inspection Reports: CxA shall submit test and inspection reports.

C. Corrective Action Documents: CxA shall submit corrective action documents.

1.10 QUALITY ASSURANCE

A. Instructor Qualifications: Factory-authorized service representatives, experienced in training, operation, and maintenance procedures for installed systems, subsystems, and equipment.

B. Test Equipment Calibration: Comply with test equipment manufacturer's calibration procedures and intervals. Recalibrate test instruments immediately whenever instruments have been repaired following damage or dropping. Affix calibration tags to test instruments. Instruments shall have been calibrated within six months prior to use.

1.11 COORDINATION

A. Coordinating Meetings: CxA shall conduct coordination meetings of the commissioning team to review progress on the commissioning plan, to discuss scheduling conflicts, and to discuss upcoming commissioning process activities.

B. Pretesting Meetings: CxA shall conduct pretest meetings of the commissioning team to review startup reports, pretest inspection results, testing procedures, testing personnel and instrumentation requirements, and manufacturers' authorized service representative services for each system, subsystem, equipment, and component to be tested.

C. Testing Coordination: CxA shall coordinate sequence of testing activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

D. Manufacturers' Field Services: CxA and Contractor shall coordinate services of

manufacturers' field services.

1.12 ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 OPERATION AND MAINTENANCE TRAINING REQUIREMENTS

A. Training Preparation Conference: Before operation and maintenance training, CxA shall convene a training preparation conference to include Owner's operation and maintenance personnel, Contractor, and subcontractors. In addition to requirements specified in Division 01 Section "Demonstration and Training," perform the following:

1. Review installed systems, subsystems, and equipment.
2. Review instructor qualifications.
3. Review instructional methods and procedures.
4. Review training module outlines and contents.
5. Review course materials (including operation and maintenance manuals).
6. Inspect and discuss locations and other facilities required for instruction.
7. Review and finalize training schedule and verify availability of educational materials, instructors, audiovisual equipment, and facilities needed to avoid delays.
8. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

B. Training Modules: Develop an instruction program that includes individual training modules for each system, subsystem, and equipment as specified in Division 01 Section "Demonstration and Training."

END OF SECTION 019113

PAGE LEFT INTENTIONALLY BLANK

SECTION 019115 - HVAC COMMISSIONING REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes requirements for commissioning the HVAC system and its subsystems and equipment. This Section supplements the general requirements specified in Division 01 Section "General Commissioning Requirements."

B. Related Sections include the following:

1. Division 01 Section "General Commissioning Requirements" for general requirements for commissioning processes that apply to this Section.

C. The following systems and/or equipment shall be commissioned:

1. Automatic temperature control system.
2. Condensate pumps.
3. Dampers.
4. Differential static pressure controllers.
5. Ductless heat pumps.
6. Exhaust fans.
7. Existing finned tube radiators.
8. HVAC controls, plug load controls, and sequences of operation.
9. Pressure independent control valves.
10. Pumps.
11. Refrigerant mitigation controls.
12. Refrigerant leak detectors.
13. Static pressure sensors.
14. Supply air terminals including heating coils.
15. Temperature sensors.
16. Unit heaters.
17. Variable air volume boxes.

1.3 DEFINITIONS

A. Architect: Includes Architect identified in the Contract for Construction between Owner and Contractor, plus consultant/design professionals responsible for design of HVAC, electrical, communications, controls for HVAC systems, and other

related systems.

B. CxA: Commissioning Authority.

C. Systems, Subsystems, and Equipment: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, and equipment.

D. TAB: Testing, Adjusting, and Balancing.

1.4 CONTRACTOR'S RESPONSIBILITIES

A. The following responsibilities are in addition to those specified in Division 01 Section "General Commissioning Requirements."

B. Contractor:

1. Attend procedures meeting for TAB Work.
2. Certify that TAB Work is complete.
3. Assist performing functional performance tests.

C. Mechanical Contractor:

1. Attend TAB verification testing.
2. Provide measuring instruments and logging devices to record test data, and data acquisition equipment to record data for the complete range of testing for the required test period.
3. Assist performing functional performance tests.

D. HVAC Instrumentation and Control Contractor: With the CxA, review control designs for compliance with the Contract Documents, controllability with respect to actual equipment to be installed, and recommend adjustments to control designs and sequence of operation descriptions. Assist with performing functional performance tests.

E. TAB Subcontractor:

1. Contract Documents Review: With the CxA, review the Contract Documents before developing TAB procedures.

a. Verify the following:
i. Accessibility of equipment and components required for TAB Work.
ii. Adequate number and placement of duct balancing dampers to allow proper balancing while minimizing sound levels in occupied spaces.
iii. Adequate number and placement of balancing valves to allow proper balancing and recording of water flow.
iv. Adequate number and placement of test ports and test instrumentation to allow reading and compilation of system and equipment performance data needed to conduct both

TAB and commissioning testing.

v. Air and water flow rates have been specified and compared to central equipment output capacities.

b. Identify discontinuities and omissions in the Contract Documents.

c. This review of the Contract Documents by the TAB Subcontractor satisfies requirements for a design review report as specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."

d. Assist performing functional performance tests.

2. Additional Responsibilities: Participate in tests specified in Division 23 Sections "Instrumentation & Controls of HVAC & Plumbing Systems."

F. Electrical Contractor:

1. With the Mechanical Contractor, coordinate installations and connections between and among electrical and HVAC systems, subsystems, and equipment.
2. Attend TAB verification testing.

1.5 COMMISSIONING DOCUMENTATION

A. The following are in addition to documentation specified in Division 01 Section "General Commissioning Requirements."

B. Test Checklists: CxA with assistance of Contractor shall develop test checklists for HVAC systems, subsystems, and equipment, including interfaces and interlocks with other systems. CxA shall prepare separate checklists for each mode of operation and provide space to indicate whether the mode under test responded as required. In addition to the requirements specified in Division 01 Section "General Commissioning Requirements," checklists shall include, but not be limited to, the following:

1. Calibration of sensors and sensor function.
2. Testing conditions under which test was conducted, including (as applicable) ambient conditions, set points, override conditions, and status and operating conditions that impact the results of test.
3. Control sequences for HVAC systems.
4. Strength of control signal for each set point at specified conditions.
5. Responses to control signals at specified conditions.
6. Sequence of response(s) to control signals at specified conditions.
7. Electrical demand or power input at specified conditions.
8. Power quality and related measurements.
9. Expected performance of systems, subsystems, and equipment at each step of test.
10. Narrative description of observed performance of systems, subsystems, and equipment. Notation to indicate whether the observed performance at each step meets the expected results.
11. Interaction of auxiliary equipment.

12. Issues log.

1.6 SUBMITTALS

A. The following submittals are in addition to those specified in Division 01 Section "General Commissioning Requirements."

B. Testing Procedures: CxA shall submit detailed testing plan, procedures, and checklists for each series of tests. Submittals shall include samples of data reporting sheets that will be part of the reports.

C. Certificate of Readiness: CxA shall compile certificates of readiness from Contractor certifying that systems, subsystems, equipment, and associated controls are ready for testing.

D. Certificate of Completion of Installation, Prestart, and Startup: CxA shall certify that installation, prestart, and startup activities have been completed. Certification shall include completed checklists provided by TAB Subcontractor as specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."

E. Test and Inspection Reports: CxA shall compile and submit test and inspection reports and certificates, and shall include them in systems manual and commissioning report.

F. Corrective Action Documents: CxA shall submit corrective action documents.

G. Certified TAB Reports: CxA shall submit verified, certified TAB reports.

1.7 ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 TESTING PREPARATION

A. Prerequisites for Testing:

1. Certify that HVAC systems, subsystems, and equipment have been completed, calibrated, and started; are operating according to the Contract Documents; and that Certificates of Readiness are signed and submitted.
2. Certify that HVAC instrumentation and control systems have been completed and calibrated; are operating according to the Contract

Documents; and that pretest set points have been recorded.

3. Certify that TAB procedures have been completed, and that TAB reports have been submitted, discrepancies corrected, and corrective work approved.
4. Test systems and intersystem performance after approval of test checklists for systems, subsystems, and equipment.
5. Set systems, subsystems, and equipment into operating mode to be tested (e.g., normal shut down, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).
6. Verify each operating cycle after it has been running for a specified period and is operating in a steady-state condition.
7. Inspect and verify the position of each device and interlock identified on checklists. Sign off each item as acceptable, or failed. Repeat this test for each operating cycle that applies to system being tested.
8. Check safety cutouts, alarms, and interlocks with duct detectors and life-safety systems during each mode of operation.
9. Annotate checklist or data sheet when a deficiency is observed.
10. Verify equipment interface with monitoring and control system and TAB criteria; include the following:

    a. All temperature alarms.
    b. Ductless heat pumps with air flow rates and temperatures.
    c. Existing finned tube radiation operation and control.
    d. Hot water coils, airflow rates, pressure drops, temperatures, and fluid flow rate.
    e. Hydronic baseboard radiation temperature and flow rates.
    f. Minimum outdoor-air intake in each operational mode and at minimum and maximum airflows.
    g. Operation of heat pump units in both heating and cooling cycles and defrost cycles.
    h. Pump flow rates, pressure, VFD alarms, and amperage at each operating mode.
    i. Refrigeration mitigation controls, interlocks, and leak detection system operation.
    j. Sequences of operation of all HVAC equipment.
    k. Supply and return air flow rates for all HVAC equipment.
    l. Supply and return flow rates for VAV and constant volume systems in each operational mode.
    m. Test and calibrate all static pressure sensors.
    n. Total exhaust airflow and total outdoor-air intake.
    o. Variable speed drive parameters at each operated mode.
    p. VAV box minimum air flow rate, maximum air flow rate, heating coil temperatures, and fluid flow rates.

11. Verify proper responses of monitoring and control system controllers and sensors to include the following:

    a. For each controller or sensor, record the indicated monitoring and control system reading and the test instrument reading. If initial test indicates that the test reading is outside of the control range of the

installed device, check calibration of the installed device and adjust as required. Retest malfunctioning devices and record results on checklist or data sheet.

b. Report deficiencies and prepare an issues log entry.

12. Verify that HVAC equipment field quality-control testing has been completed and approved. CxA shall direct, witness, and document field quality-control tests, inspections, and startup specified in individual Division 23 Sections.

B. Testing Instrumentation: Install measuring instruments and logging devices to record test data for the required test period. Instrumentation shall monitor and record full range of operating conditions and shall allow for calculation of total capacity of system for each mode of operation. For individual room cooling tests, provide temporary heaters to impose a cooling load. Operational modes include the following:

1. Heating/cooling.
2. Occupied and unoccupied.
3. Warm up and cool down.
4. Economizer cycle/relief air fan/damper operation.
5. Fluid flow rates, pressure, and temperatures for all hydronic equipment.
6. Life-safety and safety systems.
7. Fire safety.
8. Temporary upset of system operation.
9. Partial occupancy conditions.
10. Special cycles.
11. All alarms.
12. Air flow rates.
13. Flow switch shut-down and alarm.
14. Condensate overflow safety switch shut-down and alarm.
15. Condensate pump operation.
16. Switched receptacles interlocks with BMS. (Plug loads.)
17. Test operation and accuracy of vav boxes.
18. Test refrigerant mitigation controls including fan interlocks and refrigerant leak detection sensors.

3.2 TAB VERIFICATION

A. TAB Subcontractor shall coordinate with CxA for work required in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing." TAB Subcontractor shall copy CxA with required reports, sample forms, checklists, and certificates.

B. Contractor, HVAC Contractor, and CxA shall witness TAB Work.

C. TAB Preparation:

1. TAB Subcontractor shall provide CxA with data required for "Pre-Field TAB

Engineering Reports" specified in Division 23 Section "Testing Adjusting & Balancing for HVAC & Plumbing."

a. CxA shall use this data to certify that prestart and startup activities have been completed for systems, subsystems, and equipment installation.

D. Verification of Final TAB Report:

1. CxA shall select, at random, 10 percent of report for field verification.
2. CxA shall notify TAB Subcontractor 10 days in advance of the date of field verification; however, notice shall not include data points to be verified. The TAB Subcontractor shall use the same instruments (by model and serial number) that were used when original data were collected.
3. Failure of an item is defined as follows:

a. For all readings a deviation of more than 10 percent.

4. Failure of more than 10 percent of selected items shall result in rejection of final TAB report.

E. If deficiencies are identified during verification testing, CxA shall notify the HVAC Contractor and Architect and shall take action to remedy the deficiency. Architect shall review final tabulated checklists and data sheets to determine if verification is complete and that system is operating according to the Contract Documents.

F. CxA shall certify that TAB Work has been successfully completed.

3.3 TESTING

A. Test systems and intersystem performance after test checklists for systems, subsystems, and equipment have been approved.

B. Contractors and subcontractors must pre-inspect and pre-test all equipment and systems prior to requesting functional performance testing by the CxA. All pre-start/start-up checklists and functional performance test forms must be completed and submitted to Engineer prior to scheduling formal functional performance testing.

C. Perform tests using design conditions whenever possible.

1. Simulate conditions by imposing an artificial load when it is not practical to test under design conditions and when written approval for simulated conditions is received from CxA. Before simulating conditions, calibrate testing instruments. Set and document simulated conditions and methods of simulation. After tests, return settings to normal operating conditions.
2. Alter set points when simulating conditions is not practical and when written approval is received from CxA.
3. Alter sensor values with a signal generator when design or simulating conditions and altering set points are not practical. Do not use sensor to

act as signal generator to simulate conditions or override values.

D. Scope of HVAC Contractor Testing:

1. Testing scope shall include entire HVAC installation, from central equipment for heat generation and refrigeration through distribution systems to each conditioned space. It shall include measuring capacities and effectiveness of operational and control functions.
2. Test all operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and verify proper response of building automation system controllers and sensors.

E. Detailed Testing Procedures: CxA, with HVAC Contractor, TAB Subcontractor, and HVAC Instrumentation and Control Contractor, shall prepare detailed testing plans, procedures, and checklists for HVAC systems, subsystems, and equipment.

F. HVAC Instrumentation and Control System Testing:

1. Field testing plans and testing requirements are specified in Division 23 Section "Instrumentation & Controls of HVAC & Plumbing Systems". The CxA, HVAC Contractor, Equipment Provider/Manufacturer and the HVAC Instrumentation and Control Contractor shall collaborate to prepare testing plans.
2. CxA shall convene a meeting of appropriate entities to review test report of HVAC instrumentation and control systems.

G. Heat-Generation System Testing: HVAC Contractor shall prepare a testing plan to verify performance of air handling units, heat pumps, radiant heat panels, VAV box hot water coils, and existing baseboard radiation. Plan shall include the following:

1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings for each pipe sector showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.
2. Tracking checklist for managing and ensuring that all pipe sections have been tested.

H. Refrigeration/Heat Rejection System Testing: HVAC Contractor shall prepare a testing plan to verify performance of ductless units, and other refrigeration systems. Plan shall include the following:

1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.

2. Tracking checklist for managing and ensuring that all pipe sections have been tested.

I. HVAC Distribution System Testing: HVAC Contractor shall prepare a testing plan to verify performance of air, air handling units, hydronic distribution systems, pumps, special exhaust, and other distribution systems. Include HVAC terminal equipment and unitary equipment. Plan shall include the following:

1. Sequence of testing and testing procedures for each item of equipment and section of pipe to be tested, identified by identification marker. Markers shall be keyed to Drawings showing the physical location of each item of equipment and pipe test section. Drawings shall be formatted to allow each item of equipment and section of piping to be physically located and identified when referred to in the system testing plan.
2. Tracking checklist for managing and ensuring that all pipe sections have been tested.
3. Equipment, air flow rates, air temperatures, fluid flow rates, and safeties.

J. Deferred Testing:

1. If tests cannot be completed because of a deficiency outside the scope of the HVAC system, the deficiency shall be documented and reported to Owner. Deficiencies shall be resolved and corrected by appropriate parties and test rescheduled.
2. If the testing plan indicates specific seasonal testing, appropriate initial performance tests shall be completed and documented and additional tests scheduled.

K. Testing Reports:

1. Reports shall include measured data, data sheets, and a comprehensive summary describing the operation of systems at the time of testing.
2. Include data sheets for each controller to verify proper operation of the control system, the system it serves, the service it provides, and its location. For each controller, provide space for recording its readout, the reading at the controller's sensor(s), plus comments. Provide space for testing personnel to sign off on each data sheet.
3. Prepare a preliminary test report. Deficiencies will be evaluated by Architect to determine corrective action. Deficiencies shall be corrected and test repeated.

END OF SECTION 019115

PAGE LEFT INTENTIONALLY BLANK

SECTION 02 41 19
SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. The Work of this Section Includes:

1. Demolition and removal of selected portions of exterior or interior of building or structure and site elements.
2. Removal and salvage of existing items for delivery to Owner and removal of existing items for reinstallation.

B. Related Requirements:

1. Section 011000 "Summary" for restrictions on use of the premises, Owner-occupancy requirements, and phasing requirements.

2. Section 017300 "Execution" for cutting and patching procedures.

3. Section 311000 "Site Clearing" for site clearing and removal of above- and below-grade improvements not part of selective demolition.

1.2 DEFINITIONS

A. Remove: Detach items from existing construction and legally dispose of off-site unless indicated to be removed and salvaged or removed and reinstalled.

B. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and deliver to Owner as indicated.

C. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage; prepare for reuse; and reinstall where indicated.

D. Existing to Remain: Existing items of construction that are not to be removed.

1.3 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition waste becomes property of Contractor.

B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.

1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

1.4 COORDINATION

A. Arrange selective demolition schedule so as not to interfere with Owner's operations.

1.5 PREINSTALLATION MEETINGS

A. Predemolition Conference: Conduct conference at Project site.

1. Inspect and discuss condition of construction to be selectively demolished.
2. Review structural load limitations of existing structure.
3. Review and finalize selective demolition schedule and verify availability of demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.
6. Review and finalize protection requirements.
7. Review procedures for noise control and dust control.
8. Review storage, protection, and accounting for items to be removed for salvage or reinstallation.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Statements: For refrigerant recovery technician.

B. Engineering Survey: Submit engineering survey of condition of building.

C. Survey of Existing Conditions: Submit survey.

D. Proposed Protection Measures: Submit report, including Drawings, that indicates the measures proposed for protecting individuals and property, for dust control and, for noise control. Indicate proposed locations and construction of barriers.

E. Schedule of Selective Demolition Activities: Indicate the following:

1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted.
2. Temporary interruption of utility services. Indicate how long utility services will be interrupted.
3. Coordination for shutoff, capping, and continuation of utility services.

4. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.

F. Warranties: Documentation indicating that existing warranties are still in effect after completion of selective demolition.

1.7 CLOSEOUT SUBMITTALS

A. Inventory: Submit a list of items that have been removed and salvaged.

1.8 FIELD CONDITIONS

A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.

B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

1. Before selective demolition, Owner will remove the following items:

a. Existing equipment to be relocated..
b. Existing cubicles.

C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.

D. Hazardous Materials:

1. It is not expected that hazardous materials will be encountered in the Work.

a. Hazardous materials will be removed by Owner before start of the Work.
b. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.

E. On-site sale of removed items or materials is not permitted.

1.9 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials and using approved contractors so as not to void existing warranties. Notify warrantor before proceeding. Existing warranties include the following:

1. Existing Roof System.

B. Notify warrantor on completion of selective demolition, and obtain documentation verifying that existing system has been inspected and warranty remains in effect.

Submit documentation at Project closeout.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ANSI/ASSP A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped before starting selective demolition operations.

B. Review Project Record Documents of existing construction or other existing condition and hazardous material information provided by Owner. Owner does not guarantee that existing conditions are same as those indicated in Project Record Documents.

C. Verify that hazardous materials have been remediated before proceeding with building demolition operations.

D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs or video, measured drawings. Comply with Section 013233 "Photographic Documentation."

1. Inventory and record the condition of items to be removed for salvage or reinstallation. Photograph or video conditions that might be misconstrued as damage caused by removal.
2. Photograph or video existing conditions of adjoining construction including finish surfaces, that might be misconstrued as damage caused by selective demolition operations or removal of items for salvage or reinstallation.

3.2 PREPARATION

A. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

1. Strengthen or add new supports when required during progress of selective

demolition.

B. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.

1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
4. Cover and protect furniture, furnishings, and equipment that have not been removed.
5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Section 015000 "Temporary Facilities and Controls."

C. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location and cleaned and reinstalled in their original locations after selective demolition operations are complete.

3.3 UTILITY SERVICES AND BUILDING SYSTEMS

A. Existing Services/Systems to Remain: Maintain utilities and building systems and equipment to remain and protect against damage during selective demolition operations.

1. Maintain fire-protection facilities in service during selective demolition operations.

B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utilities and building systems serving areas to be selectively demolished.

1. Owner will arrange to shut off indicated utilities when requested by Contractor.
2. Arrange to shut off utilities with utility companies.
3. If disconnection of utilities and building systems will affect adjacent occupied parts of the building, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to those parts of the building.
4. Demolish and remove existing building systems, equipment, and components indicated on Drawings to be removed.

a. Piping to Be Removed: Remove portion of piping indicated to be

removed and cap or plug remaining piping with same or compatible piping material.

b. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.

c. Equipment to Be Removed: Disconnect and cap services and remove equipment and components.

5. Abandon existing building systems, equipment, and components indicated on Drawings to be abandoned in place.

a. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material and leave in place.

b. Ducts to Be Abandoned in Place: Cap or plug ducts with same or compatible ductwork material and leave in place.

6. Remove and reinstall/salvage existing building systems, equipment, and components indicated on drawings to be removed and reinstalled or removed and salvaged:

a. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment and components; when appropriate, reinstall, reconnect, and make equipment operational.

b. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and components and deliver to Owner.

3.4 SALVAGE/REINSTALL

A. Removed and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse.
2. Pack or crate items after cleaning and repairing. Identify contents of containers.
3. Protect items from damage during transport and storage.
4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

3.5 SELECTIVE DEMOLITION, GENERAL

A. General: Demolish and remove existing construction only to extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

1. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain

or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.

2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
3. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
4. Maintain adequate ventilation when using cutting torches.
5. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
6. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.

B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

1. Do not close or obstruct streets, walks, walkways, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed trafficways if required by authorities having jurisdiction.
2. Use water mist and other suitable methods to limit spread of dust and dirt. Comply with governing environmental-protection regulations. Do not use water when it may damage adjacent construction or create hazardous or objectionable conditions, such as ice, flooding, and pollution.

3.6 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Masonry: Demolish in small sections. Cut masonry at junctures with construction to remain, using power-driven saw, and then remove masonry between saw cuts.

B. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, and then break up and remove.

C. Resilient Floor Coverings: Remove floor coverings and adhesive in accordance with recommendations in RFCI's "Recommended Work Practices for the Removal of Resilient Floor Coverings."

D. Roofing: Remove no more existing roofing than what can be covered in one day by new roofing and so that building interior remains watertight and weathertight.

1. Remove existing roof membrane, flashings, copings, and roof accessories at noted locations.
2. Remove existing roofing system down to substrate.

3.7 DISPOSAL OF DEMOLISHED MATERIALS

A. Remove demolition waste materials from Project site and recycle or dispose of them in accordance with Section 017419 "Construction Waste Management and Disposal."

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
4. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."

B. Burning: Do not burn demolished materials.

3.8 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 02 41 19

SECTION 03 35 43
POLISHED CONCRETE FINISHING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Grinding and honing of the slab surface to receive clear reactive, penetrating liquid hardener/densifier to interior concrete.
2. Application of clear reactive, penetrating liquid hardener.
3. Progressively polishing and burnishing of the slab surface to achieve Finish Requirements.
4. Application of stain resistant surface treatment.

1.2 REFERENCES

A. The date of the standard is that in effect as the date of receipt of bids for the project.

B. Scientific Certification System (SCS) Indoor Air Quality Gold Certification.

C. American National Standard Institute / National Floor Safety Institute:

1. ANSI/NSFI B101.1-Test Method for Measuring Wet SCOF of Common Hard-Surface Floor Materials.
2. ANSI B101.3-Test Method for Measuring Wet DCOF of Common Hard-Surface Floor Materials.

D. ASTM International (ASTM):

1. C1028 - Standard Test Method for Determining the Static Coefficient of Friction of Ceramic Tile and Other Like Surfaces by the Horizontal Dynamometer Pull-Meter Method.
2. C1353 – Standard Test Method for Abrasion Resistance of Dimension Stone Subjected to Foot Traffic Using a Rotary Platform, Double-Head Abraser.
3. D4541 - Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers.
4. E96/96M Method B (Water Method) - Standard Test Methods for Water Vapor Transmission of Materials.
5. G154 -Standard Practice for Operating Fluorescent Ultraviolet (UV) Lamp Apparatus for Exposure of Nonmetallic Materials.

1.3 SUBMITTALS

A. Product Data: For each type of product.

1. Submit manufacturer's product data sheets and tested physical and performance properties on products to be used for the work.

B. VOC Certification: Submit certification that products furnished comply with regulations controlling use of volatile organic compounds (VOC).

C. Certificates:

1. Certificates by manufacturer stating that installer is listed applicator of special concrete finishes, and has completed the necessary training programs.

D. Floor Protection Plan.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in original containers, with seals unbroken, bearing manufacturer labels indicating brand name and directions for storage.

B. Store concrete hardener/densifier in environment recommended on published manufacturer's product data sheets.

1. Store containers upright in a cool, dry, well-ventilated place, out of the sun with temperature between 40 and 100 degrees F (4 and 38 degrees C).
2. Protect from freezing.
3. Store away from other chemicals and potential sources of contamination.
4. Keep lights, fire, sparks and heat away from containers.
5. Do not drop containers or slide across sharp objects.
6. Do not stack pallets more than three high.
7. Keep containers tightly closed when not in use.

1.5 FIELD CONDITIONS

A. Environmental limitations:

1. Comply with manufacturer's written instructions for substrate temperature and moisture content, ambient temperature and humidity, ventilation, and other conditions affecting performance and finishing requirements.

B. Close areas to traffic during floor application and after application for time period recommended in writing by manufacturer.

C. Protect the completed slab to prevent damage by the other trades during floor completion.

D. Temperature Limitations:

1. Apply when surface and air temperature are between 40 degrees F (4 degrees C) and above 95 degrees F (35 degrees C) unless otherwise indicated by manufacturer's written instructions.
2. Apply when surface and air temperatures are expected to remain above 40 degrees F (4 degrees C) for a minimum of 8 hours after application, unless otherwise indicated by manufacturer's written instructions.

E. Apply when air conditions are calm to minimize surface treatment contacting surface not intended to be finished.

F. Do not apply to frozen substrate. Allow adequate time for substrate to thaw, if freezing conditions exist before application.

G. Apply a minimum of 24 hours after rain event. Suspend application when rain is anticipated for a period of 8 hours after application, unless otherwise indicated by manufacturer's written instructions.

H. Temporary Lighting: Minimum 200 W light source, placed 8 feet (2.5 meters) above horizontal concrete surface for each 425 square feet (40 square meters) of concrete being finished.

I. Temporary Heat: Ambient temperature of 50 degrees F (10 degrees C) minimum.

J. Ventilation: Provide ventilation during coating evaporation stage in confined or enclosed areas in accordance with manufacturer's instructions.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide products from PROSOCO, Inc. or comparable product by one of the following:

1. Scofield, a Business Unit of Sika Corporation
2. H&C Decorative Concrete Products; a brand of Sherwin-Williams Co.
3. Euclid

2.2 MATERIALS

A. Liquid Concrete Repair Material: Low-odor, liquid fill material used to fill pinholes, small air voids and pop-outs, micro-cracks, and other gaps in concrete surface during grinding.

B. Pre-Densifier Concrete Cleaner: Cleaner to remove dirt, oil, grease, and other stains from existing slab surface.

C. Penetrating Concrete Hardener/Densifier: Lithium silicate hardener/densifier.

1. Product: Consolideck LS, manufactured by PROSOCO, Inc., Lawrence, KS, (800) 255-4255, www.prosoco.com.
2. Subject to compliance with the following requirements:

a. Comply with national, state and district AIM VOC regulations and contain 50 g/L or less.
b. Registered as an approved NSF International/Nonfood Compound Registration.
c. Abrasion Resistance: Greater than 50 percent improvement over untreated samples when tested in accordance with ASTM C1353.
d. Achieve 'High Traction Range' readings when tested in accordance with ANSI B101.1 and ANSI B101.3.
e. Coefficient of Friction: Greater than 0.60 dry, Greater than 0.60 wet when tested in accordance with ASTM C1028.
f. Adhesion: Greater than10 percent increase in pull-off strength when compared to an untreated sample when tested in accordance with ASTM D4541.
g. Water Vapor Transmission: 100 percent retained when compared to untreated samples when tested in accordance with ASTM E96/96M Method B (Water Method).
h. UV Stability: No degradation or yellowing of material when tested in accordance with ASTM G154.

D. Interior Concrete Protective Treatments:

1. Solvent-based, penetrating clear sealer with a VOC content of 100 g/L or less shall resist oil and food stains and repel water and water-related stains.

a. Product: Consolideck Concrete Protector SB, manufactured by PROSOCO, Inc., Lawrence, KS, (800) 255-4255, www.prosoco.com.
b. Subject to compliance with the following requirements:

1) Comply with national, state and district AIM VOC regulations.
2) Achieve 'High Traction Range' readings when tested in accordance with ANSI B101.1 and ANSI B101.3.
3) Stain Resistance: Achieve limited or no adverse effects when tested in accordance with ASTM D 1308.
4) UV Stability: No degradation or yellowing of material when tested in accordance with ASTM G154.

2.3 EQUIPMENT

A. Conform to ACI 310.1 Part 2.2, except where more stringent requirements are specified below.

B. Auto Scrubber Machine: For cleaning operations.

C. Hand Grinder or stand-up edger for edge grinding/polishing.

D. Grinding/Polishing Equipment:

1. Dry grinding/polishing machines shall include a dust extraction system, including HEPA filtration vacuum.

E. Diamond Segments:

1. Use heads from the same manufacturers throughout the entirety of the project.

F. Diamond Heads Types:

1. Metal Diamonds: 80 or 150.
2. Hybrid Style Diamonds: 50 or 100.
3. Resin Bonded, Phenolic Diamonds: 100, 200, 400, 800, 1500, and 3000 (if necessary).

G. Burnishing Machine and Burnishing Pads to produce specified results.

1. Burnishing Machine: High speed burnisher, generating pad speeds of 1,500 RPM or higher, as recommended by protective treatment manufacturer. Dust skirt must be installed at time of work.
2. Burnishing Pads: as recommended by protective treatment manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrate with installer present for conditions affecting performance of finish. Correct conditions detrimental to timely and proper work.

B. Do not begin installation until all unsatisfactory conditions are resolved. Beginning work constitutes acceptance of site conditions and responsibility for defective installation caused by prior observable conditions.

3.2 PREPARATION

A. Clean dirt, dust, oil, grease and other contaminants that interfere with penetration or performance of specified product from surfaces. Use appropriate concrete cleaners approved by the concrete surface treatment manufacturer where necessary. Rinse thoroughly using pressure water spray to remove cleaner residues. Allow surfaces to dry completely before application of product.

B. Repair, patch and fill cracks, voids, defects and damaged areas in surface as approved by the Architect. Allow repair materials to cure completely before application of product.

C. Variations in substrate texture and color will affect final appearance and should be corrected prior to application of sealer/hardener system and the polishing steps.

D. Protect surrounding areas prior to application. If product is accidentally misapplied to adjacent surfaces, flush with water immediately before material dries.

E. Avoid contact in areas not to be treated. Avoid contact with metal, glass and painted surfaces.

F. Seal open joints in accordance with Section 07 90 00.

G. Apply specified sealants and caulking and allow complete curing before application of penetrating concrete hardener/densifier.

H. Do not proceed until unsatisfactory conditions have been corrected.

3.3 CONCRETE GRINDING, HONING, AND POLISHING

A. Adhere to industry standard and conform to ACI 310.1 for grinding, honing, and polishing procedures for dry and wet grinding and honing, except where more stringent requirements are specified below.

B. Scrub and rinse slab surface with clean water and vacuum with auto-scrubber between and after final passes.

C. Sequential progression of diamond tooling steps shall be required and limited to no more than double the grit value of the previous diamonds used.

D. Overlap adjacent passes by 25 percent.

E. Perform each pass perpendicular to the other pass north/south then east/west; multiple passes may be needed.

F. Progressively grind, hone and polish the slab surface utilizing approved diamond segments as necessary to produce Finishing requirements.

G. Apply liquid concrete repair material to fill gaps, voids and pop-outs during grinding operation per manufacturer’s published recommendations.

H. Apply cutting aid chemical during the initial wet grinding process per manufacturer’s published recommendations. (Typically before the 200 grit resin or lower).

3.4 APPLICATION OF PENETRATING CONCRETE HARDENER/DENSIFIER

A. Apply hardener/densifier at the rate of 500 to 700 square feet per gallon with a low pressure sprayer fitted with a 0.5 gpm spray tip. (Typically after 200-grit and

no later than 400 grit).

B. Apply sufficient material to keep concrete surface wet for 5 to 10 minute period, without producing puddles.

C. Allow treated surface to dry.

D. Continue progressively polishing floor with required resin diamonds as necessary to produce desired final finish.

3.5 APPLICATION OF INTERIOR CONCRETE PROTECTIVE TREATMENT

A. Application of (low gloss with burnishing) solvent-based, penetrating oil, water and food stain protective treatment with a VOC content of 100 g/L or less:

B. Apply per manufacturer's published recommendations to clean, dry slab at the completion of mechanically polishing the slab surface.

C. Lightly wet a clean microfiber pad with protective treatment, leaving the pad damp.

D. Using a clean, pump-up sprayer, and working from one control joint to another, apply a light, fine spray to a small section of the floor. Apply per manufacturer's published recommended application rate.

E. Using the damp microfiber pad and firm downward pressure, immediately spread protective treatment to produce a thin, even application. Spread the product as far as possible while maintaining a wet edge.

F. Allow to dry tack free, typically 60–90 minutes.

G. Two coats are recommended for maximum protection. Repeat steps 1 through 4.

H. To remove any subsequent haze or for a high-gloss finish, wait until the final coat is dry, a minimum of 4 hours, then use a high- speed burnisher fitted with a heat polishing pad or 1500–3000 grit diamond polishing pad.

3.6 SLAB PROTECTION

A. Comply with provisions of ACI 310.1 specification for slab protection, except where more stringent requirements are specified below.

B. Protect finished floors to prevent damage including staining, gouges and scratching by construction traffic and activities until possession.

C. Do not drag or drop equipment or material across the slab which will scratch or chip it.

D. Inspect tires for debris prior to use on slab. Remove embedded items which may cause damage to floor slab.

E. Clean up spills on slab immediately. Provide cleaning chemicals and absorptive materials.

F. Develop a concrete protection procedure which addresses the following procedures:

1. Communication of protection plan to subcontractors and vendors.
2. Procedures for cleaning up slab spills, including use of and availability of cleaning chemicals and absorptive materials at Site.

G. Provide a clean slab surface using concrete maintenance cleaner within an auto scrubber, equipped with soft nylon brushes, in accordance with manufacturer's published recommendations.

3.7 FINISHING REQUIREMENTS

A. Appearance:

1. Interior exposed finished slab areas must consist of the following:

a. Slab surface must meet the desired sheen, as discussed in Pre-Installation meeting and be consistent with approved Mock-up.
b. Slab surface must have a consistent look and exhibit a finish that has no evidence of streaking or burnish marks.
c. White residue or hazy appearance is not acceptable.
d. Exposure of aggregate ACI 310.1 Table 3.2.3.1, Aggregate Exposure Class A-Cream.

2. Interior exposed finished slab areas must consist of the following CPAA Gloss Level:

a. Interior exposed finished slab areas must meet the ACI 310.1 Table 3.2.4.1- Appearance levels for distinctness of image (DOI) Level 2.

END OF SECTION 03 35 43

SECTION 04 01 20.63
BRICK MASONRY REPAIR

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Masonry materials.
2. Mortar materials.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for joint sealants, joint fillers, and sealant-joint preparation for repaired masonry.

1.2 DEFINITIONS

A. Existing to Remain: Existing items of construction that are not to be removed.

B. Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.

C. Remove: Detach items from existing construction and legally dispose of off-site unless indicated to be removed and salvaged or removed and reinstalled.

D. Remove and Salvage: Detach items from existing construction, in a manner to prevent damage, and deliver to Owner or storage as indicated.

E. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage; prepare for reuse; and reinstall where indicated.

F. Rebuilding (Setting) Mortar: Mortar used to set and anchor masonry in a structure, distinct from pointing mortar installed after masonry is set in place.

G. Saturation Coefficient: Ratio of the weight of water absorbed during immersion in cold water to weight absorbed during immersion in boiling water; used as an indication of resistance of bricks to freezing and thawing.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to brick masonry repair including, but not limited to, the following:

a. Verify brick masonry repair specialist's personnel, equipment, and

facilities needed to make progress and avoid delays.
b. Materials, material application, sequencing, tolerances, and required clearances.
c. Cleaning types and cleaning methods.
d. Quality-control program.
e. Review cleaning program.
f. Coordination with building occupants.
g. Protection and barriers for the public.

1.4 SEQUENCING AND SCHEDULING

A. Order sand and gray portland cement for colored mortar immediately after approval of Samples. Take delivery of and store at Project site enough quantity to complete Project.

B. Work Sequence: Perform brick masonry repair work in the following sequence, which includes work specified in this and other Sections:

1. Inspect masonry for open mortar joints and point them before cleaning to prevent the intrusion of water and other cleaning materials into the wall.
2. Clean masonry.
3. Rake out mortar from joints surrounding masonry to be replaced and from joints adjacent to masonry repairs along joints.
4. Repair masonry, including replacing existing masonry with new masonry materials.
5. Rake out mortar from joints to be repointed.
6. Point mortar and sealant joints.
7. After repairs and repointing have been completed and cured, perform a final cleaning to remove residues from this work.

C. As scaffolding is removed, patch anchor holes used to attach scaffolding. Patch holes in bricks in accordance with "Brick Masonry Patching" Article. Patch holes in mortar joints according to Section 040120.64 "Brick Masonry Repointing."

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include recommendations for product application and use.
3. Include test data substantiating that products comply with requirements.

B. Shop Drawings:

1. Include plans, elevations, sections, and locations of replacement bricks on the structure, showing relation of existing and new or relocated units.
2. Show provisions for expansion joints or other sealant joints.

3. Show provisions for flashing, lighting fixtures, conduits, and weep holes as required.
4. Show locations of scaffolding and points of scaffolding in contact with masonry. Include details of each point of contact or anchorage.

C. Samples for Initial Selection: For the following:

1. Colored Mortar: Submit sets of mortar that will be left exposed in the form of sample mortar strips, 6 inches long by 1/2 inch wide, set in aluminum or plastic channels.

    a. Have each set contain a close color range of at least Samples of different mixes of colored sands and cements that produce a mortar matching existing, cleaned mortar when cured and dry.
    b. Submit with precise measurements on ingredients, proportions, gradations, and source of colored sands from which each Sample was made.

2. Sand Types Used for Mortar: Minimum 8 oz. of each in plastic screw-top jars.
3. Patching Compound: Submit sets of patching compound Samples in the form of plugs (patches in drilled holes) in sample units of masonry representative of the range of masonry colors on the building.

    a. Have each set contain a close color range of at least three Samples of different mixes of patching compound that matches the variations in existing masonry when cured and dry.

4. Include similar Samples of accessories involving color selection.

D. Samples for Verification: For the following:

1. Each type of brick unit to be used for replacing existing units. Include sets of Samples to show the full range of shape, color, and texture to be expected. For each brick type, provide straps or panels containing at least four bricks. Include multiple straps for brick with a wide range.
2. Each type of patching compound in the form of briquettes, at least 3 inches long by 1-1/2 inches wide. Document each Sample with manufacturer and stock number or other information necessary to order additional material.
3. Accessories: Each type of accessory and miscellaneous support.

1.6 QUALITY ASSURANCE

A. Brick-Cleaning Specialist Firms: A firm that provides masonry cleaning, including masonry cleaners that have been used for similar applications with successful results, and is manufacturer authorized for consultation and Project-site inspection, preconstruction product testing, and on-site assistance.

B. Quality-Control Program: Prepare a written quality-control program for this Project to systematically demonstrate the ability of personnel to properly follow

methods and use materials and tools without damaging masonry. Include provisions for supervising performance and preventing damage.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver bricks to Project site strapped together in suitable packs or pallets or in heavy-duty cartons and protected against impact and chipping.

B. Deliver packaged materials to Project site in manufacturer's original and unopened containers, labeled with manufacturer's name and type of products.

C. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

D. Store hydrated lime in manufacturer's original and unopened containers. Discard lime if containers have been damaged or have been opened for more than two days.

E. Store sand where grading and other required characteristics can be maintained and contamination avoided.

F. Handle bricks to prevent overstressing, chipping, defacement, and other damage.

1.8 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit brick masonry repair work to be performed in accordance with product manufacturers' written instructions and specified requirements.

B. Temperature Limits: Repair brick masonry only when air temperature is between 40 and 90 deg F and is predicted to remain so for at least seven days after completion of the Work unless otherwise indicated.

C. Cold-Weather Requirements: Comply with the following procedures for masonry repair unless otherwise indicated:

1. When air temperature is below 40 deg F, heat mortar ingredients, masonry repair materials, and existing masonry walls to produce temperatures between 40 and 120 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for seven days after repair.

D. Hot-Weather Requirements: Protect masonry repairs when temperature and humidity conditions produce excessive evaporation of water from mortar and repair materials. Provide artificial shade and wind breaks, and use cooled materials as required to minimize evaporation. Do not apply mortar to substrates

with temperatures of 90 deg F and above unless otherwise indicated.

E. For manufactured repair materials, perform work within the environmental limits set by each manufacturer.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 MASONRY MATERIALS

A. Masonry Materials: Face brick, required to complete brick masonry repair work.

1. Brick Matching Existing: Units with colors, color variation within units, surface texture, size, and shape that match existing brickwork and with physical properties within 10 percent of those determined from preconstruction testing of selected existing units.

a. For existing brickwork that exhibits a range of colors or color variation within units, provide brick that proportionally matches that range and variation rather than brick that matches an individual color within that range.

2. Tolerances as Fabricated: In accordance with tolerance requirements in ASTM C216, Type FBX.

B. Building Brick: ASTM C62, of same vertical dimension as face brick, for masonry work concealed from view.

2.3 MORTAR MATERIALS

A. Portland Cement: ASTM C150/C150M, Type I or Type II, except Type III may be used for cold-weather construction; white or gray, or both where required for color matching of mortar.

1. Provide cement containing not more than 0.60 percent total alkali when tested in accordance with ASTM C114.

B. Hydrated Lime: ASTM C207, Type S.

C. Mortar Sand: ASTM C144.

1. Exposed Mortar: Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands if necessary to achieve suitable match.
2. Colored Mortar: Natural sand or ground marble, granite, or other sound stone of color necessary to produce required mortar color.

D. Water: Potable.

2.4 ACCESSORY MATERIALS

A. Setting Buttons and Shims: Resilient plastic, nonstaining to masonry, sized to suit joint thicknesses and bed depths of bricks, less the required depth of pointing materials unless removed before pointing.

B. Masking Tape: Nonstaining, nonabsorbent material; compatible with mortar, joint primers, sealants, and surfaces adjacent to joints; and that easily comes off entirely, including adhesive.

C. Antirust Coating: Fast-curing, lead- and chromate-free, self-curing, universal modified-alkyd primer in accordance with MPI #23 (surface-tolerant, anticorrosive metal primer) or SSPC-Paint 20 or SSPC-Paint 29 zinc-rich coating.

1. Surface Preparation: Use coating requiring no better than SSPC-SP 2, "Hand Tool Cleaning" surface preparation in accordance with manufacturer's literature or certified statement.
2. VOC Limit: Use coating with a VOC content of 400 g/L or less.

D. Other Products: Select materials and methods of use based on the following, subject to approval of a mockup:

1. Previous effectiveness in performing the work involved.
2. Minimal possibility of damaging exposed surfaces.
3. Consistency of each application.
4. Uniformity of the resulting overall appearance.
5. Do not use products or tools that could leave residue on surfaces.

2.5 MORTAR MIXES

A. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

B. Colored Mortar: Produce mortar of color required by using specified ingredients. Do not alter specified proportions without Architect's approval.

C. Do not use admixtures in mortar unless otherwise indicated.

D. Mixes: Mix mortar materials in the following proportions:

1. Rebuilding (Setting) Mortar by Type: ASTM C270, Proportion Specification, Type N unless otherwise indicated; with cementitious material limited to portland cement and lime masonry cement or mortar cement.

2. Pigmented, Colored Mortar: Add mortar pigments to produce exposed, setting (rebuilding) mortar of colors required.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrate conditions with specialist present, for compliance with approved mockup requirements for brick units, repair methods, products, and other conditions affecting performance of the Work.

3.2 PREPARATION

A. General: Comply with each manufacturer's written instructions for protecting people, motor vehicles, surrounding buildings, masonry areas not to be cleaned, nonmasonry surfaces, landscaping, equipment, and other surfaces that could be injured or harmed by such Work.

1. Provide temporary protective covers over pedestrian walkway areas and at points of entrance and exit for people, motor vehicles, and equipment that must remain during duration of repairing procedures.
2. Cover adjacent surfaces with materials that are proven to resist paint removers and chemical cleaners used unless products being used will not damage adjacent surfaces. Use protective materials that are waterproof and UV resistant.
3. Temporarily protect all open joints to prevent intrusion of washing waters into the wall structure or building interior.
4. Remove all extraneous items no longer in use on face of surface unless indicated to remain. Where not indicated, obtain approval with Architect.

3.3 PROTECTION

A. Prevent mortar from staining face of surrounding masonry and other surfaces.

1. Cover sills, ledges, and other projecting items to protect them from mortar droppings.
2. Keep wall area wet below rebuilding and repair work to discourage mortar from adhering.
3. Immediately remove mortar splatters in contact with exposed masonry and other surfaces.

3.4 MASONRY REPAIR, GENERAL

A. Appearance Standard: Repaired surfaces are to have a uniform appearance as viewed from 20 ft. away by Architect.

3.5 ABANDONED ANCHOR REMOVAL

A. Remove abandoned anchors, brackets, wood nailers, and other extraneous items no longer in use unless indicated to remain.

1. Remove items carefully to avoid spalling or cracking masonry.
2. Notify Architect before proceeding if an item cannot be removed without damaging surrounding masonry. Do the following where directed:

3. Patch hole where each item was removed unless directed to remove and replace bricks.

3.6 BRICK REMOVAL AND REPLACEMENT

A. At locations indicated, remove bricks that are damaged, spalled, or deteriorated. Carefully remove entire units from joint to joint, without damaging surrounding masonry, in a manner that permits replacement with full-size units.

1. When removing single bricks, remove material from center of brick and work toward outside edges.

B. Support and protect remaining masonry that surrounds removal area.

C. Maintain flashing, reinforcement, lintels, and adjoining construction in an undamaged condition. Coordinate with new flashing, reinforcement, and lintels, which are specified in other Sections.

D. Notify Architect of unforeseen detrimental conditions, including voids, cracks, bulges, and loose units in existing masonry backup, rotted wood, rusted metal, and other deteriorated items.

E. Remove in an undamaged condition as many whole bricks as possible.

1. Remove mortar, loose particles, and soil from brick by cleaning with hand chisels, brushes, and water.
2. Remove sealants by cutting close to brick with utility knife and cleaning with solvents.
3. Store brick for reuse. Store off ground, on skids, and protected from weather.
4. Deliver cleaned brick not required for reuse to Owner unless otherwise indicated.

F. Clean masonry surrounding removal areas by removing mortar, dust, and loose particles in preparation for brick replacement.

G. Replace removed damaged brick with other removed brick in good condition, where possible, or with new brick matching existing brick. Do not use broken units unless they can be cut to usable size.

H. Install replacement brick into bonding and coursing pattern of existing brick. If cutting is required, use a motor-driven saw designed to cut masonry with clean, sharp, unchipped edges.

1. Maintain joint width for replacement units to match existing joints.
2. Use setting buttons or shims to set units accurately spaced with uniform joints.

I. Lay replacement brick with rebuilding (setting) mortar and with completely filled bed, head, and collar joints. Butter ends with enough mortar to fill head joints and shove into place. Wet both replacement and surrounding bricks that have ASTM C67/C67M initial rates of absorption (suction) of more than 30 g/30 sq. in. per min. Use wetting methods that ensure that units are nearly saturated but surface is dry when laid.

1. Tool exposed mortar joints in repaired areas to match joints of surrounding existing brickwork.
2. Rake out mortar used for laying brick before mortar sets in accordance with Section 040120.64 "Brick Masonry Repointing." Point at same time as repointing of surrounding area.
3. When mortar is hard enough to support units, remove shims and other devices interfering with pointing of joints.

J. Curing: Cure mortar by maintaining in thoroughly damp condition for at least 72 consecutive hours, including weekends and holidays.

1. Hairline cracking within the mortar or mortar separation at edge of a joint is unacceptable. Completely remove such mortar and repoint.

3.7 PAINTING STEEL UNCOVERED DURING THE WORK

A. Notify Architect if steel is exposed during masonry removal. Where Architect determines that steel is structural, or for other reasons cannot be totally removed, prepare and paint it as follows:

1. Surface Preparation: Remove paint, rust, and other contaminants in accordance with SSPC-SP 2, "Hand Tool Cleaning", as applicable to comply with paint manufacturer's recommended preparation.
2. Antirust Coating: Immediately paint exposed steel with two coats of antirust coating, following coating manufacturer's written instructions and without exceeding manufacturer's recommended rate of application (dry film thickness per coat).

B. If on inspection and rust removal, the thickness of a steel member is found to be reduced from rust by more than 1/16 inch notify Architect before proceeding.

3.8 BRICK MASONRY PATCHING

A. Patch the following bricks unless another type of repair or replacement is indicated:

1. Bricks indicated to be patched.
2. Bricks with holes.
3. Bricks with chipped edges or corners. Patch chipped edges or corners measuring more than 3/4 inch in least dimension.
4. Bricks with small areas of deep deterioration. Patch deep deteriorations measuring more than 3/4 inch in least dimension and more than 1/4 inch deep.

B. Patching Bricks:

1. Remove loose material from masonry surface. Carefully remove additional material so patch does not have feathered edges but has square or slightly undercut edges on area to be patched and is at least 1/4 inch dimension> thick, but not less than recommended in writing by patching compound manufacturer.
2. Mask adjacent mortar joint or rake out for repointing if patch extends to edge of brick.
3. Mix patching compound in individual batches to match each unit being patched. Combine one or more colors of patching compound, as needed, to produce exact match.
4. Rinse surface to be patched and leave damp, but without standing water.
5. Brush-coat surfaces with slurry coat of patching compound in accordance with manufacturer's written instructions.
6. Place patching compound in layers as recommended in writing by patching compound manufacturer, but not less than 1/4 inch or more than 2 inches thick. Roughen surface of each layer to provide a key for next layer.
7. Trowel, scrape, or carve surface of patch to match texture and surrounding surface plane or contour of brick. Shape and finish surface before or after curing, as determined by testing, to best match existing brick.
8. Keep each layer damp for 72 hours or until patching compound has set.
9. Remove and replace patches with hairline cracks or that show separation from brick at edges, and those that do not match adjoining brick in color or texture.

3.9 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water applied by low-pressure spray.

1. Do not use metal scrapers or brushes.
2. Do not use acidic or alkaline cleaners.

B. Clean adjacent nonmasonry surfaces. Use detergent and soft brushes or cloths.

C. Clean mortar and debris from roof; remove debris from gutters and downspouts. Rinse off roof and flush gutters and downspouts.

D. Remove masking materials, leaving no residues that could trap dirt.

3.10 MASONRY WASTE DISPOSAL

A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property.

B. Masonry Waste: Remove masonry waste and legally dispose of off Owner's property.

END OF SECTION 04 01 20.63

SECTION 06 10 00
ROUGH CARPENTRY

PART 1 - GENERAL

1.1 DEFINITIONS

A. Boards or Strips: Lumber of less than **2 inches nominal** size in least dimension.

B. Dimension Lumber: Lumber of **2 inches nominal** size or greater but less than **5 inches nominal** size in least dimension.

C. Lumber grading agencies, and abbreviations used to reference them, include the following:

1. NeLMA: Northeastern Lumber Manufacturers' Association.
2. NLGA: National Lumber Grades Authority.
3. RIS: Redwood Inspection Service.
4. SPIB: The Southern Pine Inspection Bureau.
5. WCLIB: West Coast Lumber Inspection Bureau.
6. WWPA: Western Wood Products Association.

1.2 DELIVERY, STORAGE, AND HANDLING

A. Stack wood products flat with spacers beneath and between each bundle to provide air circulation. Protect wood products from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD LUMBER, GENERAL

A. Lumber: Comply with DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, comply with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Grade lumber by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.

1. Factory mark each piece of lumber with grade stamp of grading agency.

2. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry wood products.
3. Dress lumber, S4S, unless otherwise indicated.

B. Maximum Moisture Content:

1. Boards: 19 percent.
2. Dimension Lumber: 15 percent for 2-inch nominal thickness or less; 19 percent for more than 2-inch nominal thickness unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

A. Wood-Preservative-Treated Lumber by Pressure Process: AWPA U1, use categories as follows:

1. UC1, Interior/Dry: Interior construction continuously protected from weather or other sources of moisture. Include the following items:

a. Wood sills, sleepers, blocking, furring, and similar concealed members in contact with masonry or concrete.

b. Wood floor plates that are installed over concrete slabs-on-grade.

2. UC3A, Above Ground, Protected (Commodity Specification A): Coated wood products in exterior construction not in contact with ground but exposed to all weather cycles including intermittent wetting. Include the following items:

a. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.

3. After treatment, redry dimension lumber to 19 percent maximum moisture content.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or that does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

2.3 FIRE-RETARDANT-TREATED LUMBER

A. General: Where fire-retardant-treated materials are indicated, materials are to comply with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame-spread index of 25 or less when tested in accordance with ASTM E84, and with no evidence of significant progressive combustion when the test is

extended an additional 20 minutes, and with the flame front not extending more than **10.5 ft.** beyond the centerline of the burners at any time during the test.

1. Treatment is not to promote corrosion of metal fasteners.

2. Interior Type A: Treated materials are to have a moisture content of 28 percent or less when tested in accordance with ASTM D3201/D3201M at 92 percent relative humidity. Use where exterior type is not indicated.

C. Kiln-dry lumber after treatment to maximum moisture content of 19 percent. Kiln-dry plywood after treatment to maximum moisture content of 15 percent.

D. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency and other information required by authorities having jurisdiction.

E. Application: Treat items indicated on Drawings, and the following:

1. Concealed blocking.

2. Plywood backing panels.

2.4 MISCELLANEOUS LUMBER

A. Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:

1. Blocking.
2. Nailers.
3. Rooftop equipment bases and support curbs.
4. Cants.

B. Roofing Nailers: Structural- or No. 2-grade lumber or better; kiln-dried Douglas fir, southern pine, or wood having similar decay-resistant properties.

C. Wood Blocking: For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.

2.5 PLYWOOD BACKING PANELS

A. Equipment Backing Panels: Plywood, DOC PS 1.

1. Grade: , fire-retardant treated.
2. Thickness: As indicated on the drawings or, if not indicated, not less than 3/4-inch nominal thickness.

2.6 FASTENERS

A. General: Fasteners are to be of size and type indicated and comply with requirements specified in this article for material and manufacture. Provide nails or screws, in sufficient length, to penetrate not less than **1-1/2 inches** into wood substrate.

1. Where rough carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M or ASTM F2329.

B. Nails, Brads, and Staples: ASTM F1667.

C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.

2.7 ACCESSORIES

A. Metal Framing Anchors:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. MiTek Industries, Inc.
b. Simpson Strong-Tie Co., Inc.
c. Tamlyn

2. Wall Bracing:

a. T-shaped bracing made for letting into studs in saw kerf, **1-1/8 inches** wide by **9/16 inch** deep by **0.034 inch** thick with hemmed edges.
b. Angle bracing made for letting into studs in saw kerf, **15/16 by 15/16 by 0.040 inch** thick with hemmed edges.

3. Materials: Unless otherwise indicated, fabricate from the following materials:

a. Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A653/A653M, **G60** coating designation.

1) Use for interior locations unless otherwise indicated.

b. Heavy-Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A653/A653M; structural steel (SS), high-strength low-alloy steel Type A (HSLAS Type A), or high-strength low-alloy steel Type B (HSLAS Type B); **G185** coating designation; and not less than **0.036 inch** thick.

1) Use for wood-preservative-treated lumber and where indicated.

c. Stainless steel bars and shapes complying with ASTM A276/A276M.

1) Stainless Steel: Type [**304**][**316**].
2) Use for exterior locations and where indicated.

B. Flexible Flashing: Composite, self-adhesive, flashing product consisting of a pliable compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than **0.025 inch**.

1. Compound Material: Butyl rubber or rubberized asphalt.

C. Adhesives for Gluing Furring and Sleepers to Concrete or Masonry: Formulation complying with ASTM D3498 that is approved for use indicated by adhesive manufacturer.

D. Water-Repellent Preservative: Formulation containing 3-iodo-2-propynyl butylcarbamate, combined with an insecticide containing chlorpyrifos as its active ingredient.

PART 3 - EXECUTION

3.1 INSTALLATION OF ROUGH CARPENTRY, GENERAL

A. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.

B. Set work to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry accurately to other construction. Locate [**furring,**] nailers, blocking, and similar supports to comply with requirements for attaching other construction.

C. Plywood Backing Panels: Install backing panels by fastening to studs; coordinate locations with utilities requiring backing panels. Install fire-retardant-treated plywood backing panels with classification marking of testing agency exposed to view.

D. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.

1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than **16 inches** o.c.

E. Provide fire blocking in furred spaces, stud spaces, and other concealed cavities as indicated and as follows:

1. Fire block furred spaces of walls, at each floor level, at ceiling, and at not more than **96 inches** o.c. with solid wood blocking or noncombustible materials accurately fitted to close furred spaces.
2. Fire block concealed spaces of wood-framed walls and partitions at each floor level, at ceiling line of top story, and at not more than **96 inches** o.c. Where fire blocking is not inherent in framing system used, provide closely fitted solid wood blocks of same width as framing members and **2-inch nominal** thickness.
3. Fire block concealed spaces between floor sleepers with same material as sleepers to limit concealed spaces to not more than **100 sq. ft.** and to solidly fill space below partitions.
4. Fire block concealed spaces behind combustible cornices and exterior trim at not more than **20 ft.** o.c.

F. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.

G. Field Application of Preservative Treatment: Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

1. Use inorganic boron (SBX) for items that are continuously protected from liquid water.
2. Use copper naphthenate for items not continuously protected from liquid water.

H. Flexible Flashing: Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.

I. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

1. Table 2304.10.1, "Fastening Schedule," in ICC's "International Building Code" (IBC).
2. Table R602.3(1), "Fastener Schedule for Structural Members," and Table R602.3(2), "Alternate Attachments," in ICC's "International Residential Code for One- and Two-Family Dwellings."
3. ICC-ES evaluation report for fastener.

J. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 INSTALLATION OF ROOFING NAILERS

A. Install roofing nailers where indicated on Drawings and where required for

attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Securely attach roofing nailers to substrates by anchoring and fastening to withstand bending, shear, or other stresses imparted by Project wind loads and fastener-resistance loads as designed in accordance with ASCE/SEI 7.

C. Securely attach roofing nailers to substrate to resist the designed outward and upward wind loads indicated on Drawings and in accordance with SPRI ED-1, Tables A6 and A7.

3.3 INSTALLATION OF WOOD BLOCKING

A. Install wood blocking where indicated on Drawings and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Provide permanent grounds of dressed, pressure-preservative-treated, key-beveled lumber not less than **1-1/2 inches** wide and of thickness required to bring face of ground to exact thickness of finish material. Remove temporary grounds when no longer required.

3.4 PROTECTION

A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 06 10 00

SECTION 06 41 00
ARCHITECTURAL WOOD CASEWORK

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Plastic-laminate-clad casework.
2. Wood materials.
3. Casework hardware.
4. Accessories.
5. Shop finishing.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood furring, blocking, shims, and hanging strips required for installing cabinets that are concealed within other construction before cabinet installation.
2. Section 092216 "Non-Structural Metal Framing" for standard, interior non-load-bearing, metal-stud-framing required for anchoring cabinets.

1.2 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to support loads imposed by installed and fully loaded cabinets.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review locations and method of attachment of backing required for casework installation.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include panel material description and finish.
2. Include glazing.
3. Include accessories.
4. Include hardware.

5. Include shop finishing.

B. Shop Drawings:

1. Plans, elevations, sections, and attachment details.

a. Show large-scale details.
b. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
c. Show locations and sizes of cutouts and holes for items installed in architectural cabinets.
d. Show veneer leaves with dimensions, grain direction, exposed face, and identification numbers indicating the flitch and sequence within the flitch for each leaf.

2. Apply AWI's Quality Certification Program (hereafter AWI QCP) label to Shop Drawings.

C. Samples for Initial Selection: For each exposed product and for each color and finish specified, in manufacturer's standard size.

D. Samples for Verification: Provide a minimum of three samples showing the full range of color and/or grain to be expected in the finished work, for the following.

1. Lumber for Transparent Finish: Not less than **8 inches** long by **3/4 inch** thick, and as wide as practical, for each species and cut, finished on one side and one edge.
2. Veneer Leaves: Representative of and selected from flitches to be used for transparent-finished cabinets. Samples to show the full range of color and grain to be expected.
3. Veneer Panel for Transparent Finish: **8 by 8 inches** by **1/4 inch**, representative of and selected from flitches to be used for transparent-finished casework.
4. Lumber and Panel Products with Shop-Applied Opaque Finish: Not less than **8 inches** long by **3/4 inches** thick, and as wide as practical, for each species and cut for lumber and **8 by 10 inches** for panels, for each finish system and color.

a. Finish entire exposed surface.

5. Plastic Laminates: **8 by 8 inches**, for each type, color, pattern, and surface finish required.

a. Provide one Sample applied to core material with specified edge material applied to one edge.

6. Thermally Fused Laminate (TFL) Panels: **8 by 10 inches**, for each color, pattern, and surface finish.

a. Provide edgebanding on one edge.

7. Corner Pieces:

   a. Cabinet-front frame joints between stiles and rails and at exposed end pieces, **18 inches** high by **18 inches** wide by **6 inches** deep.
   b. Miter joints for standing trim.

8. Exposed Cabinet Hardware and Accessories: One full-size unit for each type and finish.

1.5 CLOSEOUT SUBMITTALS

A. Quality Standard Compliance Certificates: AWI QCP Certificate.

1.6 QUALITY ASSURANCE

A. Manufacturer Qualifications: Employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

   1. Manufacturer's Certification: Licensed participant in AWI's Quality Certification Program.

B. Installer Qualifications: Manufacturer of products.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver cabinets until painting and similar finish operations that might damage architectural cabinets have been completed in installation areas. Store cabinets in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.8 FIELD CONDITIONS

A. Environmental Limitations with Humidity Control: Do not deliver or install cabinets until building is enclosed, wet-work is complete, and HVAC system is operating and maintaining temperature between **60 and 90 deg F** and relative humidity between 30 and 55 percent during the remainder of the construction period.

B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

   1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed/concealed by construction, and indicate measurements on Shop Drawings.

C. Established Dimensions: Where cabinets are indicated to fit to other construction, establish dimensions for areas where cabinets are to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Unless otherwise indicated, comply with ANSI/AWI 0641 for duty level and grade of architectural cabinets indicated for construction, finishes, installation, and other requirements.

1. The Contract Documents contain requirements that are more stringent than the referenced woodwork quality standard. Comply with requirements of the Contract Documents in addition to those of the referenced quality standard.

2.2 PLASTIC-LAMINATE-CLAD CASEWORK

A. Architectural Woodwork Institute (AWI) Standard:

1. Structural Performance Duty Level: As indicated on Drawings.
2. Aesthetic Performance Grade: Premium.

B. Casework Construction Type: Frameless.

C. Door and Drawer-Front:

1. Design: Flush panel.
2. Style: Flush overlay.

a. Reveal Dimension: As indicated on Drawings.

D. High-Pressure Decorative Laminate (HPDL): ISO 4586-3, grades as indicated or, if not indicated, as required by quality standard.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Formica Corporation
b. Pionite; a Panolam Industries International, Inc. brand
c. Wilsonart LLC: High Pressure Laminate

E. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated by laminate manufacturer's designations.
2. Match Architect's sample.
3. As selected by Architect from laminate manufacturer's full range in the following categories:

    a. Solid colors, matte finish.
    b. Solid colors with core same color as surface, matte finish.
    c. Wood grains, matte finish.
    d. Patterns, matte finish.

F. Exposed Exterior Surfaces:

1. Plastic-Laminate Grade: HGS VGS.
2. Pattern Direction: Vertically for drawer fronts, doors, and fixed panels.
3. Edgebanding: High-pressure decorative laminate (HPDL).

G. Exposed Interior Surfaces: High-pressure decorative laminate (HPDL) the same color and pattern as exposed exterior surfaces.

1. Edgebanding: PVC or ABS, 0.018-inch minimum thickness.

H. Semiexposed Surfaces:

1. Surfaces Other Than Drawer Bodies: High-pressure decorative laminate (HPDL) cabinet liner Grade CLS, ISO 4586-3.
2. Drawer Sides and Backs: Thermally fused laminate (TFL) panels with PVC or polyester edgebanding.
3. Concealed Backs of Panels with Exposed Plastic-Laminate Surfaces: High-pressure decorative laminate (HPDL), ISO 4583-3, grade to match exposed surface.
4. Drawer Bottoms: Thermally fused laminate (TFL) panels.
5. Shelves: Adjustable.

    a. Loading Capacity: 50 lb/sq. ft.

6. Edgebanding: PVC or ABS, 0.018-inch minimum thickness.

2.3 WOOD MATERIALS

A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Do not use plain-sawn softwood lumber with exposed, flat surfaces more than **3 inches** wide.
2. Wood Moisture Content:

    a. Non-Climate-Controlled Environments: **10 to 15** percent.
    b. Climate-Controlled Environments: **8 to 13** percent.

B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of architectural cabinet and quality grade specified unless otherwise indicated.

1. Medium-Density Fiberboard (MDF): ANSI A208.2, Grade 130.
2. Particleboard (Medium Density): ANSI A208.1, Grade M-2.
3. Softwood Plywood: DOC PS 1 , medium-density overlay.

4. Thermally Fused Laminate (TFL) Panels: Particleboard or MDF finished with thermally fused, melamine-impregnated decorative paper.

2.4 CASEWORK HARDWARE

A. Cabinet Hardware: Provide cabinet hardware and accessory materials associated with architectural cabinets except for items specified in Section 087100 "Door Hardware."

B. Hinges:

1. Butt Hinges: **2-3/4-inch**, Grade 1 five-knuckle steel hinges made from **0.095-inch-** thick metal, and as follows:

a. Semi-Concealed Hinges, Back Mounted, for Overlay Doors: ANSI/BHMA A156.9, B01511.

C. Pulls and Knobs:

1. Back-Mounted Pulls: ANSI/BHMA A156.9, B02011, **3-inch** centers.

D. Catches and Latches:

1. Magnetic Catches: ANSI/BHMA A156.9, B03141.

E. Shelf Rests and Standards:

1. Adjustable Shelf Standards and Supports: ANSI/BHMA A156.9, B04102; with shelf brackets, B04112.
2. Shelf Rests: ANSI/BHMA A156.9, B04013; metal.

F. Drawer Slides: ANSI/BHMA A156.9.

1. Heavy-Duty (Grade 1HD and Grade 1HD-200): Side mount.

a. Type: Full overtravel extension.
b. Material: Galvanized-steel ball-bearing slides.
c. Motion Feature: soft close dampener.

2. Drawer Types:

a. General-purpose drawers more than **3 inches** high, but not more

than **6 inches** high and not more than **24 inches** wide, provide **75 lb** load capacity.

G. Locks for Drawer and Hinged-Doors: Cylindrical (cam) type, five-pin tumbler, brass with chrome-plated finish, and complying with ANSI/BHMA A156.11, Grade 1.

1. Provide a minimum of two keys per lock and six master keys.
2. Provide locks where indicated.

H. Door Bumpers: Manufacturer's standard self-adhering clear silicone pads.

I. Hardware Finish:

1. Exposed Hardware: Provide finish that complies with ANSI/BHMA A156.18 for ANSI/BHMA finish number indicated.

a. Satin Stainless Steel: ANSI/BHMA 630.

2. Concealed Hardware: Manufacturer's standard finish that complies with product class requirements in ANSI/BHMA A156.9.

2.5 ACCESSORIES

A. Grommets:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Doug Mockett & Company, Inc.
b. Hafele America Co.
c. W.W. Grainger, Inc.

2. Wire-Management Grommets: Circular, grommets and matching caps with slot for wire passage.

a. Finish: Molded plastic.
b. Outside Diameter: 1-1/4 inches.
c. Color: Black.

2.6 FABRICATION

A. Fabricate architectural cabinets to dimensions, profiles, and details indicated. Ease sharp edges and corners.

B. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site,

provide ample allowance for scribing, trimming, and fitting.

1. Notify Architect seven days in advance of dates and times architectural cabinet fabrication will be complete.
2. Trial fit assemblies at manufacturer's shop that cannot be shipped completely assembled. Install dowels, screws, bolted connectors, and other fastening devices that can be removed after trial fitting. Verify that various parts fit as intended and check measurements of assemblies against field measurements before disassembling for shipment.

C. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

2.7 SHOP FINISHING

A. Finish architectural cabinets at manufacturer's shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.

B. Preparation for Finishing: Comply with referenced quality standard for sanding, filling countersunk fasteners, sealing concealed surfaces, and similar preparations for finishing architectural cabinets, as applicable to each unit of work.

1. Backpriming: Apply one coat of sealer or primer, compatible with finish coats, to concealed surfaces of cabinets.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances, location of reinforcements, and other conditions affecting performance of the Work.

1. Confirm location and adequacy of blocking and supports required for installation.
2. Verify size and locations of cutouts for appliances, special equipment, sinks, plumbing, and other items to be mounted in or adjacent to casework.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Before installation, condition cabinets to humidity conditions in installation areas

for not less than 72 hours.

3.3 INSTALLATION OF CASEWORK

A. Install casework to comply with requirements of the structural and aesthetic performance specified.

B. Assemble cabinets and complete fabrication at Project site to extent that it was not completed in the shop.

C. Install cabinets level, plumb, and true in line to a tolerance of **1/8 inch in 96 inches** using concealed shims.

1. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
2. Install cabinets without distortion so doors and drawers fit openings and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.
3. Maintain veneer sequence matching of cabinets with transparent finish.

D. Anchor cabinets in accordance with AWI requirements or tested method to anchors or blocking built in or directly attached to framing or substrates.

1. Install cabinets to comply with seismic requirements as indicated on Drawings.

E. Shop Finishes: Touch up finishing after installation of architectural cabinets. Fill nail holes with matching filler.

1. Apply specified finish coats, including stains and paste fillers if any, to exposed surfaces where only sealer/prime coats are shop applied.

a. Use filler matching finish of items being installed.

3.4 ADJUSTING

A. Repair damaged and defective cabinets, where possible, to eliminate functional and visual defects. Where impossible to repair, replace architectural cabinets. Adjust joinery for uniform appearance.

3.5 CLEANING

A. Clean, lubricate, and adjust hardware and other moving parts to function smoothly.

B. Clean cabinets on exposed and semiexposed surfaces. Touch up finishes to restore damaged or soiled areas.

END OF SECTION 06 41 00

SECTION 078413 - FIRE PROTECTION, HVAC & PLUMBING PENETRATION FIRESTOPPING

PART 1 - GENERAL

1.1 SUMMARY

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

B. Section includes:

1. Through-penetration firestopping in fire rated construction.
2. Through-penetration smoke-stopping in smoke partitions.

C. Related items:

1. Fire dampers and manufactured devices: Refer to Division 23 Section HVAC Air Distribution.

1.2 REFERENCES

A. Underwriters Laboratories

1. UL Fire Resistance Directory

a. Through-penetration firestop devices (XHCR)
b. Fire resistance rating (BXUV)
c. Through-penetration firestop systems (XHEZ)
d. Fill, void, or cavity material (XHHW)

B. American Society for Testing and Materials Standards:

C. ASTM E 814-88: Standard Test Method for Fire Tests of Through-Penetration Firestops.

1.3 DEFINITIONS

A. Assembly: Particular arrangement of materials specific to given type of construction described or detailed in referenced documents.

B. Barriers: Time-rated fire walls, smoke barrier walls, time-rated ceiling/floor assemblies and structural floors.

C. Firestopping: Methods and materials applied in penetrations and unprotected openings to limit spread of heat, fire, gasses and smoke.

D. Penetration: Opening or foreign material passing through or into barrier or structural floor such that full thickness of rated materials is not obtained.

E. System: Specific products and applications, classified and numbered by Underwriters Laboratories, Inc. to close specific barrier penetrations.

F. Sleeve: Metal fabrication or pipe section extended through thickness of barrier and used to permanently guard penetration. Sleeves are described as part of penetrating system in other sections and may or may not be required.

1.4 SYSTEM DESCRIPTION

A. Design Requirements

1. Fire-rated construction: Maintain barrier and structural floor fire resistance ratings including resistance to cold smoke at all penetrations.
2. Smoke barrier construction: Maintain barrier and structural floor resistance to cold smoke at all penetrations.

1.5 SUBMITTALS

A. Submit in accordance with Division 01 Section Submittal Procedures, unless otherwise indicated.

B. Product data: Manufacturer's specifications and technical data including the following:

1. Detailed specification of construction and fabrication.
2. Manufacturer's installation instructions.

C. Shop drawings: Indicate dimensions, description of materials and finishes, general construction, specific modifications, component connections, anchorage methods, hardware, and installation procedures, plus the following specific requirements.

1. Details of each proposed assembly identifying intended products and applicable UL system number, or UL classified devices.
2. Manufacturer or manufacturer's representative shall provide qualified engineering judgment and drawings relating to non-standard applications as needed.

D. Quality control submittals:

1. Statement of qualifications.

E. Applicators' qualifications statement:

1. List past projects indicating required experience.

1.6 QUALITY ASSURANCE

A. Installer's qualifications: Fire experienced in installation or application of systems similar in complexity to those required for this project, plus the following:

1. Acceptable to or licensed by manufacturer, State or local authority where applicable.
2. At least 2 years experience with systems.
3. Successfully completed at least 5 comparable scale projects using this system.

B. Local and State regulatory requirements: Submit forms or acceptance for proposed assemblies not conforming to specific UL Firestop System numbers, or UL classified devices.

C. Materials shall have been tested to provide fire rating at least equal to that of the construction.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Packing and shipping:

1. Deliver products in original unopened packaging with legible manufacturer's identification.
2. Coordinate delivery with scheduled installation date, allow minimum storage at site.

B. Storage and protection: Store materials in a clean, dry, ventilated location. Protect from soiling, abuse, moisture and freezing when required. Follow manufacturer's instructions.

1.8 PROJECT CONDITIONS

A. Existing condition:

1. Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.
2. Proceed with installation only after penetrations of the substrate and supporting brackets have been installed.

B. Environmental requirements:

1. Furnish adequate ventilation if using solvent.
2. Furnish forced air ventilation during installation if required by manufacturer.
3. Keep flammable materials away from sparks or flame.
4. Provide masking and drop cloths to prevent contamination of adjacent surfaces by firestopping materials.

1.9 WARRANTY

A. Submit copies of written warranty agreeing to repair or replace joint sealers which fail in joint adhesion, extrusion resistance, migration resistance, or general durability or appear to deteriorate in any other manner not clearly specified by submitted manufacturer's data as an inherent quality of the material for the exposure indicated. The warranty period shall be two (2) years from date of substantial completion unless otherwise noted.

PART 2 - PRODUCTS

2.1 THROUGH-PENETRATION FIRESTOPPING OF FIRE-RATED CONSTRUCTION

A. Systems of devices listed in the UL Fire Resistance Directory under categories XHCR and XHEZ may be used, providing that it conforms to the construction type, penetrant type, annular space requirements and fire rating involved in each separate instance, and that the system be symmetrical for wall applications. Systems or devices must be asbestos-free.

1. Additional requirements: Withstand the passage of cold smoke either as an inherent property of the system, or by the use of a separate product included as a part of the UL system or device, and designed to perform this function.
2. Acceptable manufacturers and products.

a. Those listed in the UL Fire Resistance directory for the UL System involved and as further defined in the System and Applications Schedule in Part 3.6 of this section.

3. All firestopping products must be from a single manufacturer. All trades shall use products from the same manufacturer unless otherwise noted.

2.2 SMOKE-STOPPING AT SMOKE PARTITIONS

A. Through-penetration smoke-stopping: Any system complying with the requirements for through-penetration firestopping in fire-rated construction, as specified in The Systems and Applications Schedule in Part 3.6 of this section, is acceptable, provided that the system includes the specified smoke seal or will provide a smoke seal. The length of time of the fire resistance may be disregarded.

2.3 ACCESSORIES

A. Fill, void or cavity materials: As classified under category XHHW in the UL Fire Resistance Directory.

B. Forming materials: As classified under category XHKU in the UL Fire Resistance Directory.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.

1. Verify barrier penetrations are properly sized and in suitable condition for application of materials.
2. Do not proceed until unsatisfactory conditions have been corrected.

B. Coordinate an inspection of all Mechanical Firestopping systems with the Fire Marshal prior to installation of ceilings, walls, etc.

3.2 PREPARATION

A. Clean surfaces to be in contact with penetration seal materials of dirt, grease, oil, loose materials, rust, or other substances that may affect proper fitting, adhesion, or the required fire resistance.

3.3 INSTALLATION

A. Install penetration seal materials in accordance with printed instructions of the UL Fire Resistance Directory and in accordance with manufacturer's instruction.

B. Seal holes or voids made by penetrations to ensure an effective smoke barrier.

C. Protect materials from damage on surfaces subject to traffic.

D. When large openings are created in walls or floors to permit installation of pipes, ducts, or other items, close unused portions of opening with firestopping materials tested for the application. See UL Fire Resistance Directory or Section 3.6 of this document.

1. Install smoke stopping as specified for firestopping.

3.4 FIELD QUALITY CONTROL

A. Examine penetration sealed areas to ensure proper installation before concealing or enclosing areas.

B. Keep areas of work accessible until inspection by applicable code authorities.

C. Perform under this section patching and repairing of firestopping caused by cutting or penetration by other trades.

3.5 ADJUSTING AND CLEANING

A. Clean up spills of liquid components.

B. Neatly cut and trim materials as required.

C. Remove equipment, materials and debris, leaving area in undamaged, clean condition.

3.6 SYSTEMS AND APPLICATION SCHEDULES*

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/CEILING
Metal Pipe	CAJ1001 CP25S/L, CP25N/S CAJ1006 CS-195+, FS-195+ CAJ1007 FS-195+, 1-inch& 2-inch Wide CAJ1009 2000, 2000+, 2003 CAJ1010 2000, 2000+, 2003 CAJ1012 2000, 2000+, 2003 CAJ1013 2000, 2000+, 2003 CAJ1014 2000, 2000+, 2003 CAJ1015 2000, 2000+, 2003 CAJ1017 FD 150 CAJ1021 FD 150 CAJ1027 MPS-2+ CAJ1044 CP 25WB+ CAJ1052 CP 25S/L, CP 25N/S CAJ1058 2000, 2000+, 2003 CAJ1060 2000, 2000+, 2003 CAJ1063 2000, 2000+, 2003 CAJ1066 CP 25N/S,CP 25S/L, CP 25WB+ CAJ1091 CP 25N/S,CP 25S/L, CP 25WB+ CAJ1092 CP 25WB+ CAJ1112 FS-195+ CAJ1160 CP 25S/L, CP 25N/S CAJ1175 CP 25WB+ CAJ1176 CP 25WB+ CAJ1188 2000+ CBJ1020 CS-195+, FS-195+ CBJ1021 CS-195+, MPS-2+ CBJ1031 2001 CBJ1032 2001 FA1002 CP 25WB+ WJ1010 CP25WB+ WJ1023 2001	WL1001 CP 25 WL1002 FS-195+ WL1003 CP 25WB+,CP 25N/S WL1008 2000+ WL1009 2000+ WL1010 2000+ WL1016 CP 25WB+ WL1017 CP 25WB+,CP 25N/S WL1032 CP 25WB+,CP 25N/S WL1036 FD 150 WL1037 CS-195+,FS-195+ WL1067 CP 25N/S WL1073 CP 25WB+ WL1080 MPS2+ WL1082 2000+	FC1002 CP 25 FC1003 2000,2000+,20003 FC1006 CP 25WB+

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/CEILING
Non-Metallic	CAJ2001 FS-195+, 1-inch& 2-inch WIDE, PPD'S CAJ2002 FS-195+ CAJ2003 CS-195+, FS-195+ CAJ2005 FS-195 CAJ2006 FS-195+ CAJ2013 FS-195+ CAJ2019 2000, 2000+, 2003 CAJ2027 FS-195+, CP 25N/S, CP 25S/L, CP 25WB+ CAJ2028 FS-195, MPS-2+ CAJ2029 FS-195+, PPD'S CAJ2030 CS-195+, FS-195+ CAJ2040 FS-195+, CP 25WB+ CAJ2044 FS-195+, CP 25N/S, CP 25S/L CP 25 WB+ CAJ2090 FS-195+ CAJ2177 FS-195+, PPD'S FA2001 FS-195+, PPD'S FS2002 CS-195+, FS-195+, MPS-2+, PPD'S FA2011 FS-195+ WJ2012 FS-195+ 1-inch WIDE	WL2002 FS-195+, PPD'S WL2003 FS-195+ WL2004 FS-195+ WL2005 FS-195+ 4' WIDE WL2006 FS-195+ WL2013 FS-195+ WL2031 CS-195+, FS-195+ WL2032 CS-195+, FS-195+ WL2033 FS-195+ WL2073 FS-195+ 1-inch WIDE	FC2002 FS-195+, PPD'S FC2007 FS-195+, PPD'S FC2008 FS-195+ FC2009 FS-195+, PPD'S FC2024 FS-195 FC2026 FS-195+ FC2028 FS-195, 1' & 2-inch WIDE, PPD'S
Insulated Metallic Pipe	CAJ5001 CP 25N/S, CP 25S/L, CP 25WB+ CAJ5002 FS-195+ CAJ5003 FS-195+ CAJ5005 MPS-2+ CAJ5009 2000+, 2003 CAJ5017 FS-195+, CP 25 CAJ5022 FS-195+ CAJ5024 FS-195+ CAJ5030 CS-195+, FS-195+ CAJ5041 2000, 2000+, 2003 CAJ5060 CP 25WB+ CAJ5074 2000+ CBJ5002 CP 25 CBJ5003 FS-195+ FA5001 FS-195+, CP 25WB+	WL5001 FS-195+ WL5002 FS-195+ WL5009 FS-195+ WL5010 FS-195+ WL5011 CP 25WB+ WL5032 2000+ WL5038 CP 25WB+ WL5039 CP 25WB+ WL5040 CP 25WB+ WL5045 CP 25WB+ WL5053 2000+	FC5002 FS-195+ FC5008 FS-195+
Miscellaneous Mechanical HVAC Ducts	CAJ7001 CP 25N/S CP 25S/L CAJ7003 CP 25WB+ CAJ7009 DUCT WRAP, BULK PUTTY		FC7001 CP 25S/L, CP 25N/S
Mixed Penetrating Items Combos	CAJ8001 CS-195+ FS-195 CAJ8003 2000, 2000+, 20003 CAJ8004 2000, 2000+, 20003 CAJ8006 2001 CAJ8013 FS-195+, CP 25 CBJ8004 CS-195, FS-195+ CBJ8005 CS-195+, MPS-2+ CBJ8008 2001 FA8001 FS-195+, CP 25WB+	WL8002 CS-195+, FS-195+	

*Underwriter's Laboratories, Inc., Fire Resistance Directory.

END OF SECTION 078413

SECTION 07 92 00
JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Silicone joint sealants.
2. Urethane joint sealants.
3. Silane-modified polymer joint sealants.
4. Mildew-resistant joint sealants.
5. Butyl joint sealants.
6. Latex joint sealants.
7. Joint sealant backings.

B. Related Requirements:

1. Section 079100 "Preformed Joint Seals" for preformed compressible foam and precured joint seals.
2. Section 079219 "Acoustical Joint Sealants" for sealing joints in sound-rated construction.
3. Section 321373 "Concrete Paving Joint Sealants" for sealing joints in paved roads, parking lots, walkways, and curbing.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include preparation requirements and installation instructions.
2. Indicate VOC content.

B. Samples for Initial Selection: Manufacturer's standard color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.

C. Joint Sealant Schedule: Include the following information:

1. Joint sealant application, joint location, and designation.
2. Joint sealant manufacturer and product name.
3. Joint sealant formulation.
4. Joint sealant color.

5. Joint sealant backing or joint filler.
6. Joint size (width and depth).
7. Tooled joint profile.

1.3 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data.

B. Warranty Documentation

1.4 FIELD CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.5 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: **Two** years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: **Five** years from date of Substantial Completion.

C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:

1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
2. Disintegration of joint substrates from causes exceeding design specifications.
3. Mechanical damage caused by individuals, tools, or other outside agents.
4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain joint sealants from single manufacturer for each sealant type.

2.2 JOINT SEALANTS, GENERAL

A. Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application indicated, and as indicated within approved joint sealant schedule submittal based on joint sealant manufacturer's testing and field experience.

B. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.3 SILICONE JOINT SEALANTS

A. Silicone, Neutral-Curing Sealant: ASTM C920.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation 898 NST or comparable product by one of the following:

    a. Dow
    b. Sika Corporation - Building Components
    c. The Dow Chemical Company

2. Type: S
3. Grade: NS
4. Class: 25.
5. Use: NT.

2.4 NONSTAINING SILICONE JOINT SEALANTS

A. General: No staining of substrates when tested in accordance with ASTM C1248.

2.5 URETHANE JOINT SEALANTS

A. Urethane Sealant: ASTM C920.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation DynaTrol II or comparable product by one of the following:

a. Sika Corporation - Building Components
b. Tremco Incorporated

2. Type: M.
3. Grade: NS.
4. Class: 50.
5. Use: NT.

2.6 SILANE-MODIFIED POLYMER JOINT SEALANTS

A. Silane-Modified Polymer Sealant: ASTM C920.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation DynaTrol I XL Hybrid or comparable product by one of the following:

a. GE Construction Sealants; Momentive Performance Materials Inc.
b. Sika Corporation - Building Components
c. Tremco Incorporated

2. Type: S.
3. Grade: NS.
4. Class: 50.
5. Use: T and NT.
6. Polymer Type: Silyl-terminated polyurethane.

2.7 MILDEW-RESISTANT JOINT SEALANTS

A. General: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.

B. Silicone, Mildew-Resistant, Acid-Curing Sealant: ASTM C920.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation; 898 NST or comparable product by one of the following:

a. GE Construction Sealants; Momentive Performance Materials Inc.
b. Sika Corporation - Building Components
c. Tremco Incorporated

2. Type: S.
3. Grade: NS.
4. Class: 25.
5. Use: NT.

2.8 BUTYL JOINT SEALANTS

A. Butyl-Rubber-Based Joint Sealant: ASTM C1311.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation BC-158 or comparable product by one of the following:

a. Bostik; Arkema
b. GSSI Sealants
c. Sika Corporation - Building Components

2.9 LATEX JOINT SEALANTS

A. Acrylic Latex Sealant: ASTM C834.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation AC20 or comparable product by one of the following:

a. Everkem Diversified Products, Inc.
b. Tremco Incorporated
c. Master Builders Solutions

2. Type: OP.
3. Grade: NF.

2.10 JOINT SEALANT ACCESSORIES

A. Joint Sealant Backings: Provide joint sealant backings that are nonstaining, compatible with joint substrates, sealants, primers, and other joint fillers under conditions of service and application indicated, and as indicated within approved joint sealant schedule submittal based on joint sealant manufacturer's testing and field experience.

1. Cylindrical Sealant Backings: ASTM C1330, of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

a. Classification: Type C.

B. Bond-Breaker Tape : Polyethylene tape or other plastic tape recommended in writing by joint sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials, or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.11 MISCELLANEOUS MATERIALS

A. Primer: Material recommended in writing by joint sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from

preconstruction joint sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Porous Joint Substrate Surfaces: Clean by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Concrete.
    b. Masonry.
    c. Unglazed surfaces of ceramic tile.

3. Concrete Substrate Surfaces: Remove laitance and form-release agents from concrete.
4. Nonporous Joint Substrate Surfaces: Clean with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of

interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

a. Metal.
b. Glass.
c. Porcelain enamel.
d. Glazed surfaces of ceramic tile.

B. Joint Priming: Prime joint substrates where recommended by joint sealant manufacturer or as indicated by preconstruction joint sealant-substrate tests or prior experience. Apply primer to comply with joint sealant manufacturer's written instructions. Confine primers to areas of joint sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint sealant and backing manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Joint Sealant Backings: Install backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.

D. Bond-Breaker Tape: Install tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Joint Sealants: Install using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants in accordance with requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile in accordance with Figure 8A in ASTM C1193 unless otherwise indicated.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Tests and Inspections:

1. Field-Adhesion Testing: Field test joint sealant adhesion to joint substrates as follows:

a. Extent of Testing: Test completed and cured sealant joints as follows:

1) Perform 10 tests for the first **1000 ft.** of joint length for each kind of sealant and joint substrate.
2) Perform one test for each 1000 ft. of joint length thereafter or one test per each floor per elevation.

b. Test Method: Test joint sealants in accordance with Method A, Tail Procedure, in ASTM C1521.

1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

c. Inspect tested joints and report on the following:

1) Whether sealants filled joint cavities and are free of voids.
2) Whether sealant dimensions and configurations comply with specified requirements.
3) Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.

d. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test

dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.

e. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

2. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

C. Prepare test and inspection reports.

3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.7 JOINT SEALANT SCHEDULE

A. Exterior Joints in Vertical Surfaces and Horizontal Nontraffic Surfaces:

1. Joint Locations:

a. Construction joints in cast-in-place concrete.
b. Joints between plant-precast architectural concrete units.
c. Control and expansion joints in unit masonry.
d. Joints in dimension stone cladding.
e. Joints in glass unit masonry assemblies.

f. Joints between metal panels.
g. Joints between different materials listed above.
h. Perimeter joints between materials listed above and frames of doors

and windows.

i. Other joints as indicated on Drawings.

2. Joint Sealant: Urethane Sealant.
3. Color: As selected by Architect from manufacturer's full range of colors.

B. Interior Joints in Vertical Surfaces and Horizontal Nontraffic Surfaces:

1. Joint Locations:

a. Control and expansion joints on exposed interior surfaces of exterior walls.
b. Tile control and expansion joints.

c. Other joints as indicated on Drawings.

2. Joint Sealant: Silane-modified polymer sealant.
3. Color: As selected by Architect from manufacturer's full range of colors.

C. Interior Joints in Vertical Surfaces and Horizontal Nontraffic Surfaces Not Subject to Significant Movement:

1. Joint Locations:

a. Control joints on exposed interior surfaces of exterior walls.
b. Perimeter joints between interior wall surfaces and frames of interior doors and windows.

c. Joints, crevices, and irregularities wider than hairline joints in or between painted surfaces.
d. Interior joints noted as 'caulking.'

2. Joint Sealant: Acrylic latex.
3. Color: As selected by Architect from manufacturer's full range of colors.

D. Mildew-Resistant Interior Joints in Vertical Surfaces and Horizontal Nontraffic Surfaces:

1. Joint Locations:

a. Joints between plumbing fixtures and adjoining walls, floors, and counters.
b. Tile control and expansion joints where indicated.
c. Perimeters of lavatory counters.
d. Other joints as indicated on Drawings.

2. Joint Sealant: Mildew-resistant silicone.
3. Color: As selected by Architect from manufacturer's full range of colors.

E. Concealed Mastics:

1. Joint Locations:

    a. Aluminum thresholds.
    b. Sill plates.
    c. Other joints as indicated on Drawings.

2. Joint Sealant: Butyl Sealant.

END OF SECTION 07 92 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 07 92 19
ACOUSTICAL JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Acoustical joint sealants.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for elastomeric, latex, and butyl-rubber-based joint sealants for nonacoustical applications.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants, showing full range of available colors for each product exposed to view.

C. Samples for Verification: For each type and color of acoustical joint sealant required.

1. Size: **1/2-inch-** wide sealant joints formed between two **6-inch-** long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

D. Acoustical Joint Sealant Schedule: Include the following information:

1. Joint sealant application, joint location, and designation.
2. Joint sealant manufacturer and product name.
3. Joint sealant formulation.
4. Joint sealant color.

1.3 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained between **40 and 95 deg F**.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.4 FIELD CONDITIONS

A. Install joint sealant only when temperature of surfaces to be sealed and ambient air temperatures are in accordance with acoustical joint sealant manufacturer's written installation instructions

PART 2 - PRODUCTS

2.1 ACOUSTICAL JOINT SEALANTS

A. General: Acoustical joint-sealant products that effectively reduce airborne sound transmission through perimeter joints and openings in building construction, as demonstrated by testing representative assemblies in accordance with ASTM E90.

B. Acoustical Sealant for Concealed Joints: Manufacturer's standard nonsag, nondrying, nonhardening, nonskinning, nonstaining, gunnable, synthetic-rubber acoustical sealant.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. OSI Sealants; Henkel Corporation
b. Pecora Corporation
c. Tremco Incorporated

2.2 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by acoustical joint sealant manufacturer where required for adhesion of sealant to joint substrates.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive acoustical joint sealants, with Installer

present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing acoustical joint sealants to comply with joint sealant manufacturer's written instructions.

B. Joint Priming: Prime joint substrates where recommended by acoustical joint sealant manufacturer. Apply primer to comply with joint sealant manufacturer's written instructions. Confine primers to areas of joint sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF ACOUSTICAL JOINT SEALANTS

A. Comply with acoustical joint sealant manufacturer's written installation instructions.

B. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical joint sealant. Install acoustical joint sealants at both faces of partitions, at perimeters, and through penetrations. Comply with ASTM C919, ASTM C1193, and manufacturer's written instructions for closing off sound-flanking paths around or through assemblies, including sealing partitions to underside of floor slabs above acoustical ceilings.

C. Acoustical Ceiling Areas: Apply acoustical joint sealant at perimeter edge moldings of acoustical ceiling areas in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.

3.4 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturer of acoustical joint sealants and of products in which joints occur.

3.5 PROTECTION

A. Protect acoustical joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated acoustical joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION 07 92 19

SECTION 08 06 71

DOOR HARDWARE SCHEDULE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section references specification sections relating to commercial door hardware for the following:

1. Swinging doors.

B. Commercial door hardware includes, but is not necessarily limited to, the following:

1. Mechanical door hardware.

C. Related Sections:

1. Division 08 Section “Door Hardware”.

D. Codes and References: Comply with the version adopted by the Authority Having Jurisdiction.

1. ANSI A117.1 - Accessible and Usable Buildings and Facilities.
2. ICC/IBC - International Building Code.
3. NFPA 70 - National Electrical Code.
4. NFPA 80 - Fire Doors and Windows.
5. NFPA 101 - Life Safety Code.
6. NFPA 105 - Installation of Smoke Door Assemblies.
7. State Building Codes, Local Amendments.

E. Standards: Reference Related Sections for requirements regarding compliance with applicable industry standards.

1.3 SUBMITTALS

A. Product Data: Manufacturer's product data sheets including installation details, material descriptions, dimensions of individual components and profiles, operational descriptions and finishes.

B. Door Hardware Schedule: Prepared by or under the supervision of supplier, detailing fabrication and assembly of door hardware, as well as procedures and diagrams. Coordinate the final Door Hardware Schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.

1. Format: Comply with scheduling sequence and vertical format in DHI's "Sequence and Format for the Hardware Schedule."

2. Organization: Organize the Door Hardware Schedule into door hardware sets indicating complete designations of every item required for each door or opening. Organize door hardware sets in same order as in the Door Hardware Sets at the end of Part 3. Submittals that do not follow the same format and order as the Door Hardware Sets will be rejected and subject to resubmission.

3. Content: Include the following information:

a. Type, style, function, size, label, hand, and finish of each door hardware item.
b. Manufacturer of each item.
c. Fastenings and other pertinent information.
d. Location of door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
e. Explanation of abbreviations, symbols, and codes contained in schedule.
f. Mounting locations for door hardware.
g. Door and frame sizes and materials.

4. Submittal Sequence: Submit the final Door Hardware Schedule at earliest possible date, particularly where approval of the Door Hardware Schedule must precede fabrication of other work that is critical in the Project construction schedule. Include Product Data, Samples, Shop Drawings of other work affected by door hardware, and other information essential to the coordinated review of the Door Hardware Schedule.

C. Keying Schedule: Prepared under the supervision of the Owner, separate schedule detailing final keying instructions for locksets and cylinders in writing. Include keying system explanation, door numbers, key set symbols, hardware set numbers and special instructions. Owner to approve submitted keying schedule prior to the ordering of permanent cylinders.

D. Product Test Reports: Indicating compliance with cycle testing requirements, based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified independent testing agency.

E. Operating and Maintenance Manuals: Provide manufacturers operating and maintenance manuals for each item comprising the complete door hardware installation in quantity as required in Division 01, Closeout Submittals. The manual to include the name, address, and contact information of the manufacturers providing the hardware and their nearest service representatives. The final copies delivered after completion of the installation test to include "as built" modifications made during installation, checkout, and acceptance.

F. Warranties and Maintenance: Special warranties and maintenance agreements specified in the Related Sections.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Inventory door hardware on receipt and provide secure lock-up and shelving for door hardware delivered to Project site. Do not store electronic access control hardware, software or accessories at Project site without prior authorization.

B. Tag each item or package separately with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.

C. Deliver, as applicable, permanent keys, cylinders, cores, access control credentials, software and related accessories directly to Owner via registered mail or overnight package service. Instructions for delivery to the Owner shall be established at the "Keying Conference".

1.5 WARRANTY

A. General Warranty: Reference Division 01, General Requirements. Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

1.6 MAINTENANCE SERVICE

A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

PART 2 - PRODUCTS

2.1 SCHEDULED DOOR HARDWARE

A. Refer to “PART 3 – EXECUTION” for required specification sections.

PART 3 - EXECUTION

3.1 DOOR HARDWARE SETS

A. The door hardware sets represent the design intent and direction of the owner and architect. They are a guideline only and should not be considered a detailed hardware schedule. Discrepancies, conflicting hardware and missing items should be brought to the attention of the architect with corrections made prior to the bidding process.

Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application and functionality.

1. Quantities listed are for each pair of doors, or for each single door.

2. The supplier is responsible for handing and sizing all products.

3. Where multiple options for a piece of hardware are given in a single line item, the supplier shall provide the appropriate application for the opening.

4. At existing openings with new hardware the supplier shall field inspect existing conditions prior to the submittal stage to verify the specified hardware will work as required. Provide alternate solutions and proposals as needed.

B. Products listed in the hardware sets shall be supplied by and in accordance with the requirements described in the specification section as noted for each item.

1. Section 08 71 00 – Door Hardware.

C. Manufacturer's Abbreviations:

1. MK - McKinney
2. PE - Pemko
3. SU - Securitron
4. RO - Rockwood
5. SA - SARGENT
6. BE - BEST Locks & Closers
7. HS - HES
8. NO - Norton Rixson

Hardware Sets

Set: 1.0
Doors: 104-1

3	Hinge	TA2714 [NRP]	US26D	MK
1	Storeroom/Closet Lock	70 8204 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
3	Silencer	608		RO

Set: 2.0
Doors: 119-1

3	Hinge	TA2714 [NRP]	US26D	MK
1	Keypad Mortise Lock	70 KP8278 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE

1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Wall Stop	403 (or) 441CU (As Required)	US26D	RO
3	Silencer	608		RO

Set: 3.0
Doors: 220

3	Hinge	TA2714 [NRP]	US26D	MK
1	Storeroom/Closet Lock	70 8204 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Mop Plate	K1050 4" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
1	Gasketing	Provided By Door/Frame Supplier		

Set: 4.0
Doors: 120-1

1	Continuous Hinge	CFM_HD1 x Length Required		PE
1	Storeroom/Closet Lock	70 8204 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Mop Plate	K1050 4" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
3	Silencer	608		RO

Set: 5.0
Doors: 105

3	Hinge	TA2714 [NRP]	US26D	MK
1	Storeroom/Closet Lock	70 8204 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
1	Gasketing	Provided By Door/Frame Supplier		

Set: 6.0
Doors: 102-1, 103-1, 106-1.1, 106-1.2, 107-1, 109-1

3	Hinge	TA2714 [NRP]	US26D	MK
1	Office/Entry Lock	70 8255 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Mop Plate	K1050 4" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO

1	Gasketing	S88BL (Head & Jambs)		PE

Set: 7.0
Doors: 105-1

3	Hinge	T4A3786 [NRP]	US26D	MK
1	Classroom Lock	70 8237 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
3	Silencer	608		RO

Notes:
Verify and coordinate scheduled hardware with access control supplier prior to submitting/ordering.

Set: 8.0
Doors: 117-1

3	Hinge	T4A3786 [NRP]	US26D	MK
1	Classroom Lock	70 8237 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
3	Silencer	608		RO

Notes:
Verify and coordinate scheduled hardware with access control supplier prior to submitting/ordering.

Set: 9.0
Doors: 111-1, 118-1

3	Hinge	TA2714 [NRP]	US26D	MK
1	Classroom Lock	70 8237 LNMJ	US26D	SA
1	Core	As Required to Match Facility Standard	626	BE
1	Surface Closer	351 P10 / O (As Condition DIctates)	EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO
1	Mop Plate	K1050 4" high CSK BEV	US32D	RO
1	Wall Stop	406 / 409	US26D	RO
1	Gasketing	Provided By Door/Frame Supplier		

Set: 10.0
Doors: 101-1

3	Hinge	T4A3786 [NRP]	US26D	MK
1	Classroom Lock	70 8237 LNMJ	US26D	SA

1	Core	As Required to Match Facility Standard		626	BE
1	Surface Closer	351 CPS	EN	SA	
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO	
3	Silencer	608		RO	

Set: 11.0
Doors: 100A-1

3	Hinge	TA2714 [NRP]	US26D	MK	
1	Privacy Lock	V21 8265 LNMJ	US26D	SA	
1	Conc Overhead Stop	6-X36	630	NO	
1	Surface Closer	351 P10 / O (As Condition DIctates)		EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO	
1	Mop Plate	K1050 4" high CSK BEV	US32D	RO	
1	Gasketing	S88BL (Head & Jambs)		PE	

Set: 12.0
Doors: 104A-1, 104B-1

3	Hinge	TA2714 [NRP]	US26D	MK	
1	Privacy Lock	V21 8265 LNMJ	US26D	SA	
1	Surface Closer	351 P10 / O (As Condition DIctates)		EN	SA
1	Kick Plate	K1050 10" high CSK BEV	US32D	RO	
1	Mop Plate	K1050 4" high CSK BEV	US32D	RO	
1	Wall Stop	406 / 409	US26D	RO	
1	Gasketing	S88BL (Head & Jambs)		PE	

Set: 13.0
Doors: 100-1

1	Core	As Required to Match Facility Standard		626	BE
1	Cylinder Housing	As Required	US15	SA	

Notes:
Balance of hardware provided by door supplier.

END OF SECTION 08 06 71

PAGE LEFT INTENTIONALLY BLANK

SECTION 08 12 13
HOLLOW METAL FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Standard interior hollow metal frames.

2. Borrowed lite frames.

B. Related Requirements:

1. Section 087111 "Door Hardware (Descriptive Specification)" for door hardware for hollow metal doors.

1.2 DEFINITIONS

A. Minimum Steel Sheet Thickness: Minimum thickness of base metal without coatings in accordance with ANSI/SDI A250.8.

1.3 COORDINATION

A. Coordinate installing anchors for hollow metal frames, including sleeves, concrete inserts, and anchor bolts.

B. Coordinate requirements for installing door hardware, including electrified door hardware, and access control and security systems.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include construction details, material descriptions, core descriptions, and finishes.
2. Include information indicating compliance with performance requirements indicated.

B. Shop Drawings:

1. Elevations of each frame type.
2. Frame details for each frame type, including dimensioned profiles and base-metal thicknesses.
3. Locations of reinforcement and preparations for hardware.

4. Details of each wall opening condition.
5. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
6. Details of frame anchors, joints, field splices, and connections.
7. Details of accessories.
8. Details of moldings, removable stops, and glazing.

C. Product Schedule: For hollow metal frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings used on the Drawings and in schedules. Coordinate with doors and final door hardware schedule.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver hollow metal frames palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic, canvas, or other material that can entrap moisture.

1. Provide additional protection to prevent damage to factory-applied color finishes.

B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.

C. Store hollow metal frames vertically under cover at Project site with head up. Place on minimum **4-inch-** high wood blocking.

D. Immediately remove and replace damaged or wet packaging or protective material.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain hollow metal frames from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Sidelite and Transom Frames: Assemblies complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated on Drawings, based on testing in accordance with ASTM E119 or UL 263.

2.3 STANDARD INTERIOR HOLLOW METAL FRAMES

A. Manufacturers: Subject to compliance with requirements, available

manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Curries, AADG, Inc.; ASSA ABLOY Group
2. Republic Doors and Frames; an Allegion brand
3. Steelcraft; Allegion plc

B. Interior Extra-Heavy-Duty Frames: ANSI/SDI A250.8, Level 3; ANSI/SDI A250.4, Level A.

1. Steel Sheet: Uncoated.
2. Frames: Steel sheet; minimum **0.053-inch** base-metal thickness.

a. Construction: Face welded.
b. Sidelite and Transom Frames: Fabricated from same thickness material as adjacent door frame.

3. Exposed Finish: Prime painted.

2.4 BORROWED LITES

A. Borrowed Lite Frames:

1. Minimum Base-Metal Thickness: 0.053 inch.
2. Steel Sheet: Uncoated.
3. Construction: Face welded.

2.5 ACCESSORIES

A. Frame Anchors: ANSI/SDI 250.4; steel sheet; minimum base-metal thickness required by door and frame standard indicated.

1. Interior Locations: ASTM A1008/A1008M or ASTM A1011/A1011M; hot-dip galvanized in accordance with ASTM A153/A153M, Class B.

2. Jamb Anchors: Of minimum size and type required by door and frame standard indicated, and suitable for performance level indicated.

a. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each **24 inches** of frame height above **7 ft.**.
b. Postinstalled Expansion Anchor: Minimum **3/8-inch-** diameter bolts with expansion shields or inserts, with manufacturer's standard pipe spacer.

3. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor.
4. Floor Anchors for Concrete Slabs with Underlayment: Adjustable-type anchors with extension clips that allow **2-inch** height adjustment.

Terminate bottom of frames at top of underlayment.

2.6 MATERIALS

A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

B. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B; suitable for exposed applications.

C. Hot-Rolled Steel Sheet: ASTM A1011/A1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.

D. Inserts, Bolts, and Fasteners: Hot-dip galvanized in accordance with ASTM A153/A153M.

E. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow metal frames of type indicated.

F. Mineral-Fiber Insulation: ASTM C665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E136 for combustion characteristics.

G. Glazing: Comply with requirements in Section 088000 "Glazing."

2.7 FABRICATION

A. Hollow Metal Frames:

1. Welded Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles, at each joint, fabricated from metal of same or greater thickness as frames.
2. Sidelite and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints fabricated from same material as door frame. Fasten members at crossings and to jambs by welding, or by rigid mechanical anchors.
3. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
4. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers. Keep holes clear during construction.

    a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.

B. Hardware Preparation: Factory prepare hollow metal frames to receive templated mortised hardware, and electrical wiring; include cutouts,

reinforcement, mortising, drilling, and tapping in accordance with ANSI/SDI A250.6, the door hardware required, and templates.

1. Reinforce frames to receive nontemplated, mortised, and surface-mounted hardware.
2. Comply with ANSI/SDI A250.14 for preparing hollow metal frames for hardware.

2.8 STEEL FINISHES

A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.

1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with ANSI/SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.

B. Drill and tap frames to receive nontemplated, mortised, and surface-mounted hardware.

3.3 INSTALLATION OF STANDARD INTERIOR HOLLOW METAL FRAMES

A. Install in accordance with ANSI/SDI A250.8 and ANSI/SDI A250.11.

B. Install hollow metal frames plumb, rigid, properly aligned, and securely fastened in place. Comply with approved Shop Drawings and with manufacturer's written instructions.

C. Mineral-Fiber Insulation: Solidly pack mineral-fiber insulation inside frames.

D. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow metal frame manufacturer's written instructions.

3.4 INSTALLATION OF BORROWED LITE FRAMES

A. Install in accordance with ANSI/SDI A250.8 and ANSI/SDI A250.11.

B. Mineral-Fiber Insulation: Solidly pack mineral-fiber insulation inside frames.

C. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow metal door and frame manufacturer's written instructions.

3.5 FIELD QUALITY CONTROL

A. Egress-Door Acceptance Testing: Test and inspect egress doors in accordance with NFPA 101.

B. Repair or remove and replace installations where testing and inspections indicate noncompliance with specified requirements.

C. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

D. Inspection Report: Prepared and submitted in writing to Architect and Contractor within 24 hours after testing.

3.6 ADJUSTING

A. Remove and replace defective work, including frames that are warped, bowed, or otherwise defective.

3.7 CLEANING

A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

END OF SECTION 08 12 13

SECTION 08 14 16
FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid-core five-ply flush wood veneer-faced doors and transom panels for transparent finish.

B. Related Requirements:

1. Section 087111 "Door Hardware (Descriptive Specification)" for door hardware for flush wood doors.
2. Section 088000 "Glazing" for glass view panels in flush wood doors.

1.2 COORDINATION

A. Coordinate requirements for installing door hardware, including electrified door hardware, and access control and security systems.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product. Include information indicating compliance with performance requirements indicated.

1. Door core materials and construction.
2. Door edge construction.
3. Door face type and characteristics.
4. Door louvers.
5. Door trim for openings.
6. Door frame construction.
7. Factory-machining criteria.
8. Factory- finishing specifications.

B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each type of door; construction details not covered in product data; and the following:

1. Door schedule indicating door and frame location, type, size, fire protection rating, and swing.
2. Door elevations, dimension and locations of hardware, lite and louver cutouts, and glazing thicknesses.
3. Details of frame for each frame type, including dimensions and profile.
4. Details of electrical raceway and preparation for electrified hardware,

access control systems, and security systems.
5. Dimensions and locations of blocking for hardware attachment.
6. Dimensions and locations of mortises and holes for hardware.
7. Clearances and undercuts.
8. Requirements for veneer matching.
9. Doors to be factory finished and application requirements.

C. Samples for Initial Selection: For factory-finished doors.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Comply with requirements of referenced standard and manufacturer's written instructions.

B. Package doors individually in cardboard cartons, and wrap bundles of doors in plastic sheeting.

C. Mark each door on top and bottom rail with opening number used on Shop Drawings.

1.5 FIELD CONDITIONS

A. Environmental Limitations:

1. Do not deliver or install doors until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and HVAC system is operating and maintaining temperature and relative humidity at levels designed for building occupants for the remainder of construction period.
2. Do not deliver or install doors until building is enclosed and weathertight, wet work is complete, and HVAC system is operating and maintaining temperature between **60 and 90 deg F** and relative humidity between **43 and 70** percent during remainder of construction period.

1.6 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Delamination of veneer.
b. Warping (bow, cup, or twist) more than **1/4 inch** in a **42-by-84-inch** section.
c. Telegraphing of core construction in face veneers exceeding **0.01 inch in a 3-inch** span.

2. Warranty also includes installation and finishing that may be required due

to repair or replacement of defective doors.

3. Warranty Period for Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain flush wood doors indicated to be blueprint matched with paneling from single manufacturer.

2.2 FLUSH WOOD DOORS AND FRAMES, GENERAL

A. Quality Standard: In addition to requirements specified, comply with AWI/AWMAC/WI's "Architectural Woodwork Standards."

2.3 SOLID-CORE FIVE-PLY FLUSH WOOD VENEER-FACED DOORS AND TRANSOM PANELS FOR TRANSPARENT FINISH

A. Interior Doors, Solid-Core Five-Ply Veneer-Faced:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Forte Opening Solutions
    b. Oshkosh Door Company
    c. VT Industries, Inc.

2. Performance Grade: ANSI/WDMA I.S. 1A Extra Heavy Duty.

3. ANSI/WDMA I.S. 1A Quality Grade: Premium.
4. Architectural Woodwork Standards Quality Grade: Premium.
5. Faces: Single-ply wood veneer not less than **1/50 inch** thick.

    a. Species: White oak.
    b. Cut: Plain sliced (flat sliced).
    c. Match between Veneer Leaves: Book match.
    d. Assembly of Veneer Leaves on Door Faces: Center-balance match.

    e. Room Match:

        1) Match door faces within each separate room or area of building. Corridor-door faces do not need to match where they are separated by 20 ft. or more.
        2) Provide door faces of compatible color and grain within each separate room or area of building.

6. Exposed Vertical and Top Edges: Same species as faces - Architectural Woodwork Standards edge Type A.

7. Core for Non-Fire-Rated Doors:

   a. Structural Composite Lumber:

      1) Screw Withdrawal, Door Face: 550 lbf in accordance with WDMA T.M. 10.
      2) Screw Withdrawal, Vertical Door Edge: 550 lbf in accordance with WDMA T.M. 10.

8. Construction: Five plies, hot-pressed bonded (vertical and horizontal edging is bonded to core), with entire unit abrasive planed before veneering.

2.4 LIGHT FRAMES AND LOUVERS

A. Wood Beads for Light Openings in Wood Doors: Provide manufacturer's standard wood beads unless otherwise indicated.

1. Wood Species: Same species as door faces.
2. Profile: Manufacturer's standard shape.

2.5 FABRICATION

A. Factory fit doors to suit frame-opening sizes indicated.

1. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.
2. Comply with NFPA 80 requirements for fire-rated doors.

B. Factory machine doors for hardware that is not surface applied.

1. Locate hardware to comply with DHI-TDH-007.
2. Comply with final hardware schedules, door frame Shop Drawings, ANSI/BHMA-156.115-W, and hardware templates.
3. Coordinate with hardware mortises in metal frames, to verify dimensions and alignment before factory machining.
4. For doors scheduled to receive electrified locksets, provide factory-installed raceway and wiring to accommodate specified hardware.

C. Openings: Factory cut and trim openings through doors.

1. Light Openings: Trim openings with moldings of material and profile indicated.
2. Glazing: Factory install glazing in doors indicated to be factory finished. Comply with applicable requirements in Section 088000 "Glazing."

2.6 FACTORY FINISHING

A. Comply with referenced quality standard for factory finishing.

1. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
2. Finish faces, all four edges, edges of cutouts, and mortises.
3. Stains and fillers may be omitted on top and bottom edges, edges of cutouts, and mortises.

B. Factory finish doors where indicated in schedules or on Drawings as factory finished.

C. Transparent Finish:

1. ANSI/WDMA I.S. 1A Grade: Premium.

a. TR-4 Conversion Varnish.
b. TR-6 Catalyzed Polyurethane.
c. TR-8 UV Cured Acrylated Polyester/Urethane.

2. Staining: As selected by Architect from manufacturer's full range.
3. Sheen: Satin.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine doors and installed door frames, with Installer present, before hanging doors.

1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
2. Reject doors with defects.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF FLUSH WOOD DOORS AND TRANSOM PANELS

A. Hardware: For installation, see Section 087111 "Door Hardware (Descriptive Specification)."

B. Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.

C. Job-Fitted Doors:

1. Align and fit doors in frames with uniform clearances and bevels as indicated below.

    a. Do not trim stiles and rails in excess of limits set by manufacturer or permitted for fire-rated doors.

2. Machine doors for hardware.
3. Seal edges of doors, edges of cutouts, and mortises after fitting and machining.
4. Clearances:

    a. Provide **1/8 inch** at heads, jambs, and between pairs of doors.
    b. Provide **1/8 inch** from bottom of door to top of decorative floor finish or covering unless otherwise indicated on Drawings.
    c. Where threshold is shown or scheduled, provide **1/4 inch** from bottom of door to top of threshold unless otherwise indicated.

5. Bevel non-fire-rated doors **1/8 inch in 2 inches** at lock and hinge edges.

D. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.3 FIELD QUALITY CONTROL

A. Egress-Door Acceptance Testing: Test and inspect egress doors in accordance with NFPA 101.

B. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

C. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

D. Inspection Report: Prepared and submitted in writing to Architect and Contractor within 24 hours after testing.

3.4 ADJUSTING

A. Operation: Rehang or replace doors that do not swing or operate freely.

B. Factory Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 08 14 16

SECTION 08 31 13
ACCESS DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Flush access doors with exposed flanges.
2. Flush access doors with concealed flanges.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

B. Product Schedule: For access doors and frames. Use same designations indicated on Drawings.

1.3 CLOSEOUT SUBMITTALS

A. Record Documents: For fire-rated doors, list of applicable room name and number in which access door is located.

PART 2 - PRODUCTS

2.1 ACCESS DOORS AND FRAMES

A. Flush Access Doors with Exposed Flanges:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. ACUDOR Products, Inc
b. Babcock-Davis
c. Best Access Doors

2. Description: Face of door flush with frame, with exposed flange and concealed hinge.

3. Locations: Wall in unisex bathroom 104A or 104B.
4. Door Size: 14" by 14" or as required for plumbing access.

5. Uncoated Steel Sheet for Door: Insert thickness, factory primed.

6. Frame Material: Same material, thickness, and finish as door.
7. Latch and Lock: Cam latch, screwdriver operated.

B. Flush Access Doors with Concealed Flanges:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. ACUDOR Products, Inc
   b. Babcock-Davis
   c. Best Access Doors

2. Description: Face of door flush with frame; with concealed flange for gypsum board installation and concealed hinge.

3. Locations: Wall in breakroom behind bathroom.
4. Door Size: 12" by 14" or as needed for access to plumbing..
5. Uncoated Steel Sheet for Door: Nominal 0.060 inch, 16 gage, factory primed.

6. Frame Material: Same material and thickness as door.
7. Latch and Lock: Cam latch, screwdriver operated.

2.2 MATERIALS

A. Steel Plates, Shapes, and Bars: ASTM A36/A36M.

B. Steel Sheet: Uncoated or electrolytic zinc coated, ASTM A879/A879M, with cold-rolled steel sheet substrate complying with ASTM A1008/A1008M, Commercial Steel (CS), exposed.

C. Frame Anchors: Same material as door face.

D. Inserts, Bolts, and Anchor Fasteners: Hot-dip galvanized steel in accordance with ASTM A153/A153M or ASTM F2329/F2329M.

2.3 FABRICATION

A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.

B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.

C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish mounting holes, attachment devices, and fasteners of type required to secure access doors to types of supports indicated.

1. For concealed flanges with drywall bead, provide edge trim for gypsum panels securely attached to perimeter of frames.
2. For concealed flanges with plaster bead for full-bed plaster applications, provide zinc-coated expanded-metal lath and exposed casing bead welded to perimeter of frames.

D. Latch and Lock Hardware:

1. Quantity: Furnish number of latches and locks required to hold doors tightly closed.

2.4 FINISHES

A. Comply with NAAMM/NOMMA AMP 500 for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

D. Painted Finishes: Comply with coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.

1. Factory Primed: Apply manufacturer's standard, lead- and chromate-free, universal primer immediately after surface preparation and pretreatment.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF ACCESS DOORS AND FRAMES

A. Comply with manufacturer's written instructions for installing access doors and

frames.

3.3 FIELD QUALITY CONTROL

A. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

B. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

3.4 ADJUSTING

A. Adjust doors and hardware, after installation, for proper operation.

END OF SECTION 08 31 13

SECTION 08 41 13
ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Aluminum-framed entrance and storefront systems.

1.2 ACTION SUBMITTALS

A. Product Data: For each specified system and assembly, including components and accessories.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include operating characteristics, electrical characteristics, and furnished accessories.

B. Shop Drawings:

1. Include plans, elevations, sections, full-size details, and attachments to other work.
2. Include details of provisions for assembly expansion and contraction and for draining moisture occurring within the assembly to the exterior.
3. Include full-size isometric details of each type of vertical-to-horizontal intersection of aluminum-framed entrance and storefront systems, showing the following:

    a. Joinery, including concealed welds.
    b. Anchorage.
    c. Expansion provisions.
    d. Glazing.
    e. Flashing and drainage.

4. Include connection to and continuity with adjacent thermal, weather, air, and vapor barriers.
5. Include point-to-point wiring diagrams showing the following:

    a. Power requirements for each electrically operated door hardware.
    b. Location and types of switches, signal device, conduit sizes, and number and size of wires.

6. Signed and sealed by the qualified professional engineer responsible for their preparation.

C. Entrance Door Hardware Schedule: Prepared by or under supervision of supplier, detailing fabrication and assembly of entrance door hardware, as well as procedures and diagrams. Coordinate final entrance door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of entrance door hardware.

1.3 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For aluminum-framed entrance and storefront systems.

B. Maintenance Data for Structural Sealant: For structural-sealant-glazed storefront. Include ASTM C1401 recommendations for post-installation-phase quality-control program.

C. Warranty Documentation: For specified special warranties.

1.4 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of aluminum-framed entrance and storefront systems that fail in materials or workmanship within specified warranty period.

1. Failures under design conditions specified in performance requirements.

a. Breakage or loss of glass.
b. Permanent deformation of components or assemblies.

2. Warranty Period: 10 years from date of Substantial Completion.

B. Special Finish Warranty, Anodized Finishes: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of anodized finishes within specified warranty period.

1. Deterioration includes, but is not limited to, the following:

a. Color fading more than 5 Delta E units when tested in accordance with ASTM D 2244.
b. Chalking in excess of a No. 8 rating when tested in accordance with ASTM D 4214.
c. Cracking, peeling, or chipping.

2. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design aluminum-framed entrance and storefront systems.

B. General Performance: Comply with performance requirements specified, as determined by testing of aluminum-framed entrance and storefront systems representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.

1. Aluminum-framed entrance and storefront systems to withstand movements of supporting structure, including, but not limited to, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
2. Failure also includes the following:

    a. Thermal stresses transferring to building structure.
    b. Glass breakage.
    c. Noise or vibration created by wind and thermal and structural movements.
    d. Loosening or weakening of fasteners, attachments, and other components.
    e. Failure of operating units.

C. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.
2. Thermal Cycling: No buckling; stress on glass; sealant failure; excess stress on framing, anchors, and fasteners; or reduction of performance when tested in accordance with AAMA 501.5.

    a. High Exterior Ambient-Air Temperature: That which produces an exterior metal-surface temperature of 180 deg F.
    b. Low Exterior Ambient-Air Temperature: 0 deg F.
    c. Interior Ambient-Air Temperature at High Exterior Ambient-Air Temperature: 75 deg F.
    d. Interior Ambient-Air Temperature at Low Exterior Ambient-Air Temperature: 70 deg F.

D. Water Penetration under Static Pressure: Test in accordance with ASTM E331 as follows:

1. No evidence of water penetration through fixed glazing and framing areas, including entrance doors, when tested in accordance with a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than .

E. Water Penetration under Dynamic Pressure: Test in accordance with AAMA 501.1 as follows:

1. No evidence of water penetration through fixed glazing and framing areas when tested at dynamic pressure equal to 20 percent of positive wind-load design pressure, but not less than 8 lbf/sq. ftt..
2. Maximum Water Leakage: In accordance with AAMA 501.1. Water leakage does not include water controlled by flashing and gutters, or water that is drained to exterior.

F. Energy Performance: Certified and labeled by manufacturer for energy performance as follows:

1. Thermal Transmittance (U-factor):

a. Fixed Glazing and Framing Areas: U-factor for the system of not more than 0.38 Btu/sq. ft. x h x deg F as determined in accordance with ANSI/NFRC 100.

2. Air Leakage:

a. Fixed Glazing and Framing Areas: Air leakage for the system of not more than 0.06 cfm/sq. ft. at a static-air-pressure differential of 6.24 lbf/sq. ft. when tested in accordance with ASTM E283/E283M.
b. Entrance Doors: Air leakage of not more than 1.0 cfm/sq. ft. at a static-air-pressure differential of **1.57 lbf/sq. ft.** when tested in accordance with ASTM E283/E283M.

2.2 ALUMINUM-FRAMED ENTRANCE AND STOREFRONT SYSTEMS

A. Aluminum-Framed Entrance and Storefront System:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Kawneer Company, Inc.; 451T and AA425 Thermal Entrance or comparable product by one of the following:

a. EFCO Corporation; Architectural Metals; Apogee Enterprises, Inc.
b. Kawneer Company, Inc.; Arconic Corporation
c. YKK AP America Inc.

2. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.

a. Exterior Framing Construction: Thermally broken.
b. Glazing System: Retained mechanically with gaskets on four sides.
c. Glazing Plane: Front-set.
d. Finish: Clear anodic finish.
e. Fabrication Method: Field-fabricated stick system.
f. Aluminum: Alloy and temper recommended by manufacturer for type

of use and finish indicated.

g. Steel Reinforcement: As required by manufacturer.

3. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not integral, where framing abuts adjacent construction.
4. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

5. Entrance Doors: Manufacturer's standard glazed entrance doors for manual-swing or power operation.

   a. Door Construction: 1-3/4-inch overall thickness, with minimum 0.125-inch- thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.

      1) Thermal Construction: Thermally broken.

   b. Door Design: As indicated on Drawings.
   c. Glazing Stops and Gaskets: Square, snap-on, extruded-aluminum stops and preformed gaskets.

      1) Provide nonremovable glazing stops on outside of door.

   d. Finish: Match adjacent storefront framing finish.

6. Glazing: Comply with Section 088000 "Glazing."
7. Glazing Gaskets: Manufacturer's standard sealed-corner pressure-glazing system of black, resilient elastomeric glazing gaskets, setting blocks, and shims or spacers.

2.3 ACCESSORIES

A. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

   1. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
   2. Reinforce members as required to receive fastener threads.
   3. Use exposed fasteners with countersunk Phillips screw heads, fabricated from 300 series stainless steel.

B. Anchors: Three-way adjustable anchors with minimum adjustment of 1 inch that accommodate fabrication and installation tolerances in material and finish compatible with adjoining materials and recommended by manufacturer.

1. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A123/A123M or ASTM A153/A153M requirements.

C. Concealed Flashing: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding flashing compatible with adjacent materials.

D. Bituminous Paint: Cold-applied asphalt-mastic paint containing no asbestos, formulated for **30-mil** thickness per coat.

E. Joint Sealants and Backings: Provide joint sealants, backings, and other related materials in accordance with Section 079200 "Joint Sealants."

2.4 MATERIALS

A. Sheet and Plate: ASTM B209/B209M.

B. Extruded Bars, Rods, Profiles, and Tubes: **ASTM B221**.

C. Structural Profiles: ASTM B308/B308M.

2.5 FABRICATION

A. Form or extrude aluminum shapes before finishing.

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Physical and thermal isolation of glazing from framing members.
4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
5. Provisions for field replacement of glazing from exterior.
6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.

D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.

E. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.

1. At interior and exterior doors, provide compression weather stripping at fixed stops.

F. Entrance Doors: Reinforce doors as required for installing entrance door hardware.

1. At pairs of exterior doors, provide sliding-type weather stripping retained in adjustable strip and mortised into door edge.
2. At exterior doors, provide weather sweeps applied to door bottoms.

G. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.

H. After fabrication, clearly mark components to identify their locations in Project in accordance with Shop Drawings.

2.6 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF ALUMINUM-FRAMED ENTRANCE AND STOREFRONT SYSTEMS

A. General: Install aluminum-framed entrance and storefront systems in accordance with manufacturer's written instructions.

1. Do not install damaged components.
2. Fit frame joints to produce hairline joints free of burrs and distortion. Rigidly secure nonmovement joints. Seal perimeter and other joints watertight unless otherwise indicated.
3. Install components plumb and true in alignment with established lines and grades.

B. Anchorage:

1. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.

C. Metal Protection:

1. Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with materials recommended by manufacturer for this purpose or installing nonconductive spacers.
2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.

D. Joint Sealants and Backings: Install in accordance with Section 079200 "Joint Sealants."

1. Set continuous sill members and flashing in full sealant bed.
2. Seal perimeter of framing members with sealant.

E. Entrance Doors: Install entrance doors to produce smooth operation and tight fit at contact points.

1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.
2. Field-Installed Entrance Door Hardware: Install surface-mounted entrance door hardware in accordance with entrance door hardware manufacturers' written instructions using concealed fasteners to greatest extent possible.

F. Glazing: Install glazing as specified in Section 088000 "Glazing."

3.3 ERECTION TOLERANCES

A. Install aluminum-framed entrance and storefront systems to comply with the following maximum tolerances:

1. Plumb: **1/8 inch in 10 ft.**; **1/4 inch in 40 ft.**.
2. Level: **1/8 inch in 20 ft.**; **1/4 inch in 40 ft.**.
3. Alignment:

   a. Where surfaces abut in line or are separated by reveal or protruding element up to **1/2 inch** wide, limit offset from true alignment to **1/16 inch**.
   b. Where surfaces are separated by reveal or protruding element from **1/2 to 1 inch** wide, limit offset from true alignment to **1/8 inch**.
   c. Where surfaces are separated by reveal or protruding element of **1 inch** wide or more, limit offset from true alignment to **1/4 inch**.

4. Location: Limit variation from plane to **1/8 inch in 12 ft.**; **1/2 inch** over total length.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests.

B. Tests: Perform the following tests on representative areas of aluminum-framed entrance and storefront systems.

1. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect to be tested in accordance with AAMA 501.2 and to not evidence water penetration.

   a. Perform a minimum of two tests in areas as directed by Architect.
   b. Perform tests in each test area as directed by Architect. Perform at least three tests, prior to 10, 35, and 70 percent completion.

2. Air Leakage: ASTM E783 at 1.5 times the rate specified for laboratory testing in "Performance Requirements" Article but not more than **0.09 cfm/sq. ft.** at a static-air-pressure differential of **1.57 lbf/sq. ft.**.

   a. Perform a minimum of two tests in areas as directed by Architect.
   b. Perform tests in each test area as directed by Architect. Perform at least three tests, prior to 10, 35, and 70 percent completion.

3. Water Penetration: ASTM E1105 at a minimum uniform static-air-pressure differential of 0.67 times the static-air-pressure differential specified for laboratory testing in "Performance Requirements" Article, but not less than **6.24 lbf/sq. ft.**, and to not evidence water penetration.

C. Inspections:

1. Egress Door Inspections: Inspect each aluminum-framed entrance door equipped with panic hardware, located in an exit enclosure, electrically controlled, and equipped with special locking arrangements, in accordance with NFPA 101.

D. Aluminum-framed entrance and storefront systems will be considered defective if they do not pass tests and inspections.

E. Prepare test and inspection reports.

3.5 ADJUSTING

A. Adjust hardware and operable components to function smoothly, and lubricate as recommended in writing by manufacturer.

END OF SECTION 08 41 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 08 80 00
GLAZING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Monolithic glass.
2. Insulating glass units.
3. Glazing tapes.
4. Miscellaneous glazing materials.

B. Related Requirements:

1. Section 084126 "All-Glass Entrances and Storefronts."

1.2 DEFINITIONS

A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.

B. Glass Thicknesses: Indicated by thickness designations in millimeters in accordance with ASTM C1036.

C. IBC: International Building Code.

D. Interspace: Space between lites of an insulating-glass unit.

1.3 COORDINATION

A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances to achieve proper safety margins for glazing retention under each design load case, load case combination, and service condition.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials in accordance with manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

B. Comply with insulating-glass manufacturer's written instructions for venting and sealing units to avoid hermetic seal ruptures due to altitude change.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.

1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or are below **40 deg F**.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Source Limitations for Glass: Obtain glass from single source from single manufacturer.

B. Source Limitations for Glazing Accessories: For each product and installation method, obtain from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. General: Installed glazing systems to withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.

B. Safety Glazing: Where safety glazing is indicated, provide glazing that complies with 16 CFR 1201, Category II.

C. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:

1. For monolithic-glass lites, properties are based on units with lites of thickness indicated.

2. For insulating-glass units, properties are based on units of thickness indicated for overall unit and for each lite.
3. U-Factors: Center-of-glazing values, in accordance with NFRC 100 and based on most current non-beta version of LBL's WINDOW computer program, expressed as **Btu/sq. ft. x h x deg F**.
4. SHGC and Visible Transmittance: Center-of-glazing values, in accordance with NFRC 200 and based on most current non-beta version of LBL's WINDOW computer program.
5. Visible Reflectance: Center-of-glazing values, in accordance with NFRC 300.

2.3 GLASS, GENERAL

A. Glazing Publications: Comply with written instructions of glass product manufacturers and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.

1. AAMA Publications: AAMA GDSG-1 and AAMA TIR A7.

2. IGMA Publication for Insulating Glass: IGMA TM-3000.

B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction. Label indicates manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.

C. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than thickness indicated.

1. Minimum Glass Thickness for Exterior Lites: 6 mm.
2. Thickness of Tinted Glass: Provide same thickness for each tint color indicated throughout Project.

D. Strength: Where annealed float glass is indicated, provide annealed float glass, heat-strengthened float glass, or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened float glass is indicated, provide heat-strengthened float glass or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where fully tempered float glass is indicated, provide fully tempered float glass.

2.4 MONOLITHIC GLASS

A. Fully Tempered Float Glass : ASTM C1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.

B. Reflective- and Low-E-Coated Vision Glass: ASTM C1376.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Guardian Glass LLC
b. Pilkington North America; NSG Group
c. Vitro Architectural Glass

2.5 INSULATING GLASS UNITS

A. Insulating Glass Unit : Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified in accordance with ASTM E2190.

1. Sealing System: Dual seal, with manufacturer's standard primary and secondary sealants.

2. Desiccant: Molecular sieve or silica gel, or a blend of both.

B. Accessories:

2.6 GLAZING SEALANTS

A. General:

1. Compatibility: Compatible with one another and with other materials they contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
3. Colors of Exposed Glazing Sealants: As indicated by manufacturer's designations.

2.7 GLAZING TAPES

A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C1281

and AAMA 800 for products indicated below:

1. AAMA 804.3 tape, where indicated.
2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

B. Expanded Cellular Glazing Tapes: Closed-cell, PVC or acrylic foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:

1. AAMA 810.1, Type 1, for glazing applications in which tape acts as primary sealant.
2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.8 MISCELLANEOUS GLAZING MATERIALS

A. General: Provide products of material, size, and shape complying with referenced glazing standard, recommended in writing by manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.

B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

C. Setting Blocks:

1. Type: EPDM with Shore A durometer hardness of 85, plus or minus 5.
2. Type recommended in writing by sealant or glass manufacturer.

D. Spacers:

1. Type: Neoprene blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
2. Type recommended in writing by sealant or glass manufacturer.

E. Edge Blocks:

1. Type: EPDM with Shore A durometer hardness per manufacturer's written instructions.
2. Type recommended in writing by sealant or glass manufacturer.

F. Cylindrical Glazing Sealant Backing: ASTM C1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

2.9 FABRICATION OF GLAZING UNITS

A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

1. Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.

a. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:

1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
2. Presence and functioning of weep systems.
3. Minimum required face and edge clearances.
4. Effective sealing between joints of glass-framing members.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that leave visible marks in the completed Work.

3.3 GLAZING, GENERAL

A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.

B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when

installed, could weaken glass, impair performance, or impair appearance.

C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

F. Provide spacers for glass lites where length plus width is larger than **50 inches**.

1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
2. Provide **1/8-inch-** minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.

G. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and in accordance with requirements in referenced glazing publications.

H. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

I. Set glass lites with proper orientation so that coatings face exterior or interior as specified.

J. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.

K. Square cut wedge-shaped gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away; seal corner joints and butt joints with sealant recommended in writing by gasket manufacturer.

3.4 INSTALLATION OF GLAZING TAPES

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.

C. Cover vertical framing joints by applying tapes to heads and sills first, then to jambs. Cover horizontal framing joints by applying tapes to jambs, then to heads and sills.

D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.

E. Do not remove release paper from tape until right before each glazing unit is installed.

F. Center glass lites in openings on setting blocks, and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

3.5 INSTALLATION OF GLAZING GASKET (DRY)

A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.

C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.

E. Install gaskets so they protrude past face of glazing stops.

3.6 INSTALLATION OF GLAZING SEALANT

A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.

C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

3.7 CLEANING

A. Immediately after installation, remove nonpermanent labels and clean surfaces.

3.8 PROTECTION

A. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.

1. If, despite such protection, contaminating substances do contact with glass, remove substances immediately as recommended in writing by glass manufacturer. Remove and replace glass that cannot be cleaned without damage to coatings.

B. Remove and replace glass that is damaged during construction period.

3.9 MONOLITHIC GLASS SCHEDULE

A. Clear Glass Type: Fully tempered float glass .

1. Minimum Thickness: 1/4 inch.
2. Safety glazing required.

B. Low-Iron Glass Type: Fully tempered float glass .

1. Minimum Thickness: 1/4 inch.
2. Safety glazing required.

3.10 INSULATING GLASS SCHEDULE

A. Low-E-Coated, Tinted Insulating Glass Type: .

1. Overall Unit Thickness: 1 inch.
2. Minimum Thickness of Each Glass Lite: 1/4 inch.
3. Outdoor Lite: Tinted fully tempered float glass.
4. Tint Color: Color to match existing glazing.
5. Interspace Content: Air.
6. Indoor Lite: Clear fully tempered float glass.

7. Low-E Coating: Pyrolytic or sputtered on second or third surface.

END OF SECTION 08 80 00

SECTION 087100

DOOR HARDWARE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes commercial door hardware for the following:

1. Swinging doors.

B. Door hardware includes, but is not necessarily limited to, the following:

1. Mechanical door hardware.
2. Electromechanical door hardware.
3. Cylinders specified for doors in other sections.

C. Related Sections:

1. Division 01 Section "General Conditions”.
2. Division 06 Section “Rough Carpentry”.
3. Division 06 Section “Finish Carpentry”.
4. Division 08 Section “Operations and Maintenance”.
5. Division 08 Section “Hollow Metal Doors and Frames”.
6. Division 08 Section “Flush Wood Doors”.
7. Division 08 Section “Aluminum-Framed Entrances and Storefronts”.
8. Division 26 Section "Electrical”

D. Codes and References: Comply with the version adopted by the Authority Having Jurisdiction.

1. ANSI A117.1 - Accessible and Usable Buildings and Facilities.
2. ICC/IBC - International Building Code.
3. NFPA 70 - National Electrical Code.
4. NFPA 80 - Fire Doors and Windows.
5. NFPA 101 - Life Safety Code.
6. NFPA 105 - Installation of Smoke Door Assemblies.
7. State Building Codes, Local Amendments.

E. Standards: All hardware specified herein shall comply with the following industry standards as applicable. Any undated reference to a standard shall be interpreted as referring to the latest edition of that standard:

1. ANSI/BHMA Certified Product Standards - A156 Series.
2. UL10C - Positive Pressure Fire Tests of Door Assemblies.
3. ANSI/UL 294 - Access Control System Units.
4. UL 305 - Panic Hardware.
5. ANSI/UL 437- Key Locks.

1.3 SUBMITTALS

A. Product Data: Manufacturer's product data sheets including installation details, material descriptions, dimensions of individual components and profiles, operational descriptions and finishes.

B. Door Hardware Schedule: Prepared by or under the supervision of supplier, detailing, fabrication and assembly of door hardware, as well as procedures and diagrams. Coordinate the final Door Hardware Schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.

1. Format: Comply with scheduling sequence and vertical format in DHI's "Sequence and Format for the Hardware Schedule."
2. Organization: Organize the Door Hardware Schedule into door hardware sets indicating complete designations of every item required for each door or opening. Organize door hardware sets in same order as in the Door Hardware Sets at the end of Part 3. Submittals that do not follow the same format and order as the Door Hardware Sets will be rejected and subject to resubmission.
3. Content: Include the following information:

    a. Type, style, function, size, label, hand, and finish of each door hardware item.
    b. Manufacturer of each item.
    c. Fastenings and other pertinent information.
    d. Location of door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
    e. Explanation of abbreviations, symbols, and codes contained in schedule.
    f. Mounting locations for door hardware.
    g. Door and frame sizes and materials.
    h. Warranty information for each product.

4. Submittal Sequence: Submit the final Door Hardware Schedule at earliest possible date, particularly where approval of the Door Hardware Schedule must precede fabrication of other work that is critical in the Project construction schedule. Include Product Data, Samples, Shop Drawings of other work affected by door hardware, and other information essential to the coordinated review of the Door Hardware Schedule.

C. Shop Drawings: Details of electrified access control hardware indicating the following:

1. Wiring Diagrams: Upon receipt of approved schedules, submit detailed system wiring diagrams for power, signaling, monitoring, communication, and control of the access control system electrified hardware. Differentiate between manufacturer-installed and field-installed wiring. Include the following:

    a. Elevation diagram of each unique access controlled opening showing location and interconnection of major system components with respect to their placement in the respective door openings.
    b. Complete (risers, point-to-point) access control system block wiring diagrams.
    c. Wiring instructions for each electronic component scheduled herein.

2. Electrical Coordination: Coordinate with related sections the voltages and wiring details required at electrically controlled and operated hardware openings.

D. Keying Schedule: After a keying meeting with the owner has taken place prepare a separate keying schedule detailing final instructions. Submit the keying schedule in electronic format. Include keying system explanation, door numbers, key set symbols, hardware set numbers and special instructions. Owner must approve submitted keying schedule prior to the ordering of permanent cylinders/cores.

E. Informational Submittals:

1. Product Test Reports: Indicating compliance with cycle testing requirements, based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified independent testing agency.

1.4 CLOSEOUT SUBMITTALS

A. Operating and Maintenance Manuals: Provide manufacturers operating and maintenance manuals for each item comprising the complete door hardware installation in quantity as required in Division 01, Closeout Procedures.

1.5 QUALITY ASSURANCE

A. Manufacturers Qualifications: Engage qualified manufacturers with a minimum 5 years of documented experience in producing hardware and equipment similar to that indicated for this Project and that have a proven record of successful in-service performance.

B. Certified Products: Where specified, products must maintain a current listing in the Builders Hardware Manufacturers Association (BHMA) Certified Products Directory (CPD).

C. Installer Qualifications: A minimum 3 years documented experience installing both standard and electrified door hardware similar in material, design, and extent to that indicated for this Project and whose work has resulted in construction with a record of successful in-service performance.

D. Door Hardware Supplier Qualifications: Experienced commercial door hardware distributors with a minimum 5 years documented experience supplying both mechanical and electromechanical hardware installations comparable in material, design, and extent to that indicated for this Project. Supplier recognized as a factory direct distributor by the manufacturers of the primary materials with a warehousing facility in Project's vicinity. Supplier to have on staff a certified Architectural Hardware Consultant (AHC) available during the course of the Work to consult with Contractor, Architect, and Owner concerning both standard and electromechanical door hardware and keying.

E. Source Limitations: Obtain each type and variety of door hardware specified in this section from a single source unless otherwise indicated.

1. Electrified modifications or enhancements made to a source manufacturer's product line by a secondary or third party source will not be accepted.
2. Provide electromechanical door hardware from the same manufacturer as mechanical door hardware, unless otherwise indicated.

F. Each unit to bear third party permanent label indicating compliance with the referenced testing standards.

G. Keying Conference: Conduct conference to comply with requirements in Division 01 Section "Project Meetings." Keying conference to incorporate the following criteria into the final keying schedule document:

1. Function of building, purpose of each area and degree of security required.
2. Plans for existing and future key system expansion.
3. Requirements for key control storage and software.
4. Installation of permanent keys, cylinder cores and software.
5. Address and requirements for delivery of keys.

H. Pre-Submittal Conference: Conduct coordination conference in compliance with requirements in Division 01 Section "Project Meetings" with attendance by representatives of Supplier(s), Installer(s), and Contractor(s) to review proper methods and the procedures for receiving, handling, and installing door hardware.

1. Prior to installation of door hardware, conduct a project specific training meeting to instruct the installing contractors' personnel on the proper installation and adjustment of their respective products. Product training to be attended by installers of door hardware (including electromechanical hardware) for aluminum, hollow metal and wood doors. Training will include the use of installation manuals, hardware schedules, templates and physical product samples as required.
2. Inspect and discuss electrical roughing-in, power supply connections, and other preparatory work performed by other trades.
3. Review sequence of operation narratives for each unique access controlled opening.
4. Review and finalize construction schedule and verify availability of materials.

5. Review the required inspecting, testing, commissioning, and demonstration procedures

I. At completion of installation, provide written documentation that components were applied according to manufacturer's instructions and recommendations and according to approved schedule.

1.6 DELIVERY, STORAGE AND HANDLING

A. Inventory door hardware on receipt and provide secure lock-up and shelving for door hardware delivered to Project site. Do not store electronic access control hardware, software or accessories at Project site without prior authorization.

B. Tag each item or package separately with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.

C. Deliver, as applicable, permanent keys, cylinders, cores, access control credentials, software and related accessories directly to Owner via registered mail or overnight package service. Instructions for delivery to the Owner shall be established at the "Keying Conference".

1.7 COORDINATION

A. Templates: Obtain and distribute to the parties involved templates for doors, frames, and other work specified to be factory prepared for installing standard and electrified hardware. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing hardware to comply with indicated requirements.

B. Door and Frame Preparation: Doors and corresponding frames are to be prepared, reinforced and pre-wired (if applicable) to receive the installation of the specified electrified, monitoring, signaling and access control system hardware without additional in-field modifications.

1.8 WARRANTY

A. General Warranty: Reference Division 01, General Requirements. Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

B. Warranty Period: Written warranty, executed by manufacturer(s), agreeing to repair or replace components of standard and electrified door hardware that fails in materials or workmanship within specified warranty period after final acceptance by the Owner. Failures include, but are not limited to, the following:

1. Structural failures including excessive deflection, cracking, or breakage.

2. Faulty operation of the hardware.
3. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
4. Electrical component defects and failures within the systems operation.

C. Warranty Period: Unless otherwise indicated, warranty shall be one year from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Hardware shall not have any visible manufacturer names on exposed materials, except cylinders, when the door is in a closed position.

2.2 BUTT HINGES

A. Hinges: ANSI/BHMA A156.1 butt hinges with number of hinge knuckles and other options as specified in the Door Hardware Sets.

1. Quantity: Provide the following hinge quantity:

   a. Two Hinges: For doors with heights up to 60 inches.
   b. Three Hinges: For doors with heights 61 to 90 inches.
   c. Four Hinges: For doors with heights 91 to 120 inches.
   d. For doors with heights more than 120 inches, provide 4 hinges, plus 1 hinge for every 30 inches of door height greater than 120 inches.

2. Hinge Size: Provide the following, unless otherwise indicated, with hinge widths sized for door thickness and clearances required:

   a. Widths up to 3’0”: 4-1/2” standard or heavy weight as specified.
   b. Sizes from 3’1” to 4’0”: 5” standard or heavy weight as specified.

3. Hinge Weight and Base Material: Unless otherwise indicated, provide the following:

   a. Exterior Doors: Heavy weight, non-ferrous, ball bearing or oil impregnated bearing hinges unless Hardware Sets indicate standard weight.
   b. Interior Doors: Standard weight, steel, ball bearing or oil impregnated bearing hinges unless Hardware Sets indicate heavy weight.

4. Hinge Options: Comply with the following:

   a. Non-removable Pins: With the exception of electric through wire hinges, provide set screw in hinge barrel that, when tightened into a groove in hinge pin, prevents removal of pin while door is closed; for all out-swinging lockable doors.

5. Manufacturers:

    a. Hager Companies (HA) - BB Series, 5-knuckle.
    b. McKinney (MK) - TA/T4A Series, 5-knuckle.
    c. dormakaba BEST (ST) - F/FBB Series, 5-knuckle.

2.3 CONTINUOUS HINGES

A. Continuous Geared Hinges: ANSI/BHMA A156.26 Grade 1-600 continuous geared hinge. with minimum 0.120-inch thick extruded 6063-T6 aluminum alloy hinge leaves and a minimum overall width of 4 inches. Hinges are non-handed, reversible and fabricated to template screw locations. Factory trim hinges to suit door height and prepare for electrical cut-outs.

1. Manufacturers:.

    a. Hager Companies (HA).
    b. Pemko (PE).
    c. dormakaba BEST (ST).

2.4 CYLINDERS AND KEYING

A. General: Cylinder manufacturer to have minimum (10) years experience designing secured master key systems and have on record a published security keying system policy.

1. Manufacturers:

    a. Match Existing, Field Verify.

B. Cylinder Types: Original manufacturer cylinders able to supply the following cylinder formats and types:

1. Threaded mortise cylinders with rings and cams to suit hardware application.
2. Rim cylinders with back plate, flat-type vertical or horizontal tailpiece, and raised trim ring.
3. Bored or cylindrical lock cylinders with tailpieces as required to suit locks.
4. Tubular deadlocks and other auxiliary locks.
5. Mortise and rim cylinder collars to be solid and recessed to allow the cylinder face to be flush and be free spinning with matching finishes.
6. Keyway: Manufacturer’s Standard.

C. Small Format Interchangeable Cores: Provide small format interchangeable cores (SFIC) as specified, core insert, removable by use of a special key; usable with other manufacturers' cylinders.

D. Keying System: Each type of lock and cylinders to be factory keyed.

1. Supplier shall conduct a "Keying Conference" to define and document keying system instructions and requirements.
2. Furnish factory cut, nickel-silver large bow permanently inscribed with a visual key control number as directed by Owner.
3. Existing System: Field verify and key cylinders to match Owner's existing system.

E. Key Quantity: Provide the following minimum number of keys:

1. Change Keys per Cylinder: Two (2)
2. Master Keys (per Master Key Level/Group): Five (5).
3. Construction Keys (where required): Ten (10).

F. Construction Keying: Provide temporary keyed construction cores.

G. Key Registration List (Bitting List):

1. Provide keying transcript list to Owner's representative in the proper format for importing into key control software.
2. Provide transcript list in writing or electronic file as directed by the Owner.

2.5 MORTISE LOCKS AND LATCHING DEVICES

A. Mortise Locksets, Grade 1 (Heavy Duty): Provide ANSI/BHMA A156.13, Series 1000, Operational Grade 1 Certified Products Directory (CPD) listed mortise locksets. Listed manufacturers shall meet all functions and features as specified herein.

1. Manufacturers:

a. Corbin Russwin Hardware (RU) - ML2000 Series.
b. dormakaba BEST (BE) - 45H Series.
c. Sargent Manufacturing (SA) - 8200 Series.

2.6 LOCK AND LATCH STRIKES

A. Strikes: Provide manufacturer's standard strike with strike box for each latch or lock bolt, with curved lip extended to protect frame, finished to match door hardware set, unless otherwise indicated, and as follows:

1. Flat-Lip Strikes: For locks with three-piece antifriction latchbolts, as recommended by manufacturer.
2. Extra-Long-Lip Strikes: For locks used on frames with applied wood casing trim.
3. Aluminum-Frame Strike Box: Provide manufacturer's special strike box fabricated for aluminum framing.
4. Double-lipped strikes: For locks at double acting doors. Furnish with retractable stop for rescue hardware applications.

B. Standards: Comply with the following:

1. Strikes for Mortise Locks and Latches: BHMA A156.13.

2. Strikes for Bored Locks and Latches: BHMA A156.2.
3. Strikes for Auxiliary Deadlocks: BHMA A156.36.
4. Dustproof Strikes: BHMA A156.16.

2.7 CONVENTIONAL EXIT DEVICES

A. General Requirements: All exit devices specified herein shall meet or exceed the following criteria:

1. Exit devices shall have a five-year warranty.
2. At doors not requiring a fire rating, provide devices complying with NFPA 101 and listed and labeled for "Panic Hardware" according to UL305. Provide proper fasteners as required by manufacturer including sex nuts and bolts at openings specified in the Hardware Sets.
3. Where exit devices are required on fire rated doors, provide devices complying with NFPA 80 and with UL labeling indicating "Fire Exit Hardware". Provide devices with the proper fasteners for installation as tested and listed by UL. Consult manufacturer’s catalog and template book for specific requirements.
4. Except on fire rated doors, provide exit devices with hex key dogging device to hold the pushbar and latch in a retracted position. Provide optional keyed cylinder dogging on devices where specified in Hardware Sets.
5. Devices must fit flat against the door face with no gap that permits unauthorized dogging of the push bar. The addition of filler strips is required in any case where the door light extends behind the device as in a full glass configuration.
6. Lever Operating Trim: Where exit devices require lever trim, furnish manufacturer's heavy duty escutcheon trim with threaded studs for thru-bolts.

    a. Lock Trim Design: As indicated in Hardware Sets, provide finishes and designs to match that of the specified locksets.
    b. Where function of exit device requires a cylinder, provide a cylinder (Rim or Mortise) as specified in Hardware Sets.

7. Vertical Rod Exit Devices: Where surface or concealed vertical rod exit devices are used at interior openings, provide as less bottom rod (LBR) unless otherwise indicated. Provide dust proof strikes where thermal pins are required to project into the floor.
8. Narrow Stile Applications: At doors constructed with narrow stiles, or as specified in Hardware Sets, provide devices designed for maximum 2” wide stiles.
9. Dummy Push Bar: Nonfunctioning push bar matching functional push bar.
10. Rail Sizing: Provide exit device rails factory sized for proper door width application.
11. Through Bolt Installation: For exit devices and trim as indicated in Door Hardware Sets.

B. Conventional Push Rail Exit Devices (Heavy Duty): ANSI/BHMA A156.3, Grade 1 Certified Products Directory (CPD) listed exit devices. Listed manufacturers shall meet all functions and features as specified herein.

1. Manufacturers:

a. Corbin Russwin Hardware (RU) - ED4000 / ED5000 Series.
b. Sargent Manufacturing (SA) - 80 Series.
c. Von Duprin (VD) - 35A/98 XP Series.

2.8 SURFACE DOOR CLOSERS

A. All door closers specified herein shall meet or exceed the following criteria:

1. General: Door closers to be from one manufacturer, matching in design and style, with the same type door preparations and templates regardless of application or spring size. Closers to be non-handed with full sized covers.
2. Standards: Closers to comply with UL-10C for Positive Pressure Fire Test and be U.L. listed for use of fire rated doors.
3. Size of Units: Comply with manufacturer's written recommendations for sizing of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Where closers are indicated for doors required to be accessible to the Americans with Disabilities Act, provide units complying with ANSI ICC/A117.1.
4. Closer Arms: Provide heavy duty, forged steel closer arms unless otherwise indicated in Hardware Sets.
5. Closers shall not be installed on exterior or corridor side of doors; where possible install closers on door for optimum aesthetics.
6. Closer Accessories: Provide door closer accessories including custom templates, special mounting brackets, spacers and drop plates as required for proper installation. Provide through-bolt and security type fasteners as specified in the hardware sets.

B. Door Closers, Surface Mounted (Heavy Duty): ANSI/BHMA A156.4, Grade 1 Certified Products Directory (CPD) listed surface mounted, heavy duty door closers with complete spring power adjustment, sizes 1 thru 6; and fully operational adjustable according to door size, frequency of use, and opening force. Closers to be rack and pinion type, one piece cast iron or aluminum alloy body construction, with adjustable backcheck and separate non-critical valves for closing sweep and latch speed control. Provide non-handed units standard.

1. Heavy duty surface mounted door closers shall have a 30-year warranty.

2. Manufacturers:

a. Corbin Russwin Hardware (RU) - DC6000 Series.
b. LCN Closers (LC) - 4040 Series.
c. Norton Rixson (NO) - 7500 Series.

2.9 ARCHITECTURAL TRIM AND ACCESSORIES

A. Door, Frame and Wall Protective Trim: ANSI/BHMA A156.6, protective products as specified in the hardware sets. Door protection plates shall be not more than 2" less than door width on stop side and 1” less door width on the pull side or on stop side of

pairs of doors. Listed manufacturers shall meet all functions and features as specified herein.

1. Provide protective trim with functions and features as follows:

    a. Meets ADA requirements for smooth bottom door surfaces.
    b. UL Classified options for use on fire-rated doors up to 3 hours.
    c. Fabricated from stainless steel, brass, bronze, aluminum, or high-impact plastic.
    d. Available in a variety of sizes, finishes, and profiles to suit aesthetic and functional requirements.
    e. Designed to protect doors, frames, and adjacent walls from damage due to impact, abrasion, or traffic.
    f. Fasteners included; adhesive-backed options available for select models.
    g. Ten-year limited warranty.

2. Manufacturers:

    a. Hiawatha, Inc. (HI).
    b. Rockwood (RO).
    c. Trimco (TC).

2.10 DOOR STOPS AND HOLDERS

A. Door Stops and Bumpers: ANSI/BHMA A156.16, Grade 1 door stops and wall bumpers. Provide wall bumpers, either convex or concave types with anchorage as indicated, unless floor or other types of door stops are specified in Hardware Sets. Do not mount floor stops where they will impede traffic. Where floor or wall bumpers are not appropriate, provide overhead type stops and holders.

1. Manufacturers:

    a. Hiawatha, Inc. (HI).
    b. Rockwood (RO).
    c. Trimco (TC).

B. Overhead Door Stops and Holders: ANSI/BHMA A156.8, Grade 1 Certified Products Directory (CPD) listed overhead stops and holders to be surface or concealed types as indicated in Hardware Sets. Track, slide, arm and jamb bracket to be constructed of extruded bronze and shock absorber spring of heavy tempered steel. Provide non-handed design with mounting brackets as required for proper operation and function.

1. Manufacturers:

    a. Norton Rixson (NO).
    b. Rockwood (RO).
    c. Sargent Manufacturing (SA).

2.11 ARCHITECTURAL SEALS

A. General: Thresholds, weatherstripping, and gasket seals to be of type and design as specified below or in the Hardware Sets. Provide continuous weatherstrip gasketing on exterior doors and provide smoke, light, or sound gasketing on interior doors where indicated. At exterior applications provide non-corrosive fasteners and elsewhere where indicated.

B. Smoke Labeled Gasketing: Assemblies complying with NFPA 105 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for smoke control ratings indicated, based on testing according to UL 1784.

1. Provide smoke labeled perimeter gasketing at all smoke labeled openings.

C. Fire Labeled Gasketing: Assemblies complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to UL-10C.

1. Provide intumescent seals as indicated to meet UL10C Standard for Positive Pressure Fire Tests of Door Assemblies, and NFPA 252, Standard Methods of Fire Tests of Door Assemblies.

D. Sound-Rated Gasketing: Assemblies that are listed and labeled by a testing and inspecting agency, for sound ratings indicated.

E. Replaceable Seal Strips: Provide only those units where resilient or flexible seal strips are easily replaceable and readily available from stocks maintained by manufacturer.

F. Manufacturers:

1. National Guard Products (NG).
2. Pemko (PE).
3. Reese Enterprises, Inc. (RE).

2.12 FABRICATION

A. Fasteners: Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. Provide screws according to manufacturers recognized installation standards for application intended.

2.13 FINISHES

A. Standard: Designations used in the Hardware Sets and elsewhere indicate hardware finishes complying with ANSI/BHMA A156.18, including coordination with traditional U.S. finishes indicated by certain manufacturers for their products.

B. Provide quality of finish, including thickness of plating or coating (if any), composition, hardness, and other qualities complying with manufacturer's standards, but in no case less than specified by referenced standards for the applicable units of hardware

C. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine scheduled openings, with Installer present, for compliance with requirements for installation tolerances, labeled fire door assembly construction, wall and floor construction, and other conditions affecting performance.

B. Notify architect of any discrepancies or conflicts between the door schedule, door types, drawings and scheduled hardware. Proceed only after such discrepancies or conflicts have been resolved in writing.

3.2 PREPARATION

A. Hollow Metal Doors and Frames: Comply with ANSI/DHI A115 series.

B. Wood Doors: Comply with ANSI/DHI A115-W series.

3.3 INSTALLATION

A. Install each item of mechanical and electromechanical hardware and access control equipment to comply with manufacturer's written instructions and according to specifications.

1. Installers are to be trained and certified by the manufacturer on the proper installation and adjustment of fire, life safety, and security products including: hanging devices; locking devices; closing devices; and seals.

B. Paint prime coated mullions to match frames.

C. Mounting Heights: Mount door hardware units at heights indicated in following applicable publications, unless specifically indicated or required to comply with governing regulations:

1. Standard Steel Doors and Frames: DHI's "Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames."
2. DHI TDH-007-20: Installation Guide for Doors and Hardware.
3. Where indicated to comply with accessibility requirements, comply with ANSI A117.1 "Accessibility Guidelines for Buildings and Facilities."
4. Provide blocking in drywall partitions where wall stops or other wall mounted hardware is located.

D. Retrofitting: Install door hardware to comply with manufacturer's published templates and written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate

removal, storage, and reinstallation of surface protective trim units with finishing work specified in Division 9 Sections. Do not install surface-mounted items until finishes have been completed on substrates involved.

E. Push Plates and Door Pulls: When through-bolt fasteners are in the same location as a push plate, countersink the fasteners flush with the door face allowing the push plate to sit flat against the door.

F. Thresholds: Set thresholds for exterior and acoustical doors in full bed of sealant complying with requirements specified in Division 7 Section "Joint Sealants."

G. Storage: Provide a secure lock up for hardware delivered to the project but not yet installed. Control the handling and installation of hardware items so that the completion of the work will not be delayed by hardware losses before and after installation.

3.4 FIELD QUALITY CONTROL

A. Field Inspection (Punch Report): Reference Division 01 Sections “Closeout Procedures”. Produce project punch report for each installed door opening indicating compliance with approved submittals and verification hardware is properly installed, operating and adjusted. Include list of items to be completed and corrected, indicating the reasons or deficiencies causing the Work to be incomplete or rejected.

1. Organization of List: Include separate Door Opening and Deficiencies and Corrective Action Lists organized by Mark, Opening Remarks and Comments, and related Opening Images and Video Recordings.

3.5 ADJUSTING

A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.

3.6 CLEANING AND PROTECTION

A. Protect all hardware stored on construction site in a covered and dry place. Protect exposed hardware installed on doors during the construction phase. Install any and all hardware at the latest possible time frame.

B. Clean adjacent surfaces soiled by door hardware installation.

C. Clean operating items as necessary to restore proper finish. Provide final protection and maintain conditions that ensure door hardware is without damage or deterioration at time of owner occupancy.

3.7 DEMONSTRATION

A. Instruct Owner's maintenance personnel to adjust, operate, and maintain mechanical and electromechanical door hardware.

3.8 DOOR HARDWARE SETS

A. The hardware sets represent the design intent and direction of the owner and architect. They are a guideline only and should not be considered a detailed hardware schedule. Discrepancies, conflicting hardware and missing items should be brought to the attention of the architect with corrections made prior to the bidding process. Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application and functionality.

1. Quantities listed are for each pair of doors, or for each single door.
2. The supplier is responsible for handing and sizing all products.
3. Where multiple options for a piece of hardware are given in a single line item, the supplier shall provide the appropriate application for the opening.

B. Refer to Section 08 06 71, Door Hardware Sets, for hardware sets.

END OF SECTION 087100

PAGE LEFT INTENTIONALLY BLANK

SECTION 09 22 16
NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Nonstructural steel framing.

B. Related Requirements:

1. Section 054000 "Cold-Formed Metal Framing" for exterior and interior load-bearing, structural framing.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Shop Drawings:

1. Include layout, spacings, sizes, thicknesses, and types of nonstructural steel framing and fastening and anchorage details.
2. Indicate reinforcing channels, opening framing, supplemental framing, strapping, bracing, bridging, splices, accessories, and attachments to adjoining work.

1.3 INFORMATIONAL SUBMITTALS

A. Product Certificates: For code-compliance certification of studs and track.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in manufacturer's original, unopened, undamaged containers with identification labels intact.

B. Protect materials from corrosion, deformation, and other damage during delivery, storage, and handling in accordance with AISI S202.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. STC-Rated Assemblies: Where indicated on Drawings, provide assemblies incorporating nonstructural steel framing identical to those of assemblies tested in accordance with ASTM E90 and classified in accordance with ASTM E413 by an independent testing agency.

B. Horizontal Deflection: For composite wall assemblies, limited to 1/240 of the wall height based on the following horizontal loading:

1. Horizontal Loading: 5 lbf/sq. ft..

2.2 NONSTRUCTURAL STEEL FRAMING

A. Framing Members, General: Comply with requirements in AISI S220 for conditions indicated on Drawings.

1. Protective Coating: ASTM A653/A653M, G40 hot-dip galvanized or coating with demonstrated equivalent corrosion resistance. Galvannealed products are unacceptable.

a. Equivalent Corrosion-Resistant Coating: Evaluation report acceptable to authorities having jurisdiction demonstrates corrosion resistance equivalent to specified protective coating.

B. Studs and Track: Conventional members, roll-formed into standard shapes without surface deformations to stiffen framing members.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ClarkDietrich
b. Marino\WARE
c. SCAFCO Steel Stud Company; Stone Group of Companies

2. Minimum Base-Steel Thickness: As required by performance requirements for horizontal deflection.
3. Minimum Yield Strength: **33 ksi**.
4. Depth: As indicated on Drawings.

C. Slip-Type Head Joints: Where indicated on Drawings.

D. Flat Strap and Backing Plate: Steel sheet for blocking and bracing in length and width indicated on Drawings.

1. Manufacturers: Subject to compliance with requirements, available

manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ClarkDietrich
b. Marino\WARE
c. SCAFCO Steel Stud Company; Stone Group of Companies

2. Minimum Base-Steel Thickness: As indicated on Drawings.

E. U-Channel: Cold-rolled steel, **0.0538-inch** minimum base-steel thickness, with minimum **1/2-inch-** wide flanges.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ClarkDietrich
b. Marino\WARE
c. SCAFCO Steel Stud Company; Stone Group of Companies

2. Depth:

a. Bridging: As indicated on Drawings.

3. Bridging Clip Angle: Not less than **1-1/2 by 1-1/2 inches**; **0.068-inch-** base-steel thickness.

F. Rigid Hat-Shaped Furring Channels: Conventional members, roll-formed into standard shapes.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. ClarkDietrich
b. Marino\WARE
c. SCAFCO Steel Stud Company; Stone Group of Companies

2. Minimum Base-Steel Thickness: As indicated on Drawings.
3. Depth: As indicated on Drawings.

2.3 AUXILIARY MATERIALS

A. General: Provide auxiliary materials that comply with referenced installation standards.

1. Fasteners for Steel Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

B. Tie Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper.

C. Post-Installed Anchors: Fastener systems with an evaluation report, acceptable to authorities having jurisdiction, as appropriate for the substrate.

D. Power-Actuated Anchors: Fastener systems with an evaluation report, acceptable to authorities having jurisdiction, based on ICC-ES AC70.

E. Flat Hangers: Steel sheet.

1. Protective Coating: ASTM A653/A653M, G40 or G60, hot-dip galvanized.
2. Size and Length: 1 by 3/16 inch by length indicated on Drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, substrates, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF NONSTRUCTURAL STEEL FRAMING, GENERAL

A. Installation Standard: ASTM C754.

1. Gypsum Board Assemblies: Also comply with requirements in ASTM C840 that apply to framing installation.

B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.

C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.

D. Install bracing at terminations in assemblies.

E. Do not bridge building control and expansion joints with framing members. Frame both sides of joints independently.

3.3 INSTALLATION OF NONSTRUCTURAL STEEL FRAMING

A. Install framing system components at spacings indicated on Drawings, but not greater than spacings required by referenced installation standards for assembly types.

1. Single-Layer Application: 16 inches o.c. unless otherwise indicated on Drawings.
2. Multilayer Application: 16 inches o.c. unless otherwise indicated on Drawings.
3. Tile Backing Panels: 16 inches o.c. unless otherwise indicated on Drawings.

B. Install studs so flanges within framing system point in same direction.

C. Install track at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated on Drawings to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.

1. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install track section (for cripple studs) at head and secure to jamb studs.

    a. Install two studs at each jamb unless otherwise indicated on Drawings.
    b. Install cripple studs at head adjacent to each jamb stud, with a minimum **1/2-inch** clearance from jamb stud to allow for installation of control joint in finished assembly.
    c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure unless otherwise indicated on Drawings.

2. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated on Drawings. Install framing below sills of openings to match framing required above door heads.

3. STC-Rated Partitions: Install framing to comply with STC-rated assembly indicated on Drawings.

D. Installation Tolerances for Nonstructural Steel Framing:

1. Framing Members: Install each framing member so fastening surfaces vary not more than **1/8 inch** from the plane formed by faces of adjacent framing.

END OF SECTION 09 22 16

SECTION 09 29 00
GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.

2. Tile backing panels.

B. Related Requirements:

1. Section 079219 "Acoustical Joint Sealants" for acoustical joint sealants installed in gypsum board assemblies.

2. Section 092216 "Non-Structural Metal Framing" for nonstructural steel framing and suspension systems that support gypsum board panels.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1.3 DELIVERY, STORAGE, AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.4 FIELD CONDITIONS

A. Environmental Limitations: Comply with ASTM C840 requirements or manufacturer's written instructions, whichever are more stringent.

B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.

C. Do not install panels that are wet, moisture damaged, or mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of gypsum board and joint finishing material from single source with resources to provide products of consistent quality in appearance and physical properties.

2.2 PERFORMANCE REQUIREMENTS

A. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings in accordance with ASTM E90 and classified in accordance with ASTM E413; tested by a qualified testing agency.

2.3 GYPSUM BOARD, GENERAL

A. Size: Provide panel products in maximum lengths and widths available that will minimize joints in each area and that correspond with support system specified or indicated on Drawings.

2.4 INTERIOR GYPSUM BOARD

A. Gypsum Wallboard: ASTM C1396/C1396M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. CertainTeed; SAINT-GOBAIN
    b. Georgia-Pacific Gypsum LLC
    c. USG Corporation

2. Thickness: As indicated on Drawings.
3. Long Edges: Tapered.

B. Gypsum Ceiling Board: ASTM C1396/C1396M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. CertainTeed; SAINT-GOBAIN
    b. Georgia-Pacific Gypsum LLC
    c. USG Corporation

2. Thickness: 1/2 inch.

3. Long Edges: Tapered.

C. Abuse-Resistant Gypsum Board: ASTM C1396/C1396M, tested in accordance with ASTM C1629/C1629M.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed; SAINT-GOBAIN
b. Georgia-Pacific Gypsum LLC
c. USG Corporation

2. Core: As indicated on Drawings.

3. Mold Resistance: ASTM D3273, score of 10 as rated in accordance with ASTM D3274.
4. Long Edges: Tapered.

D. Acoustically Enhanced Gypsum Board: ASTM C1766; multilayer products constructed of two layers of gypsum boards sandwiching a viscoelastic sound-absorbing polymer core.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. CertainTeed; SAINT-GOBAIN
b. Gold Bond Building Products, LLC provided by National Gypsum Company
c. PABCO Gypsum

2. Core: 5/8 inch, Type X.
3. Long Edges: Tapered.

E. Trim for Interior Gypsum Board: ASTM C1047.

1. Material: Galvanized-steel sheet or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized-steel sheet.
2. Shapes:

a. Cornerbead.
b. Bullnose bead.
c. LC-Bead: J-shaped; exposed long flange receives joint compound.
d. L-Bead: L-shaped; exposed long flange receives joint compound.
e. U-Bead: J-shaped; exposed short flange does not receive joint compound.

F. Joint Treatment Materials for Interior Gypsum Board: Comply with ASTM C475/C475M requirements.

1. Joint Tape: Paper.
2. Joint Compound: For each coat, use formulation that is compatible with other compounds applied on previous or for successive coats.

    a. Mold-Resistant Joint Compound: Use mold-resistant formulations with mold-resistant gypsum board products.
    b. Prefilling: At open joints, rounded or beveled panel edges, and damaged surface areas, use setting-type taping compound.
    c. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use setting-type taping compound.
    d. Fill Coat: For second coat, use setting-type, sandable topping compound.
    e. Finish Coat: For third coat, use setting-type, sandable topping compound.

2.5 TILE BACKING PANELS

A. Water-Resistant Gypsum Backing Board: ASTM C1396/C1396M, with manufacturer's standard edges.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. American Gypsum
    b. CertainTeed; SAINT-GOBAIN
    c. Gold Bond Building Products, LLC provided by National Gypsum Company

2. Core: As indicated on Drawings.

B. Joint Treatment Materials for Tile Backing Panels: Comply with ASTM C475/C475M requirements.

1. Mold-Resistant Joint Compound: Use mold-resistant formulations with mold-resistant panel products.
2. Joint Tape: As recommended in writing by panel manufacturer.
3. Joint Compound for Tile Backing Panels:

    a. Water-Resistant Gypsum Backing Board: Use setting-type taping compound and setting-type, sandable topping compound.

2.6 AUXILIARY MATERIALS

A. Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.

B. Steel Drill Screws: ASTM C1002 unless otherwise specified or indicated on Drawings.

1. Use screws complying with ASTM C954 for fastening panels to steel members from **0.033 to 0.112 inch** thick.

C. Sound-Attenuation Blankets: ASTM C665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers as follows:

1. Non-Fire-Resistance-Rated Assemblies: Glass.

D. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and substrates including welded hollow-metal frames and support framing, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.

B. Examine panels before installation. Reject panels that are wet, moisture damaged, or mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION AND FINISHING OF GYPSUM BOARD, GENERAL

A. Comply with ASTM C840 requirements.

B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.

C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than **1/16 inch** of open space between panels. Do not force into place.

D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.

E. Form expansion (control) joints with space between edges of adjoining gypsum panels.

F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.

1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than **8 sq. ft.** in area.
2. Fit gypsum panels around ducts, pipes, and conduits.
3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow **1/4- to 3/8-inch-** wide joints to install sealant.

G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide **1/4- to 1/2-inch-** wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.

H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.

I. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C919 requirements and with manufacturer's written instructions for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.

J. Install sound-attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

3.3 INSTALLATION OF INTERIOR GYPSUM BOARD

A. Single-Layer Application:

1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated on Drawings.
2. On partitions/walls, apply gypsum panels vertically (parallel to framing) unless otherwise specified or indicated on Drawings or required by fire-resistance-rated assembly, and minimize end joints.

    a. Stagger abutting end joints not less than one framing member in alternate courses of panels.

3. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

B. Multilayer Application:

1. On partitions/walls, apply gypsum board indicated for base layers and face layers vertically (parallel to framing) with joints of base layers located over studs or furring members and face-layer joints offset at least one stud or furring member with base-layer joints unless otherwise indicated on

Drawings or required by fire-resistance-rated assembly. Stagger joints on opposite sides of partitions.

2. Fastening Methods: Fasten base layers with screws; fasten face layers with adhesive and supplementary fasteners.

C. Trim for Interior Gypsum Board: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim in accordance with manufacturer's written instructions.

1. Cornerbead: Install at outside corners unless otherwise specified or indicated on Drawings.

2. LC-Bead: Install at exposed panel edges.
3. L-Bead: Install where indicated on Drawings.
4. U-Bead: Install at exposed panel edges.

D. Joint Treatment Materials for Interior Gypsum Board: Treat joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare panel surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.

1. Prefill open joints, rounded or beveled edges, and damaged surface areas.
2. Apply joint tape over panel joints, except for trim products specifically indicated as not intended to receive tape.

E. Finish interior gypsum board panels to comply with levels indicated below and in accordance with ASTM C840:

1. Level 1: Ceiling plenum areas, concealed areas, and where indicated on Drawings.
2. Level 2: Panels that are substrate for tile.

3. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.

a. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."

3.4 INSTALLATION OF TILE BACKING PANELS

A. Water-Resistant Gypsum Backing Board: Install where indicated with **1/4-inch** gap where panels abut other construction or penetrations.

B. Where tile backing panels abut other types of panels in same plane, shim surfaces to produce a uniform plane across panel surfaces.

C. Finish tile backing panels in accordance with manufacturer's written instructions.

3.5 PROTECTION

A. Protect adjacent surfaces from joint compound and promptly remove from floors and other non-gypsum board surfaces. Repair surfaces stained, marred, or otherwise damaged during gypsum board installation and finishing.

B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.

C. Remove and replace panels that have gotten wet, moisture damaged, or mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 09 29 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 09 30 13
CERAMIC TILING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Ceramic mosaic tiles.
2. Glazed wall tiles.
3. Thresholds.
4. Setting materials.
5. Grout materials.
6. Metal edge trim.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for sealing of movement joints in tile surfaces.
2. Section 092900 "Gypsum Board" for tile backing panels.

1.2 DEFINITIONS

A. General: Definitions in ANSI A108 series of tile installation standards and in ANSI A137.1 apply to Work of this Section unless otherwise specified.

B. Face Size: Actual tile size, excluding spacer lugs.

C. Large Format Tile: Tile with at least one edge 15 inches or longer.

D. Module Size: Actual tile size plus joint width indicated.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Shop Drawings: Show locations, plans, and elevations, of each type of tile and tile pattern. Show widths, details, and locations of movement joints in tile substrates and finished tile surfaces. Show thresholds.

C. Samples for Verification:

1. Full-size units of each type and composition of tile and for each color and finish required.

2. Full-size units of each type of trim and accessory for each color and finish required.
3. Stone thresholds in 6-inch lengths.
4. Metal flooring transitions 6-inch lengths.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Extra Stock Material: Furnish extra materials, from the same production run, to Owner that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size specified.
2. Grout: Furnish quantity of grout equal to 3 percent of amount installed for each type, composition, and color indicated for Project.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.1 for labeling tile packages.

B. Store tile and cementitious materials on elevated platforms, under cover, and in a dry location.

C. Store aggregates where grading and other required characteristics can be maintained and contamination can be avoided.

D. Store liquid materials in unopened containers and protected from freezing.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Tile: Obtain tile of each type and color or finish from single source or producer.

1. Obtain tile of each type and color or finish from same production run and of consistent quality in appearance and physical properties for each

contiguous area.

B. Accessory Products: Obtain each of the following products specified in this Section from a single manufacturer:

1. Stone thresholds.

2.2 CERAMIC TILE SYSTEM, GENERAL

A. ANSI Ceramic Tile Standard: Provide tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.

B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.

C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.

2.3 CERAMIC MOSAIC TILES

A. Ceramic Mosaic Tile :

1. Basis-of-Design Product: Subject to compliance with requirements, provide Daltile or comparable product by one of the following:

a. American Olean; a brand of Dal-Tile Corporation
b. Crossville, Inc.

2. Type: Glazed.
3. Certification: Porcelain tile certified by the Porcelain Tile Certification Agency.

4. Module Face Size: See schedule on the drawings.
5. Face: Plain with cushion edges.
6. Surface: Smooth, without abrasive admixture.

7. Tile Color and Pattern: Match Architect's sample.
8. Grout Color: As selected by Architect from manufacturer's full range.
9. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable and matching characteristics of adjoining flat tile. Provide shapes as follows, selected from manufacturer's standard shapes:

a. Base: Coved, module size 3 by 12 inch.

2.4 GLAZED WALL TILES

A. Glazed Wall Tile :

1. Basis-of-Design Product: Subject to compliance with requirements, provide Daltile or comparable product by one of the following:

    a. American Olean; a brand of Dal-Tile Corporation
    b. Marazzi USA; a brand of Dal-Tile Corporation

2. Module Face Size: See schedule on the drawings.
3. Face Size Variation: Rectified.

4. Tile Color and Pattern: Match Architect's sample.
5. Grout Color: As selected by Architect from manufacturer's full range.

2.5 THRESHOLDS

A. General: Fabricate to sizes and profiles indicated or required to provide transition between adjacent floor finishes.

1. Profile: Bevel edges at 1:2 slope, with lower edge of bevel aligned with or up to 1/16 inch above adjacent floor surface. Finish bevel to match top surface of threshold. Limit height of threshold to 1/2 inch or less above adjacent floor surface.

B. Marble Thresholds : ASTM C503/C503M.

1. Finish: Honed.

2. Description:

    a. Uniform, fine- to medium-grained white stone with gray veining.
    b. Match Architect's sample.

2.6 TILE BACKING PANELS

A. Joint Treatment Materials for Tile Backing Panels: Comply with ASTM C475/C475M requirements.

1. Mold-Resistant Joint Compound: Use mold-resistant formulations with mold-resistant panel products.
2. Joint Tape: As recommended in writing by panel manufacturer.
3. Joint Compound for Tile Backing Panels: Use setting-type taping compound and setting-type, sandable topping compound.

2.7 WATERPROOF MEMBRANES

A. General: Manufacturer's standard product, selected from the following, that complies with ANSI A118.10 and ANSI A118.12 and is recommended in writing by manufacturer for application indicated. Include reinforcement and accessories recommended in writing by manufacturer.

2.8 CRACK ISOLATION MEMBRANES

A. General: Manufacturer's standard product, selected from the following, that complies with ANSI A118.12 for high performance and is recommended in writing by manufacturer for application indicated. Include reinforcement and accessories recommended in writing by manufacturer.

2.9 SETTING MATERIALS

A. Improved Modified Dry-Set Mortar (Thinset): ANSI A118.15.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. ARDEX Americas
    b. Custom Building Products
    c. Laticrete International, Inc.
    d. MAPEI Corporation

2. For wall applications, provide mortar that complies with requirements for nonsagging mortar in addition to other requirements in ANSI A118.15.

2.10 GROUT MATERIALS

A. High-Performance Tile Grout: ANSI A118.7.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. ARDEX Americas
    b. Custom Building Products
    c. MAPEI Corporation

2. Polymer Type: Dry, redispersible form, prepackaged with other dry ingredients.

2.11 MISCELLANEOUS MATERIALS

A. Metal Edge Trim: Profile designed for wall terminations and edge protection.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Profilitec Corp.
    b. Progress Profiles America Inc.
    c. Schluter Systems L.P.

2. Terminations: End caps Inside corners Outside corners matching edge-protection profile.
3. Material and Finish: Polished chrome anodized aluminum exposed-edge material.

B. Tile Cleaner : A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.

C. Grout Sealer : Grout manufacturer's standard product for sealing grout joints that does not change color or appearance of grout.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
2. Verify that concrete substrates for tile floors installed with thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.

    a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.
    b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.

3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.

4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove coatings, including curing compounds or other coatings, that are incompatible with tile-setting materials.

B. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with adhesives or thinset mortar with trowelable leveling and patching compound specifically recommended in writing by tile-setting material manufacturer.

C. Where indicated, prepare substrates to receive waterproof membrane by applying a reinforced mortar bed that complies with ANSI A108.1 and is sloped 1/4 inch per foot toward drains.

D. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

E. Substrate Flatness:

1. For tile shorter than 15 inches, confirm that structure or substrate is limited to variation of 1/4 inch in 10 ft. from the required plane, and no more than 1/16 inch in 12 inches when measured from tile surface high points.
2. For large format tile, tile with at least one edge 15 inches or longer, confirm that structure or substrate is limited to 1/8 inch in 10 ft. from the required plane, and no more than 1/16 inch in 24 inches when measured from tile surface high points.

F. Field-Applied Temporary Protective Coating: If indicated under tile type or needed to prevent grout from staining or adhering to exposed tile surfaces, precoat them with continuous film of temporary protective coating, taking care not to coat unexposed tile surfaces.

3.3 INSTALLATION OF CERAMIC TILE SYSTEM, GENERAL

A. Tile Backing Panels: Install backing panels and treat joints in accordance with ANSI A108.11 and manufacturer's written instructions for type of application indicated.

B. Waterproof Membranes: Install waterproof membrane to comply with ANSI A108.13 and manufacturer's written instructions to produce waterproof

membrane of uniform thickness that is bonded securely to substrate.

1. Allow waterproof membrane to cure and verify by testing that it is watertight before installing tile or setting materials over it.

C. Crack Isolation Membranes: Install crack isolation membrane to comply with ANSI A108.17 and manufacturer's written instructions to produce membrane of uniform thickness that is bonded securely to substrate.

1. Allow crack isolation membrane to cure before installing tile or setting materials over it.

D. Setting and Grout Materials: Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.

1. Add materials, water, and additives in accurate proportions.
2. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

E. Install tile in accordance with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of ANSI A108 series that are referenced in TCNA installation methods and specified in tile installation schedules, and apply to types of setting and grouting materials used.

1. For the following installations, follow procedures in ANSI A108 series of tile installation standards for providing 95 percent mortar coverage:

   a. Tile floors consisting of tiles 8 by 8 inches or larger.
   b. Tile floors consisting of rib-backed tiles.

2. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
3. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.
4. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.
5. Where accent tile differs in thickness from field tile, vary setting-bed thickness so that tiles are flush.
6. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.

a. For tile mounted in sheets, make joints between tile sheets same width as joints within tile sheets, so joints between sheets are not apparent in finished Work.
b. Where adjoining tiles on floor, base, walls, or trim are specified or indicated to be same size, align joints.
c. Where tiles are specified or indicated to be whole integer multiples of adjoining tiles on floor, base, walls, or trim, align joints unless otherwise indicated.

7. Lay out tile wainscots to dimensions indicated or to next full tile beyond dimensions indicated.

F. Movement Joints: Provide movement joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated on Drawings. Form joints during installation of setting materials, mortar beds, and tile. Keep joints free of dirt, debris, and setting materials prior to filling with sealants. Do not saw-cut joints after installing tiles.

1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.

G. Thresholds: Install stone and solid surface thresholds in same type of setting bed as adjacent floor unless otherwise indicated.

1. At locations where mortar bed (thickset) would otherwise be exposed above adjacent floor finishes, set thresholds in improved modified dry-set mortar (thinset).

H. Metal Flooring Transitions: Install at locations indicated.

I. Metal Wall Trim: Install at locations indicated on Drawings.

J. Grout Sealer: Apply grout sealer to cementitious grout joints in tile floors]in accordance with manufacturer's written instructions. As soon as sealer has penetrated grout joints, remove excess sealer and sealer from tile faces by wiping with soft cloth.

3.4 ADJUSTING

A. Remove and replace tile that is damaged or that does not match adjoining tile. Provide new matching units, installed as specified and in a manner to eliminate evidence of replacement.

3.5 CLEANING

A. On completion of placement and grouting, clean all ceramic tile surfaces so they are free of foreign matter.

1. Remove grout residue from tile as soon as possible.

2. Clean grout smears and haze from tile in accordance with tile and grout manufacturer's written instructions. Use only cleaners recommended in writing by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.

3.6 PROTECTION

A. Protect installed tile work with kraft paper or other heavy covering during construction period to prevent staining, damage, and wear. If recommended in writing by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls and floors.

B. Prohibit foot and wheel traffic from tiled floors for at least seven days after grouting is completed.

C. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

3.7 INTERIOR CERAMIC TILE INSTALLATION SCHEDULE

A. Interior Floor Installations, Concrete Subfloor:

1. TCNA F111: Method ANSI A108.1C. Cement mortar bed (thickset) installed over cleavage membrane.

a. Bond Coat for Cured-Bed Method: Improved modified dry-set mortar (thinset).
b. Grout: High-performance tile grout.

1) Type: Sanded.

c. Joint Width: 3/16 inch.
d. Movement Joints: Types located on Drawings.

B. Interior Wall Installations, Masonry or Concrete:

1. TCNA W202I: Thinset mortar.

a. Mortar: Improved modified dry-set mortar (thinset).
b. Grout: High-performance tile grout.

1) Type: Sanded.

c. Joint Width: 3/16 inch.
d. Movement Joints: Types located on Drawings.

END OF SECTION 09 30 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 09 51 13
ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Acoustical panels.
2. Exposed metal suspension system.
3. Metal edge moldings and trim.

B. Related Requirements:

1. Section 095123 "Acoustical Tile Ceilings" for ceilings consisting of mineral-base acoustical tiles used with fully concealed suspension systems, stapling, or adhesive bonding.

C. Products furnished, but not installed under this Section, include anchors, clips, and other ceiling attachment devices to be cast in concrete.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Samples: For each exposed product and for each color and texture specified, **6 inches** in size.

1.3 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials, from the same production run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Acoustical Panels: Full-size panels equal to 2 percent of quantity installed.
2. Suspension-System Components: Quantity of each exposed component equal to 2 percent of quantity installed.
3. Hold-Down Clips: Equal to 2 percent of quantity installed.
4. Impact Clips: Equal to 2 percent of quantity installed.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Deliver acoustical panels, suspension-system components, and accessories to Project site and store them in a fully enclosed, conditioned space where they will

be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.

B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Source Limitations for Ceiling System: Obtain each type of acoustical panel and its supporting suspension system from single source from single manufacturer.

2.2 ACOUSTICAL PANEL CEILINGS

A. Acoustical Panels: Provide manufacturer's standard panels in accordance with ASTM E1264 and designated by type, form, pattern, acoustical rating, and light reflectance unless otherwise indicated.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Ultima High NRC by Armstrong World Industries or comparable product by one of the following:

    a. CertainTeed; SAINT-GOBAIN
    b. USG Corporation

2. Color: White.
3. Ceiling Attenuation Class (CAC): Not less than 35.
4. Noise Reduction Coefficient (NRC): Not less than 0.85.
5. Articulation Class (AC): Not less than 170.
6. Edge/Joint Detail: Reveal sized to fit flange of exposed suspension-system members.
7. Thickness: 7/8 inch.
8. Modular Size: 24 by 24 inches.
9. Antimicrobial Treatment: Manufacturer's standard broad spectrum, antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested in accordance with ASTM D3273, ASTM D3274, or ASTM G21 and evaluated in accordance with ASTM D3274 or ASTM G21.

B. Exposed Metal Suspension System:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Armstrong World Industries

b. CertainTeed; SAINT-GOBAIN
c. USG Corporation

2. Metal Suspension-System Standard: Provide manufacturer's standard, direct-hung, metal suspension system and accessories in accordance with ASTM C635/C635M and designated by type, structural classification, and finish indicated.

3. Wide-Face, Capped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, **G30** coating designation; with prefinished **15/16-inch-** wide metal caps on flanges.

a. Structural Classification: Intermediate -duty system.
b. End Condition of Cross Runners: butt-edge type.
c. Face Design: Flat, flush.
d. Cap Material: Cold-rolled steel.
e. Cap Finish: Painted white.

C. Metal Edge Moldings and Trim:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Armstrong World Industries
b. CertainTeed; SAINT-GOBAIN
c. USG Corporation

2. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.

a. Edge moldings to fit acoustical panel edge details and suspension systems indicated and match width and configuration of exposed runners unless otherwise indicated.
b. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.
c. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.

3. Baked-Enamel or Powder-Coat Finish: Minimum dry film thickness of **1.5 mils**. Comply with ASTM C635/C635M and coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.

2.3 ACCESSORIES

A. Attachment Devices: Size for five times the design load indicated in ASTM C635/C635M, Table 1, "Direct Hung," unless otherwise indicated.

B. Wire Hangers, Braces, and Ties: Provide wires as follows:

1. Zinc-Coated, Carbon-Steel Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper.

2. Size: Wire diameter sufficient for its stress at three times hanger design load (ASTM C635/C635M, Table 1, "Direct Hung") will be less than yield stress of wire, but not less than 0.106-inch- diameter wire.

C. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.

D. Flat Hangers: Mild steel, zinc coated or protected with rust-inhibitive paint.

E. Hold-Down Clips: Manufacturer's standard hold-down.

F. Impact Clips: Manufacturer's standard impact-clip system designed to absorb impact forces against acoustical panels.

2.4 ACOUSTICAL SEALANT

A. Acoustical Sealant: As specified in Section 079219 "Acoustical Joint Sealants."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.

B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width

panels at borders unless otherwise indicated, and comply with layout shown on reflected ceiling plans.

B. Layout openings for penetrations centered on the penetrating items.

3.3 INSTALLATION OF ACOUSTICAL PANEL CEILINGS

A. Install acoustical panel ceilings in accordance with ASTM C636/C636M and manufacturer's written instructions.

B. Suspend ceiling hangers from building's structural members and as follows:

1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.

2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.

3. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
4. Do not attach hangers to steel deck tabs.
5. Do not attach hangers to steel roof deck. Attach hangers to structural members.
6. Space hangers not more than **48 inches** o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than **8 inches** from ends of each member.
7. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards.

C. Metal Edge Moldings and Trim: Install edge moldings and trim of type indicated at perimeter of acoustical panel ceiling area and where necessary to conceal edges of acoustical panels.

1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
2. Screw attach moldings to substrate at intervals not more than **16 inches** o.c. and not more than **3 inches** from ends. Miter corners accurately and connect securely.
3. Do not use exposed fasteners, including pop rivets, on moldings and trim.

D. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.

E. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at

borders and penetrations to provide precise fit.

1. Arrange directionally patterned acoustical panels as follows:

    a. As indicated on reflected ceiling plans.
    b. Install panels with pattern running in one direction parallel to long axis of space.
    c. Install panels in a basket-weave pattern.

2. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension-system runners and moldings.
3. For reveal-edged panels on suspension-system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
4. For reveal-edged panels on suspension-system members with box-shaped flanges, install panels with reveal surfaces in firm contact with suspension-system surfaces and panel faces flush with bottom face of runners.
5. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
6. Install hold-down impact clips in areas indicated; space in accordance with panel manufacturer's written instructions unless otherwise indicated.

    a. Hold-Down Clips: Space 24 inches o.c. on all cross runners.

3.4 ERECTION TOLERANCES

A. Suspended Ceilings: Install main and cross runners level to a tolerance of 1/8 inch in 12 ft., non-cumulative.

B. Metal Edge Moldings and Trim: Install moldings and trim to substrate and level with ceiling suspension system to a tolerance of 1/8 inch in 12 ft., non-cumulative.

3.5 CLEANING

A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage.

B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 09 51 13

SECTION 09 65 13
RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Thermoset rubber base.

2. Rubber molding accessories.

B. Related Requirements:

1. Section 024119 "Selective Demolition" for removing existing floor coverings.

2. Section 096519 "Resilient Tile and Plank Flooring" for modular resilient flooring.

3. Section 096813 "Tile Carpeting" for modular carpet tile flooring.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include manufacturer's written data on physical characteristics, durability, and fade resistance.
2. Include manufacturer's written installation instructions for each type of substrate.

B. Samples: For each exposed product and for each color and texture specified, not less than **12 inches** long.

C. Samples for Initial Selection: For each type of exposed product.

D. Samples for Verification: For each type of exposed product indicated and for each color, texture, and pattern required in manufacturer's standard-size Samples, but not less than **12 inches** long.

E. Product Schedule: For resilient base and accessory products. Use same designations indicated on Drawings.

1.3 MAINTENANCE MATERIAL SUBMITTALS

A. Extra Stock Material: Furnish extra materials, from the same production run, to

Owner that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Furnish not less than Insert dimension for every 500 linear ft. or fraction thereof, of each type, color, pattern, and size of resilient product installed.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than **50 deg F** or more than **90 deg F**.

1.5 FIELD CONDITIONS

A. Installation Temperature Requirements: Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following periods:

1. 48 hours before installation.
2. During installation.
3. 48 hours after installation.

B. Post-Installation Temperature Requirements: After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than **95 deg F**.

C. Install resilient products after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: As determined by testing identical products in accordance with ASTM E648 or ASTM E662 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

2.2 RESILIENT BASE

A. Thermoset Rubber Base:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Mannington Mills, Inc
b. Roppe Corporation; Roppe Holding Company
c. Tarkett USA

2. Classification: ASTM F1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).
3. Style and Location:

a. Style A, Straight: Provide in areas with carpet.
b. Style B, Cove: Provide in areas with resilient floor coverings.

4. Height: 4 inches.
5. Lengths: Coils in manufacturer's standard length.
6. Outside Corners: Preformed.
7. Inside Corners: Preformed.
8. Colors: Match Architect's sample.

2.3 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended in writing by resilient-product manufacturer for resilient products and substrate conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

1. Installation of resilient products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Prepare substrates in accordance with manufacturer's written instructions to ensure adhesion of resilient products.

B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

C. Do not install resilient products until materials are the same temperature as space where they are to be installed.

1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.3 INSTALLATION OF RESILIENT BASE

A. Comply with manufacturer's written instructions for installing resilient base.

B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.

C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.

D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.

E. Do not stretch resilient base during installation.

F. Preformed Corners: Install preformed corners before installing straight pieces.

3.4 CLEANING

A. Comply with manufacturer's written instructions for cleaning resilient products.

B. Perform the following operations immediately after completing resilient-product installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum horizontal surfaces thoroughly.
3. Damp-mop horizontal surfaces to remove marks and soil.

3.5 PROTECTION

A. Comply with manufacturer's written instructions for protecting resilient products.

B. After post-installation cleaning, immediately protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

C. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 09 65 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 09 65 19
RESILIENT TILE AND PLANK FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Commercial luxury vinyl floor planks.

2. Rubber floor tiles.

B. Related Requirements:

1. Section 024119 "Selective Demolition" for removing existing floor coverings.
2. Section 096513 "Resilient Base and Accessories" for wall base and accessories installed with resilient tile and plank flooring.

1.2 DEFINITIONS

A. LVP: Luxury vinyl planks. A marketing term that is applied to modular resilient floor plank products.

B. LVT: Luxury vinyl tiles. A marketing term that is applied to modular resilient floor tile products.

C. VCT: Vinyl composition tiles. A modular resilient floor tile product composed of binder, fillers, and pigments.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include manufacturers' written data on physical characteristics, durability, and fade resistance.
2. Include manufacturers' written installation instructions for each type of substrate.

B. Samples: Full-size units of each color, texture, and pattern of resilient flooring type required.

C. Samples for Verification: Full-size units of each color and pattern of resilient flooring type required.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of specified product to include the following:

1. Methods for maintaining resilient flooring, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
2. Precautions for cleaning materials and methods that could be detrimental to resilient flooring.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Extra Stock Material: Furnish extra materials, from the same production run, to Owner that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Resilient Tile and Plank Flooring: Furnish no fewer than 1 box for each 50 boxes or fraction thereof, of each type, color, pattern, and size of resilient flooring product installed.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in original packages and containers, with seals unbroken, bearing manufacturers' labels indicating brand name and directions for storing.

B. Store resilient flooring and accessory materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than **50 deg F** or more than **90 deg F**. Store resilient flooring on flat surfaces.

1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install resilient flooring until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at levels planned for building occupants during the remainder of the construction period.

B. Do not install resilient flooring over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended in writing by resilient flooring manufacturer.

C. Adhesively Applied Products:

1. Maintain temperatures during installation within range recommended in writing by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive flooring 48 hours before installation, during installation, and 48 hours after installation unless longer period is recommended in writing by manufacturer.

2. After postinstallation period, maintain temperatures within range recommended in writing by manufacturer, but not less than 55 deg F or more than 95 deg F.
3. Close spaces to traffic during flooring installation.
4. Close spaces to traffic for 48 hours after flooring installation unless manufacturer recommends longer period in writing.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For resilient tile flooring, as determined by testing identical products in accordance with ASTM E648 or ASTM E662 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

2.2 RESILIENT TILE AND PLANK FLOORING

A. Commercial Luxury Vinyl Floor Planks: Solid, resilient plank flooring product composed of binder, fillers, and pigments compounded with suitable stabilizers and processing aids; marketed as luxury vinyl planks (LVP).

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Mannington Mills, Inc
b. Shaw Industries Group, Inc.; Berkshire Hathaway Company
c. Tarkett USA

2. Classification: ASTM F1700, Class III, Printed Film Vinyl Tile.

a. Type: A, Smooth Surface.

3. Overall Thickness: 0.100 inch including manufacturer's standard clear wear layer and UV-cured polyurethane topcoat.
4. Nominal Size: 4 by 36 inches.
5. Colors and Patterns: Match Architect's samples.

B. Rubber Floor Tiles: Resilient flooring product consisting of modular rubber tiles with smooth square edges.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Altro

b. Nora by Interface
c. Tarkett USA

2. Classification: ASTM F1344, Type I-B, Homogeneous Rubber Tile, through mottled.
3. Hardness: Manufacturer's standard hardness, when measured using Shore, Type A durometer in accordance with ASTM D2240.
4. Wearing Surface: Smooth.

5. Thickness: 0.125 inch.
6. Size: 24 by 24 inches.

7. Colors and Patterns: Match Architect's samples.

2.3 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by flooring manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended in writing by floor tile and adhesive manufacturers for substrate and conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, moisture content, and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

1. Installation of resilient flooring products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Prepare substrates in accordance with manufacturer's written installation instructions to ensure adhesion of flooring.

B. Concrete Substrates: Prepare in accordance with ASTM F710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by resilient flooring manufacturer. Do not use solvents.
3. Alkalinity Testing: Perform pH testing in accordance with ASTM F710. Proceed with installation only if pH readings are not less than 7.0 and not greater than 8.5.
4. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft. and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

    a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
    b. Relative Humidity Test: Using in-situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.

C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

D. Move flooring and installation materials into spaces where they will be installed at least 48 hours in advance of installation unless manufacturer recommends a longer period in writing.

1. Do not install flooring until it is the same temperature as space where it is to be installed.

E. Sweep and vacuum clean substrates to be covered by flooring immediately before installation. After cleaning, examine substrates for moisture, alkaline salts, carbonation, and dust. Proceed with installation only after unsatisfactory conditions have been corrected.

3.3 INSTALLATION OF RESILIENT TILE AND PLANK FLOORING

A. Comply with manufacturer's written installation instructions.

B. Discard broken, cracked, chipped, or deformed tiles.

C. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.

1. Lay tiles square with room axis.

D. Tile Matching: Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered.

1. Lay tiles with grain running in one direction.

E. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.

F. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.

G. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.

H. Adhered Floor Tile: Adhere floor tiles to substrates using a full spread of adhesive applied to substrate to comply with adhesive and flooring manufacturers' written installation instructions, including those for trowel notching, adhesive mixing, and adhesive open and working times, to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

3.4 CLEANING

A. Comply with manufacturer's written instructions for cleaning flooring.

B. Perform the following operations immediately after completing flooring installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum surfaces thoroughly.
3. Damp-mop surfaces to remove marks and soil.

3.5 PROTECTION

A. Comply with manufacturer's written instructions for protecting flooring.

B. After post-installation cleaning, immediately protect flooring from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

C. Cover resilient flooring until Substantial Completion.

END OF SECTION 09 65 19

SECTION 09 68 13
TILE CARPETING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Carpet tiles.

B. Related Requirements:

1. Section 024119 "Selective Demolition" for removing existing floor coverings.
2. Section 096513 "Resilient Base and Accessories" for resilient wall base and accessories installed with carpet tile.
3. Section 096816 "Sheet Carpeting" for carpet roll goods.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include manufacturer's written data on physical characteristics, durability, and fade resistance.
2. Include manufacturer's written installation recommendations for each type of substrate.

B. Samples for Verification: Actual Sample of finished products for each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.

1. Carpet Tile: Full-size Sample.
2. Exposed Edge, Transition, and Other Accessory Stripping: 12-inch- long Samples.

C. Product Schedule: For carpet tile. Use same designations indicated on Drawings.

1.3 INFORMATIONAL SUBMITTALS

A. Sample Warranties: For carpet tile.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For carpet tiles. Include the following:

1. Methods for maintaining carpet tile, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
2. Precautions for cleaning materials and methods that could be detrimental to carpet tile.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Comply with CRI 104.

1.6 FIELD CONDITIONS

A. Comply with CRI 104 for temperature, humidity, and ventilation limitations.

B. Environmental Limitations: Do not deliver or install carpet tiles until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at levels planned for building occupants during the remainder of the construction period.

C. Do not install carpet tiles over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended in writing by carpet tile manufacturer.

1.7 WARRANTY

A. Special Warranty for Carpet Tiles: Manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period.

1. Warranty does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
2. Failures include, but are not limited to, the following:

    a. More than 10 percent loss of face fiber, edge raveling, snags, and runs.
    b. Loss of tuft-bind strength.
    c. Excess static discharge.
    d. Delamination.
    e. Dimensional instability.

3. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 CARPET TILES

A. Carpet Tile:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Mannington Commercial; a business unit of Mannington Mills, Inc.
    b. Shaw Industries Group, Inc.; Berkshire Hathaway Company
    c. Tarkett USA

2. Color: Match Architect's samples.
3. Pattern: Match Architect's samples.

4. Pile Characteristic: Cut pile.

5. Primary Backing/Backcoating: Manufacturer's standard composite materials.

6. Size: See schedule on the drawings.
7. Applied Treatments:

8. Performance Characteristics:

    a. Texture Appearance Retention Rating (TARR): Heavy traffic, 3.0 minimum in accordance with ASTM D7330.

    b. Dry Breaking Strength: Not less than 100 lbf in accordance with ASTM D2646.

2.2 ACCESSORIES

A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended in writing by carpet tile manufacturer.

B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive types to suit products and subfloor conditions indicated, that comply with flammability requirements for installed carpet tile, and that are recommended in writing by carpet tile manufacturer for releasable installation.

C. Metal Edge/Transition Strips: Extruded aluminum with mill finish of profile and width shown, of height required to protect exposed edge of carpet, and of maximum lengths to minimize running joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet tile performance.

B. Examine carpet tile for type, color, pattern, and potential defects.

C. Concrete Slabs: Verify that finishes comply with requirements specified in Section 033000 "Cast-in-Place Concrete" and that surfaces are free of cracks, ridges, depressions, scale, and foreign deposits.

1. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.

    a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
    b. Relative Humidity Test: Using in situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.
    c. Perform additional moisture tests recommended in writing by adhesive and carpet tile manufacturers. Proceed with installation only after substrates pass testing.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. General: Comply with CRI 104 and with carpet tile manufacturer's written installation instructions for preparing substrates.

B. Trowelable Leving and Patching Compounds: Use trowelable leveling and patching compounds in accordance with manufacturer's written instructions, to fill cracks, holes, depressions, and protrusions in substrates. Fill or level cracks, holes and depressions 1/8 inch wide or wider, and protrusions more than 1/32 inch unless more stringent requirements are required by manufacturer's written instructions.

C. Concrete Substrates: Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by adhesive and carpet tile manufacturers.

D. Broom and vacuum clean substrates to be covered immediately before installing

carpet tile.

3.3 INSTALLATION OF CARPET TILES

A. General: Comply with CRI 104, Section 10, "Carpet Tile," and with carpet tile manufacturer's written installation instructions.

B. Installation Method: As recommended in writing by carpet tile manufacturer.

C. Maintain dye-lot integrity. Do not mix dye lots in same area.

D. Maintain pile-direction patterns indicated on Drawings.

E. Cut and fit carpet tile to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended in writing by carpet tile manufacturer.

F. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.

G. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on carpet tile as marked on subfloor. Use nonpermanent, nonstaining marking device.

H. Install pattern parallel to walls and borders.

3.4 CLEANING

A. Perform cleaning operations immediately after installing carpet tile as follows:

1. Remove excess adhesive and other surface blemishes using cleaner recommended in writing by carpet tile manufacturer.
2. Remove yarns that protrude from carpet tile surface.
3. Vacuum carpet tile using commercial machine with face-beater element.

3.5 PROTECTION

A. Protect installed carpet tile to comply with CRI 104, Section 13.7.

B. Protect carpet tile against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet tile manufacturer.

END OF SECTION 09 68 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 09 91 23
INTERIOR PAINTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Surface preparation of interior substrates and application of the following:

1. Primers.
2. Water-based finish coatings.
3. Solvent-based finish coatings.
4. Floor sealers and paints.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include preparation requirements and application instructions.
2. Indicate VOC content.

B. Samples for Verification: For each type of paint system and each color and gloss of topcoat. Submit actual paint drawdowns as specified below for verification Samples.

1. Submit Samples on rigid backing, **8 inches** square.
2. Apply coats on Samples in steps to show each coat required for system.
3. Label each coat of each Sample.
4. Label each Sample for location and application area.

C. Product List: Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in applicable interior painting schedule articles to cross-reference paint systems specified in this Section. Include color designations.

1.3 MAINTENANCE MATERIAL SUBMITTALS

A. Extra Stock Material: Furnish extra materials that match paint products applied and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint Products: **5** percent, but not less than **1 gal.** of each material and color applied.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than **45 deg F**.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.5 FIELD CONDITIONS

A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between **50 and 95 deg F**.

B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures of less than **5 deg F** above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each paint product from single source from single manufacturer.

2.2 INTERIOR PAINTS, GENERAL

A. Interior Paints: Subject to compliance with requirements, available products that may be incorporated into the Work include but are not limited to products listed in product types below and applicable interior painting schedule articles for the paint category indicated.

B. Material Compatibility:

1. Materials for use within each paint system must be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer based on testing and field experience.
2. For each coat in a paint system, provide products recommended in writing by topcoat manufacturer for use in paint system and on substrate indicated.

C. Colors: As indicated in a color schedule.

2.3 PRIMERS

A. Interior, Institutional Low-Odor/VOC Primer Sealer: Water-based primer sealer with low-odor characteristics and a VOC of less than 10 grams per liter for use on new interior plaster, concrete, and gypsum wallboard surfaces that are

subsequently to be painted with latex finish coats.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Benjamin Moore & Co.
    b. Pittsburgh Paints Company (The)
    c. Sherwin-Williams Company (The)

B. Alkyd Metal Primer: Corrosion-resistant, solvent-based, alkyd primer formulated for use on prepared ferrous metal substrates subject to industrial and light marine environments.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Benjamin Moore & Co.
    b. Pittsburgh Paints Company (The)

2.4 WATER-BASED FINISH COATINGS

A. Interior, Latex, Institutional Low-Odor/VOC Paint: White or colored latex coating with low-odor characteristics and a VOC of less than 10 grams per liter, for use in areas, such as hospitals and other occupied buildings, where the odor and VOC levels of conventional latex products would preclude their use.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Benjamin Moore & Co.
    b. Pittsburgh Paints Company (The)
    c. Sherwin-Williams Company (The)

2. Gloss and Sheen Level: Manufacturer's standard eggshell.

B. High-Performance Textured Latex Coating: Water-based, pigmented, self-priming coating that contains sand or other hard aggregate for selected texture and is formulated for use on concrete and masonry substrates.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Benjamin Moore & Co.
    b. Pittsburgh Paints Company (The)
    c. Sherwin-Williams Company (The)

2. Gloss and Sheen Level: Manufacturer's standard flat.
3. Texture: Manufacturer's standard.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

1. Cementitious Composition Board: 12 percent.

2. Wood: 15 percent.
3. Gypsum Board: 12 percent. Verify that finishing compound is dry and sanded smooth.
4. Plaster: 12 percent. Verify that plaster is fully cured.

C. Verify suitability of substrates, including surface conditions and compatibility, with finishes and primers. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions applicable to substrates and paint systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Steel Substrates: Remove loose rust, loose mill scale, loose shop primer, and

other loose foreign matter. Clean using methods recommended in writing by paint manufacturer but not less than the following:

1. SSPC-SP 2.
2. SSPC-SP 3.

E. Galvanized Metal Substrates: Remove grease and oil residue from galvanized metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

F. Wood Substrates:

1. Scrape and clean knots. Before applying primer, apply coat of wood-knot sealer.
2. Sand surfaces that will be exposed to view and remove sanding dust.
3. Prime edges, ends, faces, undersides, and backsides of wood.
4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

3.3 APPLICATION OF INTERIOR PAINT PRODUCTS

A. Apply paints in accordance with manufacturer's written instructions.

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
4. Paint entire exposed surface of window frames and sashes.
5. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
6. Primers specified in the applicable interior painting schedule articles may be omitted on items that are factory primed or factory finished if compatible with intermediate and topcoat coatings and acceptable to intermediate and topcoat paint manufacturers.

B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat but provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.

D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

3.4 FIELD QUALITY CONTROL

A. Dry-Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry-film thickness.

1. Touch up and restore painted surfaces damaged by testing.
2. If test results show that dry-film thickness of applied paint does not comply with paint manufacturer's written recommendations, apply additional coats as needed to provide dry-film thickness that complies with paint manufacturer's written recommendations.
3. Cost of retesting is Contractor's responsibility.

3.5 CLEANING

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

1. Do not clean equipment with free-draining water and prevent solvents, thinners, cleaners, and other contaminants from entering into waterways, sanitary and storm drain systems, and ground.
2. Dispose of contaminants in accordance with requirements of authorities having jurisdiction.
3. Allow empty paint cans to dry before disposal.
4. Collect waste paint by type and deliver to recycling or collection facility.

B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

3.6 PROTECTION

A. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

B. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.7 INTERIOR PAINTING SCHEDULE, METAL SUBSTRATES

A. Steel and Iron Substrates:

1. High-Performance Architectural Latex System:

a. Prime Coat: Alkyd metal primer.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Topcoat: Interior, high-performance architectural latex.

1) Gloss and Sheen Level: Semigloss.

3.8 INTERIOR PAINTING SCHEDULE, GYPSUM-BASED SUBSTRATES

A. Gypsum Board and Plaster Substrates:

1. Institutional Low-Odor/VOC Latex System:

a. Prime Coat: Interior, institutional low-odor/VOC primer sealer.
b. Intermediate Coat: Matching topcoat.
c. Topcoat: Interior, latex, institutional low-odor/VOC paint.

1) Gloss and Sheen Level: Eggshell.

END OF SECTION 09 91 23

PAGE LEFT INTENTIONALLY BLANK

SECTION 10 14 23.16
ROOM-IDENTIFICATION PANEL SIGNAGE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Room-identification signs.

1.2 DEFINITIONS

A. Accessible: In accordance with the accessibility standard.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Shop Drawings: For room-identification signs.

1. Include fabrication and installation details and attachments to other work.
2. Show sign mounting heights, locations of supplementary supports to be provided by other installers, and accessories.
3. Show message list, typestyles, graphic elements, including raised characters and Braille, and layout for each sign at least half size.

C. Samples for Initial Selection: For each type of sign assembly, exposed component, and exposed finish.

1. Include representative Samples of available typestyles and graphic symbols.

D. Product Schedule: For room-identification signs. Use same designations indicated on Drawings or specified.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.

2.2 ROOM-IDENTIFICATION SIGNS

A. Room-Identification Sign: Sign with smooth, uniform surfaces; with message and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. ASI Sign Systems, Inc
    b. Best Sign Systems, Inc.
    c. Seton Identification Products; a Brady Corporation company
    d. Signs & Decal Corp

2. Laminated-Sheet Sign: Photopolymer face sheet with raised graphics laminated over subsurface graphics to acrylic backing sheet to produce composite sheet.

    a. Composite-Sheet Thickness: Manufacturer's standard for size of sign.
    b. Surface-Applied Graphics: Applied vinyl film.

    c. Color(s): As selected by Architect from manufacturer's full range.

3. Sign-Panel Perimeter: Finish edges smooth.

    a. Edge Condition: At vertical and horizontal edges; beveled.
    b. Corner Condition in Elevation: As indicated on Drawings.

4. Mounting: Manufacturer's standard method for substrates indicated with two-face tape.
5. Text and Typeface: Accessible raised characters and Braille. Finish raised characters to contrast with background color, and finish Braille to match background color.

2.3 SIGN MATERIALS

A. Acrylic Sheet: ASTM D4802, category as standard with manufacturer for each sign, Type UVF (UV filtering).

B. Vinyl Film: UV-resistant vinyl film with pressure-sensitive, permanent adhesive; die cut to form characters or images as indicated on Drawings.

C. Paints and Coatings for Sheet Materials: Inks, dyes, and paints that are recommended by manufacturer for optimum adherence to surface and are UV and water resistant for colors and exposure indicated.

2.4 ACCESSORIES

A. Adhesive: As recommended by sign manufacturer.

B. Two-Face Tape: Manufacturer's standard high-bond, foam-core tape, **0.045 inch** thick, with adhesive on both sides.

2.5 FABRICATION

A. General: Provide manufacturer's standard sign assemblies in accordance with requirements indicated.

1. Preassemble signs and assemblies in the shop to greatest extent possible. Disassemble signs and assemblies only as necessary for shipping and handling limitations. Clearly mark units for reassembly and installation; apply markings in locations concealed from view after final assembly.
2. Mill joints to a tight, hairline fit. Form assemblies and joints exposed to weather to resist water penetration and retention.
3. Conceal connections if possible; otherwise, locate connections where they are inconspicuous.
4. Provide rabbets, lugs, and tabs necessary to assemble components and to attach to existing work. Drill and tap for required fasteners. Use concealed fasteners where possible; use exposed fasteners that match sign finish.

B. Subsurface-Applied Graphics: Apply graphics to back face of clear face-sheet material to produce precisely formed image. Image must be free of rough edges.

2.6 GENERAL FINISH REQUIREMENTS

A. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 INSTALLATION OF ROOM-IDENTIFICATION SIGNS

A. General: Install signs using mounting methods indicated and in accordance with manufacturer's written instructions.

1. Install signs level, plumb, true to line, and at locations and heights indicated, with sign surfaces free of distortion and other defects in appearance.

2. Install signs so they do not protrude or obstruct in accordance with the accessibility standard.
3. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.

B. Accessibility: Install signs in locations on walls as indicated on Drawings in accordance with the accessibility standard.

C. Mounting Methods:

1. Two-Face Tape: Clean bond-breaking materials from substrate surface and remove loose debris. Apply tape strips symmetrically to back of sign and of suitable quantity to support weight of sign without slippage. Keep strips away from edges to prevent visibility at sign edges. Place sign in position, and push to engage tape adhesive.

3.2 ADJUSTING

A. Remove and replace damaged or deformed signs and signs that do not comply with specified requirements. Replace signs with damaged or deteriorated finishes or components that cannot be successfully repaired by finish touchup or similar minor repair procedures.

3.3 CLEANING

A. Remove temporary protective coverings and strippable films as signs are installed.

B. On completion of installation, clean exposed surfaces of signs in accordance with manufacturer's written instructions, and touch up minor nicks and abrasions in finish. Maintain signs in a clean condition during construction and protect from damage until acceptance by Owner.

END OF SECTION 10 14 23.16

SECTION 10 26 00
WALL AND DOOR PROTECTION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Corner guards.
2. End-wall guards.
3. Abuse-resistant wall coverings.

1.2 ACTION SUBMITTALS

A. Product Data: For each specified system and assembly, including components and accessories.

1. Include construction details, material descriptions, impact strength, dimensions of individual components and profiles, and finishes.
2. Include fire ratings of units recessed in fire-rated walls and listings for door protection items attached to fire-rated doors.

B. Samples for Initial Selection: For each type of impact-resistant wall protection unit indicated, in each color and texture specified.

1. Include Samples of accent strips and accessories to verify color selection.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of wall and door protection product.

1. Include recommended methods and frequency of maintenance for maintaining best condition of plastic covers under anticipated traffic and use conditions. Include precautions against using cleaning materials and methods that may be detrimental to finishes and performance.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store wall and door protection in original undamaged packages and containers inside well-ventilated area protected from weather, moisture, soiling, extreme temperatures, and humidity.

1. Maintain room temperature within storage area at not less than **70 deg F** during the period plastic materials are stored.

2. Keep plastic materials out of direct sunlight.
3. Store plastic wall and door protection components for a minimum of 72 hours, or until plastic material attains a minimum room temperature of **70 deg F**.

    a. Store corner-guard covers in a vertical position.
    b. Store wall-guard covers in a horizontal position.

1.5 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of wall and door protection units that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

    a. Structural failures, including detachment of components from each other or from the substrates, delamination, and permanent deformation beyond normal use.
    b. Deterioration of metals, metal finishes, plastics, and other materials beyond normal use.

2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain wall and door protection products of each type from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E84 or UL 723; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 450 or less.

B. Regulatory Requirements: Comply with applicable provisions in the United States Access Board's ADA-ABA Accessibility Guidelines and ICC A117.1.

C. Structural Performance: Handrails, including attachment to building construction, must withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated:

1. Uniform load of 50 lbf/ft. applied in any direction.
2. Concentrated load of **200 lbf** applied in any direction.
3. Uniform and concentrated loads need not be assumed to act concurrently.

2.3 ABUSE-RESISTANT WALL COVERINGS

A. Abuse-Resistant Sheet Wall Covering: Fabricated from semirigid, plastic sheet wall-covering material.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Construction Specialties, Inc.
b. inpro Corporation
c. Koroseal Interior Products, LLC

2. Size: 48 by 96 inches for sheet.
3. Sheet Thickness: 0.040 inch.
4. Color and Texture: As selected by Architect from manufacturer's full range.
5. Height: As indicated.
6. Trim and Joint Moldings: Extruded, rigid plastic that matches wall-covering color.
7. Mounting: Adhesive.

2.4 MATERIALS

A. Plastic Materials: Chemical- and stain-resistant, high-impact-resistant plastic with integral color throughout; extruded and sheet material as required; thickness as indicated.

B. Polycarbonate Plastic Sheet: ASTM D6098, S-PC01, Class 1 or Class 2, abrasion resistant; with a minimum impact-resistance rating of **15 ft.-lbf/in.** of notch when tested in accordance with ASTM D256, Test Method A.

C. Fasteners: Aluminum, nonmagnetic stainless steel, or other noncorrosive metal screws, bolts, and other fasteners compatible with items being fastened. Use security-type fasteners where exposed to view.

D. Adhesive: As recommended in writing by protection product manufacturer.

2.5 FABRICATION OF WALL AND DOOR PROTECTION

A. Fabricate wall and door protection in accordance with requirements indicated for design, performance, dimensions, and member sizes, including thicknesses of components.

B. Factory Assembly: Assemble components in factory to greatest extent possible

to minimize field assembly. Disassemble only as necessary for shipping and handling.

C. Quality: Fabricate components with uniformly tight seams and joints and with exposed edges rolled. Provide surfaces free of wrinkles, chips, dents, uneven coloration, and other imperfections. Fabricate members and fittings to produce flush, smooth, and rigid hairline joints.

2.6 FINISHES

A. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

B. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and wall areas, with Installer present, for compliance with requirements for installation tolerances, fire rating, and other conditions affecting performance of the Work.

B. Examine walls to which wall and door protection will be attached for blocking, grounds, and other solid backing that have been installed in the locations required for secure attachment of support fasteners.

1. For wall and door protection attached with adhesive, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Complete finishing operations, including painting, before installing wall and door protection.

B. Before installation, clean substrate to remove dust, debris, and loose particles.

3.3 INSTALLATION OF WALL AND DOOR PROTECTION

A. Install wall and door protection in accordance with manufacturer's written instructions, level, plumb, and true to line without distortions. Do not use materials with chips, cracks, voids, stains, or other defects that might be visible in the finished Work.

B. Accessories: Provide splices, mounting hardware, anchors, trim, joint moldings, and other accessories required for a complete installation.

1. Provide anchoring devices and suitable locations to withstand imposed loads.
2. Where splices occur in horizontal runs of more than **20 ft.**, splice aluminum retainers and plastic covers at different locations along the run, but no closer than **12 inches** apart.
3. Adjust end and top caps as required to ensure tight seams.

C. Abuse-Resistant Wall Coverings: Install top and edge moldings, corners, and divider bars as required for a complete installation.

3.4 CLEANING

A. Immediately after completion of installation, clean plastic covers and accessories using a standard ammonia-based household cleaning agent.

B. Remove excess adhesive using methods and materials recommended in writing by manufacturer.

END OF SECTION 10 26 00

PAGE LEFT INTENTIONALLY BLANK

SECTION 10 28 00
TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Public-use washroom accessories.

2. Childcare accessories.
3. Underlavatory guards.

4. Hand-sanitizer dispensers.

B. Related Requirements:

1. Section 088300 "Mirrors" for frameless mirrors.
2. Section 093013 "Ceramic Tiling" for ceramic toilet and bath accessories.
3. Section 102813.63 "Detention Toilet Accessories" for accessories designed for installation in detention facilities.

1.2 ALTERNATES

A. See Section 012300 "Alternates" for description of alternates affecting items specified in this Section.

1.3 COORDINATION

A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
3. Include electrical characteristics.

B. Product Schedule: Indicating types, quantities, sizes, and installation locations

by room of each accessory required.

1. Identify locations using room designations indicated.
2. Identify accessories using designations indicated.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For accessories to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Structural Performance: Design accessories and fasteners to comply with the following requirements:

1. Grab Bars: Installed units are able to resist **250 lbf** minimum concentrated load applied in any direction and at any point.

2.2 PUBLIC-USE WASHROOM ACCESSORIES

A. Source Limitations: Obtain public-use washroom accessories from single source from single manufacturer.

B. Waste Receptacle:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Bobrick Washroom Equipment, Inc. or comparable product by one of the following:

a. ASI-American Specialties, Inc.
b. Bradley Corporation
c. Brey-Krause Manufacturing Co.

2. Mounting: Semirecessed.

3. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).
4. Liner: Reusable vinyl liner.
5. Lockset: Tumbler type for waste receptacle.

C. Grab Bars:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Bobrick Washroom Equipment or comparable product by one of the following:

    a. ASI-American Specialties, Inc.
    b. Bradley Corporation
    c. Brey-Krause Manufacturing Co.

2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, **0.05 inch** thick.

    a. Finish: Smooth, ASTM A480/A480M No. 4 finish (satin).

4. OD: 1-1/2 inches.
5. Configuration and Length: As indicated on Drawings.

D. Seat-Cover Dispenser:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Georgia-Pacific or comparable product by one of the following:

    a. ASI-American Specialties, Inc.
    b. Bobrick Washroom Equipment, Inc
    c. Bradley Corporation

2. Mounting: Surface mounted.

3. Exposed Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

E. Mirror Unit:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Bobrick Washroom Equipment, Inc. or comparable product by one of the following:

    a. ASI-American Specialties, Inc.
    b. Bradley Corporation
    c. Brey-Krause Manufacturing Co.

2. Frame: Stainless steel channel.

    a. Corners: Manufacturer's standard.

3. Size: As indicated on Drawings.

F. Hook:

1. Manufacturers: Subject to compliance with requirements, provide products by the following:

a. ASI-American Specialties, Inc.
b. Bobrick Washroom Equipment, Inc
c. Bradley Corporation

2. Description: Combination hat and coat hook.
3. Mounting: Concealed.
4. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin).

2.3 PRIVATE-USE BATHROOM ACCESSORIES

A. Source Limitations: Obtain private-use bathroom accessories from single source from single manufacturer.

2.4 CHILDCARE ACCESSORIES

A. Source Limitations: Obtain childcare accessories from single source from single manufacturer.

B. Diaper-Changing Station:

1. Manufacturers: Subject to compliance with requirements, provide products by the following:

a. ASI-American Specialties, Inc.
b. Koala Kare Products; Bobrick Washroom Equipment, Inc.
c. Safe-Strap Company, LLC

2. Description: Horizontal unit that opens by folding down from stored position and with child-protection strap.

a. Structural Performance: Engineered to support minimum of 250 lb static load when opened.

3. Mounting: Surface mounted, with unit projecting not more than 4 inches from wall when closed.
4. Operation: By pneumatic shock-absorbing mechanism.
5. Material and Finish: Stainless steel, ASTM A480/A480M No. 4 finish (satin), exterior shell with rounded plastic corners; HDPE interior in manufacturer's standard color.
6. Liner Dispenser: Provide built-in dispenser for disposable sanitary liners.

2.5 UNDERLAVATORY GUARDS

A. Underlavatory Guard:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Truebro LavShield or comparable product by one of the following:

a. Buckaroos, Inc.
b. Plumberex Specialty Products, Inc.
c. ProFlo; a Ferguson Enterprises, Inc. brand

2. Description: Insulating pipe covering for supply and drain piping assemblies that prevents direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.6 HAND-SANITIZER DISPENSERS

A. Source Limitations: Obtain hand-sanitizer dispensers from single source from single manufacturer.

B. Hand-Sanitizer Dispenser:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. GOJO Industries
b. Rubbermaid Commercial Products
c. Tork; Essity Professional Hygiene North America LLC

2. Description: Manually operated dispenser with drip tray, designed for dispensing alcohol-based hand rub in gel form. Designed to not release contents unless manually activated and to not dispense more hand rub than the amount required for hand hygiene consistent with label instructions.
3. Mounting: Wall mounted.

a. Protrusion Limit: Installed unit protrudes maximum **4 inches** from wall surface.

4. Materials: ABS plastic, dark gray.
5. Lockset: Tumbler type.
6. Refill Indicator: Window type.

2.7 FABRICATION

A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.

B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION OF TOILET, BATH, AND LAUNDRY ACCESSORIES

A. Install accessories in accordance with manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer in writing. Install units level, plumb, and firmly anchored in locations and at heights indicated.

1. Remove temporary labels and protective coatings.

B. Grab Bars: Install to comply with specified structural-performance requirements.

C. Folding Shower Seats: Install to comply with specified structural-performance requirements.

D. Private-Use Folding Shower Seats: Install to comply with specified structural-performance requirements.

3.2 ADJUSTING

A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.

3.3 CLEANING

A. Clean and polish exposed surfaces in accordance with manufacturer's written instructions.

END OF SECTION 10 28 00

SECTION 10 44 13
FIRE PROTECTION CABINETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fire-protection cabinet.

B. Related Requirements:

1. Section 104416 "Fire Extinguishers" for portable, hand-carried fire extinguishers accommodated by fire-protection cabinets.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Show door hardware, cabinet type, trim style, and panel style. Include roughing-in dimensions and details showing recessed-, semirecessed-, or surface-mounting method and relationships of box and trim to surrounding construction.
2. Show location of knockouts for hose valves.

B. Shop Drawings: For fire-protection cabinets.

1. Include plans, elevations, sections, and attachment details.

C. Product Schedule: For fire-protection cabinets. Indicate whether recessed, semirecessed, or surface mounted. Coordinate final fire-protection cabinet schedule with fire-extinguisher schedule to ensure proper fit and function. Use same designations indicated on Drawings.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance Data: For fire-protection cabinets.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain fire-protection cabinets, accessories, and fire extinguishers from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Fire-Rated Fire-Protection Cabinets: Listed and labeled to comply with requirements in ASTM E814 for fire-resistance rating of walls where they are installed.

2.3 FIRE-PROTECTION CABINETS

A. Fire-Protection Cabinet:

1. Basis-of-Design Product: Subject to compliance with requirements, provide Ambassador Architectural Series by JL Industries or comparable product by one of the following:

    a. Larsen's Manufacturing Company
    b. Nystrom, Inc.
    c. Potter Roemer LLC; a Division of Morris Group International

2. Fire-Protection Cabinet Type: Suitable for fire extinguisher.
3. Cabinet Construction: Nonrated.

4. Cabinet Material: Cold-rolled steel sheet.

    a. Shelf: Same metal and finish as cabinet.

5. Semirecessed Cabinet: One-piece combination trim and perimeter door frame overlapping surrounding wall surface, with exposed trim face and wall return at outer edge (backbend).

    a. Square-Edge Trim: **1-1/4- to 1-1/2-inch** backbend depth.

6. Cabinet Trim Material: Same material and finish as door.
7. Door Material: Steel sheet.
8. Door Style: Vertical duo panel with frame.
9. Door Glazing: Tempered float glass (clear).

10. Door Hardware: Manufacturer's standard door-operating hardware of proper type for cabinet type, trim style, and door material and style indicated.

    a. Provide manufacturer's standard.
    b. Provide continuous hinge, of same material and finish as trim, permitting door to open 180 degrees.

11. Accessories:

    a. Mounting Bracket: Manufacturer's standard steel, designed to secure fire extinguisher to fire-protection cabinet, of sizes required for types and capacities of fire extinguishers indicated, with plated or baked-enamel finish.

b. Lettered Door Handle: One-piece, cast-iron door handle with the word "FIRE" embossed into face.

c. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated.

1) Identify fire extinguisher in fire-protection cabinet with the words " **FIRE EXTINGUISHER**."

a) Location: Applied to cabinet door.
b) Application Process: Silk-screened.
c) Lettering Color: Red.
d) Orientation: Vertical.

12. Materials:

a. Cold-Rolled Steel: ASTM A1008/A1008M, Commercial Steel (CS), Type B.

1) Finish: Baked enamel, TGIC polyester powder coat, HAA polyester powder coat, epoxy powder coat, or polyester/epoxy hybrid powder coat, complying with AAMA 2603.
2) Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
3) Color: As selected by Architect from manufacturer's full range.

b. Tempered Float Glass: ASTM C1048, Kind FT, Condition A, Type I, Quality q3, 3 mm thick, Class 1 (clear).

2.4 FABRICATION

A. Fire-Protection Cabinets: Provide manufacturer's standard box (tub) with trim, frame, door, and hardware to suit cabinet type, trim style, and door style indicated.

1. Weld joints and grind smooth.
2. Miter corners and grind smooth.
3. Provide factory-drilled mounting holes.
4. Prepare doors and frames to receive locks.
5. Install door locks at factory.

B. Cabinet Doors: Fabricate doors according to manufacturer's standards, from materials indicated and coordinated with cabinet types and trim styles.

1. Fabricate door frames with tubular stiles and rails and hollow-metal design, minimum **1/2 inch** thick.
2. Fabricate door frames of one-piece construction with edges flanged.
3. Miter and weld perimeter door frames and grind smooth.

C. Cabinet Trim: Fabricate cabinet trim in one piece with corners mitered, welded, and ground smooth.

2.5 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM AMP 500for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces of fire-protection cabinets from damage by applying a strippable, temporary protective covering before shipping.

C. Finish fire-protection cabinets after assembly.

D. Appearance of Finished Work: Noticeable variations in same piece are unacceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine walls and partitions for suitable framing depth and blocking where semirecessed cabinets will be installed.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare recesses for semirecessed fire-protection cabinets as required by type and size of cabinet and trim style.

3.3 INSTALLATION OF FIRE-PROTECTION CABINETS

A. General: Install fire-protection cabinets in locations and at mounting heights indicated or, if not indicated, at height indicated below:

1. Fire-Protection Cabinet Mounting Height: 42 inches above finished floor to top of fire extinguisher.

B. Fire-Protection Cabinets: Fasten cabinets to structure, square and plumb.

1. Unless otherwise indicated, provide recessed fire-protection cabinets. If wall thickness is inadequate for recessed cabinets, provide semirecessed fire-protection cabinets.

2. Fasten mounting brackets to inside surface of fire-protection cabinets, square and plumb.

3.4 ADJUSTING

A. Remove temporary protective coverings and strippable films, if any, as fire-protection cabinets are installed unless otherwise indicated in manufacturer's written installation instructions.

B. Adjust fire-protection cabinet doors to operate easily without binding. Verify that integral locking devices operate properly.

3.5 CLEANING

A. On completion of fire-protection cabinet installation, clean interior and exterior surfaces as recommended by manufacturer.

B. Touch up marred finishes, or replace fire-protection cabinets that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by fire-protection cabinet and mounting bracket manufacturers.

C. Replace fire-protection cabinets that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 10 44 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 10 44 16
FIRE EXTINGUISHERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Portable, hand-carried fire extinguishers.

B. Owner-Furnished Material: Hand-carried fire extinguishers.

C. Related Requirements:

1. Section 104413 "Fire Protection Cabinets."

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include rating and classification, material descriptions, dimensions of individual components and profiles, and finishes for fire extinguisher.

B. Product Schedule: For fire extinguishers. Coordinate final fire-extinguisher schedule with fire-protection cabinet schedule to ensure proper fit and function.

1.3 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For fire extinguishers to include in maintenance manuals.

1.4 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace fire extinguishers that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Failure of hydrostatic test in accordance with NFPA 10 when testing interval required by NFPA 10 is within the warranty period.
b. Faulty operation of valves or release levers.

2. Warranty Period: Six years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. NFPA Compliance: Fabricate and label fire extinguishers to comply with NFPA 10, "Portable Fire Extinguishers."

B. Fire Extinguishers: Listed and labeled for type, rating, and classification by an independent testing agency acceptable to authorities having jurisdiction.

1. Provide fire extinguishers approved, listed, and labeled by FM Approvals.

2.2 PORTABLE, HAND-CARRIED FIRE EXTINGUISHERS

A. Hand-Carried Fire Extinguishers: Type, size, and capacity for each fire-protection cabinet indicated.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. JL Industries; Activar Construction Products Group, Inc.
b. Kidde; Carrier Global Corporation
c. Larsen's Manufacturing Company
d. Nystrom, Inc.

2. Source Limitations: Obtain fire extinguishers, fire-protection cabinets, and accessories from single source from single manufacturer.
3. Valves: Manufacturer's standard.
4. Handles and Levers: Manufacturer's standard.
5. Instruction Labels: Include pictorial marking system complying with NFPA 10, Appendix B.

6. Multipurpose Dry-Chemical Type in Steel Container: UL-rated 3-A:40-B:C, 6-lb nominal capacity, with monoammonium phosphate-based dry chemical in enameled-steel container.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine fire extinguishers for proper charging and tagging.

1. Remove and replace damaged, defective, or undercharged fire extinguishers.

B. Proceed with installation only after unsatisfactory conditions have been

corrected.

3.2 INSTALLATION OF FIRE EXTINGUISHERS

A. General: Install fire extinguishers in locations indicated and in compliance with requirements of authorities having jurisdiction.

B. Mounting Brackets: Fasten mounting brackets to surfaces, square and plumb, at locations indicated.

1. Mounting Height: Top of fire extinguisher to be at 42 inches above finished floor.

END OF SECTION 10 44 16

PAGE LEFT INTENTIONALLY BLANK

ECTION 10 73 13
AWNINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fixed awnings.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include styles, material descriptions, construction details, fabrication details, dimensions of individual components and profiles, hardware, fittings, mounting accessories, features, and finishes for awnings.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

B. Shop Drawings:

1. Include plans, elevations, sections, mounting heights, and attachment details.
2. Detail fabrication and assembly of awnings.

3. Show locations for blocking, reinforcement, and supplementary structural support.

C. Samples: For each exposed product and for each color and texture specified.

D. Product Schedule: For awnings. Use same designations indicated on Drawings.

1.3 INFORMATIONAL SUBMITTALS

A. Welding certificates.

B. Sample Warranty: For special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For awnings to include in operation and maintenance manuals.

1.5 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

B. Installer Qualifications: Fabricator of products.

C. Welding Qualifications: Qualify procedures and personnel according to the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum."

1.6 WARRANTY

A. Special Warranty: Manufacturer and fabricator agree to repair or replace components of awnings that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including framework.

b. Deterioration of metals, metal finishes, and other materials beyond normal weathering.

1.7 DELIVER, STORAGE AND HANDLING

A. Canopy must conform to local building codes.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Canopy must conform to local building codes.

B. PE Stamped calculations are required and must be signed and sealed by an engineer licensed within the state canopy is installed.

2.2 AWNING FRAME AND ACCESSORY MATERIALS

A. Aluminum: Alloy and temper recommended by awning manufacturer for type of use and finish indicated and with not less than the strength and durability properties of alloy and temper required by structural loads.

1. Aluminum Plate and Sheet: **ASTM B209**.

2. Intermediate framing members shall be extruded aluminum, alloy 6063-T6, in profile and thickness.
3. Hanger rods and attachment hardware shall be a standard finish.
4. Fascia shall be standard extruded 8" J style.
5. Fascia shall be standard extruded 8" J style.
6. Drawn Seamless Tubing: **ASTM B210**.
7. Decking shall consist of 3" extruded flat soffit .078 decking.

B. Anchors, Fasteners, Fittings, Hardware, and Installation Accessories: Complying with performance requirements indicated and suitable for exposure conditions, supporting structure, anchoring substrates, and installation methods indicated. Corrosion-resistant or noncorrodible units; weather-resistant, tamperproof, vandal- and theft-resistant, compatible, nonstaining materials. Provide as required for awning assembly, mounting, and secure attachment. Number as needed to comply with performance requirements and to maintain uniform appearance; evenly spaced. Where exposed to view, provide finish and color as selected by Architect from manufacturer's full range.

1. Lag Bolts: **ASME B18.2.1**.
2. Zinc-Coated High-Strength Bolts, Nuts, and Washers: ASTM F3125/F3125M,**Grade A325**, Type 1, heavy-hex steel structural bolts; **ASTM A563, Grade DH,** heavy-hex carbon-steel nuts; and ASTM F436/F436M, Type 1, hardened carbon-steel washers, zinc coated.

3. Adhesive-Bonded Anchors: Anchor bolt and sleeve assembly with capability to sustain, without failure, a load equal to six times the load imposed when installed in unit masonry assemblies and equal to four times the load imposed when installed in concrete as determined by testing according to ASTM E1512 conducted by a qualified independent testing and inspecting agency.

    a. Material: Stainless steel with bolts and nuts complying with **ASTM F593 and ASTM F594, Alloy Group 1 or 2**.

C. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D1187.

2.3 FIXED AWNINGS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Super Lumideck by Mapes Canopies or comparable product by one of the following:

1. Architectural Louvers Company
2. Vestis Manufacturing
3. Lawrence Fabric & Metal Structures

B. Aluminum Finish: 2-Coat Kynar finish complying with finish manufacturer's written instructions for surface preparation including pretreatment, application, baking, and minimum dry film thickness.

1. Color: As selected by Architect from manufacturer's full range.

2.4 FIXED AWNING FABRICATION

A. All connections shall be mechanically assembled utilizing 3/16 fasteners with a minimum shear stress of 350 lb. Pre-welded or factory-welded connections are not acceptable.

B. Concealed drainage. Water shall drain from covered surfaces into intermediate trough and be directed to Downspout From Rear Gutter.

C.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for supporting members, blocking, inserts, installation tolerances, operational clearances, accurate locations of connections to building electrical system, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Install awnings at locations and in position indicated, securely connected to supports, free of rack, and in proper relation to adjacent construction. Use mounting methods of types described and in compliance with Shop Drawings and fabricator's written instructions.

B. Install awnings after other finishing operations, including joint sealing and painting, have been completed.

C. Slip fit frame connections accurately together to form hairline joints, and tighten to secure.

D. Anchoring to In-Place Construction: Use anchors, fasteners, fittings, hardware, and installation accessories where necessary for securing awnings to structural support and for properly transferring load to in-place construction.

E. Corrosion Protection: Coat concealed surfaces of aluminum that come in contact with grout, concrete, masonry, wood, or dissimilar metals with a heavy coat of bituminous paint.

F. Coordinate awning installation with flashing and joint-sealant installation so these

materials are installed in sequence and in a manner that prevents exterior moisture from passing through completed exterior wall and roof assemblies.

3.3 CLEANING AND PROTECTION

A. Touch up factory-applied finishes to restore damaged or soiled areas.

END OF SECTION 10 73 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 12 24 13
ROLLER WINDOW SHADES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Manually operated, single-roller shades.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood blocking and grounds for mounting roller shades and accessories.
2. Section 079200 "Joint Sealants" for sealing the perimeters of installation accessories for light-blocking shades with a sealant.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include rated capacities, operating characteristics, electrical characteristics, features, and furnished accessories.

B. Shop Drawings:

1. Show fabrication and installation details for roller shades, including shadeband materials, their orientation to rollers, and their seam and batten locations.
2. Motor-Operated Shades: Include diagrams for power, signal, and control wiring.

C. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type and color of shadeband material and for each type of exposed finish.

1. Include Samples of accessories involving color selection.

D. Samples for Verification: Actual Sample of finished products for each type of roller shade including actual shadeband material and installation accessories.

1. Size: Manufacturers' standard size.

E. Product Schedule: For roller shades. Use same designations indicated on

Drawings.

1.3 INFORMATIONAL SUBMITTALS

A. Product Certificates: For each type of shadeband material.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For roller shades.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver roller shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

1.7 FIELD CONDITIONS

A. Environmental Limitations: Do not install roller shades until construction and finish work in spaces, including painting, is complete and dry and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operating hardware of operable glazed units through entire operating range. Notify Architect of installation conditions that vary from Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of products that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Defects in materials and workmanship beyond normal wear and tear.
b. Faulty operation of operating system components.
c. Deterioration of fabric beyond normal use.

2. Warranty Period:

a. Roller Window Shades: 10 year(s) from date of Substantial Completion.

b. Fabric: 10 year(s) from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain roller shades from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

A. Window Covering Safety Standard: Provide roller window shades that comply with WCMA A100.1 and are listed and labeled as "Best for Kids" by a qualified testing agency.

B. Fire Performance: Tested in accordance with and meeting the flame propagation performance criteria of Test 1 or Test 2, as appropriate, of NFPA 701; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

C. Accessibility Standards: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1 for roller window shades designated as accessible.

2.3 MANUALLY OPERATED ROLLER WINDOW SHADES

A. Manually Operated, Single-Roller Shades: For interior use in rectangular openings.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Lutron Electronics or comparable product by one of the following:

a. Draper, Inc.
b. Insolroll Window Shading Systems
c. MechoShade Systems, LLC

2. Rollers: Corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shadebands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shadebands for service.

a. Roller Drive-End Location: Right side of interior face of shade.

b. Direction of Shadeband Roll: Regular, from back (exterior face) of roller.
c. Shadeband-to-Roller Attachment: Manufacturer's standard method.

3. Roller-Coupling Assemblies: Coordinated with operating mechanism and designed to join up to six inline rollers into a multiband shade that is operated by one roller drive-end assembly.
4. Shadebands:

a. Shadeband Material: Light-filtering fabric.
b. Shadeband Bottom (Hem) Bar: Steel or extruded aluminum.

1) Type: Elliptical slat with endcaps, enclosed in open pocket of shadeband material.
2) Color and Finish: As selected by Architect from manufacturer's full range.

5. Mounting Hardware: Brackets or endcaps, with endcap covers where exposed, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and installation location and conditions indicated.
6. Installation Accessories:

a. Front Fascia: Aluminum extrusion that conceals front and underside of roller and shadeband assembly and attaches to roller endcaps without exposed fasteners.

1) Shape: **L-shaped**
2) Height: Manufacturer's standard height required to conceal roller and shadeband assembly when shade is fully open, but not less than **4 inches**.

b. Installation Accessories Color and Finish: As selected from manufacturer's full range.

2.4 MANUAL OPERATION

A. Manual Corded Operation:

1. Chain-and-Clutch Operating Mechanisms: With continuous-loop bead chain and clutch that stops shade movement when bead chain is released; permanently adjusted and lubricated.

a. Bead Chains: Stainless steel bead chain with WCMA A100.1 compliant tension device installed on roller window shade by manufacturer and mounted on jamb.

1) Loop Length: Full length of roller shade.
2) Limit Stops: Provide upper and lower ball stops.

b. Spring Lift-Assist Mechanisms: Manufacturer's standard for balancing roller shade weight and for lifting heavy roller shades.

1) Provide for shadebands that weigh more than 10 lb or for shades as recommended by manufacturer, whichever criterion is more stringent.

2.5 SHADEBAND MATERIALS

A. Light-Filtering Fabric: Woven fabric, stain and fade resistant.

1. Source: Roller shade manufacturer.

a. Basis of Design: Basketweave Eco2 by Lutron Frabics.

2. Type: Thermoplastic Olefin (TPO).
3. Weave: Basketweave.
4. Thickness: 0.03 inches.

5. Orientation on Shadeband: As indicated on Drawings.
6. Openness Factor: 3 percent.
7. Color: As selected by Architect from manufacturer's full range.

2.6 FABRICATION OF ROLLER WINDOW SHADES

A. Unit Sizes: Fabricate units in sizes to fill window and other openings as follows, measured at **74 deg F**:

1. Between (Inside) Jamb Installation: Width equal to jamb-to-jamb dimension of opening in which shade is installed less **1/4 inch** per side or **1/2-inch** total, plus or minus **1/8 inch**. Length equal to head-to-sill or -floor dimension of opening in which shade is installed less **1/4 inch**, plus or minus **1/8 inch**.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF ROLLER WINDOW SHADES

A. Install roller shades level, plumb, aligned and centered on openings, and aligned with adjacent units in accordance with manufacturer's written instructions.

1. Located so shadeband is not closer than 2 inches to interior face of glass. Allow clearances for window operation hardware.

B. Roller Shade Locations: At exterior windows.

3.3 ADJUSTING

A. Adjust and balance roller window shades to operate smoothly, easily, safely, and free from binding or malfunction through full operational range.

3.4 CLEANING

A. Clean roller window shade surfaces, after installation, in accordance with manufacturer's written instructions.

B. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

3.5 PROTECTION

A. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller window shades are without damage or deterioration at time of Substantial Completion.

3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain motor-operated roller window shades.

END OF SECTION 12 24 13

SECTION 12 35 53.16
PLASTIC-LAMINATE-CLAD LABORATORY CASEWORK

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Auxiliary cabinets.
2. Countertops.
3. Laboratory accessories.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood blocking for anchoring laboratory casework.
2. Section 092216 "Non-Structural Metal Framing" for reinforcements in metal-framed partitions for anchoring laboratory casework.
3. Section 096513 "Resilient Base and Accessories" for resilient base applied to laboratory casework.

1.2 COORDINATION

A. Coordinate layout and installation of framing and reinforcements for support of laboratory casework.

B. Coordinate installation of laboratory casework with installation of laboratory equipment.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Shop Drawings: For laboratory casework.

1. Include plans, elevations, sections, and attachments to other work including blocking and reinforcements required for installation.
2. Indicate types and sizes of casework.
3. Indicate manufacturer's catalog numbers for casework.
4. Show fabrication details, including types and locations of hardware.
5. Indicate locations and types of service fittings.
6. Include details of utility spaces showing supports for conduits and piping.
7. Include details of exposed conduits, if required, for service fittings.
8. Indicate locations of and clearances from adjacent walls, doors, windows, other building components, and laboratory equipment.

9. Include coordinated dimensions for laboratory equipment specified in other Sections.

C. Keying Schedule: Include schematic keying diagram, and index each key set to unique designations that are coordinated with the Contract Documents.

D. Samples for Verification: For each type of casework, exposed-hardware, and countertop-material finish, in manufacturer's standard sizes.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Protect finished surfaces during handling and installation with protective covering of polyethylene film or other suitable material.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install laboratory casework until building is enclosed, utility roughing-in and wet-work are complete, and HVAC system is operating and maintaining temperature and relative humidity at levels planned for building occupants during the remainder of the construction period.

B. Established Dimensions: Where laboratory casework is indicated to fit to other construction, establish dimensions for areas where casework is to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

C. Field Measurements: Where laboratory casework is indicated to fit to existing construction, verify dimensions of existing construction by field measurements before fabrication and indicate measurements on Shop Drawings. Provide fillers and scribes to allow for trimming and fitting.

D. Locate concealed framing, blocking, and reinforcements that support casework by field measurements before enclosing them, and indicate measurements on Shop Drawings.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain laboratory casework from single source from single manufacturer unless otherwise indicated.

B. Obtain countertops from casework manufacturer.

C. Product Designations: Drawings indicate sizes and configurations of laboratory casework by referencing designated manufacturer's catalog numbers. Other manufacturers' laboratory casework of similar sizes and similar door and drawer

configurations and complying with the Specifications may be considered. See Section 016000 "Product Requirements."

2.2 COUNTERTOPS

A. General: Provide laboratory countertops with integral sink as indicated on Drawings.

B. Epoxy: Factory-molded, modified epoxy-resin formulation with smooth, nonspecular finish.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Epoxy Scientific LLC
b. Durcon; a Wilsonart Company
c. Prime Industries, Inc

2. Physical Properties:

a. Flexural Strength: Not less than **10,000 psi**.
b. Modulus of Elasticity: Not less than **2,000,000 psi**.
c. Hardness (Rockwell M): Not less than 100.
d. Water Absorption (24 Hours): Not more than 0.02 percent.
e. Heat Distortion Point: Not less than **260 deg F**.
f. Chemical Resistance: Minimum acceptable chemical-resistance performance to result in no more than four (4) Level 3 conditions when tested with indicated reagents in accordance with SEFA 3.

3. Color: As selected by Architect from epoxy manufacturer's full range.

2.3 COUNTERTOP FABRICATION

A. Countertops, General: Provide units with smooth surfaces in uniform plane, free of defects. Make exposed edges and corners straight and uniformly beveled. Provide front and end overhang of **1 inch**.

B. Epoxy:

1. Countertops: Fabricate with factory cutouts for sinks, holes for service fittings and accessories, and butt joints assembled with epoxy adhesive and concealed metal splines.

a. Flat Configuration: 1 inch thick with continuous drip groove on underside **1/2 inch** from overhang edge.

1) Edges and Corners: Beveled.
2) Backsplash: Integral coved.

b. Construction: Uniform throughout full thickness.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances, location of reinforcements, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF COUNTERTOPS

A. Comply with installation requirements in SEFA 2. Abut top and edge surfaces true in plane with flush hairline joints and with internal supports placed to prevent deflection. Locate joints where indicated on Shop Drawings.

B. Field Jointing: Where possible, make in same manner as shop-made joints, using dowels, splines, fasteners, adhesives, and sealants recommended by manufacturer. Shop prepare edges for field-made joints.

1. Plastic-Laminate Countertops: Secure field-made joints using concealed clamping devices located within **6 inches** of front and back edges and at intervals not exceeding **24 inches**. Tighten in accordance with manufacturer's written instructions to exert a uniform heavy pressure at joints.

C. Fastening:

1. Secure countertops, except for epoxy countertops, to cabinets with Z-type fasteners or equivalent, using two or more fasteners at each cabinet front, end, and back.
2. Secure epoxy countertops to cabinets with epoxy cement, applied at each corner and along perimeter edges at not more than **48 inches** o.c.
3. Where necessary to penetrate countertops with fasteners, countersink heads approximately **1/8 inch** and plug hole flush with material equal to countertop in chemical resistance, hardness, and appearance.

D. Provide holes and cutouts required for service fittings.

E. Provide scribe moldings for closures at junctures of countertop, curb, and splash with walls as recommended by manufacturer for materials involved. Match materials and finish to adjacent laboratory casework. Use chemical-resistant, permanently elastic sealing compound where recommended by manufacturer.

F. Dress joints smooth, remove surface scratches, and clean entire surface.

3.3 INSTALLATION OF SINKS

A. Comply with installation requirements in SEFA 2.

B. Semiflush Installation of Stainless Steel Sinks: Before setting, apply sink and countertop manufacturers' recommended sealant under rim lip and along top. Remove excess sealant while still wet and finish joint for neat appearance.

3.4 INSTALLATION OF LABORATORY ACCESSORIES

A. Install accessories in accordance with Shop Drawings, installation requirements in SEFA 2, and manufacturer's written instructions.

B. Securely fasten adjustable shelving supports, stainless steel shelves, and pegboards to partition framing, wood blocking, or reinforcements in partitions.

C. Install shelf standards plumb and at heights to align shelf brackets for level shelves. Install shelving level and straight, closely fitted to other work where indicated.

D. Securely fasten pegboards to partition framing, wood blocking, or reinforcements in partitions.

3.5 CLEANING AND PROTECTING

A. Clean finished surfaces, touch up as required, and remove or refinish damaged or soiled areas to match original factory finish, as approved by Architect.

B. Protect countertop surfaces during construction with **6-mil** plastic or other suitable water-resistant covering. Tape to underside of countertop at a minimum of **48 inches** o.c.

END OF SECTION 12 35 53.16

PAGE LEFT INTENTIONALLY BLANK

SECTION 12 48 13
ENTRANCE FLOOR MATS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Resilient entrance mats.

1.2 COORDINATION

A. Coordinate size and location of recesses in concrete to receive floor mats and frames.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for floor mats and frames.

B. Samples: For the following products, in manufacturer's standard sizes:

1. Floor Mat: Assembled sections of floor mat.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For floor mats and frames to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 ENTRANCE FLOOR MATS AND FRAMES, GENERAL

A. Accessibility Standard: Comply with applicable provisions in the DOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.

2.2 RESILIENT ENTRANCE MATS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include,

but are not limited to, the following:

1. American Floor Products Company, Inc
2. Kadee Industries, Inc
3. SBEMCO Matting By Design

2.3 FABRICATION

A. Floor Mats: Shop fabricate units to greatest extent possible in sizes indicated. Unless otherwise indicated, provide single unit for each mat installation; do not exceed manufacturer's recommended maximum sizes for units that are removed for maintenance and cleaning. Where joints in mats are necessary, space symmetrically and away from normal traffic lanes. Miter corner joints in framing elements with hairline joints or provide prefabricated corner units without joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and floor conditions for compliance with requirements for location, sizes, and other conditions affecting installation of floor mats and frames.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install surface-type units to comply with manufacturer's written instructions; coordinate with entrance locations and traffic patterns.

3.3 PROTECTION

A. After completing frame installation and concrete work, provide temporary filler of plywood or fiberboard in recesses and cover frames with plywood protective flooring. Maintain protection until construction traffic has ended and Project is near Substantial Completion.

END OF SECTION 12 48 13

SECTION 13 49 00
RADIATION PROTECTION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Lead-lined gypsum board.
2. Lead glass.
3. Lead-lined hollow-metal frames.
4. Informational signs.

1.2 DEFINITIONS

A. Lead Equivalence: The thickness of lead that provides the same attenuation (reduction of radiation passing through) as the material in question under the specified conditions.

1. Lead equivalence specified for materials used in diagnostic x-ray rooms is as measured at 100 kV unless otherwise indicated.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Doors and Frames: Include construction details, material descriptions, core descriptions, and finishes.

B. Shop Drawings: Show layout of radiation-protected areas, indicating lead thickness or lead equivalence of components. Show components and installation conditions not fully dimensioned or detailed in product data.

1. Show details of joints between radiation protection materials.

C. Samples: For units with factory-applied color finishes.

D. Product Schedule: For observation windows and doors and frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Lead-Lined Gypsum Panels and Plywood: Store inside under cover, and keep dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install radiation protection until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Obtain each type of radiation protection product from single source from single manufacturer unless otherwise indicated.

2.2 PERFORMANCE REQUIREMENTS

A. Provide materials and workmanship, including joints and fasteners, that maintain continuity of radiation protection at all points and in all directions equivalent to materials specified in thicknesses and locations indicated.

B. Materials, thicknesses, and configurations of radiation protection products indicated are based on radiation protection design prepared by Owner's radiation health physicist. This design is available to Contractor upon request.

C. Lead-Lined Assemblies: Unless otherwise indicated, provide lead thickness in lead-lined assemblies of not less than lead thickness indicated for assemblies in which they are installed.

D. Lead Glazing: Unless otherwise indicated, provide lead equivalence of not less than that indicated for assembly in which glazing is installed.

2.3 LEAD-LINED GYPSUM BOARD

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. A&L Shielding Inc.

2. MarShield Custom Radiation Shielding Products, a division of Mars Metal Company
3. NELCO Worldwide
4. Ray-Bar Engineering Corp

B. Lead-Lined Gypsum Board: 5/8-inch- thick gypsum board complying with Section 092900 "Gypsum Board," of width and length required for support spacing and to prevent cracking during handling, and with a single sheet of lead laminated to the back of the board.

1. Lead Sheet Lining: Full width of board and length necessary to extend from floor to 84 inches above floor. Extend lead sheet lining 1 inch beyond one vertical edge of board.
2. Furnish 2-inch- wide lead strips for backing joints.
3. Furnish finishing materials, accessories, and trim for lead-lined gypsum board complying with Section 092900 "Gypsum Board."

2.4 LEAD GLASS

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. A&L Shielding Inc.
2. MarShield Custom Radiation Shielding Products, a division of Mars Metal Company
3. McGrory Glass, Inc
4. NELCO Worldwide
5. Ray-Bar Engineering Corp

B. Lead Glass: Lead-barium, polished glass containing not less than 60 percent heavy metal oxides, including not less than 48 percent lead oxide by weight.

1. Tempered Safety Glass: ASTM C1048, Kind FT (fully tempered), lead glass with thickness as needed to provide lead equivalence indicated.

2.5 LEAD-LINED HOLLOW-METAL FRAMES

A. Hollow-Metal Frames: Steel frames complying with NAAMM-HMMA 861, except as indicated.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. A&L Shielding Inc.
b. MarShield Custom Radiation Shielding Products, a division of Mars Metal Company
c. NELCO Worldwide
d. Ray-Bar Engineering Corp
e. Republic Doors and Frames; an Allegion brand

2. Provide borrowed lite observation window frames of split or telescoping design with welded corners, allowing frame to be installed after construction of partition.

    a. Construct so lead lining overlaps glazing material perimeter by at least 3/8 inch, and furnish removable stops.

3. Provide observation window frames from steel sheet with minimum thickness of 0.0667 inch.
4. Furnish with additional reinforcements and internal supports to adequately carry the weight of lead-lined doors. Install reinforcements and supports before installing lead lining.
5. Line frame with lead sheet of thickness not less than that required for doors and walls where frames are used. Form lead sheet to match frame contour, continuous in each jamb and across the head, lapping the stops. Form lead shields around areas prepared to receive hardware. Fabricate lead lining wide enough to maintain an effective lap with lead of adjacent shielding.
6. Finish: Apply manufacturer's standard primer immediately after cleaning and pretreating.

2.6 MISCELLANEOUS MATERIALS

A. Glazing Compounds, Gaskets, and Accessories: Comply with requirements in Section 088000 "Glazing."

B. Accessories and Fasteners: Manufacturer's standard fasteners and accessories as required for installation, maintaining same lead equivalence as rest of system.

C. Asphalt Coating: Cold-applied asphalt emulsion complying with ASTM D1187/D1187M.

D. Asphalt Felt: ASTM D226/D226M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates with Installer present for compliance with requirements, installation tolerances, and other conditions affecting performance of radiation protection.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF LEAD-LINED GYPSUM BOARD

A. Install and finish lead-lined gypsum board in accordance with Section 092900

"Gypsum Board."

B. Install lead-lined gypsum board panels with long edge parallel to supports and lead lining facing supports. Provide blocking at end joints. Install using construction adhesive and supplementary fasteners.

C. Install lead-lined gypsum board panels in sequence, so lead lining that extends beyond edge of gypsum board is covered by next panel installed.

D. At joints where lead lining does not extend beyond edge of gypsum board panels, install lead strips 2 inches wide and same thickness as lead lining to face of framing and blocking. Secure lead strips with construction adhesive.

E. Provide shims at face of supports and blocking, where lead lining does not overlap, to provide a uniform plane across panel surfaces.

F. Fasten lead-lined gypsum board to framing, with steel drill screws spaced as recommended in writing by lead-lined gypsum board manufacturer.

G. Openings: Extend lead-lined gypsum board into frames of openings, lapping lead lining with lead frames or frame linings at least 1 inch. Arrange board around openings, so neither horizontal nor vertical joints occur at corners of openings.

H. Install control and expansion joints where indicated, with appropriate trim accessories. Install lead strip on face of framing, extending across joint, and lap with lead lining of gypsum board.

3.3 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections after radiology equipment has been installed and placed in operating condition.

B. Correct deficiencies in or remove and replace radiation protection that inspection reports indicate does not comply with specified requirements.

3.4 PROTECTION

A. Lock radiation-protected rooms once doors and locks are installed, and limit access to only those persons performing work in the rooms.

END OF SECTION 13 49 00

SECTION 210500 - COMMON WORK RESULTS FOR FIRE PROTECTION

PART 1 - GENERAL

1.1 SUMMARY

A. All work under Division 21 is subject to the Division 01, General Conditions and Special Requirements for the entire contract.

B. Provide all labor, materials, equipment, and services necessary for and incidental to the complete installation and operation of all mechanical work.

C. Unless otherwise specified, all submissions shall be made to, and acceptances and approvals made by the Architect.

D. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange piping, equipment, and other work generally as shown on the contract drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed shop drawings for approval in accordance with Submittals specified below. The right is reserved to make reasonable changes in location of equipment, and piping up to the time of rough-in or fabrication.

E. Conform to the requirements of all rules, regulations and codes of local, state and federal authorities having jurisdiction.

F. Coordinate the work under Division 21 with the work of all other construction trades.

G. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the contract documents.

H. Modify sprinkler piping, sprinkler head locations, and extend fire protection system as required to accommodate wall changes, bulkheads, ceiling changes, and M/E/P changes. Hydraulically calculate all pipe sizes based on NFPA-13.

I. The existing fire protection system shall remain unless otherwise noted. Re-located fire protection piping, hangers, valves, sprinkler heads, and fire alarm wiring as required to accommodate demolition and new work as shown on the Contract Documents. Install new heads, piping, and hangers as required.

J. Existing fire protection system, piping, sprinkler heads, and fittings shall be modified to accommodate demolition work and installation of new systems.

K. Provide new sprinkler heads where new ceilings and bulkheads are provided. Extend sprinkler piping to coordinate with new ceiling heights, bulkheads, and ductwork, piping and equipment installation. Refer to architectural reflected ceiling plans.

L. Fire protection contractor shall survey existing fire suppression system and submit hydraulic drawings and calculations to State Fire Marshal for review and approval.

1.2 PERMITS AND FEES

A. Obtain all permits and pay taxes, fees and other costs in connection with the work. File necessary plans, prepare documents, give proper notices and obtain necessary approvals. Deliver inspection and approval certificates to Owner prior to final acceptance of the work.

B. Permits and fees shall comply with the Division 01, General Requirements of the specification.

1.3 EXAMINATION OF SITE

A. Examine the site, determine all conditions and circumstances under which the work must be done, and make all necessary allowances for same. No additional cost to the Owner will be permitted for Contractors failure to do so.

B. Examine and verify specific conditions described in individual specifications sections.

C. Verify that utility services are available, of the correct characteristics, and in the correct locations.

1.4 CONTRACTOR QUALIFICATION

A. Any Contractor or Subcontractor performing work under Division 21 shall be fully qualified and acceptable to the Architect and Owner. Submit the following evidence when requested:

1. A list of not less than five comparable projects which the Contractor completed.
2. Letter of reference from not less than three registered professional engineers, general contractors or building owners.
3. Local and/or State License, where required.
4. Membership in trade or professional organizations where required.

B. A Contractor is any individual, partnership, or corporation, performing work by contract or subcontract on this project.

C. Acceptance of a Contractor or Subcontractor will not relieve the Contractor or subcontractor of any contractual requirements or his responsibility to supervise

and coordinate the work, of various trades.

1.5 MATERIALS AND EQUIPMENT

A. Materials and equipment installed as a permanent part of the project shall be new, unless otherwise indicated or specified, and of the specified type and quality. Existing items of equipment are being relocated under another Division of these specifications. The Contractor shall be responsible for connecting all utilities as shown on the drawings, to equipment identified as existing.

B. Where material or equipment is identified by proprietary name, model number and/or manufacturer, furnish named item, or its equal, subject to approval by Engineer. Substituted items shall be equal or better in quality and performance and must be suitable for available space, required arrangement, and application. Submit all data necessary to determine suitability of substituted items, for approval.

C. The suitability of named item only has been verified. Where more than one item is named, only the first named item has been verified as suitable. Substituted items, including items other than first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement and application. Contractor, by providing other than the first named manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation. Adjustments and modifications shall include but not be limited to electrical, structural, support, and architectural work.

D. Substitution will not be permitted for specified items of material or equipment where noted.

E. All items of equipment furnished shall have a service record of at least five (5) years.

1.6 FIRE SAFE MATERIALS

A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA and ASTM standards for fire safety with smoke and fire hazard rating not exceeding flame spread of 25 and smoke developed of 50.

1.7 REFERENCED STANDARDS, CODES AND SPECIFICATIONS

A. Specifications, Codes and Standards listed below are included as part of this specification, latest edition.

B. ASTM - American Society for Testing and Materials

C. FM - Factory Mutual

D. IBC - International Building Code

E. IEEE - Institute of Electrical and Electronics Engineers

F. MSSP Industry - Manufacturers Standards Society of the Valve and Fittings

G. NEC - National Electrical Code

H. NEMA - National Electrical Manufacturers Association

I. NFPA - National Fire Protection Association

J. UL - Underwriters' Laboratories

K. State of Delaware Fire Protection Requirements.

L. All equipment materials, piping and installation shall comply with the codes and standards listed in the enforceable edition of the Applicable National Fire Protection Association Pamphlets.

M. Fire Protection Systems design, equipment and installation shall comply with the Delaware State Fire Prevention Regulations, latest edition including all Annexes and Addendums.

1.8 SUBMITTALS, REVIEW AND ACCEPTANCE

A. Equipment, materials, installation, workmanship and arrangement of work are subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Architect to be in best interest of Owner.

B. After acceptance of Material and Equipment List, submit three (3) copies or more as required under General Conditions of complete descriptive data for all items. Data shall consist of specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, wiring diagrams, installation instructions, and any other information necessary to indicate complete compliance with Contract Documents. Edit submittal data specifically for application to this project.

C. Thoroughly review and stamp all submittals to indicate compliance with contract requirements prior to submission. Coordinate installation requirements and any electrical requirements for equipment submitted. Contractor shall be responsible for correctness of all submittals.

D. Submittals will be reviewed for general compliance with design concept in accordance with contract documents, but dimensions, quantities, or other details will not be verified.

E. Identify submittals, indicating intended application, location and service of submitted items. Refer to specification sections or paragraphs and drawings where applicable. Clearly indicate exact type, model number, style, size and

special features of proposed item. Submittals of a general nature will not be acceptable. For substituted items, clearly list on the first page of the submittal all differences between the specified item and the proposed item. The contractor shall be responsible for corrective action and maintaining the specification requirements if differences have not been clearly indicated in the submittal.

F. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Call attention, in writing, to deviation from contract requirements.

G. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted. Use only final or corrected submittals and data prior to fabrication and/or installation.

H. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.

I. For resubmissions, the Contractor must address in writing all of the Engineer’s comments on the original submission to verify compliance.

1.9 SHOP DRAWINGS

A. Prepare and submit shop drawings for all mechanical equipment, specially fabricated items, modifications to standard items, specially designed systems where detailed design is not shown on the contract drawings, or where the proposed installation differs from that shown on contract drawings.

B. Submit data and shop drawings including but not limited to the list below, in addition to provisions of the paragraph above. Identify all shop drawings by the name of the item and system and the applicable specification paragraph number and drawing number.

C. Every submittal including, but not limited to the list below, shall be forwarded with its own transmittal as a separate, distinct shop drawing. Grouping of items/systems that are not related shall be unacceptable.

D. Items and Systems

1. Access Doors/Panels including layout and location
2. Alarm Check Valves
3. Coordinated Drawings
4. Drip Pans
5. Fire Protection System including Hydraulic Calculations, Equipment and Devices
6. Fire Stopping - Methods and Materials

7. Identification System
8. Material and Equipment List
9. Operations and Maintenance Manuals
10. Pipe Materials Including Itemized Schedule
11. Preliminary and Final Pipe Pressure Tests
12. Pressure Gauges
13. Pressure Relief Valves
14. Sprinkler Heads
15. Strainers
16. Test Certificates
17. Valves
18. Wiring Diagrams, Flow Diagrams and Operating Instructions
19. Zone Valve Assemblies

E. Contractor, additionally, shall submit for review any other shop drawings as required by the Architect. No item shall be delivered to the site, or installed, until the Contractor has received a submittal from the Engineer marked Reviewed or Comments Noted. After the proposed materials have been reviewed, no substitution will be permitted except where approved by the Architect.

F. For any shop drawing requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.

1.10 SUPERVISION AND COORDINATION

A. Provide complete supervision, direction, scheduling, and coordination of all work under the Contract, including that of subcontractors.

B. Coordinate rough-in of all work and installation of sleeves, anchors, and supports for piping, equipment, and other work performed under Division 21.

C. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction to allow for fire protection installations.

D. Coordinate electrical work required under Division 21 with that under Division 26. Coordinate all work under Division 21 with work under all other Divisions.

E. Supply services of an experienced (10 years minimum) and competent Project Manager to be in constant charge of work at site.

F. Where a discrepancy exists within the specifications or drawings or between the specifications and drawings, the more stringent (or costly) requirement shall apply until clarification can be obtained from the Engineer. Failure to clarify such discrepancies with the Engineer will not relieve the Contractor of the responsibility of conforming to the requirements of the Contract.

G. Failure of contractor to obtain a full and complete set of contract documents (either before or after bidding) will not relieve the contractor of the responsibility of complying with the intent of the contract documents.

H. Coordinate installation of large equipment requiring positioning before closing in building.

1.11 CUTTING AND PATCHING

A. Accomplish all cutting and patching necessary for the installation of work under Division 21. Damage resulting from this work to other work already in place, shall be repaired at Contractor's expense. Where cutting is required, perform work in neat and workmanlike manner. Restore disturbed work to match and blend with existing construction and finish, using materials compatible with the original. Use mechanics skilled in the particular trades required.

B. Do not cut structural members without approval from the Architect or Structural Engineer.

1.12 PENETRATION OF WATERPROOF CONSTRUCTION

A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls, and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary curbs, sleeves, flashings, fittings and caulking to make penetrations absolutely watertight.

1.13 CONNECTIONS AND ALTERATIONS TO EXISTING WORK

A. Unless otherwise noted on the drawings, where existing fire protection work is removed, pipes, valves, etc., shall be removed, including hangers, to a point below finished floors or behind finished walls and capped. Such point shall be far enough behind finished surfaces to allow for installation of normal thickness of required finish material.

B. Where work specified in Division 21 connects to existing equipment and piping, etc., Contractor shall perform all necessary alterations, cuttings, fittings, etc., of existing work as may be necessary to make satisfactory connections between new and existing work, and to leave completed work in a finished and workmanlike condition.

C. Where the work specified under Division 21, or under other Divisions, requires relocation of existing equipment, piping, etc., Contractor shall perform all work and make necessary changes to existing work as may be required to leave completed work in a finished and workmanlike condition.

D. Where the relocation of existing equipment is required for access or the installation of new equipment, the contractor shall temporarily remove and/or relocate and re-install as required to leave the existing and new work in a finished and workman

like condition.

E. Fire suppression system will remain active throughout the duration of the project. Contractor shall provide temporary wire baskets to protect sprinkler heads during construction. Include all provisions for fire watch as determined by the Fire Marshal.

1.14 DEMOLITION

A. Unless otherwise noted all existing equipment, piping, etc., shall remain.

B. Where existing equipment is indicated to be removed, all associated piping, conduit, power, controls, insulation, hangers, supports and housekeeping pads, etc. Patch, paint and repair walls/roof/floor to match existing and/or new finishes.

C. Provide necessary piping, valves, temporary feeds, etc., as required. Drain and refill piping systems as often as necessary to accommodate phasing and to minimize time lengths of outages.

D. The Contractor shall be responsible for visiting the site and determining the existing conditions in which the work is to be performed.

E. Refer to phasing plans for additional requirements.

F. Where any abandoned pipes in existing floors, walls, pipe tunnels, ceilings, etc., conflict with new work, remove abandoned pipes as necessary to accommodate new work.

G. The location of all existing equipment, piping, etc., indicated is approximate only and shall be checked and verified. Install all new fire protection work to connect to or clear existing work as applicable.

H. Maintain egress at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and the authorities having jurisdiction.

I. Make provisions and include in bid all costs associated with confined entry/space requirements and all applicable OSHA regulations.

J. Where required to maintain the existing systems in operation, temporarily backfeed existing systems from new equipment. Contractor shall temporarily extend existing piping systems to new piping systems with the appropriate shut-off valves and tamper switches.

K. At completion of project all temporary piping, valves, controls, etc., shall be removed in their entirely.

L. Existing piping, equipment, materials, etc., not required for re-use or re-installation in this project, shall be removed from the project site.

M. Deliver to the Owner, on the premises where directed, existing equipment and

materials which are removed and which are desired by the Owner or are indicated to remain the property of the Owner.

N. All other materials and equipment which are removed shall become property of the Contractor and shall be promptly removed, from the premises, and disposed of by the Contractor, in an approved manner.

O. Where piping is removed, remove all pipe hangers which were supporting the removed piping. Patch the remaining penetration voids with like materials and paint to match existing construction.

P. Where required, provide and coordinate removal and re-installation of existing equipment. Take care to protect materials and equipment indicated for reuse. Contractor shall repair or replace items which are damaged. Contractor shall have Owner's representative present to confirm condition of equipment prior to demolition.

Q. Before demolition begins, and in the presence of the Owners representative, test and note all deficiencies in all existing systems affected by demolition but not completely removed by demolition. Provide a copy of the list of system deficiencies to the Owner and the Engineer. Videotape existing conditions in each space prior to beginning demolition work.

R. The Owner shall have the first right of refusal for all devices and equipment removed by the Contractor.

S. All devices and equipment designated by the Owner to remain the property of the Owner shall be moved and stored by the Contractor at a location on site as designated by the Owner. It shall be the Contractor's responsibility to store all devices and equipment in a safe manner to prevent damage while stored.

T. All existing equipment refused by the Owner shall become the property of the Contractor and shall be removed from the site by the Contractor in a timely manner and disposed of in a legal manner.

U. Work Abandoned in Place: cut and remove underground pipe a minimum of 2 inches beyond face of adjacent construction. Cap and patch surface to match existing finish.

V. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.

W. Terminate services and utilities in accordance with local laws, ordinances, rules and regulations.

X. After demolition of ceilings install aluminum inverted pie plates above each sprinkler head. Maintain throughout construction phase. Remove with the installation of new ceilings.

1.15 ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

1.16 DEFINITIONS

A. Approve - to permit use of material, equipment or methods conditional upon compliance with contract documents requirements.

B. Furnish and install or provide means to supply, erect, install, and connect to complete for readiness for regular operation, the particular work referred to.

C. Contractor means the mechanical contractor and any of his subcontractors, vendors, suppliers, or fabricators.

D. IgCC refers to International Green Construction Code.

E. Piping includes pipe, all fittings, valves, hangers, insulation, identification, and other accessories relative to such piping.

F. Concealed means hidden from sight in chases, formed spaces, shafts, hung ceilings, or embedded in construction.

G. Exposed means not installed underground or concealed as defined above.

H. Invert Elevation means the elevation of the inside bottom of pipe.

I. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceiling, and unexcavated spaces.

J. Review - limited observation or checking to ascertain general conformance with design concept of the work and with information given in contract documents. Such action does not constitute a waiver or alteration of the contract requirements.

K. Building Line: Exterior wall of building.

PART 2 - ELECTRICAL REQUIREMENTS

2.1 GENERAL MOTOR AND ELECTRICAL REQUIREMENTS

A. Furnish and install control and interlock wiring for the equipment furnished. In general, power wiring and motor starting equipment will be provided under Division 26. Carefully review the contract documents to coordinate the electrical work under Division 21 with the work under Division 26. Where the electrical requirements of the equipment furnished differ from the provisions made under Division 26, make the necessary allowances under Division 21. Where no

electrical provisions are made under Division 26, include all necessary electrical work under Division 21.

B. All electrical work performed under Division 21 shall conform to the applicable requirements of Division 26 and conforming to the National Electrical Code. All wiring, conduit, etc., installed in ceiling plenums must be plenum rated per NFPA and the IBC.

C. Provide wiring diagrams with electrical characteristics and connection requirements.

D. Test Reports: Indicate test results verifying nominal efficiency and power factor for three phase motors larger than five (5) horsepower.

E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weatherproof covering. For extended outdoor storage, remove motors from equipment and store separately.

F. All motors shall be furnished with visible nameplate indicating motor horsepower, voltage, phase, cycles, RPM, full load amps, locked rotor amps, frame size, manufacturer's name and model number, service factor, power factor and efficiency.

G. Nominal efficiency and power factor shall be as scheduled at full load and rated voltage when tested in accordance with IEEE 112.

H. Brake horsepower load requirement at specified duty shall not exceed 85 percent of nameplate horsepower times NEMA service factor for motors with 1.0 and 1.15 service factors.

I. All single phase motors shall be provided with thermal protection: Internal protection shall automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature ratings of motor insulation. Thermal protection device shall automatically reset when motor temperature returns to normal range, unless otherwise indicated.

J. Where equipment under this Division is specified with integral disconnecting means, the same shall be a single disconnecting means for disconnecting all ungrounded main power supply conductors that is capable of being locked in the open ("off") position in accordance with the National Electrical Code and the local electrical inspector.

2.2 WIRING DIAGRAMS

A. The Contractor is responsible for obtaining and submitting wiring diagrams for all major items of equipment.

B. Wiring diagrams shall be provided with shop drawings for all equipment requiring electric power.

2.3 ENCLOSURES

A. Electrical enclosures including factory provided enclosures, field provided and installed enclosures, and automatic temperature control system enclosures shall be as follows:

1. Dry Interior Locations: NEMA 1.
2. Damp/Wet Locations, Including Exterior Locations: NEMA 3R.
3. Corrosive Locations, Including Laboratories, Chemical Storage Rooms, Janitor's Closets, and Similar Space = NEMA 4X.

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

A. Install equipment to provide maximum possible headroom, if mounting heights are not indicated.

B. Install equipment according to approved submittal data. Portions of the work are shown only in diagrammatic form. Refer conflicts to Architect.

C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.

D. Install fire protection equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.

E. Install equipment giving right of way to piping installed at required slope.

F. Install flexible connectors on equipment side of shutoff valves, horizontally and parallel to equipment shafts if possible.

G. Do not install equipment or piping over electrical gear, electrical panels, motor controllers, and similar electrical equipment. Install equipment and piping to maintain clear space above and in front of all electrical components per the National Electric Code.

3.2 SUPPORTS, HANGERS AND FOUNDATIONS

A. Provide supports, hangers, braces, attachments and foundations required for the work. Support and set the work in a thoroughly substantial and workmanlike manner without placing strains on materials, equipment, or building structure, submit shop drawings for approval. Coordinate all work with the requirements of the structural division.

B. Supports, hangers, braces, and attachments shall be standard manufactured

items or fabricated structural steel shapes. All interior hangers shall be galvanized or steel with rust inhibiting paint. For un-insulated copper piping provide copper hanger to prevent contact of dissimilar metals. All exterior hangers shall be stainless steel including hangers, rods, nuts, washers, bolts, etc.

3.3 DEMONSTRATION AND TRAINING VIDEO RECORDINGS

A. General: Record demonstration and training video recordings. Record each training module separately.

1. At beginning of each training module, record each chart containing learning objective and lesson outline.

B. Video Recording Format: Provide high-quality color video recordings with menu navigation in format acceptable to Engineer

C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to show area of demonstration and training. Display continuous running time.

D. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.

E. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.

3.4 PROVISIONS FOR ACCESS

A. The contractor shall provide access panels and doors for all concealed equipment, valves, strainers, controls, control devices, and other devices requiring maintenance, service, adjustment, balancing or manual operation.

B. Where access doors are necessary, furnish and install manufactured painted steel door assemblies consisting of hinged door, key locks, and frame designed for the particular wall or ceiling construction. Properly locate each door. Door sizes shall be a minimum of 12 inches x 12 inches for hand access, 18 inches x 18 inches for shoulder access and 20 inches x 30 inches for full body access where required. Review locations and sizes with Architect prior to fabrication. Provide U.L. approved and labeled access doors where installed in fire rated walls or ceilings. Doors shall be Milcor Metal Access Doors as manufactured by Inland-Ryerson, Mifab, or approved equal.

1. Acoustical or Cement Plaster: Style B
2. Hard Finish Plaster: Style K or L
3. Masonry or Dry Wall: Style M

C. Where access is by means of liftout ceiling tiles or panels, mark each ceiling grid using small color-coded and numbered tabs. Provide a chart or index for identification. Place markers within ceiling grid not on ceiling tiles.

D. Access panels, doors, etc. described herein shall be furnished under the section of specifications providing the particular service and to be turned over to the pertinent trade for installation. Coordinate installation with installing contractor. All access doors shall be painted in baked enamel finish to match ceiling or wall finish.

E. Submit shop drawings indicating the proposed location of all access panels/doors. Access doors in finished spaces shall be coordinated with air devices, lighting and sprinklers to provide a neat and symmetrical appearance.

F. Where access doors are installed in wet locations (i.e. toilet rooms and similar spaces, etc.) provide aluminum access doors/frames.

3.5 PAINTING AND FINISHES

A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc. shall be stainless steel.

B. Clean surfaces prior to application of insulation, adhesives, coatings, paint, or other finishes.

C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pretreatment.

D. Protect all finishes and restore any finishes damaged as a result of work under Division 21 to their original condition.

E. The preceding requirements apply to all work, whether exposed or concealed.

F. Remove all construction marking and writing from exposed equipment, piping and building surfaces. Do not paint manufacturer's labels or tags.

G. All exposed piping, equipment, etc. shall be painted. Colors shall be as stated in this division or as selected by the Architect in Division 09 and conform to ANSI Standards.

H. All exposed piping, equipment, etc. in finished spaces shall be painted. Colors shall be as selected by the Architect and conform to ANSI Standards.

I. Refer to Division 09 for additional painting requirements.

3.6 CLEANING OF SYSTEMS

A. Thoroughly clean systems after satisfactory completion of pressure tests and before permanently connecting equipment, and other accessory items. Blow out and flush piping until interior surfaces are free of foreign matter.

B. Flush piping to remove cutting oil, excess pipe joint compound, solder slag and other foreign materials. Do not use system pumps until after cleaning and flushing has been accomplished to the satisfaction of the Engineer. Employ chemical cleaners, including a non-foaming detergent, not harmful to system components. After cleaning operation, final flushing and refilling, the residual alkalinity shall not exceed 300 parts per million. Submit a certificate of completion to Engineer stating the name of service company used.

C. Pay for labor and materials required to locate and remove obstructions from systems that are clogged with construction refuse after acceptance. Replace and repair work disturbed during removal of obstructions.

D. Leave systems clean, and in complete running order.

3.7 COLOR SELECTION

A. Color of finishes shall be as selected by the Architect.

B. Submit color of factory-finished equipment for acceptance prior to ordering.

3.8 PROTECTION OF WORK

A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.

B. Cover temporary openings in piping and equipment to prevent the entrance of water, dirt, debris, or other foreign matter. Deliver pipes and tubes with factory applied end caps.

C. Cover or otherwise protect all finishes.

D. Replace damaged materials, devices, finishes and equipment.

E. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, where stored inside.

3.9 OPERATION OF EQUIPMENT

A. Clean all systems and equipment prior to initial operation for testing, or other purposes. Lubricate, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.

B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment. Where factory start-up of equipment is not specified, provide field start-up by qualified technician.

C. Submit factory start-up sheets or field start-up sheets for all equipment.

3.10 IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS

A. Contractor shall submit for approval working fire protection drawings of each piping system installed in the building. Diagrams shall indicate the location and the identification number of each valve in the particular system. Following approval by all authorities, the diagrams shall be framed, mounted under safety glass and hung in each Mechanical Room where directed. Contractor shall deliver the tracing or sepia from which the diagrams were reproduced to the Owner.

B. All valves shall be plainly tagged. For any bypass valves, install sign indicating valve position as “Normally Open” or “Normally Closed” as required.

C. All items of equipment, including motor starters and disconnects, shall be furnished with white on black plastic permanent identification cards. Lettering shall be a minimum of ¼ inch high. Identification plates shall be secured, affixed to each piece of equipment, starters, disconnects, panels by screw or adhesive (tuff bond #TB2 or as approved equal). Equipment identification and room name or area served shall be on each label.

D. Provide three (3) hard copies and one (1) electronic copy of operating and maintenance instructions for all principal items of equipment furnished. This material shall be bound as a volume of the Operation and Maintenance Booklet as hereinafter specified.

E. All piping installed under this contract shall be stenciled with direction of flow arrows and with stenciled letters naming each pipe and service. Refer to Division 21 Section, “Fire Suppression System Piping, Fittings, Valves, Etc”. Color code all direction of flow arrows and labels. In finished spaces omit labeling and direction of flow arrows. Paint in color as selected by Architect.

F. Submit list of wording, symbols, letter size, and color coding for fire protection identification. Submit samples of equipment identification cards, piping labels, and valve tags to Engineer for review prior to installation.

G. Provide at least four (4) hours of straight time instruction to the operating personnel. Time of instruction shall be designated by the Owner.

H. Contractor shall demonstrate Sequences of Operation of all fire protection equipment in presence of Owner’s representative, and Fire Marshal.

3.11 WALL AND FLOOR PENETRATION

A. All penetrations of partitions, ceilings, roofs and floors by piping or conduit under Division 21 shall be sleeved, sealed, and caulked airtight for sound and air transfer control.

B. All penetration of fire rated assemblies shall be sleeved, sealed, caulked and protected to maintain the rating of the wall, roof, or floor. Fire Marshal approved U.L. assemblies shall be utilized. See Division 07 Section, “Fire Protection, HVAC and Plumbing Protection Firestopping”.

C. Where piping extends through exterior walls or below grade, provide waterproof pipe penetration seals, as specified in another division of these specifications.

D. Provide pipe escutcheons for sleeved pipes in finished areas.

E. Piping sleeves:

1. Galvanized steel pipe, standard weight where pipes are exposed and roofs and concrete and masonry walls. On exterior walls provide anchor flange welded to perimeter.
2. Twenty-two (22) gauge galvanized steel elsewhere.

F. Extend all floor sleeves through floor at least 2-inches above finished floor, caulk sleeve the entire depth and furnish and install floor plate.

G. For renovation projects where new pipes penetrate existing floors, furnish ground penetrating radar to properly map out acceptable locations for pipe penetrations. Review penetrations with Structural Engineer.

3.12 RECORD DRAWINGS

A. Upon completion of the mechanical installations, the Contractor shall deliver to the Architect one complete set of prints of the fire protection drawings which shall be legibly marked in red pencil to show all changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.

B. Contractor shall incorporate all sketches, addendums, value engineering, change orders, etc., into record drawings prior to delivering to Architect.

3.13 WARRANTY

A. Contractor's attention is directed to warranty obligations contained in the GENERAL CONDITIONS.

B. The above shall not in any way void or abrogate equipment manufacturer's guarantee or warranty. Certificates of equipment manufacturer’s warranties shall be included in the operations and maintenance manuals.

C. The contractor guarantees for a two (2) year period from the time of final acceptance by the Owner.

1. That the work contains no faulty or imperfect material or equipment or any imperfect, careless, or unskilled workmanship.

2. That all work, equipment, machines, devices, etc. shall be adequate for the use to which they are intended, and shall operate with ordinary care and attention in a satisfactory and efficient manner.
3. That the contractor will re-execute, correct, repair, or remove and replace with proper work, without cost to the Owner, any work found to be deficient. The contractor shall also make good all damages caused to their work or materials in the process of complying with this section.
4. That the entire work shall be water-tight and leak-proof.

3.14 OPERATION AND MAINTENANCE MANUALS

A. The Contractor shall have prepared three (3) hardcopies and one (1) electronic copy of the Operation and Maintenance Manuals and deliver these copies of the manuals to the Owner. The manuals shall be as specified herein. The manuals must be approved and will not be accepted as final until so stamped.

B. The manuals shall be bound in a three ring loose-leaf binder similar to National No. 3881 with the following title lettered on the front: Operations and Maintenance Manuals – DTCC – Carter Partnership Dental Suite – Fire Protection. No sheets larger than 8-1/2 inches x 11 inches shall be used, except sheets that are neatly folded to 8-1/2 inches x 11 inches and used as a pull-out. Provide divider tabs and table of contents for organizing and separating information.

C. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of Volume 1 (if applicable) of hard copies of the manual.

D. Provide the following data in the booklet:

1. As first entry, an approved letter indicating the starting/ending time of Contractor’s warranty period.
2. Maintenance, operation, and lubrication instructions on each piece of equipment furnished.
3. Manufacturer's extended limited warranties on equipment.
4. Chart form indicating frequency and type of routine maintenance for all fire protection equipment. The chart shall also indicate model number of equipment, location and service.
5. Provide sales and authorized service representatives names, address, and phone numbers of all equipment and subcontractors.
6. Provide supplier and subcontractor’s names, address, and phone number.
7. Catalog data of all equipment, valves, etc. shall include wiring diagrams, parts list and assembly drawing.
8. Provide and install in locations as directed by the Owner, valve charts including valve tag number, valve type, valve model number, valve manufacturer, style, service and location. Each valve chart shall be enclosed in a durable polymer based frame with a cover safety glass.
9. Access panel charts with index illustrating the location and purpose of access panels.

10. Approved Fire Suppression System Certificates.
11. Start-up reports for equipment.
12. NFPA Test Reports.
13. Pipe Pressure Testing Test Reports.

E. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of volume 1 (if applicable) of hard copies of the manual.

F. Submit Operations and Maintenance Manuals prior to anticipated date of substantial completion for Engineer review and approval. Substantial completion requires that Operations and Maintenance Manuals be reviewed and approved.

3.15 INSTALLATION AND COORDINATION DRAWINGS

A. Prepare, submit, and use composite installation and coordination drawings to assure proper coordination and installation of work. Drawings shall include, but not be limited, to the following:

1. Complete Plumbing, Sprinkler and HVAC Piping Drawings showing coordination with lights, electrical equipment, HVAC equipment and structural amenities.

B. Draw plans to a scale not less than 3/8-inch equals one foot. Include plans, sections, and elevations of proposed work, showing all equipment, and piping in areas involved. Fully dimension all work including lighting fixtures, conduits, pullboxes, panelboards, and other electrical work, walls, doors, ceilings, columns, beams, joists and other architectural and structural work.

C. Identify all equipment and devices on wiring diagrams and schematics. Where field connections are shown to factory-wired terminals, include manufacturer's literature showing internal wiring.

3.16 PIPING SYSTEMS TESTING

A. The entire new fire protection piping systems shall be tested hydrostatically before insulation covering is applied and proven tight under the following gauge pressures for a duration of twenty-four (24) hours. Testing to be witnessed by Owner's representative and documented in writing.

SYSTEM	**TEST PRESSURE**
Fire Suppression Piping (Refer to NFPA)	200 psi

B. Testing and acceptance thereof shall be in accordance with local requirements and shall meet approval of authority having jurisdiction. Submit certificates and approved permits and insert one (1) copy in the Operations and Maintenance

Manuals.

3.17 OUTAGES

A. Provide a minimum of fourteen (14) days' notice to schedule outages. The Contractor shall include in their bid outages and/or work in occupied areas to occur on weekends, holidays, or at night. Coordinate and get approval of all outages with the Owner.

B. Submit Outage Request form, attached at end of this Section, to Owner for approval.

END OF SECTION 210500

OUTAGE REQUEST

DATE APPLIED: _____ BY: _____

DATE FOR OUTAGE: _____ FIRM: _____

START OUTAGE-TIME: _____ DATE: _____

END OUTAGE -- TIME: _____ DATE: _____

AREAS AND ROOMS: _____

FLOOR(S): _____

AREA(S): _____

ROOM(S): _____

WORK TO BE PERFORMED: _____

SYSTEM(S): _____

REQUEST APPROVED BY: _____

(FOREMAN OR OTHER PERSON IN CHARGE)

(FOR OWNER'S USE ONLY):

APPROVED: _____

YES ____ NO ___ BY: _____ DATE: _____

DATE/TIME-AS REQUESTED: _____ OTHER: _____

OWNER'S PRESENCE REQUIRED: _____

YES: ____ NO: ___ NAME: _____

POINT OF CONTACT: _____ PHONE:

SECTION 210505 - FIRE SUPPRESSION SYSTEM PIPING, FITTINGS & VALVES

PART 1 - GENERAL

1.1. SUMMARY

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SYSTEM DESCRIPTION CONDITIONS

A. Provide all labor and materials necessary to furnish and install all piping systems on this project as herein specified and/or shown on the drawings.

B. All piping and insulation installed in ceiling plenums must be plenum rated and comply with NFPA and the authority having jurisdiction.

C. Where more than one piping system material is specified, ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

D. Use unions, flanges, and couplings downstream of valves and at equipment or apparatus connections. Do not use direct welded or threaded connections to valves, equipment or other apparatus.

E. Use non-conducting dielectric connections whenever jointing dissimilar metals in open systems.

F. Provide pipe hangers and supports in accordance with ASTM B31.9, MSS SP69 and NFPA-13 unless indicated otherwise.

G. Use 3/4 inch (20 mm) ball valves with cap and chain for drains at main shut-off valves, low points of piping, bases of vertical risers, and at equipment. Pipe to nearest floor drain.

1.3. QUALITY ASSURANCE

A. Valves: Manufacturer's name and pressure rating marked on valve body.

B. To assure uniformity and compatibility of piping components in grooved piping systems, all grooved products utilized shall be supplied by a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved components.

C. If the product is available domestically it shall be supplied as such.

1.4. DELIVERY, STORAGE AND HANDLING

A. Deliver, store, protect and handle products to site under as hereinbefore specified.

B. Accept valves on site in shipping containers with labeling in place. Inspect for damage.

C. Provide temporary protective coating on cast iron and steel valves.

D. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

E. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed systems.

1.5. ENVIRONMENTAL REQUIREMENTS

A. Do not install underground piping when bedding is wet or frozen.

1.6. ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1. PIPE MATERIALS

A. All materials, unless otherwise specified, shall be new and of the best quality of their respective kinds, and shall conform to the requirements and ordinances of local, state and insurance authorities having jurisdiction.

1. Fire Suppression System Piping (NFPA-13):

a. Piping Above Grade (Inside): Steel, schedule 40, ASTM A53, black pipe. Piping 4 inches and smaller shall be ASTM A120, black steel pipe. Sizes 4-inches and above shall be standard weight, black, cast iron with screwed fittings, schedule 10 steel piping shall be acceptable when approved by the authority having jurisdiction.

b. Piping Above Grade (Outside): Galvanized Steel

c. Wet Pipe Fittings: Steel fittings shall be ASME B16.9, wrought steel, butt welded. Cast iron fittings shall be ASME 16.1, flanges and flanged fittings. Malleable iron fittings shall be ASME B16.3, threaded fittings. Mechanical grooved couplings shall be malleable iron housing clamps to engage and lock C shaped elastomeric sealing gasket, steel bolts, nuts, and washers; galvanized for galvanized pipe. Mechanical formed fittings shall be carbon steel housing with integral pipe stop and O-ring and O-ring uniformity

compressed into permanent mechanical engagement onto pipe.

d. Dry Pipe Fittings: UL listed for dry pipe service.

e. Victaulic, Grinnell, or approved equal, grooved end fittings and mechanical couplings shall be used for wet pipe and dry pipe systems 2" and larger. Couplings and fitting shall be UL listed and FM approved. Fittings shall be ASTM A536 ductile iron, ASTM A234 forged steel or ASTM A53 fabricated steel with factory grooved ends designed to accept Victaulic couplings.

f. Victaulic, Grinnell, or approved equal, mechanical couplings shall consist of two ASTM A536 ductile iron housings, pressure-responsive, synthetic rubber gasket and plated steel bolts and nuts.

i. Rigid Type: Housings shall be cast with offsetting, angle-pattern bolt pads to provide system rigidity and support and hanging in accordance with NFPA-13. Tongue and recess rigid type couplings shall only be used if the contractor uses a torque wrench for installation. Required torque shall be in accordance with the manufacturer's latest recommendation.

1) 1-1/4" through 8": "Installation Ready" stab-on rigid coupling, designed for direct 'stab' installation onto grooved end pipe without prior field disassembly and no loose part. Victaulic FireLock EZ Style 009H (1-1/4" – 4") and Victaulic QuickVic Style 107H (2"-8").

2) 2" and Larger: Standard rigid coupling design. Victaulic Style 07 Zero-Flex.

ii. Flexible Type: use in seismic areas and where required by NFPA-13.

1) 2" through 8": "Installation Ready" stab-on flexible coupling, designed for direct 'stab' installation onto grooved end pipe without prior field disassembly and no loose parts. Victaulic QuickVic Style 177.

2) 2" and Larger: Standard flexible coupling design. Victaulic Style 75 or 77.

Fire Suppression System Service	Temperature Range	Gasket Recommendation
Water/Wet Systems	Ambient	Grade EPDM, Type A-C Shaped, FireLock EZ, or QuickVic Design

g. Gate Valves: 2-1/2 inches & larger - listed 175 lb. OS&Y, flanged. 2 inches & smaller - UL/FM listed 175 lb., bronze, screwed. Furnish all sprinkler control valves with slow close manual operator and position indicator. Tamper switches furnish under Division 21.

h. Grooved End Gate Valves: 2-1/2inches and Larger – UL listed/FM approved, 250 psi maximum pressure rating, OS&Y, ductile iron body, bronze mounted, grooved ends. Victaulic FireLock Series 771.

i. Grooved End Butterfly Valves: 2 inches & Larger: UL listed/FM approved, up to 365 psi maximum pressure rating, ductile iron body, nickel-plated ductile iron disc, Nitrile seat, weather-proof actuator with two pre-wired supervisory switches. Victaulic FireLock Series 765 or Series 705.

j. Globe Valves: 2 inches & smaller - 175 lb., bronze, screwed, UL/FM listed.

k. Check Valves: 2-1/2 inches & smaller - UL/FM listed 175 lb., flanged swing check. 2 inches & smaller - listed 175 lb., bronze swing check, screwed.

l. Grooved End Check Valves: 2 inches and Larger: UL listed/FM approved, up to 365 psi maximum pressure rating, ductile iron body, spring-loaded stainless steel or EPDM coated ductile iron disc, nickel-plated or welded-in nickel seat. Victaulic FireLock Series 717H or Series 717.

m. Finish: All exposed fire suppression piping shall be primed and painted with epoxy red paint. White letters shall indicate pipe and indicate direction of flow. Painting shall be provided under Division 09.

n. Special Requirements: All fire suppression piping, valves, fittings and joints shall comply with applicable National Fire Protection Pamphlets (NFPA) local codes, building codes, Fire Marshal, Owner's Insurance Underwriter, and the authority having jurisdiction.

B. Steel pipe shall be similar and equal to National Allied Tube or Wheatland black or zinc-coated (galvanized) as hereinafter specified. Pipe shall be free from all defects which may affect the durability for the intended use. Each length of pipe shall be stamped with the manufacturer's name.

C. Copper pipe shall be Revere, Anaconda or Chase with approved solder fittings.

D. Welding fittings for steel pipe shall meet the requirements of ASTM Standard A-23 and shall be standard catalog products. Fittings fabricated by metering and notching pipe will not be accepted.

2.2. PIPE HANGERS

A. All hangers for metallic piping shall be adjustable, wrought clevis type, or adjustable malleable split ring swivel type, having rods with machine threads. Hangers shall be Grinnell Company's Figure 260 for pipe ¾-inch and larger, and Figure 65 for pipe 2-inches and smaller, or approved equal. Adjustable pipe stanchion with U-bolt shall be Grinnell Company's Figure 191. Pipe roller supports shall be Grinnell's Figure 181 or Figure 271. Exterior pipe hangers shall be galvanized or stainless steel construction. For copper piping in direct contact with the hanger, hanger construction shall be copper coated to prevent contact of dissimilar metals similar to Grinnell's Figure CT-65. Hanger spacing and rod sizes for steel and copper pipe shall not be less than the following:

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
3/4 & 1	6	5	3/8
1 - ½	6	8	3/8
2	8	8	3/8
2 – ½	10	9	½
3	12	10	½
4	14	12	5/8
5	14	12	5/8
6	16	14	3/4
8	18	16	7/8
10	20	18	7/8
12	20	18	7/8

B. Anchors, guides, and roller supports shall be installed in accordance with the contract drawings and manufacturer's recommendations to provide pipe support and control pipe movement for all piping systems. Anchors and guides shall be securely attached to the pipe support structure. Submit shop drawing for proposed pipe support structure for guides and anchors for approval of the Structural Engineer. Pipe alignment guides shall be Fig. 255 Grinnell, or as approved equal. Guides shall be sized to accommodate the pipe with insulation. Guides shall be steel factory, fabricated, with bolted two section outer cylinder and base for alignment of piping and two section guiding spider for bolting to pipe.

C. Hangers for pipe sizes ½ to 1 ½ inch (13 to 38 mm): Carbon steel, adjustable swivel, split ring, comply with NFPA-13.

D. Hangers for pipe sizes 2 to 4 inches (50 to 100 mm): Carbon steel, adjustable, clevis. Comply with NFPA-13.

E. Hangers for cold pipe sizes 6 inches (150 mm) and over: adjustable steel yoke, cast iron roll, double hanger, comply with NFPA-13.

F. Multiple or Trapeze hangers: Steel channels with welded spacers and hanger rods.

G. Wall support for pipe sizes to 3 inches (76 mm): cast iron hook, comply with NFPA-13.

H. Wall support for pipe sizes 4 inches (100 mm) and over: Welded steel bracket and wrought steel clamp, comply with NFPA-13.

I. Wall support for pipe sizes 6 inches (150 mm) and over: welded steel bracket and wrought steel clamp with adjustable steel yoke and cast iron roll, comply with NFPA-13.

J. Vertical Support: Steel riser clamp, comply with NFPA-13.

K. Floor support for pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support, comply with NFPA-13.

L. Copper pipe support: Carbon steel ring, adjustable, copper plated, comply with NFPA-13.

M. Hanger rods: Mild steel threaded both ends, threaded one end, or continuous threaded, comply with NFPA-13.

N. Inserts: Malleable iron case of galvanized steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

O. Victaulic Style 009H, 107H, and 07, Grinnell, or approved equal, rigid couplings may be used with IPS steel piping systems, which meet the support and hanging requirements of NFPA-13. An adequate number of Victaulic Style 177, 75, and 77, Grinnell, or approved equal, flexible couplings shall also be used to compensate for thermal expansion/contraction of the pipe.

P. For Pipe Hangers installed in corrosive environments such as the chemical storage rooms, Janitor’s Closets…etc. the same shall be finished with an Electro-Galvanized finish such as Galv-Krom® or approved equal.

2.3. VALVES

A. Provide parts list and assembly drawings (exploded view) for all valves in shop drawing submittals. Provide valves of the same type by the same manufacturer. All valves shall be provided with tamper switches and coordinated with Division 28.

2.4. PRESSURE GAUGES

A. Unless otherwise indicated, pressure gauges shall be the bronze bourdon tube type, 4-1/2-inch dial, stem mounting, cast aluminum adjustable pointer, 1 percent accuracy over middle half of scale range, 1-1/2 percent over balance: Trerice Model 600C; Weksler Instruments, Ernst Gage Co., Miljoco, or as approved equal.

B. Gauges shall have pressure, vacuum, compound, or retard ranges as required,

select ranges so that the normal readings are at the approximate midpoint and maximum system pressures do not exceed full scale.

C. Furnish and install a gauge valve at each pressure gauge. Gauge valves shall be Crane Model No. 88, Needle Valve, Ernst Gage Co. FLG 200, Wexler Instrument Corp. Type BBV4, or approved equal, rated for pressure intended.

D. Gauge connections for pressure gauges or control instruments shall be made using tee fittings, except that gauge connections up to 1-inch size in steel may be using threaded extra heavy pipe couplings welded directly to the main, provided that the main is at least 2-inch size for 2-inch connections, 3-inch size for 3/4-inch connections, and 4-inch size for 1-inch connections. Minimum gauge connection shall be 2-inch ips.

E. Provide snubbers on all gauges. Snubbers shall be No. 872 by Trerice, RS1/RS6 by Wexler Instruments, Miljoco or as approved equal.

2.5. ESCUTCHEONS

A. Provide chromium plated escutcheons properly fitted and secured with set screws on all exposed piping which passes through walls, floors or ceilings of finished spaces.

B. All escutcheon plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface. Plastic escutcheon plates will not be accepted.

2.6. DIELECTRIC CONNECTIONS:

A. Furnish and install electrically insulated dielectric waterway fittings, unions or flanges, as manufactured by EPCO Sales, Inc., or Victaulic Co. at the following locations:

1. Where steel piping systems join copper piping.

2. Avoid the installation of steel nipples, cast iron or steel valves and specialties, or other ferrous components in predominately copper piping systems. Where such installation is necessary, isolate the component with dielectric connections. Do not mix steel pipe and copper tube in the same run of pipe or in the same section of a piping system.

2.7. SLEEVES

A. Sleeves shall be provided around all pipes through walls, floors, ceilings, partitions, roof structure members or other building parts. Sleeves shall be standard weight galvanized iron pipe two sizes larger than the pipe or insulation so that pipe or insulation shall pass through masonry or concrete walls or floors. Provide 20 gauge galvanized steel sheet or galvanized pipe sleeves for all piping passing

through frame walls.

B. Sleeves through floors shall be flush with the floor except for sleeves passing through Equipment Rooms which shall extend ¾-inch above the floor. Space between the pipe and sleeve shall be caulked. Escutcheon plates shall be constructed to conceal the ends of sleeves. Each trade shall be responsible for drilling existing floors and walls for necessary sleeve holes. Drilling methods and tools shall be as hereinbefore specified.

C. Sleeves through walls and floors shall be sealed with with a waterproof caulking compound.

D. Firestop at sleeves that penetrate smoke barriers smoke partitions and/or rated walls/floors.

2.8. WATER PROOF PIPE PENETRATION SEALS

A. Provide and install waterproof pipe penetration seals at all pipes that enter the building below grade or through exterior wall.

B. Link seals are to be Metraflex Metraseals, Model MS, Linkseal, or approved equal, black EPDM seal material, glass reinforced plastic pressure plates, zinc plated nuts and bolts, seals are to be resistant to sunlight and ozone, pressure rated to make a hydrostatic seal of up to 20 psig and up to 40 feet of head, temperature rated from –40 degrees F to 250 degrees F.

PART 3 - EXECUTION

3.1. GENERAL PIPING INSTALLATION REQUIREMENTS

A. All pipes shall be cut accurately to measurements established at the building, and shall be worked into place without springing or forcing, properly clearing all windows, doors and other openings. Excessive cutting or other weakening of the building structure to facilitate piping installation will not be permitted. All pipes shall be so installed as to permit free expansion and contraction without causing damage. All open ends of pipe lines, equipment, etc., shall be properly capped or plugged during installation to keep dirt or other foreign material out of the system. All pipes shall be run parallel with the lines of the building and as close to walls, columns and ceilings as may be practical, with proper pitch. All piping shall be arranged so as not to interfere with removal of other equipment or devices and not to block access to doors, windows, manholes, or other access openings. Flanges or unions, as applicable for the type of piping specified, shall be provided in the piping at connections to all items of equipment, and installed so that there will be no interference with the installation of the equipment. All valves and specialties shall be placed to permit easy operation and access and all valves shall be regulated, packed and glands adjusted at the completion of the work before final acceptance. All piping shall be installed so as to avoid air or liquid pockets throughout the work. Ends of pipe shall be reamed so as to remove all burrs.

B. All piping shall be run to provide a minimum clearance of 2-inches between finished covering on such piping and all adjacent work. Group piping wherever practical at common elevations.

C. All valves and other fittings shall be readily accessible.

D. Drain valves with hose connections shall be provided at low points for drainage of piping systems. Blow down valves shall be provided at the ends of all mains and branches so as to properly clean by blowing down the lines throughout in the direction of normal flow.

E. Spring clamp plates (escutcheons) shall be provided where pipes are exposed in the building and run through walls, floors, or ceilings. Plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface.

F. Install all valves with stem upright or horizontal, not inverted.

G. Where pipe support members are welded to structural building framing, scrape, brush clean, weld and apply one coat of zinc rich primer.

H. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.

3.2. PRESSURE GAGE INSTALLATION REQUIREMENTS.

A. Install pressure gages in piping tees with pressure-gage valve located on a pipe at most readable location.

B. Adjust faces of pressure gauges to proper angle for best visibility.

C. Clean windows of gages and clean factory-finished surfaces. Replace cracked and broken window, and repair scratched and marred surfaces with manufacturer's touch up paint.

3.3. VALVE INSTALLATION REQUIREMENTS

A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.

B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

C. Operate valves from fully open to fully closed positions. Examine guides and seats made accessible by such operation.

D. Examine threads on valve and mating pipe for form and cleanliness.

E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.

F. Do not attempt to repair defective valves; replace with new valves.

G. Install valves as indicated, according to manufacturer's written instructions.

H. Piping installation requirements are specified in other Division 21 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.

I. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.

J. Locate valves for easy access and provide separate support where necessary.

K. Install valves in horizontal piping with stem at or above the center of the pipe.

L. Install valves in a position to allow full stem movement.

M. Adjust or replace packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if leak persists.

3.4. PIPE JOINTS INSTALLATION REQUIREMENTS

A. Screwed Joints: All screwed joints shall be made with tapered threads properly cut. Screwed joints shall be made perfectly tight with a stiff mixture of graphite and oil, applied with a brush to the male threads on the fittings.

B. Grooved Joints: Install in accordance with the manufacturer’s (Victaulic, Grinnell, or approved equal) guidelines and recommendations. All grooved couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved components. The gasket style and elastomeric material (grade) shall be verified as suitable for the intended service as specified. Gaskets shall be molded and produced by Victaulic. Grooved end shall be clean and free from indentations, projections, and roll marks in the area from pipe end to groove for proper gasket sealing. A Victaulic factory-trained field representative shall provide on-site training for contractor’s field personnel in the proper use of grooving tools and installation of grooved piping products. Factory-trained representative shall periodically review the product installation. Contractor shall remove and replace any improperly installed products.

C. Soldered Joints and Copper Piping: Joints in copper piping shall conform to the following minimum standards.

1. The pipes shall be cut to a length making certain that the ends are square, using a fins hacksaw blade or tube cutter. The ends of all pipes shall be reamed and all burrs removed.

2. The outside end of the pipe and the cut end of the fitting shall be cleaned with steel wool, sand cloth, or steel wire brush. All dark spots shall be removed.

3. The flux shall be applied evenly and sparingly to the outside end of the pipe and the inside of the outer end of the fitting until all surfaces to be jointed are completely covered. The piping and fitting shall be slipped together and reworked several times to insure an even distribution of the flux.

4. The correct amount of solder per joint for each size pipe shall be used in accordance with the manufacturer's recommendations.

5. Solder joints shall be made by using a direct flame from a torch.

6. On pipe sizes larger than ¼-inch, the fittings and valves in the pipe shall be moved or tapped with a hammer when the solder starts to melt to insure an even distribution of the solder.

7. The excess solder shall be removed while it is still in the plastic state leaving a fillet around the cup of the fitting.

8. Solder joints shall be suitable for working pressure of 100 psig and for working temperature of not less than 250 degrees F. The type of solder and flux used will be submitted for approval. Type 95-5 shall be the minimum standard.

D. Where copper piping joins steel piping, approved bronze adapters shall be used.

E. Prohibited Connections: No direct weld, soldered, or brazed connections, without unions or flanges, shall be made to valves, strainers, apparatus, or related equipment. Right and left couplings, long threads, or caulking of pipe threads or gasket joints will not be permitted.

3.5. HANGERS AND SUPPORTS INSTALLATION REQUIREMENTS

A. General: All hangers shall be of an approved type arranged to maintain the required grading and pitching of lines to prevent vibration and to provide for expansion and contraction. Saddles shall be Grinnells Figure 173/273 or approved equal. Provide approved spacers between saddles and pipe where flexible insulation is specified. Provide insulation protection shields for insulated piping without saddles. Shield shall be Grinnell Figure 167 or as approved equal. Comply with NFPA-13.

B. Spacing: Regardless of spacing, hangers shall be provided at or near all changes in direction, both vertical and horizontal, for all piping.

C. Vertical Lines: Shall be supported at their bases, using either a suitable hanger placed in a horizontal line near the riser, or a base type fitting set on a pedestal, foundation or support. All vertical lines extending through more than one floor level shall be supported at each floor with a riser clamp. Riser clamp shall be Grinnell

Co.'s Figure 261, or approved equal. All vertical drops to pump suction elbows shall be supported by floor posts.

D. Racks and Brackets: All horizontal piping on vertical walls shall be properly supported by suitable racks securely anchored into the wall construction. Where not practical to obtain ceiling anchorage, all piping near walls shall be supported by approved brackets securely anchored into the wall construction. Washer plates (Fib. 60, 60L) and other miscellaneous attachments, fasteners, etc., shall be Grinnell or as approved equal. All exterior hanger and bracket systems in their entirety shall be galvanized.

E. Pipe Hangers and supports shall be attached to the panel point at the top chord of bar joist or at a location approved by the structural engineer.

F. Select hangers and components for loads imposed. Secure rods with double nuts.

G. Support of horizontal piping shall allow for vertical adjustment after installation of piping.

H. Support overhead piping with clevis hangers.

I. Do not support all parallel piping from the same joist. Stagger all supports in accordance with the structural engineer's recommendations.

J. Fabricate and install steel anchors by welding steel shapes, plates, and bars to piping and to structure. Comply with ASME B31.9 and AWS D1.1.

K. Construct concrete anchors of poured in place concrete of dimensions indicated and include embedded fasteners.

L. Refer to structural documents for appropriate connection/attachment materials to building.

M. Fire protection pipes shall be supported independently of other building trade supports per NFPA-13.

3.6. PIPING IDENTIFICATION INSTALLATION REQUIREMENTS

A. All piping shall be identified with painted background marked with the name of the service with arrows to indicate flow direction. Color code and system identification shall comply with ANSI Standards and piping identification system shall comply with ASME A13.1-81., scheme for the identification of piping systems and NFPA pamphlets, latest edition.

B. Markings shall be plain block letters, stenciled on pipes, and shall be located near each branch connection, near each valve, and at least every 10 feet on straight runs of pipe. Where pipes are adjacent to each other, markings shall be neatly lined up. All markings shall be located in such manner as to be easily legible from the floor. Pipe identification schedule shall be as follows:

OUTSIDE DIAMETER OF PIPE OR COVERING (INCHES)	LENGTH OF COLOR FIELD (INCHES)	SIZE OF LETTERS (INCHES)
½ to 1 ¼	8	½
1-½ to 2	8	¾
2 ½ to 6	12	1 ¼
8 to 10	24	2 ½
Over 10	32	3 ½

3.7. VALVE IDENTIFICATION REQUIREMENTS

A. All valves shall be tagged with a numbered tag.

B. The tags shall be made of 1-inch diameter brass tags fastened to the valve by means of brass chains. Numbers shall agree with valve numbers on diagrammatic herein before specified.

C. Provide a minimum of three (3) valve charts with valve numbers indicating valve type, size, manufacturer and service.

D. Additional valve charts shall be mounted behind glazed wooden frames and be hung in the main fire protection riser room. Additional copies shall be provided in each copy of the O&M manuals.

END OF SECTION 210505

PAGE LEFT INTENTIONALLY BLANK

SECTION 211003 - WATER BASED FIRE SUPPRESSION SYSTEM - SPRINKLERS

PART 1 - GENERAL

1.1. REFERENCE

A. The conditions of the Contract and General Requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 21 Section, Common Work Results for Fire Protection and Division 01 Section, General Requirements.

B. Submit complete shop drawings of all equipment utilized with the system in accordance with Division 21 Section, Common Work Results for Fire Protection. Submittals shall include but not be limited to the following fire protection system and accessories:

1. Pressure Sensing Devices, Valves
2. Alarm Check Valves
3. Pressure/Vacuum Gauges
4. Inspector’s Test Station
5. Eccentric Reducers
6. Pressure Switches
7. Valves and Piping
8. Flow Switches
9. Tamper Switches
10. Auxiliary Drains

C. Provide sprinklers, piping and associated equipment complete and ready for operation. Equipment materials, installation, workmanship, fabrication, assembly, erection, examination, inspection, and testing shall be in accordance with NFPA-13, NFPA-70, NFPA-72E, and NFPA-101. Devices and equipment for fire protection service shall be U.L listed or FM approved.

D. All of the equipment and devices shall be included within the project Operations and Maintenance Manuals.

E. Refer to Division 21 Section, Fire Protection Pipes, Valves, and Fittings for pipe materials.

F. Fire Protection Systems design, equipment and installation shall comply with the

Delaware State Fire Prevention Regulations, latest edition including all Annexes and Addendums.

1.2. DESCRIPTION

A. Provide all facilities, labor, materials, tools, equipment, appliances, transportation, supervision, and related work necessary to complete the work specified in this Section and as shown on the drawings. The work shall be performed by a licensed sprinkler contractor only. All equipment, piping, devices, and valves shall be sized based on hydraulic calculations. Include a 10 psig safety factor with hydraulic calculations.

B. Layout sprinkler system complete and size all fire protection piping in accordance with requirements of the National Fire Protection Association and the State Fire Marshal. System shall be designed for occupancy as required by applicable codes. Conceal fire protection piping in finished spaces unless indicated otherwise. System drains and inspector's test shall not be located in finished spaces.

C. Sprinkler equipment and work shall conform to requirements of National Fire Protection Association Standard No. 13 and No. 24. In addition, all work shall conform to requirements of all codes and regulations of authorities having jurisdiction over this work, including, but not limited to, State Fire Marshal, County Fire Marshal, Life Safety Codes and International Code, and Insurance Underwriter.

D. Preliminary Shop Drawing: Prior to preparing detailed working drawings for submission to State Fire Marshal, submit preliminary sprinkler system layout to the Architect for review and approval. Show all finished ceilings, light fixtures, air diffusers and other ceiling mounted devices. Coordinate sprinkler head types and locations with ceiling types. All sprinkler heads in acoustic tile ceilings shall be centered in the tile.

E. The fire protection contractor shall prepare dimensioned and detailed working drawings, specifications, and hydraulic calculations and submit same to the State Fire Marshal and/or County Fire Marshal for review and approval. Prior to submission to the Fire Marshal, the Fire Protection Contractor shall have all fire protection drawings, submittals, calculations reviewed and approved by a registered Fire Protection Engineer or a level III Nicet Technician. One set of these approved documents shall be provided to the Engineer for record purposes. All costs related to changes required to obtain the Fire Marshal's or Insurance Underwriters’ approval shall be the responsibility of the contractor.

F. Manufactured equipment and materials shall be submitted to the Engineer for review and approval, in accordance with the requirements of Division 21 Section, Common Work Results for Fire Protection.

G. Hydraulic calculations should be based on an available water supply as follows:

Static Pressure =	45 psig
Residual Pressure =	39 psig
Flow =	891 gpm
Location =	Campus Loop Road
Size of Mains =	8 inches
Existing Pipe Material	For Hydraulic Calculations Assume Roughness Coefficient C factor = 100 for all Exterior Piping.

H. Hydraulic calculations shall include a 10 psig safety factor to account for pipe aging and deterioration of water supply.

I. For small areas subject to freezing (exterior canopy, etc.), Contractor shall provide and install freeze proof heads, piping, control valves, tamper switches, test stations, etc., as required by NFPA-13 and the authority having jurisdiction.

J. Where combustible construction materials are located above ceilings, provide above ceiling fire protection in accordance with N.F.P.A-13.

K. Where the architectural documents indicate ceiling “clouds” provide sprinklers above and below the same per NFPA-13. Coordinate exact locations of sprinkler heads and piping with Architect. Submit to Architect for review/approval sprinkler head/piping layout in these areas prior to submitting to working drawings.

1.3. DELIVERY, STORAGE AND PROTECTION

A. Refer to Division 01 Section, General Requirements: Transport, handle, store, and protect products.

B. Accept equipment and devices on site in factory packing. Inspect for damage. Comply with manufacturer’s rigging and installation instructions for all equipment.

C. Protect components from physical damage including effects of weather, water, and construction debris.

D. Provide temporary inlet and outlet caps, and maintain in place until installation.

1.4. EXTRA MATERIALS

A. Provide extra sprinklers under provisions of NFPA-13. Provide suitable wrenches for each sprinkler type and metal storage cabinet.

1.5. PERMITS FROM THE AUTHORITY HAVING JURISDICTION AND FEES

A. Pay all permits, fees, and charges required for this work.

1.6. HYDRANT FLOW TESTS

A. The Fire Protection Contractor shall perform a hydrant flow test.

B. The hydrant flow test shall be performed by the Fire Protection Contractor in the vicinity of each building at no additional cost to the Owner.

C. Where practical, tests shall be performed between 9:00 a.m. and 5:00 p.m. on a normal working day during summer. If conducting the test is impractical during these hours, then a local Fire Department representative shall be present to "observe" the test during "off peak" hours and to acknowledge the correctness of results.

D. The tests shall be submitted for review prior to submitting any hydraulic calculations. The test data shall contain the following:

1. Date of the test

2. Who performed the test and who was present.

3. Site plan indicating locations and diameters of water mains and locations of the hydrants tests.

4. Grade elevation of the hydrant tests

5. Static pressure in psig

6. Flow in GPM

7. Residual pressure in psig

8. Hydrant butt size in inches

9. Hydrant coefficient

1.7. ALTERNATES

A. Refer to Division 01 Section, Alternates - Alternates for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1. SPECIALTIES

A. All sprinkler heads shall be U.L. listed and shall be of the same manufacturer throughout the building.

B. Piping shall be in accordance with Division 21 Section, Fire Suppression System

Piping, Fittings, and Valves, etc. All exposed fire protection piping in unfinished areas shall be painted with red epoxy paint. White letters shall identify piping and indicate direction of flow. Exposed fire protection piping within finished areas shall be painted in color as determined by the Architect/Engineer.

C. Shut-off valves shall be UL approved O.S. and Y. double disc gate valves or UL/FM approved grooved end butterfly valves.

D. Check valves shall be swing check type or spring-loaded type UL approved for the application.

E. Coordinate the fire protection systems with the fire alarm system specified under Division 26. Provide alarm initiating devices with proper contact arrangement. All electrical wiring shall be furnished and installed under Division 26.

F. Flow control valve, alarm switches and valve supervision shall be furnished and installed under this Division. All wiring shall be accomplished by the electrical contractor, under Division 26. Provide any additional flow control valves, alarm switches, tamper switches and flow switches required by NFPA-13 but not indicated on contract drawings. Coordinate with the alarm system and electrical subcontractor.

G. Pipe and fittings shall meet the requirements of NFPA-13 and NFPA-24.

2.2. SPRINKLER HEADS

A. Suspended or Drywall Ceilings:

1. Manufacturer: Victaulic, Viking, Grinnell, Reliable, or approved equal.

2. All sprinkler heads installed in suspended ceilings and drywall ceilings including bulkheads shall be Victaulic Model V38 concealed quick response sprinkler or approved equal. Cover plate shall be finished with a polyester baked enamel finish. Color selection by Architect. Provide cover assembly with each head. Frangible glass bulb shall be temperature rated for specific area hazard.

B. Exposed Area Type:

1. Manufacturers: Victaulic, Viking, Grinnell, Reliable, or approved equal.

2. Sprinkler heads in unfinished or exposed areas shall be Victaulic Model V27, or approved equal. These sprinklers shall be standard, ½ inch upright, pendant or conventional where required. Provide guards where hereinafter indicated. Sprinklers shall be brass with frangible glass bulb temperature rated for specific area hazard. Provide standard brass, screw on flat escutcheon plate.

C. Sidewall type:

1. Manufacturers: Victaulic, Viking, Grinnell, Reliable, or approved equal.

2. Sidewall sprinklers shall be Victaulic Model V27 semi-recessed horizontal sidewall type with matching screw on escutcheon plate. Sprinkler and escutcheon plate finish shall be chrome plated. Frangible glass bulb shall be temperature rated for specific area hazard.

D. The temperature rating of the sprinklers shall be as required by N.F.P.A.-13 and or the authority having jurisdiction.

E. All sprinkler heads installed in lay-in ceiling tiles shall be located in the center of the tile to provide a symmetrical, aesthetic and neat appearance. All sprinkler heads installed in bulkheads, recesses, and soffits shall be centered to provide a symmetrical, aesthetic and neat appearance.

F. Provide extended escutcheons in rooms with surface mounted lighting fixtures.

G. Additional heads shall be furnished as required by NFPA-13. The heads shall be in a cabinet designed to hold the heads and include one sprinkler head wrench for each type of sprinkler. Cabinet shall be mounted where indicated in the field.

H. Head guards shall be provided in mechanical spaces, janitors' closets, electrical rooms, and storage areas. Finish for head guards in finished spaces shall be selected by Architect.

I. Sprinkler escutcheons and guards shall be listed, supplied, and approved for use with the sprinkler, by the sprinkler manufacturer.

J. Provide high temperature sprinkler heads for use adjacent to skylights, heaters, lights, or other high temperature areas.

K. All sprinklers, piping, and pipe hangers installed in corrosive areas (chemical rooms, janitor's closets, etc.) shall be provided with a protective coating.

2.3. FLEXIBLE SPRINKLER DROPS

A. Stainless Steel Sprinkler Fittings

1. Manufacturer: Victaulic AquaFlex® or Grinnel.

2. In lieu of rigid pipe offsets for concealed locations only, or return bends for sprinkler drops, the Victaulic AquaFlex® stainless steel, multiple-use, sprinkler fitting system may be used to locate sprinklers as required by final finished ceiling tiles and walls. The drop system shall consist of a braided or unbraided (corrugated) type 304 stainless steel flexible tube, a zinc-plated steel 1" NPT male threaded nipple for connection to branch-line piping, and a zinc-plated steel reducer with ½" or ¾" NPT female thread for connection to the sprinkler head. Union joints shall be provided for ease of installation. The flexible drop shall attach to the ceiling grid using a one-piece open gate bracket. The braided drop system is FM approved for

sprinkler services to 200 psi and can be installed without the use of tools, and the unbraided system is UL listed for sprinkler services to 175 psi.

2.4. SIGNS

A. Provide 9 inch x 7 inch signs suspended from control valves which indicate the purpose of the valve and its normal position, Central Type A or approved equal.

B. All control, drain, and test connection valves shall be provided with signs indicating purpose.

C. Signs shall be fabricated of an approved material, painted red with white lettering.

D. Signs shall have typed labels. Handwritten labels shall not be acceptable.

2.5. DRAINS

A. The sprinkler systems shall be arranged to be completely drainable. Means of drainage shall be provided with adequate protection from freezing.

B. Drain valve may be combined with sprinkler alarm test valve and sight glass, G/J Innovations Sure-Test, Reliable Automatic Sprinkler Co., Tyco Fire Products, Victaulic, or approved equal. Valve shall be UL listed with positive off handle for off, test or drain, integral sight glass, orifice size equal to smallest sprinkler orifice and full 1 inch drain.

2.6. ALARM DEVICES

A. All valves controlling water supply for sprinklers shall be electrically supervised in accordance with requirements of NFPA 13 and 72A, and provided under this Division. Provide separate valve chart for all fire protection valve indicating valve type, normal position, size, location and type of supervision insert in O&M manual and mount additional copies in fire pump room and mechanical rooms.

B. Valve tamper switches shall be Model OSY2 as manufactured by System Sensor or Model OSYSU-A2 as manufactured by Potter Electric Signal Company or approved equal. The valve tamper switches shall monitor the open position of all OS&Y gate valves. Each tamper switches shall contain two sets of single pole double throw, Form C contacts. All valve tamper switches shall have tamper resistant covers that upon removal of the cover will cause the switches to operate. Tamper switches shall be suitable for 125/250 VAC @ 15 AMPS. All tamper switches shall be U.L. listed and F.M. approved.

2.7. GAUGES

A. A listed 3 ½ inch dial spring pressure gauge shall be connected to the top of each standpipe. Gauges shall be located in a suitable place to prevent freezing. Each

gauge shall be controlled by a valve having arrangement for draining.

B. Listed pressure gauges with connections not smaller than ¼ inch shall be installed at the system main drain, at each main drain associated with a floor control valve, and above and below each alarm check-valve.

C. All pressure gauges shall be listed and shall have a maximum limit not less than twice the normal working pressure at the point where installed. They shall be installed to permit removal and shall be located where they will not be subject to freezing.

2.8. VALVES

A. Provide and install control valves as indicated on contract drawings and as required by N.F.P.A.-13. Gate valves shall be listed O.S. & Y. type. All control valves shall be supervised open. Supervision shall be as required by N.F.P.A.-13. Victaulic Series 705 and 765 grooved end butterfly valves shall be supervised in the open position.

PART 3 - EXECUTION

3.1. GENERAL INSTALLATION REQUIREMENTS

A. Install equipment in accordance with manufacturer's instructions.

B. Place pipe runs to minimize obstruction to other work.

C. Place piping in concealed spaces above finished ceilings.

D. Center sprinklers in two directions in ceiling tile and provided piping offsets as required.

E. Apply masking tape or paper cover to ensure concealed sprinklers, cover plates, and sprinkler escutcheons do not receive field paint finish. Remove after painting. Replace painted sprinklers.

F. Flush entire piping system of foreign matter.

G. Install guards on sprinklers where subject to abuse and where specified.

H. Hydrostatically test entire system.

I. Test must be witnessed by Fire Marshal/authority having jurisdiction/ Owner’s insurance underwriter/ Architect/Engineer.

J. Refer to plumbing floor plans for approximate locations of sprinkler zones control valve assemblies and routing of fire protection mains.

K. The fire protection contractor shall hydraulically prove the most remote area per NFPA-13.

L. Coordinate locations of sprinkler heads with lights, diffusers, ceiling types, etc.

M. Hydrostatically test system at 200 PSI for 4 hours, per NFPA-13.

N. The sprinkler bulb protector must remain in place until the sprinkler is completely installed and before the system is placed in service. Remove bulb protectors carefully by hand after installation. Do not use any tools to remove bulb protectors.

O. Refer to Architectural Drawings for exact location and extent of all fire rated walls and smoke barriers.

P. Grooved joint piping systems shall be installed in accordance with the manufacturer's (Victaulic) guidelines and recommendations. All grooved couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved components. The gasket style and elastomeric material (grade) shall be verified as suitable for the intended service as specified. Gaskets shall be molded and produced by Victaulic. Grooved end shall be clean and free from indentations, projections, and roll marks in the area from pipe end to groove for proper gasket sealing.

3.2. INTERFACE WITH OTHER PRODUCTS

A. Ensure required devices are installed and connected as required to fire alarm system.

3.3. LAYOUT

A. Coordinate layout and installation of fire protection system with all other buildings structural, mechanical and electrical work. Locate sprinkler heads symmetrically with respect to ceiling tiles, lighting fixtures, registers, grilles, diffusers, etc. Provide piping offsets as required to maintain symmetry. Note that a preliminary sprinkler layout is to be submitted for review. Contractor is cautioned that sprinkler mains must be located to prevent conflict with other work and in any case, sprinkler contractor shall be responsible for coordination of his work with work of other trades.

B. Unless otherwise indicated, the entire building shall be protected throughout with a wet pipe sprinkler system. Where required by NFPA-13 and/or the authority having jurisdiction, install sprinkler heads above and below ceilings.

3.4. WET PIPE SPRINKLER SYSTEM

A. System components shall include, but not be limited to flow control valves, electrical connections to central fire alarm system, fire department connection,

check valves, main piping, branch piping, inspector's test, drains, sprinkler heads, ball drip valves, signs, etc. and all other incidental appurtenances as required.

3.5. VALVE INSTALLATION

A. Gate Valves: Install fire-protection-service valves supervised-open, located to control sources of water supply except from fire department connections. Provide permanent identification signs indicating portion of system controlled by each valve.

B. Install check valve in each water-supply connection.

3.6. CONNECTIONS

A. Connect water supplies to sprinklers. Include backflow preventers.

B. Connect piping to specialty valves, specialties, fire department connections, and accessories.

C. Connect alarm devices to fire alarm.

3.7. COMMISSIONING

A. Verify that specialty valves, trim, fittings, controls, and accessories are installed and operate correctly.

B. Verify that specified tests of piping are complete.

C. Verify that damaged sprinklers and sprinklers with paint or coating not specified are replaced with new, correct type.

D. Verify that sprinklers are correct types, have correct finishes and temperature ratings, and have guards as required for each application.

E. Fill wet-pipe sprinkler piping with water.

F. Energize circuits to electrical equipment and devices.

G. Adjust operating controls and pressure settings.

H. Coordinate with fire alarm tests. Operate as required.

3.8. DRAINS

A. The sprinkler system shall be arranged to be completely drainable. Means of drainage shall be provided with adequate protection from freezing.

3.9. TESTS

A. The sprinkler systems installation shall be hydrostatically tested, inspected, and approved, in accordance with NFPA Standard No. 13 and NFPA Standard No. 25. Test certificate shall be forwarded to the Office of the State Fire Marshal and the Architect as proof of compliance.

B. Tests shall be performed in accordance with the requirements of the Office of the State Fire Marshal and shall prove the systems to be adequate and satisfactory in every respect. All tests shall be performed in the presence of the State Fire Marshal or his representative.

C. Any deficiencies revealed by these tests shall be corrected and the systems shall be retested until acceptable results are obtained.

3.10. AS-BUILT DRAWINGS & PROJECT CLOSEOUT

A. Provide separate as-built drawings of all fire protection systems meeting requirements of General Mechanical Requirements hereinbefore specified.

B. At the completion of the work, provide a sealed plan of the building indicating the locations of all control valves, low point drains, flow switches, and Inspectors Test Stations. The plan shall be neatly drawn and color coded to indicate the portion of the building protected by each system, framed under glass and permanently mounted on the wall adjacent to the system header.

C. Include manufacturers literature, cleaning procedures, replacement parts, lists, and repair data for equipment.

D. Include manufacturers’ instructions, start-up data, troubleshooting, check lists for all equipment.

3.11. WARRANTY

A. The Contractor's attention is directed to the warranty obligations contained in the Article of the General Conditions of the specifications entitled "warranty".

3.12. OWNER TRAINING

A. Upon completion of the project, furnish a complete copy of NFPA-25 to Owner. Provide correspondence indicating that the pamphlet has been turned over to the Owner.

1. Contractor shall provide at least four (4) hours of training to the Owner on the proper inspection, testing, and maintenance of the installed fire protection system.

2. Schedule training with the Owner through the Architect and/or Engineer

with at least seven (7) days prior notice.

3. A Victaulic factory-trained field representative shall provide on-site training for contractor's field personnel in the proper use of grooving tools and installation of grooved piping products. Factory-trained representative shall periodically review the product installation. Contractor shall remove and replace any improperly installed products.

END OF SECTION 211003

SECTION 220500 - COMMON WORK RESULTS FOR PLUMBING

PART 1 - GENERAL

1.1. SUMMARY

A. All work under Division 22 is subject to the Division 01, General Requirements, the General Conditions and Supplementary Conditions.

B. Provide all labor, materials, equipment, and services necessary for and incidental to the complete installation and operation of all plumbing work.

C. Unless otherwise specified, all submissions shall be made to, and acceptances and approvals made by the Architect and the Engineer.

D. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange piping, equipment, and other work generally as shown on the contract drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed shop drawings for approval in accordance with Submittals specified below. The right is reserved to make reasonable changes in location of equipment, piping, up to the time of rough-in or fabrication.

E. Conform to the requirements of all rules, regulations and codes of local, state and federal authorities having jurisdiction.

F. Coordinate the work under Division 22 with the work of all other construction trades.

G. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the contract documents.

1.2. PERMITS AND FEES

A. Obtain all permits and pay taxes, fees and other costs in connection with the work. File necessary plans, prepare documents, give proper notices and obtain necessary approvals. Deliver inspection and approval certificates to Owner prior to final acceptance of the work.

B. Permits and fees shall comply with the Division 01, General Requirements of the specification.

1.3. EXAMINATION OF SITE

A. Examine the site, determine all conditions and circumstances under which the work must be done, and make all necessary allowances for same. No additional cost to the Owner will be permitted for contractors failure to do so.

B. Examine and verify specific conditions described in individual specifications sections.

C. Verify that utility services are available, of the correct characteristics, and in the correct locations.

1.4. CONTRACTOR QUALIFICATION

A. Any Contractor or Subcontractor performing work under Division 22 shall be fully qualified and acceptable to the Architect and Owner. Submit the following evidence when requested:

1. A list of not less than five comparable projects which the Contractor completed.

2. Letter of reference from not less than three registered professional engineers, general contractors or building owners.

3. Local and/or State License, where required.

4. Membership in trade or professional organizations where required.

B. A Contractor is any individual, partnership, or corporation, performing work by contract or subcontract on this project.

C. Acceptance of a Contractor or Subcontractor will not relieve the Contractor or subcontractor of any contractual requirements or his responsibility to supervise and coordinate the work, of various trades.

1.5. MATERIALS AND EQUIPMENT

A. Materials and equipment installed as a permanent part of the project shall be new, unless otherwise indicated or specified, and of the specified type and quality. Existing items of equipment are being relocated under another Division of these specifications. The Contractor shall be responsible for connecting all utilities as shown on the drawings, to equipment identified as existing.

B. Where material or equipment is identified by proprietary name, model number and/or manufacturer, furnish named item, or its equal, subject to approval by Engineer. Substituted items shall be equal or better in quality and performance and must be suitable for available space, required arrangement, and application. Submit all data necessary to determine suitability of substituted items, for approval.

C. The suitability of named item only has been verified. Where more than one item is named, only the first named item has been verified as suitable. Substituted items, including items other than first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement and application. Contractor, by providing other than the first named manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation. Adjustments and modifications shall include but not be limited to electrical, structural, support, and architectural work.

D. Substitution will not be permitted for specified items of material or equipment where noted.

E. All items of equipment furnished shall have a service record of at least five (5) years.

1.6. FIRE SAFE MATERIALS

A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA and ASTM standards for fire safety with smoke and fire hazard rating not exceeding flame spread of 25 and smoke developed of 50.

1.7. REFERENCED STANDARDS, CODES AND SPECIFICATIONS

A. Specifications, Codes and Standards listed below are included as part of this specification, latest edition.

B.	ASHRAE	-	American Society of Heating, Refrigerating and Air Conditioning Engineers
C.	ASME	-	American Society of Mechanical Engineers
D.	ASPE	-	American Society of Plumbing Engineers
E.	ASTM	-	American Society for Testing and Materials
F.	AWWA	-	American Water Works Association
G.	CAGI	-	Compressed Air and Gas Institute
H.	CS	-	Commercial Standard
I.	CSD	-	Control and Safety Devices
J.	DNREC	-	Delaware Department of Natural Resources and Environmental Control
K.	FM	-	Factory Mutual

L. IBC - International Building Code

M. IEEE - Institute of Electrical and Electronics Engineers

N. MSSP - Manufacturers Standards Society of the Valve and Fittings Industry

O. NEC - National Electrical Code

P. NEMA - National Electrical Manufacturers Association

Q. NSF - National Sanitation Foundation

R. UL - Underwriters' Laboratories

S. NFPA - Dental Piping Systems

T. All plumbing equipment and materials shall comply with the codes and standards listed in the latest edition of ASHRAE HVAC Applications Handbook, Chapter entitled Codes and Standards.

1.8. SUBMITTALS, REVIEW AND ACCEPTANCE

A. Equipment, materials, installation, workmanship and arrangement of work are subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Architect to be in best interest of Owner.

B. After acceptance of Material and Equipment List, submit three (3) copies or more as required under General Conditions of complete descriptive data for all items. Data shall consist of specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, wiring diagrams, installation instructions, and any other information necessary to indicate complete compliance with Contract Documents. Edit submittal data specifically for application to this project.

C. Thoroughly review and stamp all submittals to indicate compliance with contract requirements prior to submission. Coordinate installation requirements and any electrical requirements for equipment submitted. Contractor shall be responsible for correctness of all submittals.

D. Submittals will be reviewed for general compliance with design concept in accordance with contract documents, but dimensions, quantities, or other details will not be verified.

E. Identify submittals, indicating intended application, location and service of submitted items. Refer to specification sections or paragraphs and drawings where applicable. Clearly indicate exact type, model number, style, size and special features of proposed item. Submittals of a general nature will not be acceptable. For substituted items, clearly list on the first page of the submittal all

differences between the specified item and the proposed item. The contractor shall be responsible for corrective action and maintaining the specification requirements if differences have not been clearly indicated in the submittal.

F. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Call attention, in writing, to deviation from contract requirements.

G. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted. Use only final or corrected submittals and data prior to fabrication and/or installation.

H. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.

I. For resubmissions, the Contractor must address in writing all of the Engineer’s comments on the original submission to verify compliance.

1.9. SHOP DRAWINGS

A. Prepare and submit shop drawings for all plumbing equipment, specially fabricated items, modifications to standard items, specially designed systems where detailed design is not shown on the contract drawings, or where the proposed installation differs from that shown on contract drawings.

B. Submit data and shop drawings including but not limited to the list below, in addition to provisions of the paragraph above. Identify all shop drawings by the name of the item and system and the applicable specification paragraph number and drawing number.

C. Every submittal including, but not limited to the list below, shall be forwarded with its own transmittal as a separate, distinct shop drawing. Grouping of items/systems that are not related shall be unacceptable.

D. Items and Systems

1. Access Doors/Panels including layout and location

2. Dental Air Compressors/Vacuum Pumps

3. Automatic Temperature Control System and Equipment as it relates to plumbing system

4. Dental Sink Plaster Traps

5. Backflow Preventers

6. Compressed Air Filters
7. Dental Compressed Air Regulators
8. Dental Compressed Air Drain Traps
9. Dental Compressed Air Valve Boxes
10. Dental Compressed Air Quick Disconnects
11. Coordinated Drawings
12. Direct Buried Piping
13. Drain Valves
14. Drip Pans
15. Emergency Fixtures & Thermostatic Mixing Valves
16. Equipment Rails
17. Exterior Equipment/Piping Supports
18. Fire Stopping - Methods and Materials
19. Floor Drains
20. Hose Bibbs
21. Identification System
22. Interceptors
23. Material and Equipment List
24. Dental Plumbing Systems
25. Operations and Maintenance Manuals
26. Pipe Enclosures
27. Pipe Guides and Anchors.
28. Pipe Materials Including Itemized Schedule
29. Plumbing Fixtures & Trim
30. Preliminary Testing and Balancing Report
31. Pressure/Temperature Relief Valves

32. Refrigerated Air Dryers (for compressed air systems)

33. Roof Curbs

34. Screenshots of ATC System Graphics

35. Shock Absorbers

36. Strainers

37. Test Certificates

38. Thermal Insulation Materials Include Table Summary

39. Thermometers and Gauges

40. Thermostatic Mixing Valves

41. Trap Priming Station/Valves

42. Vacuum Breakers

43. Valves

44. Vibration Isolation Materials

45. Weatherproof Assembly Components

46. Water Filters

47. Wiring Diagrams, Flow Diagrams and Operating Instructions

E. Contractor, additionally, shall submit for review any other shop drawings as required by the Architect. No item shall be delivered to the site, or installed, until the Contractor has received a submittal from the Engineer marked Reviewed or Comments Noted. After the proposed materials have been reviewed, no substitution will be permitted except where approved by the Architect.

1.10. SUPERVISION AND COORDINATION

A. Provide complete supervision, direction, scheduling, and coordination of all work under the Contract, including that of subcontractors.

B. Coordinate rough-in of all work and installation of sleeves, anchors, and supports for piping, equipment, and other work performed under Division 22.

C. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.

D. Coordinate electrical work required under Division 22 with that under Division 26.

Coordinate all work under Division 22 with work under all other Divisions.

E. Supply services of an experienced (10 years minimum) and competent Project Manager to be in constant charge of work at site.

F. Where a discrepancy exists within the specifications or drawings or between the specifications and drawings, the more stringent (or costly) requirement shall apply until clarification can be obtained from the Engineer. Failure to clarify such discrepancies with the Engineer will not relieve the Contractor of the responsibility of conforming to the requirements of the Contract.

G. Failure of contractor to obtain a full and complete set of contract documents (either before or after bidding) will not relieve the contractor of the responsibility of complying with the intent of the contract documents.

1.11. CUTTING AND PATCHING

A. Accomplish all cutting and patching necessary for the installation of work under Division 22. Damage resulting from this work to other work already in place, shall be repaired at Contractor's expense. Where cutting is required, perform work in neat and work¬manlike manner. Restore disturbed work to match and blend with existing construction and finish, using materials compatible with the original. Use mechanics skilled in the particular trades required.

B. Do not cut structural members without approval from the Architect or Engineer.

1.12. PENETRATION OF WATERPROOF CONSTRUCTION

A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls, and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary curbs, sleeves, flashings, fittings and caulking to make penetrations absolutely watertight.

B. Where plumbing vents or other pipes penetrate roofs, flash pipe with Stoneman Stormtite, Pate or approved equal, roof flashing assemblies with skirt and caulked counter flashing sleeve.

C. Furnish and install pitch pockets or weather tight curb assemblies where required.

D. Furnish and install roof drains, curbs, and vent assemblies specifically designed for application to the particular roof construction, and install in accordance with the manufacturer's instructions. The Contractor shall be responsible for sleeve sizes and locations. All roof penetrations shall be installed in accordance with manufacturer’s instructions, the National Roofing Contractors Association, SMACNA, and as required by other divisions of these specifications.

E. All work associated with the existing roof shall be performed so as to maintain the existing roof warranty.

1.13. CONCRETE AND MASONRY WORK

A. Furnish and install concrete and masonry work for equipment founda¬tions, supports, pads, and other items required under Division 22. Perform work in accordance with requirements of other applicable Divisions of these specifications.

B. Concrete shall test not less than 3,000 psi compressive strength after 28 days.

C. Grout shall be non-shrink, high strength mortar, free of iron of chlorides and suitable for use in contact with all metals, without caps or other protective finishes. Apply in accordance with manufacturer's instructions and standard grouting practices.

D. Paint perimeter of all housekeeping pads safety yellow.

1.14. CONNECTIONS AND ALTERATIONS TO EXISTING WORK

A. Unless otherwise noted on the drawings, where existing plumbing work is removed all pipes, valves, etc., shall be removed, including hangers, to a point below finished floors or behind finished walls and capped. Such point shall be far enough behind finished surfaces to allow for installation of normal thickness of required finish material.

B. Where work specified in Division 22 connects to existing equipment, piping, etc., Contractor shall perform all necessary alterations, cuttings, fittings, etc., of existing work as may be necessary to make satisfactory connections between new and existing work, and to leave completed work in a finished and workmanlike condition.

C. Where the work specified under Division 22, or under other Divisions, requires relocation of existing equipment, piping, etc., Contractor shall perform all work and make necessary changes to existing work as may be required to leave completed work in a finished and workmanlike condition. Where existing insulation is disturbed, replace insulation where removed or damaged equal to existing, in type, thickness, density, finish and thermal resistance (R-value) value.

D. Where the relocation of existing equipment is required for access or the installation of new equipment, the contractor shall temporarily remove and/or relocate and re-install as required to leave the existing and new work in a finished and workman like condition.

1.15. DEMOLITION

A. Unless otherwise noted all existing equipment, piping, etc., shall remain.

B. Where existing equipment is indicated to be removed, all associated piping, conduit, power, controls, control panels, sensors, tubing, insulation, hangers, supports and housekeeping pads, etc., patch, paint and repair walls/roof/floor to match existing and/or new finishes.

C. Provide necessary piping, valves, traps, temporary feeds, etc., as required. Drain and refill piping systems as often as necessary to accommodate phasing and to minimize time lengths of outages.

D. The Contractor shall be responsible for visiting the site and determining the existing conditions in which the work is to be performed.

E. Where any abandoned pipes in existing floors, walls, pipe tunnels, ceilings, etc., conflict with new work, remove abandoned pipes as necessary to accommodate new work.

F. The location of all existing equipment, piping, etc., indicated is approximate only and shall be checked and verified. Install all new plumbing work to connect to or clear existing work as applicable.

G. Maintain egress at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and the authorities having jurisdiction.

H. When applicable, make provisions and include in bid all costs associated with confined entry/space requirements and all other applicable OSHA regulations.

I. Where required to maintain the existing systems in operation, temporarily backfeed existing systems from new equipment. Contractor shall temporarily extend existing piping systems to new piping systems with the appropriate shut-off valves.

J. At completion of project all temporary piping, valves, controls, etc., shall be removed in their entirely.

K. Existing piping, equipment, materials, etc., not required for re-use or re-installation in this project, shall be removed from the project site.

L. Deliver to the Owner, on the premises where directed, existing equipment and materials which are removed and which are desired by the Owner or are indicated to remain the property of the Owner.

M. All other materials and equipment which are removed shall become property of the Contractor and shall be promptly removed, from the premises, and disposed of by the Contractor, in an approved manner. Contractor shall be responsible for proper disposal of all removed equipment containing refrigerants. Contractor shall include in his bid all cost associated with the evacuation, removal and disposal of all existing equipment containing refrigerants in accordance with EPA and Health Department requirements.

N. Where piping is removed, remove all pipe hangers which were supporting the removed piping. Patch the remaining penetration voids with like materials and paint to match existing construction.

O. Where required, provide and coordinate removal and re-installation of existing equipment. Take care to protect materials and equipment indicated for reuse. Contractor shall repair or replace items which are damaged. Contractor shall have Owner’s representative present to confirm condition of equipment prior to

demolition.

P. Before demolition begins, and in the presence of the Owners representative, test and note all deficiencies in all existing systems affected by demolition but not completely removed by demolition. Provide a copy of the list of system deficiencies to the Owner and the Engineer. Videotape existing conditions in each space prior to beginning demolition work.

Q. The Owner shall have the first right of refusal for all plumbing fixtures, devices and equipment removed by the Contractor.

R. All plumbing fixtures, devices and equipment designated by the Owner to remain the property of the Owner shall be moved and stored by the Contractor at a location on site as designated by the Owner. It shall be the Contractor's responsibility to store all plumbing fixtures, devices and equipment in a safe manner to prevent damage while stored.

S. All existing equipment refused by the Owner shall become the property of the Contractor and shall be removed from the site by the Contractor in a timely manner and disposed of in a legal manner.

T. Work Abandoned in Place: cut and remove underground pipe a minimum of 2 inches beyond face of adjacent construction. Cap and patch surface to match existing finish.

U. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.

V. Terminate services and utilities in accordance with local laws, ordinances, rules and regulations.

1.16. EXCAVATION AND BACKFILLING

A. GENERAL

1. Perform all necessary excavation, or installation of work under Division 22, in whatever materials or conditions encountered, using suitable methods and equipment.

2. Accurately establish required lines and grades and properly locate the work.

3. Determine the locations of all existing utilities before commencing the work.

B. Excavation: (Refer also to other portions of the specifications)

1. Excavate only the required elevations. If excavation is carried below the foundation lines or other required limits, backfill the excess with concrete.

2. Keep banks of trenches as nearly vertical as possible, and provide sheeting

and/or shoring as required for protection of work and safety of personnel. Follow local, State, and OSHA Guidelines.

3. Keep excavations dry. Protect excavations from freezing.

C. Backfilling: (Refer also to other portions of the specifications)

1. Backfill excavations to the required elevations and restore surfaces to their original or required conditions.

2. Backfill shall be similar material, free from objectionable matter such as rubbish, roots, stumps, brush, rocks and other sharp objects. Unless otherwise indicated, suitable material from the excavation may be used for backfill.

3. Carefully place and mechanically tamp backfill in layers not exceeding 12 inches loose thickness. Compact to 95 percent minimum.

4. Do not backfill against frozen material. Do not use frozen material for backfill.

1.17. DRIVE GUARDS

A. Provide safety guards on all exposed belt drives, motor couplings, and other rotating machinery. Provide fully enclosed guards where machinery is exposed from more than one direction.

B. When available, guards shall be factory fabricated and furnished with the equipment. Otherwise fabricate guards of heavy gauge steel, rigidly braced, removable, and finish to match equipment served. Provide openings for tachometers. Guards shall meet local, State and O.S.H.A. requirements.

1.18. VIBRATION ISOLATION

A. Furnish and install vibration isolators, flexible connections, supports, anchors and/or foundations required to prevent transmission of vibration from equipment, or piping to building structure. See Division 23 Section, Vibration Controls for HVAC, Plumbing and Fire Protection.

1.19. ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

1.20. DEFINITIONS

A. Approve - to permit use of material, equipment or methods conditional upon

compliance with contract documents requirements.

B. Furnish and install or provide means to supply, erect, install, and connect to complete for readiness for regular operation, the particular work referred to.

C. Contractor means the mechanical contractor and any of his subcontractors, vendors, suppliers, or fabricators.

D. Piping includes pipe, all fittings, valves, hangers, insulation, identification, and other accessories relative to such piping.

E. Concealed means hidden from sight in chases, formed spaces, shafts, hung ceilings, or embedded in construction.

F. Exposed means not installed underground or concealed as defined above.

G. Invert Elevation means the elevation of the inside bottom of pipe.

H. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceiling, and unexcavated spaces.

I. Review - limited observation or checking to ascertain general conformance with design concept of the work and with information given in contract documents. Such action does not constitute a waiver or alteration of the contract requirements.

J. Building Line: Exterior wall of building.

1.21. MINIMUM EFFICIENCY REQUIREMENTS

A. All plumbing equipment shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.

B. All piping and equipment insulation shall comply with ASHRAE Standard 90.1, latest edition.

C. All plumbing devices, controls, accessories, and components shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.

D. Where Energy Star certification exists for equipment utilized on this project, the equipment must be Energy Star certified. Provide Energy Star certification with submittals.

1.22. SYSTEM INTEGRATION

A. For all plumbing equipment specified to be provided with packaged controls and interfaced with the automatic temperature control system, provide system integration between the equipment manufacturer and the automatic temperature

control subcontractor.

B. Plumbing equipment submittals requiring system integration as defined above must identify all required system integration points.

C. Plumbing equipment manufacturers must coordinate with ATC subcontractor regarding system integration prior to submitting on the equipment.

D. A system integration meeting must be arranged by the Mechanical Contractor and include, but not be limited to the systems integrator for the plumbing equipment manufacturer and the ATC Subcontractor. This portion of systems integration must occur prior to plumbing equipment being delivered to the project.

E. Once the plumbing equipment is on site, a second systems integration meeting must be arranged by the Mechanical Contractor to coordinate the packaged controls with the ATC system. The plumbing equipment manufacturer's representative familiar with system integration and the ATC subcontractor familiar with programming must be present.

F. A final system integrations meeting shall occur once all equipment is in place and ready for operation. The Mechanical Contractor, the plumbing equipment systems' integrator, and the ATC Subcontractor shall meet on site to jointly program, schedule, verify points, interlock devices, and fully set up all systems integration components.

G. All systems integration coordination, programming, and graphics must be completed prior to requesting commissioning and/or inspections by the Engineer of Record.

1.23. LEAD FREE REQUIREMENTS

A. All plumbing fixtures, equipment, and devices that contact potable water must be lead free per the State requirements. Potable water systems shall also comply with NSF 61 – Annex G and NSF-372.

1.24. COORDINATION WITH DTCC I.T. DEPARTMENT

A. All equipment that interfaces with the internet shall be coordinated with the Delaware Technical and Community College I.T. Department to verify that the same is suitable for use on the Delaware Technical and Community College IT infrastructure. Coordinate with the Delaware Technical and Community College I.T. Department regarding the allowable frequency bands to avoid interference with the Delaware Technical and Community College I.T. infrastructure.

PART 2 - ELECTRICAL REQUIREMENTS

2.1. GENERAL MOTOR AND ELECTRICAL REQUIREMENTS

A. Furnish and install control and interlock wiring for the equipment furnished. In general, power wiring and motor starting equipment will be provided under Division 26. Carefully review the contract documents to coordinate the electrical work under Division 22 with the work under Division 26. Where the electrical requirements of the equipment furnished differ from the provisions made under Division 26, make the necessary allowances under Division 22. Where no electrical provisions are made under Division 26, include all necessary electrical work under Division 22.

B. All electrical work performed under Division 22 shall conform to the applicable requirements of Division 26 and conforming to the National Electrical Code. All wiring, conduit, etc., installed in ceiling plenums must be plenum rated per NFPA & International Building Code.

C. Provide wiring diagrams with electrical characteristics and connection requirements.

D. Test Reports: Indicate test results verifying nominal efficiency and power factor for three phase motors larger than five (5) horsepower.

E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weatherproof covering. For extended outdoor storage, remove motors from equipment and store separately.

F. All motors shall be furnished with visible nameplate indicating motor horsepower, voltage, phase, cycles, RPM, full load amps, locked rotor amps, frame size, manufacturer’s name and model number, service factor, power factor and efficiency.

G. Motors located in exterior locations, wet air streams and outdoors shall be totally enclosed weatherproof epoxy-treated type.

H. Nominal efficiency and power factor shall be as scheduled at full load and rated voltage when tested in accordance with IEEE 112.

I. Brake horsepower load requirement at specified duty shall not exceed 85 percent of nameplate horsepower times NEMA service factor for motors with 1.0 and 1.15 service factors.

J. All single phase motors shall be provided with thermal protection: Internal protection shall automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature ratings of motor insulation. Thermal protection device shall automatically reset when motor temperature returns to normal range, unless otherwise indicated.

K. Where equipment under this Division is specified with integral disconnecting

means, the same shall be a single disconnecting means for disconnecting all ungrounded main power supply conductors that is capable of being locked in the open ("off") position in accordance with the National Electrical Code and the local electrical inspector.

2.2. MOTORS AND CONTROLS

A. Motors and controls shall conform to the latest requirements of IEEE, NEMA, NFPA-70 and shall be UL listed. Motor sizes are specified with the driven equipment. Motor starting and control equipment is specified either with the motor which is controlled or in an electrical specification section. The Contractor is advised to consult all specification sections to determine responsibility for motors and controls.

B. Motors shall be designed, built and tested in accordance with the latest revision of NEMA Standard MG I.

C. Motors shall be suitable for use under the conditions and with the equipment to which applied, and designed for operation on the electrical systems specified or indicated.

1. Motor capacities shall be such that the horsepower rating and the rated full-load current will not be exceeded while operating under the specified operating conditions. Under no condition shall the motor current exceed that indicated on the nameplates.

2. Motor sizes noted in the individual equipment specifications are minimum requirements only. It is the responsibility of the equipment manufacturers and of the Contractor to furnish motors, electrical circuits and equipment of ample capacity to operate the equipment without overloading, exceeding the rated full-load current, or overheating at full-load capacity under the most severe operating service of this equipment. Motors shall have sufficient torque to accelerate the total WR2 of the driven equipment to operating speed.

3. Motors shall be continuous duty type and shall operate quietly at all speeds and loads.

4. Motors shall be designed for operation on 60 hertz power service. Unless otherwise specified or shown, motors less than ½ horsepower shall be single phase, and motors ½ horsepower and larger shall be 3 phase unless otherwise noted.

5. Motors shall be mounted so that the motor can be removed without removing the entire driven unit.

D. Single phase motors, smaller than 1/20 horsepower shall be ball or sleeve bearing; drip-proof, totally enclosed or explosion proof, as specified; 120 volts; permanent-split capacitor or shaded pole type. These motors shall not be used for general power purposes, and shall only be provided as built-in components of plumbing

equipment. When approved by the Engineer, deviations from the specifications will be permitted as follows:

1. Open motors may be installed as part of an assembly where enclosure within a cabinet provides protection against moisture.

2. Motors used in conjunction with low voltage control systems may have a voltage rating less than 115 volts.

E. Single phase motors, greater than 1/20 horsepower and less than ½ horsepower shall be ball bearing; drip-proof, totally enclosed or explosion proof, as specified, with Class A or B insulation, as standard with the motor manufacturer; 115 or 120/208/240 volts as required; capacitor start-induction run, permanent split capacitor, or repulsion start-induction run type with minimum efficiency of 70 percent and a minimum full load power of 77 percent.

F. Except as otherwise specified in the various specification sections, 3 phase motors 60 horsepower and smaller shall be NEMA design B squirrel cage induction type meeting the requirements of this paragraph. Motors shall be drip-proof, totally enclosed or explosion proof, as specified or indicated. Insulation shall be Class B or F, at 40 degrees C ambient temperature. Drip-proof motors shall have a 1.15 service factor and totally enclosed and explosion proof motors shall have a service factor of 1.00 or higher. Motors specified for operation at 480, 240, and 208 volts shall be nameplated 460, 230, 200 volts, respectively. Efficiencies and percent power factor at full load for three phase motors shall be not less than the values listed below for premium efficiency motors:

MOTOR NAMEPLATE	MINIMUM PERCENT EFFICIENCY AT NOMINAL SPEED AND RATED LOAD	MINIMUM PERCENT POWER FACTOR
1HP and above to	85.5 percent	84 percent
1-½ HP	86.5 percent	85 percent
2HP	86.5 percent	85 percent
3HP	89.5 percent	86 percent
5HP	89.5 percent	87 percent
7½ HP	91 percent	86 percent
10HP	91.7 percent	85 percent
15HP	93.0 percent	85 percent
20HP	93.0 percent	86 percent
25HP	93.6 percent	85 percent

G. Three phase motors ½ HP or greater shall be the Duty Master XE by Reliance

Electric Company, Super-E Premium Efficiency of Baldor Motor and Drives, E-plus Efficient Standard Duty Motor of the Electric Motor Division of Gould, Inc., the MAC II High Efficiency motor of Westinghouse Electric Corp., the equivalent product of General Electric, or approved equal.

H. For motors serving equipment being controlled by a variable speed drive, motor shall be premium efficiency inverter duty rated.

I. Motor frames shall be NEMA Standard T-Frames of steel, aluminum, or cast iron with end brackets of cast-iron or aluminum with steel inserts.

J. Control of each motor shall be manual or automatic as specified for each in the various mechanical sections. In general, and unless otherwise specified for a particular item in the various mechanical sections of the specifications, motor starters and controls shall be specified and provided under the various electrical sections of these specifications.

2.3. MOTOR INSTALLATION

A. Install in accordance with manufacturer’s instructions.

B. Install securely on firm foundation. Mount ball bearing motors to support shaft regardless of shaft position.

C. Check line voltage and phase and ensure agreement with nameplate. Check that proper thermal overloads have been installed prior to operating motors.

2.4. WIRING DIAGRAMS

A. The Contractor is responsible for obtaining and submitting wiring diagrams for all major items of equipment.

B. Wiring diagrams shall be provided with shop drawings for all equipment requiring electric power.

C. Provide wiring diagrams for all major plumbing items of equipment to electrical contractor and ATC subcontractor for coordination.

2.5. ENCLOSURES

A. Electrical enclosures including factory provided enclosures, field provided and installed enclosures, and automatic temperature control system enclosures shall be as follows:

1. Dry Interior Locations: NEMA 1.

2. Damp/Wet Locations, Including Exterior Locations: NEMA 3R.

3. Corrosive Locations, Laboratories, Janitor's Closets, and Similar Space = NEMA 4X.

2.6 BACKFLOW PREVENTER (DOUBLE CHECK VALVE ASSEMBLY TYPE)

A. Furnish and install double check valve assembly backflow preventers at all cold water make-up connections to washdown for dental vacuum and where else indicated on contract documents.

B. The assembly shall consist of two positive seating check modules with captured springs and rubber seat discs. The check module sets and seat discs shall be replaceable.

C. Service of all internal components shall be through a single access cover secured with stainless steel bolts. The assembly shall include two resilient seated isolation valves and four top mounted, resilient seated test cocks.

1. Furnish each backflow preventer with the following accessories and options:

a. bronze strainer
b. quarter turn, full port, resilient seated ball valve shut-off
c. union connections

D. Provide minimum 18-inch clearance for servicing and testing.

E. The assembly shall meet the requirement of ASSE Std 1015 and AMCA Std C510.

F. Double check valve backflow preventers shall be Watts No. 007, Conbraco, Wilkens, Ancon, or approved equal.

G. Furnish test kit for field testing units. Watts Model TK-9A Analog Differential Gauge or approved equal.

PART 3 - EXECUTION

3.1. EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

A. Install equipment to provide maximum possible headroom, if mounting heights are not indicated.

B. Install equipment according to approved submittal data. Portions of the work are shown only in diagrammatic form. Refer conflicts to the Architect and Engineer.

C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.

D. Install plumbing equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with

minimum interference to other installations. Extend grease fittings to accessible locations.

E. Install equipment giving right of way to piping installed at required slope.

F. Install flexible connectors on equipment side of shutoff valves, horizontally and parallel to equipment shafts if possible.

G. Do not install equipment or piping over electrical gear, electrical panels, motor controllers, and similar electrical equipment. Install equipment and piping to maintain clear space above and in front of all electrical components per the National Electric Code.

3.2. SUPPORTS, HANGERS AND FOUNDATIONS

A. Provide supports, hangers, braces, attachments and foundations required for the work. Support and set the work in a thoroughly substantial and workmanlike manner without placing strains on materials, equipment, or building structure, submit shop drawings for approval. Coordinate all work with the requirements of the structural division.

B. Supports, hangers, braces, and attachments shall be standard manufactured items or fabricated structural steel shapes. All interior hangers shall be galvanized or steel with rust inhibiting paint. For un-insulated copper piping provide copper hanger to prevent contact of dissimilar metals. All exterior hangers shall be constructed of stainless steel utilizing stainless steel rods, nuts, washers, bolts, etc.

C. Concrete housekeeping pads and foundations shall be not less than 4 inches high and shall extend a minimum of 6 inches beyond equipment bases. Provide wire-mesh reinforcement; chamfer exposed edges and corners; and finish exposed surfaces smooth.

D. Where new concrete housekeeping pads are placed on existing concrete, saw cut the existing concrete to the perimeter dimension of the new pad to a depth of ½ inch. Break out the top ½ inch area of the existing concrete. Add stubs of #4 rebar angled into the existing concrete at a depth of approximately 50 percent of the existing slab thickness. The top portion of the rebar stub shall extend into the new pad by approximately 50 percent of its thickness. Furnish one rebar stub per every two square feet of new pad. Chemically bond the new concrete to the existing concrete.

3.3. DEMONSTRATION AND TRAINING VIDEO RECORDINGS

A. General: Record demonstration and training video recordings. Record each training module separately.

1. At beginning of each training module, record each chart containing learning objective and lesson outline.

B. Video Recording Format: Provide high-quality color video recordings with menu navigation in format acceptable to Engineer

C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to show area of demonstration and training. Display continuous running time.

D. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.

E. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.

3.4. PROVISIONS FOR ACCESS

A. The contractor shall provide access panels and doors for all concealed equipment, valves, strainers, dampers, filters, controls, control devices, cleanouts, traps, and other devices requiring maintenance, service, adjustment, balancing or manual operation.

B. Where access doors are necessary, furnish and install manufactured painted steel door assemblies consisting of hinged door, key locks, and frame designed for the particular wall or ceiling construction. Properly locate each door. Door sizes shall be a minimum of 12 inches x 12 inches for hand access, 18 inches x 18 inches for shoulder access and 20 inches x 30 inches for full body access where required. Review locations and sizes with Architect prior to fabrication. Provide U.L. approved and labeled access doors where installed in fire rated walls or ceilings. Doors shall be Milcor Metal Access Doors as manufactured by Inland-Ryerson, Mifab, Acudor Products, Babcock-Davis, Nystrom, or approved equal.

1. Acoustical or Cement Plaster: Style B

2. Hard Finish Plaster: Style K or L

3. Masonry or Dry Wall: Style M

C. Where access is by means of liftout ceiling tiles or panels, mark each ceiling grid using small color-coded and numbered tabs. Provide a chart or index for identification. Place markers within ceiling grid not on ceiling tiles.

D. Access panels, doors, etc. described herein shall be furnished under the section of specifications providing the particular service and to be turned over to the pertinent trade for installation. Coordinate installation with installing contractor. All access doors shall be painted in baked enamel finish to match ceiling or wall finish.

E. Submit shop drawings indicating the proposed location of all access panels/doors. Access doors in finished spaces shall be coordinated with air devices, lighting and sprinklers to provide a neat and symmetrical appearance.

F. Where access doors are installed in wet locations (i.e. toilet rooms, kitchen rooms,

and similar spaces, etc.) provide aluminum access doors/frame.

3.5. PAINTING AND FINISHES

A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc. shall be stainless steel.

B. Clean surfaces prior to application of insulation, adhesives, coatings, paint, or other finishes.

C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pretreatment.

D. Protect all finishes and restore any finishes damaged as a result of work under Division 22 to their original condition.

E. The preceding requirements apply to all work, whether exposed or concealed.

F. Remove all construction marking and writing from exposed equipment, piping and building surfaces. Do not paint manufacturer's labels or tags.

G. All exposed piping, equipment, etc. shall be painted. Colors shall be as stated in this division or as selected by the Architect and conform to ANSI Standards.

H. All exterior roof mounted equipment, piping and vents shall be painted to match roof in color as selected by Architect.

I. All exposed piping, equipment, etc. in finished spaces shall be painted. Colors shall be as selected by the Architect and conform to ANSI Standards.

J. All exposed piping, equipment, etc., in Mechanical Rooms and Storage where PVC jacketed shall not require painting. Label and identify and color code as specified.

3.6. CLEANING OF SYSTEMS

A. Thoroughly clean systems after satisfactory completion of pressure tests and before permanently connecting fixtures, equipment, traps, strainers, and other accessory items. Blow out and flush piping until interior surfaces are free of foreign matter.

B. Flush piping in re-circulating water systems to remove cutting oil, excess pipe joint compound, solder slag and other foreign materials. Do not use system pumps until after cleaning and flushing has been accomplished to the satisfaction of the Engineer. Employ chemical cleaners, including a non-foaming detergent, not harmful to system components. After cleaning operation, final flushing and refilling, the residual alkalinity shall not exceed 300 parts per million. Submit a

certificate of completion to Engineer stating name of Service Company used.

C. Maintain strainers and dirt pockets in clean condition.

D. Pay for labor and materials required to locate and remove obstructions from systems that are clogged with construction refuse after acceptance. Replace and repair work disturbed during removal of obstructions.

E. Leave systems clean, and in complete running order.

3.7. COLOR SELECTION

A. Color of finishes shall be as selected by the Architect.

B. Submit color of factory-finished equipment for acceptance prior to ordering.

3.8. PROTECTION OF WORK

A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.

B. Cover temporary openings in piping and equipment to prevent the entrance of water, dirt, debris, or other foreign matter. Deliver pipes and tubes with factory applied end caps.

C. Cover or otherwise protect all finishes.

D. Replace damaged materials, devices, finishes and equipment.

E. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, where stored inside.

3.9. OPERATION OF EQUIPMENT

A. Clean all systems and equipment prior to initial operation for testing, balancing, or other purposes. Lubricate, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.

B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment. Where factory start-up of equipment is not specified, provide field start-up by qualified technician.

C. Submit factory start-up sheets or field start-ups sheets for all equipment prior to the commencement of testing and balancing work. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by

Engineer and forwarded to Testing and Balancing Agency.

D. Do not use plumbing systems for temporary services or temporary conditioning during construction. Refer to Division 01 section "Temporary Facilities and Controls" for temporary plumbing during construction.

E. Upon completion of work, clean and restore all equipment to new conditions; replace expendable items such as filters.

3.10. IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS

A. Contractor shall submit for approval schematic piping diagrams of each piping system installed in the building. Diagrams shall indicate the location and the identification number of each valve in the particular system. Following approval by all authorities, the diagrams shall be framed, mounted under safety glass and hung in each Mechanical Room where directed. Contractor shall deliver the tracing or sepia from which the diagrams were reproduced to the Owner.

B. All valves shall be plainly tagged. For any bypass valves, install sign indicating valve position as “Normally Open” or “Normally Closed” as required.

C. All items of equipment, including motor starters and disconnects shall be furnished with white on black plastic permanent identification cards. Lettering shall be a minimum of ¼ inch high. Identification plates shall be secured, affixed to each piece of equipment, starters, disconnects, panels by screw or adhesive (tuff bond #TB2 or as approved equal). Equipment identification and room name or area served shall be on each panel.

D. Provide three (3) copies of operating and maintenance instructions for all principal items of equipment furnished. This material shall be bound as a volume of the Operations and Maintenance Manuals as hereinafter specified.

E. All piping installed under this contract shall be stenciled with direction of flow arrows and with stenciled letters naming each pipe and service. Refer to Division 22 Section, Plumbing Piping, Fittings, Valves, Etc. Color code all direction of flow arrows and labels. In finished spaces omit labeling and direction of flow arrows. Paint in color as selected by Architect.

F. Submit list of wording, symbols, letter size, and color coding for plumbing identification. Submit samples of equipment identification cards, piping labels, labels, and valve tags to Engineer for review prior to installation.

G. Provide at least eight (8) hours of straight time instruction to the operating personnel. Time of instruction shall be designated by the Owner. Additional instruction time for the automatic temperature control (ATC) system is specified in Division 23 Section, Instrumentation and Controls of HVAC and Plumbing Systems.

H. Contractor shall demonstrate Sequences of Operation of all plumbing equipment

in presence of Owner's representative, Engineer, and ATC subcontractor.

3.11. WALL AND FLOOR PENETRATION

A. All penetrations of partitions, ceilings, roofs and floors by piping or conduit under Division 22 shall be sleeved, sealed, and caulked airtight for sound and air transfer control. Penetrations of mechanical room partitions, ceilings, and floors shall be as specified in Division 07 Section, "Fire Protection, HVAC and Plumbing Penetration Firestopping".

B. All penetration of fire rated assemblies shall be sleeved, sealed, caulked and protected to maintain the rating of the wall, roof, or floor. Fire Marshal approved U.L. assemblies shall be utilized. See Division 07 Section, "Fire Protection, HVAC and Plumbing Penetration Firestopping".

C. Where piping extends through exterior walls or below grade, provide waterproof pipe penetration seals, as specified in another division of these specifications.

D. Provide pipe escutcheons for sleeved pipes in finished areas.

E. Piping sleeves:

1. Galvanized steel pipe, standard weight where pipes are exposed and roofs and concrete and masonry walls. On exterior walls provide anchor flange welded to perimeter.

2. Twenty-two (22) gauge galvanized steel elsewhere.

F. Extend all floor sleeves through floor at least 2-inches above finished floor, caulk sleeve the entire depth and furnish and install floor plate.

G. For renovation projects where new pipes penetrate existing floors, furnish ground penetrating radar to properly map out acceptable locations for pipe penetrations. Review penetrations with Structural Engineer.

3.12. RECORD DRAWINGS

A. Upon completion of the mechanical installations, the Contractor shall deliver to the Architect one complete set of prints of the mechanical contract drawings which shall be legibly marked in red pencil to show all changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.

B. Contractor shall incorporate all sketches, addendums, value engineering, change orders, etc., into record drawings prior to delivering to Architect.

3.13. WARRANTY

A. Contractor's attention is directed to warranty obligations contained in the General Conditions and Supplementary Conditions.

B. The above shall not in any way void or abrogate equipment manufacturer's guarantee or warranty. Certificates of equipment manufacturer's warranties shall be included in the operations and maintenance manuals.

C. The contractor guarantees for a two (2) year period from the time of final acceptance by the Owner.

1. That the work contains no faulty or imperfect material or equipment or any imperfect, careless, or unskilled workmanship.

2. That all work, equipment, machines, devices, etc. shall be adequate for the use to which they are intended, and shall operate with ordinary care and attention in a satisfactory and efficient manner.

3. That the contractor will re-execute, correct, repair, or remove and replace with proper work, without cost to the Owner, any work found to be deficient. The contractor shall also make good all damages caused to their work or materials in the process of complying with this section.

4. That the entire work shall be water-tight and leak-proof.

3.14. LUBRICATION

A. All bearings, motors, and all equipment requiring lubrication shall be provided with accessible fittings for same. Before turning over the equipment to the Owner, the Contractor shall fully lubricate each item of equipment, shall provide one year's supply of lubricant for each, and shall provide Owner with complete written lubricating instructions, together with diagram locating the points requiring lubrication. Include this information in the Operations and Maintenance Manuals.

B. In general, all motors and equipment shall be provided with grease lubricated roller or ball bearings with Alemite or equal accessible or extended grease fittings and drain plugs.

3.15. OPERATIONS AND MAINTENANCE MANUALS

A. The Contractor shall have prepared three (3) hardcopies and one (1) electronic copy of the Operations and Maintenance Manuals and deliver these copies of the manuals to the Owner. The manuals shall be as specified herein. The manuals must be approved and will not be accepted as final until so stamped.

B. The manuals shall be bound in a three ring loose-leaf binder similar to National No. 3881 with the following title lettered on the front: Operations and Maintenance Manual – DTCC Carter Partnership Dental Suite – Plumbing Systems. No sheets

larger than 8-1/2 inches x 11 inches shall be used, except sheets that are neatly folded to 8-1/2 inches x 11 inches and used as a pull-out. Provide divider tabs and table of contents for organizing and separating information.

C. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of Volume 1 (if applicable) of hard copies of the manual.

D. Provide the following data in the booklet:

1. As first entry, an approved letter indicating the starting/ending time of Contractor's warranty period.

2. Catalog data on each piece of plumbing equipment furnished.

3. Maintenance, operation, and lubrication instructions on each piece of plumbing equipment furnished.

4. Complete catalog data on each piece of plumbing equipment furnished including approved shop drawing.

5. Manufacturer's extended limited warranties on equipment.

6. Chart form indicating frequency and type of routine maintenance for all plumbing equipment. The chart shall also indicate model number of equipment, location and service.

7. Provide sales and authorized service representatives names, address, and phone numbers of all equipment and subcontractors.

8. Provide supplier and subcontractor's names, address, and phone number.

9. Catalog data of all equipment, valves, etc. shall include wiring diagrams, parts list and assembly drawing.

10. Provide and install in locations as directed by the Owner, valve charts including valve tag number, valve type, valve model number, valve manufacturer, style, service and location. Each valve chart shall be enclosed in a durable polymer based frame with a cover safety glass. .

11. Copy of the approved balancing report for plumbing equipment/system.

12. Access panel charts with index illustrating the location and purpose of access panels.

13. Approved Health Department, Plumbing, and Electrical Certificates.

14. Start-up reports for equipment.

15. Insert color graphic with embedded parameters for ATC system into

Record and Information Booklet.

16. Pipe Pressure Test Logs/Reports.

E. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of volume 1 (if applicable) of hard copies of the manual.

F. Submit Operations and Maintenance Manuals prior to the anticipated date of substantial completion for Engineer review and approval. Substantial completion requires that Operations and Maintenance Manuals are reviewed and approved.

3.16. INSTALLATION AND COORDINATION DRAWINGS

A. Prepare, submit, and use composite installation and coordination drawings to assure proper coordination and installation of work. Drawings shall include, but not be limited, to the following:

1. Complete Plumbing, Sprinkler and HVAC Piping Drawings showing coordination with lights, electrical equipment, HVAC equipment and structural amenities.

B. Draw plans to a scale not less than 3/8-inch equals one foot. Include plans, sections, and elevations of proposed work, showing all equipment, and piping in areas involved. Fully dimension all work including lighting fixtures, conduits, pullboxes, panelboards, and other electrical work, walls, doors, ceilings, columns, beams, joists and other architectural and structural work.

C. Identify all equipment and devices on wiring diagrams and schematics. Where field connections are shown to factory-wired terminals, include manu¬facturer's literature showing internal wiring.

3.17. PIPING SYSTEMS TESTING

A. The entire new plumbing piping systems shall be tested hydrostatically before insulation covering is applied and proven tight under the following gauge pressures for a duration of twenty-four (24) hours. Testing to be witnessed by Owner's representative and documented in writing.

SYSTEM	**TEST PRESSURE**
Domestic Water & Coil Drain Piping	100 psig
Sanitary & Storm Water Piping	As specified below
Dental Compressed Air Piping	150 psig
Dental Vacuum Piping	100 psig

B. All storm, waste, vent and water piping shall be tested by the Contractor and approved by the Engineer before acceptance. All storm, soil, and waste piping, located underground, shall be tested before backfilling. The costs of all equipment required for tests are to be included in the contract price.

C. The entire new drainage system and venting system (including acid waste/vent systems) shall have all necessary openings plugged and filled with water to the level of the highest stack above or at the roof. The system shall hold this water for thirty (30) minutes without showing a drop greater than 1inch. Where a portion of the system is to be tested, the test shall be conducted in the same manner as described for the entire system, except a vertical stack 10 feet above the highest horizontal line to be tested may be installed and filled with water to maintain sufficient pressure, or a pump may be used to supply the required pressure. The pressure shall be maintained for thirty (30) minutes. All testing shall be in accordance with the local Plumbing Code and witnessed by the Plumbing Inspector or authority having jurisdiction.

D. Upon completion of roughing-in and before setting equipment and fixtures, the entire new water piping system shall be tested at a hydrostatic pressure of not less than one hundred (100) pounds per square inch gauge and proven tight at this pressure. Where a portion of the water piping system is to be concealed before completion, this portion shall be tested separately in a manner described for the entire system.

E. Testing and acceptance thereof shall be in accordance with local requirements and shall meet approval of authority having jurisdiction. Submit certificates and approved permits and insert one (1) copy in the Operations and Maintenance Manuals.

3.18. EQUIPMENT BY OTHERS

A. This Contractor shall make all system connections required to equipment furnished and installed under other divisions or furnished by the Owner. Connections shall be complete in all respects to render this equipment functional to its fullest intent.

B. It shall be the responsibility of the supplier of this equipment to furnish complete instructions for connections. Failure to do so will not relieve this contractor of any responsibility for improper equipment operation.

C. Coordinate all connections to dental equipment and fixtures with dental equipment provider.

3.19. PHASING

A. Refer to Architectural Specifications and contract drawings for any required phasing.

B. Maintain building egress and traffic ways at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and Authorities having

jurisdiction.

C. Provide dust barriers/partitions, penetration closures, etc., to ensure safety of building occupants and protection of existing surroundings.

D. The Building shall remain watertight at all times.

E. Provide necessary piping, valves, etc. as required. Drain and refill piping systems as often as necessary to accommodate phasing and to minimize time length of outages. Provide valves, to maintain existing systems in operation until all equipment is connected. Temporarily feed new systems with existing system where required or shown on contract drawings.

F. Within thirty days of Award of Contract, the Contractor shall submit a minimum of six (6) copies of the proposed Phasing Plan (Drawings and detailed written description) to the Architect for review and approval based on the general and specific requirements indicated on the Drawings and Specifications. The phasing plan shall reflect the work of all trades. The phasing plan shall be updated as often as needed (i.e. major deviations and/or modified sequence of events) and reviewed during each progress meeting so the facility and Architect can be aware of the areas of construction and progress as it relates to the approved schedule.

G. Due to phased construction, some systems must be operated at part load conditions until later phases are completed.

H. While work is in progress, except for designated short intervals during which connections are made, continuity of service shall be maintained to all existing systems. Interruptions shall be coordinated with the Owner as to time and duration. The contractor shall be responsible for any interruptions to service and shall repair any damages to existing systems caused by his operations.

3.20. OUTAGES

A. Provide a minimum of fourteen (14) days' notice to schedule outages. The Contractor shall include in their bid outages and/or work in occupied areas to occur on weekends, holidays, or at night. Coordinate and get approval of all outages with the Owner.

B. Submit Outage Request form, attached at end of this Section, to Owner for approval.

3.21 BACKFLOW PREVENTER (DOUBLE CHECK VALVE ASSEMBLY TYPE)

A. Furnish and install double check valve assembly backflow preventers at all cold water make-up connections to washdown for dental vacuum and where else indicated on contract documents.

B. The assembly shall consist of two positive seating check modules with captured springs and rubber seat discs. The check module sets and seat discs shall be replaceable.

C. Service of all internal components shall be through a single access cover secured with stainless steel bolts. The assembly shall include two resilient seated isolation valves and four top mounted, resilient seated test cocks.

1. Furnish each backflow preventer with the following accessories and options:

a. bronze strainer
b. quarter turn, full port, resilient seated ball valve shut-off
c. union connections

D. Provide minimum 18-inch clearance for servicing and testing.

E. The assembly shall meet the requirement of ASSE Std 1015 and AMCA Std C510.

F. Double check valve backflow preventers shall be Watts No. 007, Conbraco, Wilkens, Ancon, or approved equal.

G. Furnish test kit for field testing units. Watts Model TK-9A Analog Differential Gauge or approved equal.

END OF SECTION 220500

OUTAGE REQUEST

DATE APPLIED: _____ BY: _____

DATE FOR OUTAGE: _____ FIRM: _____

START OUTAGE-TIME: _____ DATE: _____

END OUTAGE -- TIME: _____ DATE: _____

AREAS AND ROOMS: _____

FLOOR(S): _____

AREA(S): _____

ROOM(S): _____

WORK TO BE PERFORMED: _____

SYSTEM(S): _____

REQUEST APPROVED BY: _____

(FOREMAN OR OTHER PERSON IN CHARGE)

(FOR OWNER'S USE ONLY):

APPROVED: _____

YES ____ NO ___ BY: _____ DATE: _____

DATE/TIME-AS REQUESTED: _____ OTHER : _____

OWNER'S PRESENCE REQUIRED: _____

YES: ____ NO: ___ NAME: _____

SECTION 220505 - PLUMBING PIPING, FITTINGS AND VALVES

PART 1 - GENERAL

1.1. SUMMARY

A. The conditions of the contract and other general requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 22 Section, Common Work Results for Plumbing and Division 01, General Requirements.

B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SYSTEM DESCRIPTION CONDITIONS

A. Provide all labor and materials necessary to furnish and install all piping systems on this project as herein specified and/or shown on the drawings. Final connections to equipment furnished in other sections of the specifications shall be included under this section.

B. All piping and insulation installed in ceiling plenums must be plenum rated and comply with NFPA and International Building Code (IBC).

C. Where more than one piping system material is specified, ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

D. Use unions, flanges, and couplings downstream of valves and at equipment or apparatus connections. Do not use direct welded or threaded connections to valves, equipment or other apparatus.

E. Use non-conducting dielectric connections whenever jointing dissimilar metals in open systems.

F. Provide pipe hangers and supports in accordance with ASTM B31.9 and MSS SP69 unless indicated otherwise.

G. Use spring loaded "silent" check valves on discharge of all pumps.

H. Use 3/4 inch (20 mm) ball valves with cap and chain for drains at main shut-off valves, low points of piping, bases of vertical risers, and at equipment. Pipe to nearest floor drain.

I. At all runout piping serving equipment, use swing joints with elbows to prevent excessive movement of piping due to expansion.

1.3. QUALITY ASSURANCE

A. Valves: Manufacturer's name and pressure rating marked on valve body.

B. Welding Materials and Procedures: Conform to ASME Code and applicable state labor regulation. Provide certificate of compliance from authority having jurisdiction indicating approval of welders.

C. Welders Certification: In accordance with ASME Section 9.

D. All grooved joint couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved components.

E. All castings used for coupling housings, fittings, and valve bodies shall be date stamped for quality assurance and traceability.

F. Maintain one copy of each document on site.

1.4. DELIVERY, STORAGE AND HANDLING

A. Deliver, store, protect and handle products to site under as hereinbefore specified.

B. Accept valves on site in shipping containers with labeling in place. Inspect for damage.

C. Provide temporary protective coating on cast iron and steel valves.

D. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

E. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed systems.

1.5. ENVIRONMENTAL REQUIREMENTS

A. Do not install underground piping when bedding is wet or frozen.

1.6. EXTRA MATERIALS

A. Provide one (1) repacking kit for each size valve.

1.7. ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

1.8. LEAD FREE REQUIREMENTS

A. All plumbing fixtures, equipment, and devices that contact potable water must be lead free per the State requirements.

1.9. PLASTIC PIPE PENETRATIONS

A. Install UL listed collars, sealing methods, and firestopping at all plastic pipe penetrations of smoke walls and fire rated walls per NFPA.

PART 2 - PRODUCTS

2.1. PIPE MATERIALS

A. All materials, unless otherwise specified, shall be new and of the best quality of their respective kinds, and shall conform to the requirements and ordinances of local, state and insurance authorities having jurisdiction.

1. Sanitary Underground - Within Building to 5 Feet Outside of Foundation Wall:

a. PVC Pipe: Schedule 40 DWV or cellular core. Fittings: Schedule 40 PVC, ASTM D 2665 or ASTM F891 socket fittings. Joints: ASTM D2855, solvent weld with ASTM D2564 solvent cement.

2. Sanitary and Vents Above Floor Inside Building:

a. PVC Pipe: Schedule 40 DWV or cellular core. Fittings: Schedule 40 PVC, ASTM D 2665 or ASTM F891 socket fittings. Joints: ASTM D2855, solvent weld with ASTM D2564 solvent cement.

3. Indirect Waste Piping:

a. Pipe & Fittings: Hard drawn Type L copper tubing with cast brass drainage fittings. ASTM B88-78 and ANSI B16.1877. All exposed indirect waste piping shall be chrome plated or primed and painted with silver paint.

4. Domestic Hot, Cold, and Hot Water Recirculating Water Piping Outside of Building Below Ground or Under Building to Point 5 Feet from Building Line:

a. Pipe: 2-1/2 inches & smaller, soft temper type K. ASTM B88.
3 inches & larger, ductile iron pipe for water, ANSI 21.50 & 21.51 with double thickness cement mortar lining, ANSI 21.4.

b. Fittings & Joints: wrought copper brazed joint fittings, ASME B16.22. Joints for copper piping shall be ASTM B32, BRAZED, grade 95TA.
Cast iron pressure fittings, ANSI 21.10, Class 250. Mechanical

specification for mechanical joint for cast iron pressure pipe & fittings ANSI A21.11. Joints for ductile iron pipe shall be AWWA C111, rubber gasket with 3/4 inch diameter rods.

c. Brazed filler materials shall conform to AWS-A5.8.

5. Domestic Hot, Cold, and Hot Water Recirculating Water Piping Inside Buildings, Above Grade:

a. Pipe or Tubing: 2 inches & smaller, all water lines soft temper Type K copper tubing below ground, hard temper Type L copper tubing above ground, ASTM B88, or Type 304/304L, Schedule 10S, stainless steel to ASTM A312.
2-1/2 inches & larger, hot dipped galvanized steel A120, ASTM A53, Grade B, Schedule 40 steel, or hard copper tube, Type L with copper-tube dimensioned grooved ends; copper ground - end fittings; copper tubing, keyed couplings; and grooved joints. (Flaring of tube or fitting ends to accommodate alternate sized couplings is not permitted.)
Provide dielectric fittings between steel and copper. Victaulic Style 47 or approved equal.

b. Fittings & Joints: Copper tubing fittings and joints shall be solder type wrought copper - 95-5 silver solder or braze (lead and antimony based solders are prohibited). Galvanized steel pipe fittings and joints shall be ANSI B16.12 hot dipped galvanized threaded ends and 125 lb. galvanized cast iron fittings or 150 lb. galvanized malleable iron.

i. Stainless steel fittings shall be Vic-Press or approved equal for Schedule 10S pipe. Fittings shall be precision, cold drawn, stainless steel with EPDM O-ring seals. (Seals shall be UL classified in accordance with ANSI/NSF61 for Potable Water service.) Fittings rated for working pressures to 500-psi.

ii. Grooved joint couplings shall consist of two ductile iron housing segments cast with offsetting angle pattern bolt pads, FlushSeal elastomer gasket, and ASTM A449 electroplated steel bolts and nuts. (Gasket shall be UL classified in accordance with ASNI/NSF61 for Potable Water service, and shall meet the lead content requirements of NSF-372.) Installation-Ready, for direct stab installation without field disassembly. Victaulic Style 807N or approved equal. Couplings shall be coated blue enamel.

iii. Installation-Ready™ fittings for grooved end copper tubing shall be manufactured to copper-tube dimensions. Fittings shall be ductile iron conforming to ASTM A-536, Grade 65-45-12, with Installation-Ready™ ends, complete with PVDF (Poly Vinylidene Fluoride) and Grade “EHP” EPDM-HP (Grade ‘T’ Nitrile) gasket; and ASTM A449 electroplated steel bolts and nuts. System shall be rated to 300 psi (2065 kPa) with Type K or L Copper Tubing.

1) UL classified in accordance with NSF-61 for potable water service. The system shall meet the low-lead requirements of NSF-372.

iv. For copper/stainless steel/CPVC pipe the gasket shall be potable water grade P compound with a red and blue stripe color code for operating temperatures from 0°F to 180°F.

1) Reference shall always be made to the latest published Victaulic selection guide for gaskets for proper gasket selection for the intended purpose.

c. Gate Valves: 2-1/2 inches & larger - OS&Y, IBBM flanged, 125 lb. standard solid wedge.

i. 2 inches & smaller - bronze solder end, bronze body, solid wedge, rising stem, 200 lb. w.o.g. non-shock. However, use brass valves only on all copper pipe.

d. Butterfly Valves: Cast brass body to UNS C87850, elastomer pressure responsive seat, aluminum-bronze disc with stainless steel stem. Stem shall be offset from the disc centerline to provide complete 360-degree circumferential seating. Copper-tube dimensioned grooved ends, suitable for working pressures to 300-psig CWP Victaulic Style 608N or approved equal.

e. Ball Valves: Shut-off valves 2-inches and smaller shall be ball valves. Ball valves shall be 150 lbs, brass or bronze body, standard port, 2 piece body, TFE seats with bronze trim. Ball valves shall be threaded end or solder end, or Vic-Press end as required to accommodate piping. Ball valves shall be as manufactured by Victaulic, Conbraco, Crane, Apollo, Nibco, Watts or engineer approved equal.

f. Unions: 2-1/2 inches & larger - 150 lb. brass companion flanges.

i. 2 inches & smaller - wrought copper, ground joint solder ends; threaded hexagonal stainless steel union with Vic-Press ends, Victaulic P589 or approved equal.

g. Check Valves: 2-1/2 inches & larger - IBBM, 125 lb. std. flanged bronze swing check, with metal disc; 2-inches and smaller - 125 lb. std. screwed or solder ends.

h. Globe Valves: 2 inches and smaller, bronze body, bronze trim, rising stem, hand wheel, inside screw, renewable composition disc, solder ends, 150 lb, with back seating capacity.

i. 2 inches & larger: IBBM, 150 lb, bronze trim, rising stem, handwheel OS&Y, plug type disc, flanged ends, renewable seat and disc.

ii. Globe valves shall be Conbraco, Crane, Nibco, Milwaukee, Watts or approved equal.

i. Combination Shut-off/Balancing Valves:

i. Victaulic/TA Hydronics, Taco Circuit Setter, Bell & Gossett Circuit Setter Plus, Flowset Accuset, Gerand, or engineer approved equal, ½ inch-3 inches 300 psi rated globe type or ball valve with DZR brass Ametal (copper-alloy) or bronze body/brass ball construction with glass and carbon filled TFE seats, in-line flow meter and balancing and shut-off

valve with built in ball valve for flow adjustment. Valve shall have memory stop, calibrated nameplate, Schrader valve connections and preformed molded insulation. Valves shall be leaktight at full rated working pressure. Balance valve size shall be selected based on manufacturer's acceptable flow range and design flow rate. Pressure drop through combination shut off balance valves shall not exceed 5 feet of head at design flow rate. Where required for flow rates below 0.6 GPM, provide "reduced flow" combination shut-off balance valves sized so that the flow rate is within the manufacturer's recommended flow range.

j. Extended Valve Stems: Provide and install round collar type extended valve stems on all valves installed in insulated piping. Valve stem and collar shall be selected to suit insulation thickness and maintain valve handles outside of insulation.

k. (Alternate): At contractor's option, Viega ProPress pressure seal mechanical fittings may be utilized.

i. Viega ProPress, Mueller Streamline PRS or approved equal, Pressure Seal Fittings: Bronze, or copper shall conform to ASME B16.51, ICC LC 1002, IAPMO PS 117, NSF 61, and NSF 61-G or NSF 372. Pressure Seal fittings ½-inch thru 4-inch for use with ASTM B88 copper tube type L and ½-inch up to 1-1/4-inch annealed copper tube. Pressure Seal fittings shall have an EPDM sealing element grip ring, PBT separator ring, EPDM sealing element and Smart Connect (SC) or Sure PS Leak Detection.

B. Copper pipe shall be Revere, Anaconda or Chase with approved solder fittings.

2.2. PIPE HANGERS

A. All hangers for metallic piping shall be adjustable, wrought clevis type, or adjustable malleable split ring swivel type, having rods with machine threads. Hangers shall be Grinnell Company's Figure 260, Carpenter and Patterson, or approved equal for pipe ¾-inch and larger, and Figure 65 for pipe 2-inches and smaller, or approved equal. Adjustable pipe stanchion with U-bolt shall be Grinnell Company's Figure 191. Pipe roller supports shall be Grinnell's Figure 181 or Figure 271. Exterior pipe hangers shall be galvanized or stainless steel construction. For copper piping in direct contact with the hanger, hanger construction shall be copper coated to prevent contact of dissimilar metals similar to Grinnell's Figure CT-65. Hanger spacing and rod sizes for steel and copper pipe shall not be less than the following:

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
3/4 & 1	6	5	3/8
1 - ½	6	8	3/8
2	8	8	3/8
2 – ½	10	9	½
3	12	10	½
4	14	12	5/8
5	14	12	5/8
6	16	14	3/4
8	18	16	7/8
10	20	18	7/8

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
12	20	18	7/8

B. Install hangers for storm water and soil piping with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/2 and NPS 2 (DN 40 and DN 50): 48 inches (1200 mm) with 3/8-inch (10-mm) rod.

2. NPS 3 (DN 80): 48 inches (1200 mm) with 1/2-inch (13-mm) rod.

3. PS 4 and NPS 5 (DN 100 and DN 125): 48 inches (1200 mm) with 5/8-inch (16-mm) rod.

4. NPS 6 (DN 150): 48 inches (1200 mm) with 3/4-inch (19-mm) rod.

5. NPS 8 to NPS 12 (DN 200 to DN 300): 48 inches (1200 mm) with 7/8-inch (22-mm) rod.

6. NPS 15 (DN 375): 48 inches (1200 mm) with 1-inch (25-mm) rod.

7. Spacing for 10-foot (3-m) lengths may be increased to 10 feet (3 m). Spacing for fittings is limited to 60 inches (1500 mm).

C. Install supports for vertical soil piping every 4 feet (1200 mm).

D. Anchors, guides, and roller supports shall be installed in accordance with the contract drawings and manufacturer's recommendations to provide pipe support and control pipe movement for all piping systems. Anchors and guides shall be securely attached to the pipe support structure. Submit shop drawing for proposed pipe support structure for guides and anchors for approval of the Structural Engineer. Pipe alignment guides shall be Fig. 255 Grinnell, or as approved equal. Guides shall be sized to accommodate the pipe with insulation. Guides shall be steel factory, fabricated, with bolted two section outer cylinder and base for alignment of piping and two section guiding spider for bolting to pipe.

E. Hangers for pipe sizes ½ to 1 ½ inch (13 to 38 mm): Carbon steel, adjustable swivel, split ring.

F. Hangers for cold pipe sizes 2 inches (50 mm) and over: Carbon steel, adjustable, clevis.

G. Hangers for cold pipe sizes 2 to 4 inches (50 to 100 mm): Carbon steel, adjustable, clevis.

H. Hangers for cold pipe sizes 6 inches (150 mm) and over: adjustable steel yoke, cast iron roll, double hanger.

I. Multiple or Trapeze hangers: Steel channels with welded spacers and hanger rods.

J. Multiple or Trapeze hangers for hot pipe sizes 6 inches (150 mm) and over: Steel channels with welded spacers and hanger rod, cast iron roll.

K. Wall support for pipe sizes to 3 inches (76 mm): cast iron hook

L. Wall support for pipe sizes 4 inches (100 mm) and over: Welded steel bracket and wrought steel clamp.

M. Wall support for hot pipe sizes 6 inches (150 mm) and over: welded steel bracket and wrought steel clamp with adjustable steel yoke and cast iron roll.

N. Vertical Support: Steel riser clamp.

O. Floor support for cold pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

P. Floor support for hot pipe sizes to 4 inches (100 mm): Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

Q. Floor support for hot pipe sizes 6 inches (150 mm) and over: Adjustable cast iron roll and stand, steel screws, and concrete pier or steel support.

R. Copper pipe support: Carbon steel ring, adjustable, copper plated.

S. Hanger rods: Mild steel threaded both ends, threaded one end, or continuous threaded.

T. Inserts: Malleable iron case of galvanized steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

U. For Pipe Hangers installed in corrosive environments such as chemical storage rooms, janitor’s closets…etc. the same shall (including hardware) shall be finished with on Electro-Galvanized Finish such as Galv-Krom® or approved equal.

2.3. VALVES

A. Provide parts list and assembly drawings (exploded view) for all valves in shop drawing submittals. Provide valves of the same type by the same manufacturer.

2.4. STRAINERS

A. Strainers shall be of the basket or "Y" type and shall be heavy and durable, constructed of best grade gray iron with the bottoms drilled and plugged. Bodies shall have arrows clearly cast on the sides to show flow direction. Strainers shall be equipped with easily removable covers and brass sediment baskets made of brass not less than #22 gauge in thickness. Total area of basket perforations shall be not less than four times the cross section of the entering pipe. Flow shall be into basket, and then out through the perforations. Strainers shall be suitable for water or the intended fluid. Strainers 2 inches and smaller shall have threaded or solder ends, 2 inches and larger shall have flanged ends.

B. Strainer screens shall be stainless steel with perforations and shall be 1/16-inch for pipe sizes 5 inches and less, 1/8-inch (40 percent open area) perforations for pipe sizes 6-inch and greater.

C. Provide valved and capped (with chain) blowdowns in each strainer. Blowdown valves shall be Appolo 78-100/200 series or as approved equal.

D. Strainers shall be manufactured by Watts, Mueller, Armstrong, Yarway, Spirax/Sarco or as approved equal.

2.5. UNIONS, FLANGES, AND COUPLINGS

A. Unions in steel pipe 2-inches and smaller shall be malleable iron with brass inserted seats designed for a working pressure of 150 psig.

B. Unions in copper pipe 2-inches and smaller shall be sweat fittings with bronze seats designed for a working pressure of 125 psig.

C. Flanges for steel pipe over 2 inches shall be 150 psig, forged steel, and slip on type. Gaskets shall be 1/16 inch thick pre-formed neoprene.

D. Flanges for copper pipe over 2 inches shall be bronze. Gaskets shall be 1/16 inch thick preformed neoprene.

2.6. MANUAL AIR VENTS

A. Manual air vents shall be similar to the hereinafter specified gauge valves. Provide 1/4-inch size on ¾-inch pipe and smaller, ½ -inch size on 1-inch pipe and larger. Install at all high points of piping. Valves shall be Crane No. 88, Honeywell or as approved equal, with threaded ends, bronze body, bronze or brass bonnet and bronze stem.

2.7. THERMOMETERS

A. Unless otherwise indicated, thermometers shall be ASTM E1, in a glass type, organic filled, 9-inch scale size, corrosion-resistant metal case, with "any-angle"

mounting with positive locking device. Trerice Industrial Thermometers, Weksler Instruments, Ernst Gage Co., Miljoco, or approved equal. Insertion stem length shall suite the pipe size and configuration. Thermometer wells shall be brass with brass union hubs in copper and in ferrous piping. Where piping is insulated or otherwise covered, use wells with lagging extension. Where wells are installed in pipe tees at turns, increase pipe size so that well does not restrict flow. Accuracy shall be 2 percent.

B. Unless otherwise indicated, thermometer ranges shall be as follows:

1. Domestic cold water: 0 degrees F to 100 degrees F, 1 degrees F Division.

2. Domestic hot and hot water recirculating: 30 degrees F to 180 degrees F, 2 degrees F Division.

3. Tempered Water: 30 degrees F to 100 degrees F, 2 degrees F Division.

C. Provide heat conducting compound in wells.

2.8. PRESSURE GAUGES

A. Unless otherwise indicated, pressure gauges shall be the bronze bourdon tube type, 4-1/2-inch dial, stem mounting, cast aluminum adjustable pointer, 1 percent accuracy over middle half of scale range, 1-1/2 percent over balance: Trerice Model 600C; Weksler Instruments, Ernst Gage Co., Miljoco, or as approved equal.

B. Gauges shall have pressure, vacuum, compound, or retard ranges as required, select ranges so that the normal readings are at the approximate midpoint and maximum system pressures do not exceed full scale.

C. Furnish and install a gauge valve at each pressure gauge. Gauge valves shall be Crane Model No. 88, Needle Valve, Ernst Gage Co. FLG 200, Wexler Instrument Corp. Type BBV4, or approved equal, rated for pressure intended.

D. Gauge connections for pressure gauges, thermometers, or control instruments shall be made using tee fittings, except that gauge connections up to 1-inch size in steel may be using threaded extra heavy pipe couplings welded directly to the main, provided that the main is at least 2-inch size for 2-inch connections, 3-inch size for 3/4-inch connections, and 4-inch size for 1-inch connections. Minimum gauge connection shall be 2-inch ips.

E. Provide snubbers on all gauges. Snubbers shall be No. 872 by Trerice, RS1/RS6 by Wexler Instruments, Miljoco or as approved equal.

2.9. PIPING SPECIALTIES

A. Furnish and install flexible pipe connections, as specified and/or shown on the drawings, at connections to dental air compressors, connections to dental vacuum pumps, all vibrating equipment, and elsewhere as shown. Refer to Division 23

Section, Vibration Control for HVAC, Plumbing and Fire Protection Equipment for specifications.

B. Pressure relief valves shall be provided in the number and sizes required to relieve 110 percent of the full input to the systems. Valves shall be rated; and installed in accordance with ASME, and CSD-1 including all amendments. Pipe discharge full size to floor drain, (with union) and support discharge pipe to prevent exerting any strain on relief valve body, piping to be Type-L copper. Water safety relief valves shall be Watts Series 740, Conbraco, Series 154A, Bell and Gossett, or approved equal. Provide pressure gauge adjacent to all safety relief valves.

2.10. ESCUTCHEONS

A. Provide chromium plated escutcheons properly fitted and secured with set screws on all exposed piping which passes through walls, floors or ceilings of finished spaces.

B. All escutcheon plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface. Plastic escutcheon plates will not be accepted.

2.11. DIELECTRIC CONNECTIONS:

A. Furnish and install electrically insulated dielectric unions, waterway fittings, or flanges, as manufactured by Victaulic Company, EPCO Sales, Inc., at the following locations:

1. Where steel piping systems join copper piping.

2. Where copper tube connects to domestic water storage tanks, water heaters, heat exchangers, expansion tanks, and other steel vessels.

3. Avoid the installation of steel nipples, cast iron or steel valves and specialties, or other ferrous components in predominately copper piping systems. Where such installation is necessary, isolate the component with dielectric connections. Do not mix steel pipe and copper tube in the same run of pipe or in the same section of a piping system.

4. Dielectric Waterway: Copper silicon casting conforming to UNS C87850 with grooved and/or threaded ends. UL classified in accordance with NSF-61 for potable water service, and shall meet the low lead requirements of NSF-372. Basis of Design: Victaulic Series 647.

2.12. SLEEVES

A. Sleeves shall be provided around all pipes through walls, floors, ceilings, partitions, roof structure members or other building parts. Sleeves shall be standard weight galvanized iron pipe two sizes larger than the pipe or insulation so that pipe or

insulation shall pass through masonry or concrete walls or floors. Provide 20 gauge galvanized steel sheet or galvanized pipe sleeves for all piping passing through frame walls.

B. Sleeves through floors shall be flush with the floor except for sleeves passing through Equipment Rooms which shall extend ¾-inch above the floor. Refer to Division 23 Section, Vibration Controls for HVAC, Plumbing and Fire Protection Equipment for mechanical equipment room penetrations additional requirements. Space between the pipe and sleeve shall be caulked. Escutcheon plates shall be constructed to conceal the ends of sleeves. Each trade shall be responsible for drilling existing floors and walls for necessary sleeve holes. Drilling methods and tools shall be as hereinbefore specified.

C. Sleeves through walls and floors shall be sealed with a waterproof caulking compound.

D. Firestop at sleeves that penetrate smoke barriers smoke partitions and/or rated walls/floors.

2.13. WATER PROOF PIPE PENETRATION SEALS

A. Provide and install waterproof pipe penetration seals at all pipes that enter the building below grade or through exterior wall.

B. Link seals are to be Metraflex Metraseals, Model MS, Linkseal, or approved equal, black EPDM seal material, glass reinforced plastic pressure plates, zinc plated nuts and bolts, seals are to be resistant to sunlight and ozone, pressure rated to make a hydrostatic seal of up to 20 psig and up to 40 feet of head, temperature rated from –40 degrees F to 250 degrees F.

2.14. TRANSITION FITTINGS

A. General Requirements:

1. Same size as pipes to be joined.

2. Pressure rating at least equal to pipes to be joined.

3. End connections compatible with pipes to be joined.

B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.

C. Plastic-to-Metal Transition Fittings:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Charlotte Pipe and Foundry Company.

b. Harvel Plastics, Inc.
c. Spears Manufacturing Company.

2. Description: PVC or CPVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions; one end with threaded brass insert and one solvent-cement-socket end.

D. Plastic-to-Metal Transition Unions:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Colonial Engineering, Inc.
b. NIBCO INC.
c. Spears Manufacturing Company.

2. Description: PVC or CPVC four-part union. Include brass threaded end, solvent-cement-joint plastic end, rubber O-ring, and union nut.

PART 3 - EXECUTION

3.1. GENERAL PIPING INSTALLATION REQUIREMENTS

A. All pipes shall be cut accurately to measurements established at the building, and shall be worked into place without springing or forcing, properly clearing all windows, doors and other openings. Excessive cutting or other weakening of the building structure to facilitate piping installation will not be permitted. All pipes shall be so installed as to permit free expansion and contraction without causing damage. All open ends of pipe lines, equipment, etc., shall be properly capped or plugged during installation to keep dirt or other foreign material out of the system. All pipes shall be run parallel with the lines of the building and as close to walls, columns and ceilings as may be practical, with proper pitch. All piping shall be arranged so as not to interfere with removal of other equipment on devices not to block access to doors, windows, manholes, or other access openings. Flanges or unions, as applicable for the type of piping specified, shall be provided in the piping at connections to all items of equipment, coils, etc., and installed so that there will be no interference with the installation of the equipment, ducts, etc. All valves and specialties shall be placed to permit easy operation and access and all valves shall be regulated, packed and glands adjusted at the completion of the work before final acceptance. All piping shall be installed so as to avoid air or liquid pockets throughout the work. Ends of pipe shall be reamed so as to remove all burrs.

B. All piping shall be graded to convey entrained air to high points where automatic air vents shall be provided and shall allow for proper drainage. The size of supply and return pipes for each piece of equipment shall in no case be smaller than the outlets in the equipment.

C. All piping shall be run to provide a minimum clearance of 2-inches between finished covering on such piping and all adjacent work. Group piping wherever

practical at common elevations.

D. All valves, strainers, Schrader valves, drain valves, caps, and other fittings shall be readily accessible.

E. Rough-in and final connections are required to all equipment and fixtures provided under this Contract.

F. Drain valves with hose connections shall be provided at low points for drainage of piping systems. Blow down valves shall be provided at the ends of all mains and branches so as to properly clean by blowing down the lines throughout in the direction of normal flow.

G. Discharge lines from all relief valves shall be piped to within 4-inches of floor and extend to floor drains wherever floors are not pitched to drains. Pitch the relief valve piping away from the relief valve to issue that no fluid can be trapped in valve discharge. Support all relief valve piping to prevent exerting strain on the relief valve body. The end of the relief valve discharge piping shall not be threaded to prevent capping or plugging.

H. All branches from water mains shall be taken from the top of the supply mains at an angle of forty-five (45) degrees above the horizontal, unless otherwise directed. Branches feeding down shall be taken from the side or bottom of the main on water mains only. All connections shall be carefully made to insure unrestricted circulation, eliminate air pockets or trapped condensate, and permit the complete drainage of the system.

I. Cutoff valves shall be provided on each branch line from the mains on all plumbing lines.

J. Shut-off valves shall be installed at the inlet and outlet of each piece of equipment to permit isolation for maintenance and repair.

K. Balancing valves shall be installed in all domestic re-circulating systems and at all pumps, and where indicated on the drawings.

L. Unions shall be installed on all bypasses, at all connections to equipment, where shown on drawings or where required to facilitate removal of equipment whether shown or not.

M. Spring clamp plates (escutcheons) shall be provided where pipes are exposed in the building and run through walls, floors, or ceilings. Plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface.

N. If the size of any piping is not clearly evident in the drawings, the Contractor shall request instructions for the Engineer as to the proper sizing. Any changes resulting from the Contractor's failure to request clarification shall be at his expense. Where pipe size discrepancies or conflicts exist in the drawings, the larger pipe size shall govern.

O. Install all valves with stem upright or horizontal, not inverted.

P. Where pipe support members are welded to structural building framing, scrape, brush clean, weld and apply one coat of zinc rich primer.

Q. Provide clearance for installation of insulation and access to valves and fittings.

R. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.

S. Provide manual air vents at top of piping systems.

T. Where access doors are required, install piping so that valves can be grouped together to minimize the quantity of access doors.

U. Install manufactured U.L. listed firestop collars at all floor/wall penetrations for all PVC pipe penetrations.

3.2. THERMOMETER AND PRESSURE GAGE INSTALLATION REQUIREMENTS.

A. Install thermometers/gauges and adjust vertical and tilted positions.

B. Install separable sockets in vertical position in piping tees where fixed thermometers are indicated.

1. Install with socket extending to one-third diameter of pipe.

2. Fill sockets with oil or graphite and secure caps.

C. Install pressure gages in piping tees with pressure-gage valve located on a pipe at most readable location.

D. Adjust faces of thermometer and gages to proper angle for best visibility.

E. Clean windows of thermometer and gauges and clean factory-finished surfaces. Replace cracked and broken window, and repair scratched and marred surfaces with manufacturer's touch up paint.

3.3. VALVE INSTALLATION REQUIREMENTS

A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.

B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

C. Operate valves from fully open to fully closed positions. Examine guides and seats

made accessible by such operation.

D. Examine threads on valve and mating pipe for form and cleanliness.

E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.

F. Examine grooved ends for form and cleanliness. Grooved ends shall be clean and free from indentations, projections, and roll marks in the area from pipe end to groove.

G. Do not attempt to repair defective valves; replace with new valves.

H. Install valves as indicated, according to manufacturer's written instructions.

I. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.

J. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.

K. Locate valves for easy access and provide separate support where necessary.

L. Install valves in horizontal piping with stem at or above the center of the pipe.

M. Install valves in a position to allow full stem movement.

N. Adjust or replace packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if leak persists.

3.4. WASTE AND VENT PIPING INSTALLATION REQUIREMENTS

A. Each pipe shall be laid true to line and grade and in such manner as to form a close concentric joint with the adjoining pipe and to prevent sudden offsets of the flow line. All pipe when laid shall rest on the full length of the barrel and bell holes shall be dug in trench bottoms to make joints. Pipe shall not be adjusted to grade by use of block or wedges. Where rock or old foundations are encountered, trenches shall be excavated 6-inches below grade and crusher run limestone shall be used as a bedding material to support barrel of pipe.

B. As the work progresses, the interior of the sewer shall be cleared of all dirt and superfluous materials of every description.

C. Trenches shall be kept free from water until the pipe jointing material has set and pipe shall not be laid when the conditions of the trench or the weather is unsuitable for such work. At all times, when work is not in progress, all open ends of pipe and fittings shall be securely closed to the satisfaction of the Engineer, so that no trench water, earth or other substance will enter the pipe or fittings.

D. Slip joints will be permitted only in trap seals or on the inlet side of the trap. Unions on the sewer side of the trap shall be ground faced, and shall not be concealed or enclosed. Install bell and spigot pipe with bell end upstream.

E. Threaded joints shall be American Standard taper screw threads with permacel joint compound applied to the male thread. Connections between threaded pipe and cast iron pipe shall have a ring or half coupling screwed on to form a spigot end on the threaded pipe.

F. Establish invert elevations, slopes for drainage to 1/8 inch per foot. Maintain gradients.

3.5. PIPE JOINTS INSTALLATION REQUIREMENTS

A. Grooved Joints: Grooved joint shall be installed in accordance with the manufacturer's written recommendations. Grooved ends shall be clean and free from indentations, projections, or roll marks. The gasket shall be molded and produced by the coupling manufacturer of an elastomer suitable for the intended service. The coupling manufacturer's factory trained representative shall provide on-site training for the contractor's field personnel in the use of grooving tools and installation of product. The representative shall periodically visit the job site to ensure best practices in grooved product installation are being followed. (A distributor's representative is not considered qualified to conduct the training.)

B. Screwed Joints: All screwed joints shall be made with tapered threads properly cut. Screwed joints shall be made perfectly tight with a stiff mixture of graphite and oil, applied with a brush to the male threads on the fittings.

C. Soldered Joints and Copper Piping: Joints in copper piping shall conform to the following minimum standards.

1. The pipes shall be cut to a length making certain that the ends are square, using a fins hacksaw blade or tube cutter. The ends of all pipes shall be reamed and all burrs removed.

2. The outside end of the pipe and the cut end of the fitting shall be cleaned with steel wool, sand cloth, or steel wire brush. All dark spots shall be removed.

3. The flux shall be applied evenly and sparingly to the outside end of the pipe and the inside of the outer end of the fitting until all surfaces to be jointed are completely covered. The piping and fitting shall be slipped together and reworked several times to insure an even distribution of the flux.

4. The correct amount of solder per joint for each size pipe shall be used in accordance with the manufacturer's recommendations.

5. Solder joints shall be made by using a direct flame from a torch.

6. On pipe sizes larger than ¼-inch, the fittings and valves in the pipe shall be

moved or tapped with a hammer when the solder starts to melt to insure an even distribution of the solder.

7. The excess solder shall be removed while it is still in the plastic state leaving a fillet around the cup of the fitting.

8. Solder joints shall be suitable for working pressure of 100 psig and for working temperature of not less than 250 degrees F. The type of solder and flux used will be submitted for approval. Type 95-5 shall be the minimum standard.

9. Lead and antimony-based solders shall not be used for potable water systems. Brazing and silver solders are acceptable.

D. Where copper piping joins steel piping, approved bronze adapters shall be used.

E. Prohibited Connections: No direct weld, soldered, or brazed connections, without unions or flanges, shall be made to valves, strainers, apparatus, or related equipment. Right and left couplings, long threads, or caulking of pipe threads or gasket joints will not be permitted.

F. Plastic piping solvent cement joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe handling practice of cleaners, primers, and solvent cements. Apply primer.

2. PVC Piping: Join according to ASTM D2855.

3. CPVC Piping: Join according to ASTM D284.6/D 2845M Appendix.

3.6. HANGERS AND SUPPORTS INSTALLATION REQUIREMENTS

A. General: All hangers shall be of an approved type arranged to maintain the required grading and pitching of lines to prevent vibration and to provide for expansion and contraction. Provide protection saddles between hangers and insulation on heating water insulated pipe. Saddles shall be Victaulic, Grinnells Figure 173/273, Sure-Joint, or approved equal. Provide approved spacers between saddles and pipe where flexible insulation is specified. Provide insulation protection shields for insulated piping without saddles. Shields shall be Carpenter Patterson, Grinnell Figure 167 or as approved equal.

B. Spacing: Regardless of spacing, hangers shall be provided at or near all changes in direction, both vertical and horizontal, for all piping. For cast iron soil pipe, one hanger shall be placed at each hub or bell.

C. Vertical Lines: Shall be supported at their bases, using either a suitable hanger placed in a horizontal line near the riser, or a base type fitting set on a pedestal, foundation or support. All vertical lines extending through more than one floor level shall be supported at each floor with a riser clamp. Riser clamp shall be Carpenter

Patterson, Grinnell Co.'s Figure 261, or approved equal. All vertical drops to pump suction elbows shall be supported by floor posts.

D. Racks and Brackets: All horizontal piping on vertical walls shall be properly supported by suitable racks securely anchored into the wall construction. Where not practical to obtain ceiling anchorage, all piping near walls shall be supported by approved brackets securely anchored into the wall construction. Washer plates (Fib. 60, 60L) and other miscellaneous attachments, fasteners, etc., shall be Carpenter Patterson, Grinnell or as approved equal. All exterior hanger and bracket systems in their entirety shall be galvanized.

E. Pipe Hangers and supports shall be attached to the panel point at the top chord of bar joist or at a location approved by the structural engineer.

F. Select hangers and components for loads imposed. Secure rods with double nuts.

G. Support of horizontal piping shall allow for vertical adjustment after installation of piping.

H. Support overhead piping with clevis hangers.

I. Do not support all parallel piping from the same joist. Stagger all supports in accordance with the structural engineer's recommendations.

J. Refer to structural documents for appropriate connection/attachment materials to building.

3.7. AIR VENTING INSTALLATION REQUIREMENTS

A. The top of each plumbing piping system and other points as indicated or where necessary for the removal of air from the system or equipment, shall be vented using an approved type of manual air vent.

B. In addition to manual air vents at high points of system, each item of water heat transfer equipment shall be manually vented using an approved type manual air vent. All air vents shall be accessible.

3.8. SWING CONNECTION INSTALLATION REQUIREMENTS

A. Install expansion fittings according to manufacturer's written instructions.

B. Install expansion fittings in sizes matching pipe size in which they are installed.

C. Align expansion fittings to avoid end loading and torsional stress.

D. Install pipe bends and loops cold sprung in tension or compression as required to partly absorb tension or compression produced during anticipated change in temperature.

E. Attach pipe bends and loops to anchors.

1. Steel Anchors: Attach by welding. Comply with ASME B31.9 and ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."

2. Concrete Anchors: Attach by fasteners. Follow fastener manufacturer's written instructions.

F. Connect risers and branch connections to mains with at least five pipe fittings, including tee in main.

G. Connect risers and branch connections to plumbing equipment with at least four pipe fittings, including tee in riser.

H. Connect mains and branch connections to plumbing equipment with at least four pipe fittings, including tee in main.

I. Install expansion loops, guides, and anchors on all CPVC domestic water piping as required per manufacturer’s instructions.

3.9. PIPING IDENTIFICATION REQUIREMENTS

A. All piping shall be identified with painted background marked with the name of the service with arrows to indicate flow direction. Color code and system identification shall comply with ANSI Standards and piping identification system shall comply with ASME A13.1-81., scheme for the identification of piping systems and ASHRAE Fundamentals Handbook, latest edition.

B. Markings shall be plain block letters, stenciled on pipes, and shall be located near each branch connection, near each valve, and at least every 10 feet on straight runs of pipe. Where pipes are adjacent to each other, markings shall be neatly lined up. All markings shall be located in such manner as to be easily legible from the floor. Pipe identification schedule shall be as follows:

OUTSIDE DIAMETER OF PIPE OR COVERING (INCHES)	LENGTH OF COLOR FIELD (INCHES)	SIZE OF LETTERS (INCHES)
½ to 1 ¼	8	½
1-½ to 2	8	¾
2 ½ to 6	12	1 ¼
8 to 10	24	2 ½
Over 10	32	3 ½

3.10. VALVE IDENTIFICATION REQUIREMENTS

A. All valves shall be tagged with a numbered tag.

B. The tags shall be made of 1-inch diameter brass tags fastened to the valve by means of brass chains. Numbers shall agree with valve numbers on diagrammatic herein before specified.

C. Provide a minimum of three (3) valve charts with valve numbers indicating valve type, size, manufacturer and service.

D. Additional valve charts shall be mounted behind glazed wooden frames and be hung in each mechanical equipment room including each air handling unit mechanical equipment room. Additional copies shall be provided in each copy of the O&M manuals.

3.11. CLEANING PIPING AND EQUIPMENT REQUIREMENTS

A. All water, plumbing piping, and pumped condensate systems shall be cleaned by filling with a solution of one (1) pound of trisodium phosphate to each 50 gallons of water and circulating this solution for a period of six (6) hours during which time the system shall reach operating temperature. The systems shall then be flushed with fresh water and refilled with fresh water purged of all air.

B. All water, plumbing, and pumped condensate piping system shall be flushed clean with fresh water. See Division 22 Sections, Plumbing Fixture and Plumbing Equipment for domestic potable water cleaning and sterilization.

3.12. PRESSURE SEAL FITTING INSTALLATION REQUIREMENTS

A. Viega, ProPress Pressure Seal bronze, Mueller Streamline, or approved equal or copper fittings: Sealing element shall be verified for the intended use. Tube ends shall be cut on a right angle (square) to the tube. Tube ends shall be reamed and chamfered, all grease oil or dirt shall be removed from the tube end with a clean rag. Visually examine the fitting sealing element to ensure there is no damage, and it is properly seated into the fitting. Utilizing a Viega Insertion Depth Inspection Gauge mark the tube wall, with a felt tip pen, at the appropriate location, or insert the tube fully into the fitting and mark the tube wall at the face of the fitting. Always examine the tube to ensure it is fully inserted into the fitting prior to pressing the joint. ProPress fittings shall be installed according to the most current edition of the Viega installation guidelines. Installers shall attend a Viega ProPress installation training class.

B. After ProPress, Mueller Streamline, or approved equal. Pressure seal fittings have been installed a “two step test” shall be followed. Pressurize the system with application appropriate test medium, water between 15 and 85 psi, or air/dry nitrogen between .5 and 45 psi. Check the pressure gauge for pressure loss. If the system does not hold pressure, walk the system and check for un-pressed fittings. Should you identify an un-pressed fitting ensure the tube is fully inserted

into the fitting and properly marked, prior to pressing the joint. After appropriate repairs have been made, retest the system per local code, or specification requirements, not to exceed 600 psi with water or 200 psi when using air fitting.

END OF SECTION 220505

PAGE LEFT INTENTIONALLY BLANK

SECTION 220701 - PLUMBING INSULATION

PART 1 - GENERAL

1.1. REFERENCE

A. The Conditions of the Contract and other General Requirements apply to the work specified in this Section. All work under this Section shall be subject to the requirements of Division 22 Section, Common Work Results for Plumbing.

B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section

1.2. DESCRIPTION

A. All piping and equipment installed under this Contract shall be covered as specified.

1.3. SCOPE

A. The work covered by this specification consists of furnishing all labor, equipment, materials and accessories, and performing all operations required, for the correct fabrication and installation of thermal insulation applied to all piping, equipment, and systems, in accordance with applicable project specifications and drawings, subject to the terms and conditions of the contract.

1.4. STANDARDS

A. Thermal insulation materials shall meet the property requirements of one or more of the following specifications as applicable to the specific product or use:

1. American Society for Testing of Materials Specifications:

   a. ASTM C 547, “Standard Specification for Mineral Fiber Preformed Pipe Insulation”.
   b. ASTM C 533, “Standard Specification for Calcium Silicate Pipe & Block Insulation”.
   c. ASTM C 55, “Standard Specification for Mineral Fiber Blanket and Felt Insulation”.
   d. ASTM E 96, “Standard Test Methods for Water Vapor Transmission of Materials”.
   e. ASTM C 585, “Recommended Practice for Inner and Outer Diameters of Rigid Pipe Insulation for Nominal Sizes of Pipe and Tubing (NPS System)”.
   f. ASTM C 612, “Standard Specification for Mineral Fiber Block and

Board Thermal Insulation".

g. ASTM C 1136, "Standard Specification for Barrier Material, Vapor, "Type 1 or 2 (Jacket only).

h. ASHRAE 90.1 "Energy efficient design of new buildings except low-rise residential buildings", latest edition.

B. Insulation materials, including all weather and vapor barrier materials, closures, hangers, supports, fitting covers, and other accessories, shall be furnished and installed in strict accordance with project drawings, plans, and specifications.

1.5. SYSTEM PERFORMANCE

A. Insulation materials furnished and installed hereunder should meet the minimum economic insulation thickness requirements of the North American Insulation Manufacturers' Association (NAIMA) (formerly known as TIMA), to ensure cost-effective energy conservation performance. Alternatively, materials should meet the minimum thickness requirements of National Voluntary Consensus Standard 90.1, (latest edition) and "Energy Efficient Design of New Buildings," of the American Society of Heating, Refrigeration, and Air-Conditioning Engineers (ASHRAE), latest edition. However, if other factors such as condensation control or personnel protection are to be considered, the selection of the thickness of insulation should satisfy the controlling factor. As minimum, all insulation thicknesses shall be as hereinafter specified.

B. Insulation materials furnished and installed hereunder shall meet the fire hazard requirements of any one of the following specifications:

1. American Society for Testing of Materials ASTM E 84

2. Underwriters' Laboratories, Inc. UL 723

3. National Fire Protection Association NFPA 255

C. Calcium silicate products shall include a visual identification system to permit positive field determination of their asbestos-free characteristics.

1.6. QUALITY ASSURANCE

A. Insulation materials and accessories furnished and installed hereunder shall, where required, be accompanied by manufacturers' current submittal or data sheets showing compliance with applicable specifications listed in Section 1.4 above.

B. Insulation materials and accessories shall be installed in a workmanlike manner by skilled and experienced workers who are regularly engaged in commercial insulation work.

1.7. DELIVERY AND STORAGE OF MATERIALS

A. All of the insulation materials and accessories covered by this specification shall be delivered to the job site and stored in a safe, dry place with appropriate labels and/or other product identification.

B. The Contractor shall use whatever means are necessary to protect the insulation materials and accessories before, during, and after installation. No insulation material shall be installed that has become damaged in any way. The Contractor shall also use all means necessary to protect work and materials installed by other trades.

C. If any insulation material has become wet because of transit or job site exposure to moisture or water, the Contractor shall not install such material, and shall remove it from the job site. An exception may be allowed in cases where the Contractor is able to demonstrate that wet insulation when fully dried out (either before installation, or afterward following exposure to system operating temperatures) will provide installed performance that is equivalent in all respects to new, completely dry insulation. In such cases, consult the insulation manufacturer in writing for technical assistance.

D. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements. Protect all insulation from water, construction traffic, dirt, chemical and mechanical damage.

1.8. ALTERNATES

A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1. GENERAL

A. All materials to be insulated shall be thoroughly cleaned, after completion of successful tests, and shall be covered as specified below. Fiberglass insulation shall be Owens-Corning, Manville, Armstrong, or P.P.G, or as approved equal.

2.2. PIPE INSULATION MATERIALS

A. Unless otherwise noted, insulation shall be one piece or half sectional molded fibrous glass with “K” rating of .23 at 75 degrees F mean temperature, for service temperatures between -60 degrees F and +450 degrees F with all service poly-encapsulated jacket. Pipe insulation shall be fiberglass ASJmax SSL II with double closure system as manufactured by Owens Corning, Johns Manville, Knauf or approved equal.

B. All below grade dental vacuum, dental compressed air, domestic cold water, hot water and hot water recirculating piping shall be insulated with Armacell or approved equal elastomeric insulation.

C. Unless otherwise noted, pipe insulation jacket shall be factory-applied vinyl coated, embossed and reinforced vapor barrier laminate, with a perm rating of not more than 0.02 perms. All hot and cold, concealed, and exposed butt strips shall be of the same material as the jacket. Jacket and butt strips shall be sealed with field-applied Foster 85-20/85-50 or Childers CP-82 (5 gallon cans only) adhesive. Jacket and butt strips shall be off-white color and shall be equivalent to Owens-Corning Fiberglass 25-ASJ, Johns Manville, Knauf, or approved equal.

D. For fittings on all piping, valves, and flanges, apply fiberglass molded or segmented insulation equal in thickness to the adjoining insulation and securely fasten in place using wire. Cold piping: Apply a tack coat of vapor barrier coating and reinforcing mesh. After ½ hour, apply second coat of same vapor barrier coating, UL labeled, Type C, for cold water piping. Hot piping, Type H for hot water piping: Apply tack of breather mastic. Wrap fitting with fiberglass reinforcing cloth overlapping adjoining sections of pipe insulation by 2-inches. Apply a second coat of breather mastic over the reinforcing cloth, working it to a smooth finish. As an option to the above hot fittings, a polyvinyl chloride fitting cover may be supplied.

E. All pipe insulation, jackets, or facings, and adhesives used to adhere jacket or facing to the insulation, including fittings and butt strips, shall have non-combustible fire and smoke hazard system rating and label as tested by ASTM E-84, NFPA 225, and UL 73, not exceeding Flame Spread 25, Fuel Contributed 50, Smoke Developed 50. Accessories such as adhesives, mastic cements, tapes and cloth for fittings shall have the same ratings as listed above. All products or their shipping cartons shall bear the Underwriter's label indicating that flame and smoke ratings do not exceed the above criteria.

F. For piping having a vapor barrier insulation and for all insulated piping requiring supports, hangers and supports shall be installed outside the insulation. Wherever hangers and supports are installed outside the insulation, pipe insulation protecting shields shall be provided. Where insulation is a load bearing material, of sufficient strength to support the weight of the piping, pipe shields one-third the circumference of the insulation and of a length not less than three times the diameter of the insulation (maximum length 24-inches) shall be provided. Insulation of 7-1/4 pound or greater density will be considered as load bearing for pipe sizes up to and including 2-inches. Where insulation is not of sufficient strength to support the weight of the piping, a half section of high density fiberglass or foam inserts, shall be provided. Vapor barrier and finish shall be applied as required to match adjoining insulation. In addition, shields shall be furnished as specified above.

G. For piping located outside of the building, a corrugated aluminum weatherproof jacketing system shall be provided. This system shall be Micro-Lot ML as manufactured by Manville, Polyweld by Pabco Metals Corp., Childers, or as approved equal, and installed per the manufacturer's recommendations. Where outdoor piping is receiving electric heat tape, the insulation shall be oversized so

that the heat tape is not compressed tightly to the pipe. Pipe jacketing shall be corrugated (3/16-inch) deep aluminum, .016-inch thickness of H-14 temper with aluminum strapping of .75-inch width and .020 inch thickness with moisture barrier. Aluminum jacketing elbows shall be smooth, .016-inch thickness and 1100 alloy. All jacketing shall have an integrally bonded moisture barrier over the entire surface in contact with the insulation. Longitudinal joints shall be applied so they will shed water and shall be sealed completely and shall be sealed completely with metal jacketing sealant. Sealant shall be Foster 95-44 or Childers CP-76. Circumferential joints shall be closed using preformed butt strips following manufacturer's recommendations for securement. Jacket seams shall be located on the bottom side of the horizontal piping.

H. All disturbed piping insulation in existing areas shall be re-insulated with insulation type, density, and thickness as specified for new piping. Insulation damaged due to new work and demolition only shall be replaced unless otherwise noted.

I. On cold systems such as domestic cold water, vapor barrier performance is extremely important. All penetrations and seams of the ASJ and exposed ends of insulation must be sealed with vapor barrier coating. The ASJ must be protected with either a vapor barrier coating or a suitable vapor retarding outer jacket. Vapor seals at butt joints shall be applied at every fourth pipe section joint and at each fitting to provide isolation of water incursion. Vapor Barrier Coating: Foster 30-65; Childers CP-34 or Vimasco 749. Permeance shall be 0.03 perms or less at 45 mils dry at test by ASTM E96.

J. Fittings and valves shall be insulated with pre-formed fiberglass fittings, fabricated sections of Fiberglass pipe insulation, Fiberglass pipe and tank insulation, Fiberglass blanket insulation, or insulating cement. Thickness shall be equal to adjacent pipe insulation. Finish shall be with pre-formed PVC fitting covers or as otherwise specified on contract drawings. Where applicable, grooved joint PVC fitting valve and coupling covers shall be utilized. Grooved joint PVC covers shall be installed with matching pipe insulation jacketing material, vinyl tape, solvent weld adhesive and appropriate fasteners.

1. Flanges, couplings and valve bonnets shall be covered with an oversized pipe insulation section sized to provide the same insulation thickness as on the main pipe section. An oversized insulation section shall be used to form a collar between the two insulation sections with low density blanket insulation being used to fill gaps. Jacketing shall match that used on straight pipe sections. Rough cut ends shall be coated with a suitable weather or vapor-resistant mastic as dictated by the system location and service. Finish valve installation with a Tyvac jacket with ends that secure to adjacent piping.

2. On hot systems where fittings are to be left exposed, insulation ends should be beveled away from bolts for easy access.

3. On cold systems, particular care must be given to vapor sealing the fitting cover or finish to the pipe insulation vapor barrier. All valve stems must be sealed with caulking which allows free movement of the stem but provides

a seal against moisture incursion. All gauge and thermometer penetrations and extensions shall be correctly sealed and insulated to prevent surface condensation.

K. All piping shall be supported in such a manner that neither the insulation or the vapor/weather barrier is compromised by the hanger or the effects of the hanger. In all cases, hanger spacing must be such that the circumferential joint may be made outside the hanger. On cold systems, vapor barrier must be continuous, including material covered by the hanger saddle.

1. Piping systems 3-inches (7.5cm) in diameter or less, insulated with Fiberglass insulation, may be supported by placing saddles of the proper length and spacing, as designated in Owens-Corning Pub. 1-IN-12534, under the insulation. Hangers saddles shall be minimum 16 gauge with a saddle arc of 120 degrees minimum.

2. For hot or cold piping systems larger than 3-inches (7.5 cm) in diameter, operating at temperatures less than +200 degrees F (93 degrees C) and insulated with fiber glass, high density inserts such as foam with sufficient compressive strength shall be used to support the weight of the piping system. At temperatures exceeding +_200 degrees F (93 degrees C), Owens-Corning Pink or IIG, Calcium Silicate pipe insulation shall be used for high density inserts.

3. Owens-Corning Pink Calcium Silicate pipe insulation may be used to support the entire weight of the piping system provided the hanger saddle is designed so the maximum compressive load does not exceed 100 psi (7kg/cm).

4. Where pipe shoes and roller supports are required, insulation shall be inserted in the pipe shoe to minimize pipe heat loss. Where possible, the pipe shoe shall be sized to be flush with the outer pipe insulation diameter.

5. Thermal expansion and contraction of the piping and insulation system shall generally be taken care of by utilizing double layers of insulation and staggering both longitudinal and circumferential joints. Where long runs are encountered, expansion joints may be required where single layers of insulation are being used and should be so noted on the contract drawings.

6. On vertical runs, insulation support rings shall be used.

2.3. PIPING INSULATION THICKNESSES SCHEDULE

A. All piping shall be insulated with pipe insulation of the thicknesses indicted below:

PIPING INSULATION THICKNESS SCHEDULE SERVICES	THICKNESS
Above Grade Trap Priming Lines	½ -inch thickness

PIPING INSULATION THICKNESS SCHEDULE SERVICES	THICKNESS
All Above Grade Floor Drain Piping Serving AHU Condensate Drains include Drain Sumps and Auxiliary Drain Pipes from Auxiliary Pans	1-inch thickness
All Above Grade Domestic Hot and Cold Water Piping, including Hot Water Re-circulating Piping	1-inch thickness
All Below Grade/Slab Domestic Hot and Cold Water Piping, including Hot Water Re-circulating Piping	1-inch thickness
All Drain Piping from Cooling Coils/Evaporators	½-inch thickness
All Horizontal Roof Drain Piping Including Sumps	1-inch thickness
Emergency Fixture Tepid Water Piping	1-inch thickness
Existing Floor Drain Piping that collects condensate	1-inch thickness
Dental Vacuum Pump Exhaust Piping	1-½-inch thickness
Below Grade Dental Vacuum and Compressed Air Piping	½-inch thickness

2.4. EQUIPMENT INSULATION MATERIALS AND THICKNESSES

A. The following equipment shall be insulated with Fiberglass Rigid Board Insulation or Foam Plastic Insulation:

1. Backflow Preventer Valve Bodies.

B. Insulation for cold surfaces shall be 1-1/2-inch thickness, 6 lb. density, 705 FRK with a "K" rating of .23 at 75 degrees F mean temperature. Insulation for hot surfaces except as otherwise noted shall be 1-1/2-inch thickness, 6 lb. density, 705 with a "K" rating of .23 at 75 degrees F mean temperature. Insulation shall be applied with staggered joints firmly butted and joined. The insulation shall be held in place by steel bands. Bands shall be 1-inch by 25 gauge galvanized steel spaced on not over 12-inch centers. All joints and voids shall be filled with Owens-Corning #110 cement, well troweled into openings. For 705 FRK insulation, all joints and voids shall be FRK taped and vapor sealed. There shall be applied over the insulation surface 1-inch galvanized wire netting laced together at all edges and wired to the steel bands with 16 gauge soft annealed wire. Over this shall be applied 2-inch thick layer of Owens-Corning #110 cement applied in two layers. Install metal corner beads at all corners and edges in order to provide a permanent installation. Onto the dry cement surface apply a brush coat of Foster Sealfas 30-36 or Childers CP-50AMV1 lagging adhesive at the rate of 60-70 square feet per gallon. Cleanouts, nameplates, and manholes shall not be insulated, and the insulation on surrounding surfaces shall be neatly beveled off at such openings.

C. Insulation Installation on Pumps:

1. Fabricate metal boxes lined with insulation. Fit boxes around pumps and coincide box joints with splits in pump casings. Fabricate joints with outward bolted flanges. Bolt flanges on 6-inch (150-mm) centers, starting at corners. Install 3/8-inch- (10-mm-) diameter fasteners with wing nuts. Alternatively, secure the box sections together using a latching mechanism.

2. Fabricate boxes from aluminum at least 0.040 inch (1.0 mm) thick.

3. For below ambient services, install a vapor barrier coating at seams, joints, and penetrations. Seal between flanges with replaceable gasket material to form a vapor barrier.

D. Mechanical fasteners shall be utilized to hold insulation to surface with bands as required to hold the curvature of the material.

E. Support rings shall be provided to support the top head insulation where required.

F. Outdoor installations require a weather barrier mastic for protection of the insulation jacketing.

G. Insulation types materials shall be suitable for temperatures encountered by each item of equipment.

H. Install removable insulation sections at all cleanouts, test ports, and items that must be periodically tested.

2.5. ACCESSORY MATERIALS

A. Accessory materials installed as part of insulation work under this section shall include, but not be limited to:

1. Closure Materials - Butt strips, bands, wires, staples, mastics, adhesives; pressure-sensitive tapes.

2. Field-applied jacketing materials - sheet metal, plastic, canvas, fiber glass cloth, insulating cement; PVC fitting covers, PVC jacketing.

3. Support Materials - Hanger straps, hanger rods, saddles.

4. Fasteners, weld pins/studs, speed clips, insulation washers.

5. Metal mesh or expanded metal lagging.

B. All accessory materials shall be installed in accordance with project drawings and specifications, manufacturer's instructions, and/or in conformance with the current edition of the Midwest Insulation Contractors Association (MICA) "Commercial & Industrial Insulation Standards."

2.6. FIELD-APPLIED JACKET

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.

1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

a. Johns Manville; Zeston.
b. P.I.C. Plastics, Inc.; FG Series.
c. Proto PVC Corporation; LoSmoke.
d. Speedline Corporation; SmokeSafe.

2. Adhesive: As recommended by jacket material manufacturer. VOC content not to exceed 250 g/L.

3. Color: High Gloss White

4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.

a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

PART 3 - EXECUTION

3.1. WORKMANSHIP

A. The Contractor shall take special care to prevent soiling equipment below or adjacent to areas being insulated. He shall be completely responsible for removing insulation cement splashes and smears and all surfaces that he mars or otherwise soils or defaces, and he will be totally responsible for restoring these damaged surfaces to their like-new condition when delivered to the site.

3.2. SITE INSPECTION

A. Before starting work under this section, carefully inspect the site and installed work of other trades and verify that such work is complete to the point where installation of materials and accessories under this section can begin.

B. Verify that all materials and accessories can be installed in accordance with project drawings and specifications and material manufacturers' recommendations.

C. Verify, by inspecting product labeling, submittal data, and/or certifications which may accompany the shipments, that all materials and accessories to be installed on the project comply with applicable specifications and standards and meet specified thermal and physical properties.

3.3. PREPARATION

A. Ensure that all pipe and equipment surfaces over which insulation is to be installed are clean and dry.

B. Ensure that insulation is clean, dry, and in good mechanical condition with all factory-applied vapor or weather barriers intact and undamaged. Wet, dirty, or damaged insulation shall not be acceptable for installation.

C. Ensure that pressure testing of piping systems has been completed prior to installing insulation.

3.4. INSTALLATION

A. Piping Systems

1. General:

a. Install all insulation materials and accessories in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
b. Install insulation on piping subsequent to installation of heat tracing, painting, testing, and acceptance tests.
c. Install insulation materials with smooth and even surfaces. Insulate each continuous run of piping with full-length units of insulation, with single cut piece to complete run. Do not use cut pieces or scraps abutting each other. Butt insulation joints firmly to ensure complete, tight fit over all piping surfaces.
d. Maintain the integrity of factory-applied vapor barrier jacketing on all pipe insulation, protecting it against puncture, tear or other damage. Seal all tears, punctures and other penetrations of the pipe insulation vapor barrier coating.
e. On exposed piping, locate insulation and cover seams in least visible location.
f. All below grade domestic cold water, hot water and hot water recirculating piping shall be insulated with Armacell or approved equal elastomeric insulation. Below grade dental vacuum and dental compressed air.

2. Fittings: Cover valves, fittings, unions, flanges, strainers, flexible connections, expansion joints, pump bodies, strainers, blowdowns, backflow preventers, autoflow valves and similar items in each piping system using one of the following:

a. Mitered sections of insulation equivalent in thickness and composition to that installed on straight pipe runs.
b. Insulation cement equal in thickness to the adjoining insulation.
c. PVC fitting covers insulated with material equal in thickness and composition to adjoining insulation.

3. Penetrations: Extend piping insulation without interruption through walls, floors, and similar piping penetrations, except where otherwise specified.

4. Joints:

a. Butt pipe insulation against hanger inserts. For hot pipes, apply 3-inch (7.5cm) wide vapor barrier tape or bank over butt joints. For cold piping, apply wet coat of vapor barrier lap cement on butt joints, and seal joints with 3-inch (7.5cm) wide vapor barrier tape or band.
b. All pipe insulation ends shall be tapered and sealed, regardless of service.

B. Equipment Insulation:

1. General:

a. Install insulation in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
b. Install insulation on equipment after installation of heat tracing, painting, testing, and acceptance tests.
c. Install insulation materials with smooth, even surfaces. Rework poorly fitted joints. Do not use joint sealer or mastic as filler for joint gaps and excessive voids resulting from poor workmanship. Apply insulation using staggered joint method for both single and double layer installation, applying each layer of insulation separately.
d. Coat insulated surfaces where specified on contract drawings with layer of insulating cement, troweled in a workmanlike manner, leaving a smooth and continuous surface. Fill in seams, broken edges, and depressions. Cover over wire mesh and joints with cement sufficiently thick to remove surface irregularities.
e. Maintain the integrity of factory-applied vapor barrier jacketing on all insulation, protecting it against puncture, tears or other damage. Seal all tears, punctures and other penetrations of equipment insulation facing.
f. Where specification calls for field-applied all-service vapor barrier jacketing, it shall be neatly fitted and tightly secured. Lap seams 2-inches (5cm) (min.). Seal all joints with adhesive. Tape with 3-inches (7.5cm) matching pressure-sensitive tape or 3-inch (7.5cm) glass fabric and vapor barrier coating.
g. On exposed equipment, locate insulation and cover seams in least visible location.

2. Removable Insulation: Provide removable insulation sections to cover

parts of equipment which must be opened periodically for maintenance, such as vessel covers, fasteners, flanges, frames accessories, manholes, handholes, cleanouts ASME stamp, and manufacturer nameplates.

3. Areas Left Uninsulated: Items such as manholes, handholes, clean-outs, ASME stamp, and manufacturers' nameplates should be left uninsulated unless omitting insulation would cause a condensation problem. When such is the case, provide removable insulation and appropriate tagging to identify the presence of these items. Provide neatly beveled edges at interruptions of insulation.

4. Equipment Exposed to Weather: Protect outdoor insulation from weather by installation of weather barrier mastic protective finish or jacketing as recommended by the jacketing manufacturer.

3.5. FIELD QUALITY ASSURANCE

A. Upon completion of all insulation work covered by this specification, visually inspect the work and verify that it has been correctly installed. This may be done while work is in progress, to assure compliance with requirements herein to cover and protect insulation materials during installation.

3.6. PROTECTION

A. Replace damaged insulation which cannot be satisfactorily repaired, including insulation with vapor barrier damage and moisture-saturated insulation.

B. The insulation contractor shall advise the general and/or the mechanical contractor as to requirements for protection of the insulation work during the remainder of the construction period, to avoid damage and deterioration of the finished insulation work.

3.7. SAFETY PRECAUTIONS

A. Insulation contractor's employees shall be properly protected during installation of all insulation. Protection shall include proper attire when handling and applying insulation materials, and shall include (but not be limited to) disposable dust respirators, gloves, hard hats, and eye protection.

B. The insulation contractor shall conduct all job site operations in compliance with applicable provisions of the Occupational Safety and Health Act, as well as with all state and/or local safety and health codes and regulations that may apply to the work.

3.8. INSULATION COVERING

A. Unless otherwise noted, all exposed equipment insulation shall have a field applied

PVC jacket cover neatly cut and pasted over equipment insulation. PVC shall be high gloss white and shall be 20 mils thick. Exposed areas include, but are not limited to, all mechanical equipment rooms/fan rooms, above architectural ceiling clouds, mezzanines, penthouses, boiler rooms, janitor's closets, kitchens, electric rooms, and piping and ductwork exposed in an occupied space.

B. Unless otherwise noted, all exposed pipe insulation required to be insulated shall be jacketed with a PVC Jacketing with fitting covers. PVC jacket shall be color fade resistant, white high gloss, U.S.D.A. authorized as manufactured by Proto Corporation or approved equal. PVC jacketing shall be high impact, ultraviolet resistant PVC. Minimum thickness shall be 20 mils, roll stock ready for shop or field cutting and forming.

C. Where PVC jackets are indicated, install with 1 inch overlap at longitudinal seams and end joints, for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturers recommended adhesive.

1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

END OF SECTION 220701

PAGE LEFT INTENTIONALLY BLANK

PART 1. GENERAL

1.1. RELATED DOCUMENTS

A. This project is to be LEED certified. Refer to Division 01 Sections, including “Sustainable Design Requirements”, “Construction Waste Managements”, and “Commissioning Requirements” for mandatory work which may apply to all contractors, installers, and suppliers.

1.2. GENERAL

A. For General Mechanical Requirements, see Division 22 Section, Common Work Results for Plumbing & Division 01, General Requirements.

B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 specifications apply to this Section.

C. All exposed bolts, screws, etc., shall be vandal proof.

D. All plumbing materials, equipment and fixtures shall be new and of best grade, free of defects and complete with all required appurtenances and accessories.

E. Piping and insulation are specified under other sections.

F. Use "Sani-Sett" setting compound for fixtures.

G. Provide all materials, equipment and perform all labor required to install plumbing system complete as specified, as drawings indicated and as required by the following:

1. State of Delaware
2. Sussex County local code
3. City of Georgetown, Delaware Code
4. All other authorities have jurisdiction.

H. Comply with the current lead-free laws per the requirements of the state in which the project is being constructed.

I. Provide stops for all plumbing fixtures and equipment. Stops are to be accessible.

J. Provide P traps on fixtures for which traps have not been included as part of furnished equipment. Trap size to equal size of fixture tailpiece.

K. All exposed metal parts of fixtures shall be chromium plated brass. Piping, fittings, valves, traps and accessories including escutcheons for piping shall be chromium

plated where exposed in finished areas.

L. All faucets for the following list shall be listed for drinking-water or commercial applications by the National Sanitation Foundation (NSF) or Underwriters Laboratory (U.L.). All required faucets shall comply with NSF Standard 61 for both lead content and leaching rate. Submit documentation indicating compliance for all required faucets.

1. Sinks

2. Lavatories

M. Ensure products and installation of specified products are in conformance with recommendations and requirements of the following organizations:

1. American Gas Association (AGA).
2. National Sanitation Foundation (NSF).
3. American Society of Mechanical Engineers (ASME).
4. National Electrical Manufacturers' Association (NEMA).
5. Underwriters Laboratories (UL).

1.3. REFERENCES

A. ANSI/ASME A112.6.1 - Supports for Off-the-floor Plumbing Fixtures for Public Use

B. ASME A112.18.1 - Finished and Rough Brass Plumbing Fixture Fittings.

C. ANSI/ASME A112.19.1 - Enameled Cast Iron Plumbing Fixtures.

D. ANSI/ASMI A112.19.2 - Vitreous China Plumbing Fixtures.

E. ANSI/ASME A112.19.3 - Stainless Steel Plumbing Fixtures (Designed for Residential Use).

F. ANSI/ASME A112.19.4 - Porcelain Enameled Formed Steel Plumbing Fixtures.

G. ANSI Z358.1 - Emergency Eyewash and Shower Equipment.

H. ANSI/NFPA 70 - National Electrical Code.

I. IBC - International Building Code

1.4. DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, protect and handle products to site under provisions of Division 01, Section General Requirements.

B. Accept fixtures on site in factory packaging. Inspect for damage.

C. Protect installed fixtures from damage by securing areas and by leaving factory packaging in place to protect fixtures and prevent use.

1.5. FIELD MEASUREMENTS

A. Verify that field measurements are as indicated on shop drawings and per the manufacturer.

B. Confirm that millwork is constructed with adequate provisions for the installation of counter top lavatories and sinks.

1.6. EXTRA MATERIALS

A. Provide two sets of faucet washers and flush valve service kits to the Owner. Provide correspondence to Engineer that extra materials have been turned over to the Owner.

B. For battery operated plumbing fixtures, furnish to Owner in a suitable container a spare set of batteries for each fixture.

1.7. GRAB BAR COORDINATION

A. For handicapped plumbing fixtures coordinate location of flush valves with grab bars prior to installation.

1.8. ALTERNATES

A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1. WALL-MOUNTED WATER CLOSETS

A. WC-3A Wall Hung, Exposed, Hard-Wired, Infrared Sensor Flush Valve with Manual Override Button, Handicapped

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Kohler Model K-4325 Kingston
b. American Standard
c. Crane
d. Sloan
e. Zurn

2. Bowl:

a.	Material:	Vitreous china
b.	Type:	Siphon Jet
c.	Style:	Flushometer Valve
d.	Height:	A.D.A. Compliant
e.	Rim Contour:	Elongated
f.	Spud Size; Location:	NPS 1-1/2; Top

3. Flushometer Valve:

   a. Diaphragm Type: Sloan Model Royal #111-ES-S, Delany, Zurn or approved equal.
   b. Chrome plated brass.
   c. Self-Adaptive Hard-wired, infrared sensor for automatic “no hands” operation.
   d. Courtesy flush override button
   e. Non-hold open integral solenoid operator.
   f. Infrared sensor range adjustment.
   g. Initial set-up range indicator light.
   h. Transformer to convert 120-VAC power to 24-VAC control circuit power.
   i. 1-inch I.P.S. screwdriver back check angle stop.
   j. Spud coupling and flange.
   k. Locking vandal resistant stop cap.
   l. Adjustable tail piece.
   m. High back pressure vacuum breaker flush connection with one-piece bottom hex coupling nut.
   n. Sweat solder adapter with cover tube and cast set screw wall flange.
   o. Split Ring Wall Support: Sloan Model J-312-A.
   p. Provide 3-year limited Manufacturer's warranty.]

4. Transformer: One transformer (Sloan Model EL-154) must be provided for each toilet room with five (5) flushometers or less. Additional transformers shall be provided for every five (5) additional flushometers.

5. Seat: Kohler Model K-4670-C, American Standard 5901.100, solid plastic white seat with open front and check hinge.

6. Carrier: Zurn, Josam, or Watts cast iron watercloset Carrier with fittings as required. ANSI/ASME A112.6.1 adjustable cast iron frame integral drain hub and vent, adjustable speed, lugs for floor and wall attachment, threaded fixture studs with nuts and washers.

2.2. WALL-MOUNTED LAVATORIES

A. LAV-3A Wall-Hung, Deck Mounted, Hard-Wired, Infrared Sensor Faucet, Handicapped

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Kohler Model K-2032 Greenwich
    b. American Standard Lucerne
    c. Crane
    d. Zurn

2. Fixture:

    a. Material: Vitreous china
    b. Type: Wall-Hung
    c. Rim Mounting Height: A.D.A. Compliant
    d. Nominal Size: 20-3/4”L x 18-1/4”W
    e. Faucet-Hole Punching: Holes, 4-inch centers
    f. Faucet-Hole Location: Top
    g. Color: White
    h. Mounting Material: Concealed Arm Carrier

3. Faucet:

    a. Chicago Faucet 116.706.AB.1 (0.35 GPM), Sloan, American Standard
    b. Deck Mounted
    c. Sensor and Solenoid above deck within faucet
    d. Low-Flow, vandal-proof outlet
    e. Polished Chrome Finish
    f. 4-inch Spout
    g. Integral check cartridges
    h. Unit shall be A.D.A. Compliant
    i. 12 Volt AC Transformer
    j. Splash-proof circuit control module
    k. Sensor range adjustment screw

4. Strainer:

    a. Chicago Faucet Model 327A, American Standard
    b. 1-1/4-inch tailpiece
    c. Non-removable brass strainer
    d. Grid strainer waste
    e. Chrome plated finished.

5. P-Trap:

    a. Cast Brass 1-1/4-inch "P" trap

6. Stops:

    a. Chicago Faucet Model l005-ABCP valve stops.
    b. 3/8-inch loose key cap
    c. Removable tee handle

d. Wall flange
e. Chrome plated finished.

7. Thermostatic Mixing Valves:

a. Provide and install below fixture.
b. See Part 2 “Thermostatic Mixing Valves”.

8. Carrier:

a. Zurn, Josam, or Watts cast iron and steel carrier.
b. ANSI/ASME A112.6.1
c. Cast iron and steel frame with tubular legs.
d. Lugs for floor and wall attachment.
e. Concealed arm supports.
f. Bearing plate and studs.

9. Lavatory Protective Enclosure:

a. Provide and install Truebro Model # 2018 lav shield lavatory enclosure on all lavatories with sensor operated faucets. Protective enclosure shall be ADA conforming, 20-inch x 18-inch wheel chair accessible. Unit shall have white finish, be constructed of high impact, stain resistant vinyl, and include seven (7) wall anchors.

2.3. MOP SINKS – SERVICE SINKS

A. JS-6 Service Sink

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Kohler Model K-6716
b. American Standard
c. Ceco

2. Fixture:

a. Material: Enameled, Cast Iron
b. Type: Trap Mounted
c. Nominal Basin Size: 24-1/4”x20-1/4”x13”
d. Rim Guard: Stainless Steel
e. Wall Hanger Supports
f. Provide and install stainless steel BP splash Catcher panels on adjacent walls.

3. Faucet:

a. Chicago Faucet 305-VBRCF, American Standard
b. Rough Chrome Finish

c. Vacuum breaker spout
d. Adjustable Stop supply arms
e. 3/4-inch hose thread outlet.
f. Pail Hook
g. Vandal Proof Lever Handles

4. Strainer:

a. Jomar Model SS-306 Snap-N-Loc basket strainer with brass locknut and tailnut.
b. Deep cup body and basket shall be 300 series stainless steel

5. Trap:

a. Kohler Model K-6673, American Standard
b. 3-inch trap standard with cleanout

2.4. COUNTER SINKS

A. S-1A Counter Sink – Single Bowl (Handicapped)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Elkay Manufacturing Co. – Lustertone LRAD Series
b. Just Manufacturing Co.

2. Fixture:

a. Type: Single Bowl, Counter Mounted, Self-Rimming.
b. Overall Dimensions (L x W x D) inches:

15 x 17-1/2 x 5-1/2

c. Material: 302 Stainless Steel, 18 gauge, fully coated underside.

3. Faucet:

a. Standard: ASME A112.18/CSA B125.1
b. General: Include hot and cold water indicators; coordinate faucet inlets with supplies and fixture hold punchings; coordinate outlet with spout and sink receptor.
c. Model: Chicago Faucet Model 201-AGN8AE3-317ABCP
d. Body Type: Centerset, 8” fixed centers
e. Finish: Chrome Plated
f. Handle(s): Model 317 Wrist Blade Handles, A.D.A. Compliant
g. Mounting Type: Deck, concealed.
h. Spout Type: Swivel gooseneck.
i. Spout Outlet: E3 Aerator

4. Strainer: Jomar Model SS-306 Snap-N-Loc, or Just J-35 basket strainer and brass locknut and tailnut. Deep cup body and basket shall be 300 series stainless steel. Provide 1 ½-inch tailpiece.

5. P-Trap: Cast Brass 1 ½ -inch "P" trap.

6. Stops: Chicago Faucets Model 1005ABCP valve stops with riser supply, 3/8-inch loose key cap and removable tee handle, wall flange, chrome plated finish.

B. S-4A Counter Sink – Double Bowl (Handicapped)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Elkay Manufacturing Co. – Lustertone LRAD Series
   b. Just Manufacturing Co.

2. Fixture:

   a. Type: Double Bowl, Counter Mounted, Self-Rimming.
   b. Overall Dimensions (L x W x D) inches:

      29 x 18 x 5-1/2

   c. Material: 304 Stainless Steel, 18 gauge, fully coated underside.

3. Faucet:

   a. Standard: ASME A112.18/CSA B125.1
   b. General: Include hot and cold water indicators; coordinate faucet inlets with supplies and fixture hold punchings; coordinate outlet with spout and sink receptor.
   c. Model: Chicago Faucet Model 201-AGN8AE3-317ABCP
   d. Body Type: Centerset, 8” fixed centers
   e. Finish: Chrome Plated
   f. Handle(s): Model 317 Wrist Blade Handles, A.D.A. Compliant
   g. Mounting Type: Deck, concealed.
   h. Spout Type: Swivel gooseneck.
   i. Spout Outlet: E3 Aerator
   j. Sprayer: Provide 4 ft. of vinyl nylon netted hose and hand held hose spray.

4. Strainer: Jomar Model SS-306 Snap-N-Loc, or Just J-35 basket strainer and brass locknut and tailnut. Deep cup body and basket shall be 300 series stainless steel. Provide 1 ½-inch tailpiece.

5. Stops: Chicago Faucets Model 1005ABCP valve stops with riser supply, 3/8-inch loose key cap and removable tee handle, wall flange, chrome plated finish.

6. Plaster Trap: Gleco or approved equal plaster trap in lieu of fixture “P”-trap. Unit shall by polypropylene with 19 oz. storage bottle, integral trap, unions and ball type drain valve. Furnish each sink with spare gasket and spare replacement bottle. Provided by dental equipment provider.

2.5. EMERGENCY FIXTURES

A. EM-4 Emergency Eyewash (Table/Deck Mounted Drench Hose)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Bradley S19-465

   b. Water Saver EW1022

   c. Guardian G5022

   d. Approved Equal

2. Fixture:

   a. Unit and installation shall comply with ANSI Z358.1, ANSI A117.1 and ADA latest edition.

   b. 8-foot reinforced high pressure PVC hose, 275 PSI maximum working pressure.

   c. Chrome plated brass spray head assembly.

   d. Twin angled soft flow eye wash heads with dust covers.

   e. Squeeze valve activated by stainless steel lever handle. Locking clip engages when handle is depressed, providing hands free operation.

   f. Unit to be mounted on Counter next to sink. Furnish with deck flange with handle holder.

   g. Provide and mount universal identification sign.

3. Units shall be tested per ANSI Z358.1 prior to turning over to Owner. Contractor shall train Owner in proper usage per Manufacturer's Instructions and ANSI requirements.

4. Furnish each unit with all equipment necessary for field testing of emergency fixtures per ANSI Z358.1 requirements.

5. Refer to Part 2 “Products” of this section for Emergency Mixing Valve.

6. Furnish with flow switch including local audible/visual alarm and interlock to the building management system.

7. Furnish and install solid state signaling system flow switch for drench shower emergency fixtures; 85dB horn, green/amber LED beacon, and double pole, double throw flow switch 1/2 inch NPT, 24VDC; remote building management system compatible; recessed NEMA 1 General Purpose interior use enclosure for electrical components.

2.6. OUTLET BOXES – WATER SUPPLY

A. OB-1 Refrigerator

1. Refrigerator provided in another Division of Specifications. Provide rough-in, Outlet box and final connections under this Division.

2. Sioux Chief: Model No. 696-RG1010MF with top supply and shut-off valve with water hammer arrester. Provide flexible hose (1/2-inch) between Refrigerator and outlet box. Provide vacuum breaker on threaded outlets to prevent back siphonage. Unit shall be 16-gauge steel with white epoxy finish.

3. Provide sufficient copper tubing to allow movement of refrigerator for cleaning.

B. OB-2 Coffee Maker

1. Coffee Maker provided in another Division of Specifications. Provide rough-in, Outlet box and final connections under this Division.

2. Sioux Chief: Model No. 696-RG1010MF with top supply and shut-off valve with water hammer arrester. Provide flexible hose (1/2-inch) between Coffee Maker and outlet box. Provide vacuum breaker on threaded outlets to prevent back siphonage. Unit shall be 16-gauge steel with white epoxy finish.

3. Provide sufficient copper tubing to allow movement of coffee maker for cleaning.

2.7. HOSE BIBBS - HYDRANTS

A. HB-1 Hose Bibb

1. Chicago Faucet No. 952 or approved equal hose and faucet. Bronze or brass with integral mounting flange, replaceable hexagonal disc, hose threaded spout, polished chrome plated where exposed in finished areas, with hand wheel and removable key, integral vacuum breaker in conformance with ANSI/ASSE 1011.

2. Hose bibbs in finished areas shall be polished chrome finish.

3. Approved Manufacturers: Chicago Faucet, American Standard, Crane, T&S Brass, or Watts.

2.8. FLOOR DRAINS

A. General Requirements

1. Provide Nikaloy strainers on all floor drains unless specified otherwise.

2. Provide flashing clamps on all drains penetrating waterproofing membrane.

3. Provide suitable flashing material and clamping collar for drains which are not set in place when slab is poured.

4. Provide backwater valves for all floor drains connecting directly to the storm water system. Depending on conditions of the particular installation, backwater valves may be an integral part of the drains or a separate device. Accessibility to valves must be maintained for maintenance. Provide an adequately sized extension sleeve up to floor or grade as required.

5. Backwater valves are normally closed, flapper type with bronze or brass seat and disc and stainless steel pin.

6. Provide traps for all floor drains connected to the sanitary system.

7. Provide E & S, Sioux Chief, or PPP primer valve (one valve per trap, per floor drain) on all remote floor drains. When installed on fixture in finished area, primer valve shall be concealed behind a Josam 58650, Watts, or Zurn access door. In Mechanical Rooms, mezzanines, penthouses, and all other locations indicated on the contract drawing, priming lines shall be connected to automatic trap primer.

8. In lieu of joints specified in piping section, neoprene gaskets may be used if designed for use with the drains and cleanouts employed and if approved by the local plumbing authority.

9. When floor drains collect condensate from a neutralizer kit, the floor drains shall be provided with epoxy coating.

10. Approved Manufacturers: Josam, J.R. Smith, Zurn, Wade, Ancon, Mifab, Watts.

B. FD-1 Floor Drain – Round – Nickel Bronze Strainer

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Zurn ZN-415B

b. Watts FD-100-A

2. Floor and shower drain, dura coated cast iron body with bottom outlet, combination invertible membrane clamp and adjustable collar with seepage slots and Type "B" polished nickel bronze strainer. Provide with ½ -inch trap primer connection.

2.9. FLOOR SINKS

A. FS-1 Floor Sink (8”x8”x6”)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Zurn Z-1910
b. Watts

2. Sani-Flor receptor, 8-inch x 8-inch x 6-inch deep cast iron body and square slotted medium duty grate, with white acid resisting coated interior and top, complete with aluminum anti splash interior bottom dome strainer.

a. Two (2) removable ½ grates with each unit.
b. ½ -inch trap primer connection.
c. Stainless steel mesh bucket screen.

B. FS-3 Floor Sink (12”x12”x8”)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Zurn Z-1901
b. Watts FS-740

2. Sani-Flor receptor, 12-inch x12-inch x 8-inch deep cast iron body and square, slotted grate with white acid resisting coated interior and top, complete with aluminum anti splash interior bottom dome strainer.

a. Two (2) removable ½ grates with each unit.
b. ½ -inch trap primer connection.
c. Stainless steel mesh bucket screen.

2.10. THERMOSTATIC MIXING VALVES (INDIVIDUAL FIXTURE TYPE)

A. Furnish and install thermostatic mixing valves at all lavatories and sinks.

B. Thermostatic mixing valves shall be Bradley S59-4000A, Watts, Moen, Leonard Eco-Mix, Acorn, Caleffi, or approved equal for installation under lavatories. Provide in-line check valves, lead free body, escutcheon plates, inlet filters, and insulation as required. Thermostatic mixing valves shall be adjusted to deliver

105 degrees Fahrenheit hot water when supplied with 140 degrees Fahrenheit hot water. Furnish with adjusting cap with locking feature.

C. The thermostatic mixing valves shall be listed for use at the scheduled flow rate of the equipment served.

D. The thermostatic mixing valves shall be ASSE standard 1070 listed.

2.11. PLUMBING FIXTURE SUPPORTS

A. Wall mounted urinal supports, Josam 17810 plate type with cast iron headers, box steel stanchions, block type cast iron feet with bearing plate.

B. Support for wall mounted urinals, lavatories, sinks, drinking fountains, etc.:

C. Where fixtures are supported from concrete or cinder block walls, install No.10 USSG Steel plate on the opposite side of the wall and bolt hangers or supports through plate. Where opposite side of wall is exposed to view, place bolts in core of blocks and fill core with cement.

D. Where lavatories with wall hangers have been specified and fixtures are supported from metal stud frame partitions, fixture brackets or mounting lugs shall be through bolted to steel channel crosspieces not less than 1-1/2-inch wide anchored to studs. Bolt heads shall be welded to channel web.

E. Concealed arm type lavatory supports, Josam 17100 with cast iron headers, box steel stanchions, block type cast iron feet and header; and chrome plated cast brass threaded escutcheons for slab type lavatories.

F. Flush mounted drinking water cooler supports, Josam 17550 plate type, box steel stanchions, block type cast iron feet.

G. Water closet chair carriers, Josam 12000 Series for horizontal and vertical installations.

2.12. HANDICAPPED LAVATORY/SINK INSULATION

A. All handicapped lavatories and sinks shall be provided with under counter pipe and trim insulation.

B. Insulation shall be fully molded "P" trap and angle valve insulated Hand-I-Lav Guard, Truebro, Pro-Extreme Model #101, 102, and 105 to suit.

C. Insulation to meet ADA #4 19.4, ANSI A117.1, ASTM C1822, Type III and International Plumbing Code.

D. Self-extinguishing ASTM D635 burn characteristics, thermal conductivity ASTM C177 K-Value ' 1.17.

E. Insulation thickness to be minimum 2 inch.

F. Where lav. Guards are provided insulation may be omitted.

2.13. EMERGENCY EYEWASH MIXING VALVES

A. Furnish and install factory fabricated, hot-and cold-water-tempering equipment with thermostatic mixing valve. Units shall be manufactured by Guardian Equipment, Power's, Speakman, Leonard or approved equal.

B. Thermostatic mixing valve: Designed to provide 85 degree F (29 degree C) tepid, potable water at emergency eyewash stations to maintain temperature at plus or minus 5 degree F (3 degree C) throughout required 15-minute test period, and in case of unit failure to continue cold-water flow with Union connections, controls, integral strainer, metal piping adjustable high temperature unit, outlet and inlet, thermometers, check stops and where indicated a corrosion resistant enclosure.

C. Capacity Range: As scheduled on Contract Drawings.

D. Furnish each unit with painted, heavy duty mounting bracket from securing valve to panel on wall. Cabinet shall be (surface mounted) stainless steel, lockable type.

E. Units shall be provided such that inlets can be rotated 360 degrees for top or bottom supply.

F. Comply with ANSI requirements and lead free law per the requirements of the state in which the project is being constructed.

G. Emergency fixture mixing valves shall be ASSE 1071 compliant.

2.14. FIXTURE STOPS/SUPPLIES

A. For all lavatories/sinks stops and supplies shall be Chicago Faucets No. 1017-CR43829, Angle Stop Fitting with Supply Tube and Loose Key, Chrome plated solid brass construction. 2-1/4" Metal tee handles with tapered square. Slow compression check cartridge that shall open and close 360º for fine adjustment, valves shall close with water pressure, furnish with square tapered stem. ½" NPT female thread inlet 3/8" O.D. female compression outlet. Slip wall flange. 3/8" O.D. x 12" bullnose flexible supply riser. ECAST construction with less than 0.25% lead content by weighted average. This product shall be tested and certified to industry standards: ASME A112.18.1/CSA B125.1, Certified to NSF/ANSI 61, Section 9 by CSA, California Health and Safety Code 116875 (AB1953-2006), Vermont Bill S. 152, and NSF/ANSI 372 Low Lead Content.

PART 3 - EXECUTION

3.1. GENERAL INSTALLATION REQUIREMENTS

A. Install all equipment in accordance with manufacturer's instructions.

B. Setting heights of lavatories, drinking fountains, etc., shall be as directed prior to installation and shall be coordinated with Architectural Contract Documents.

C. Install floor mounted fixtures only after finished floor has been installed.

D. Provide rubber concussion washers between vitreous china fixtures and supporting brackets.

E. Protect chromium plated trim from corrosive solutions used to clean tile work.

F. Provide white, silicone caulking where fixtures come in contact with walls and floors. Sealant shall be mildew resistant type in accordance with ANSI A-136.1.

G. Install components plumb and level.

H. Unless otherwise noted, drains are to be installed at the low point of floors. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.

I. Install floor drains in low points so the top of grates are at or below the finished floor level.

J. Drains not functioning properly shall be removed and re-installed properly at the expense of the contractor.

K. Coordinate cutting and forming of roof and floor construction to receive drains to required invert elevations.

L. Install and secure fixtures in place with wall supports, wall carriers and bolts.

M. Solidly attach water closets to floor with lug screws. Lead flashing is not intended to hold fixture in place.

N. Install flush valve handles on the open side of all ADA waterclosets in accordance with ANSI requirements.

O. Fixtures shall be vitreous china unless otherwise noted. Cast iron fixtures shall have acid resisting enamel finish unless noted otherwise, color shall be white.

P. Flush valves shall be self-closing, non-hold open type with vacuum breaker and perform satisfactorily when subject to inlet water pressure varying from 15 to 75 psi. Flush valves shall be as specified, Sloan, Delaney, Zurn, Toto, or approved equal.

Q. Provide flexible risers and loose key stops for all lavatories and sinks. Provide 17 ga. chrome plated brass tail piece and trap with cleanout for all lavatories and sinks.

R. Fittings for fixtures supplied by others, such as equipment, are provided under another division of these specifications. Connections of these fixtures to the plumbing system are provided under this section.

S. Coordinate with plumbing piping and related fuel piping, gas venting and electrical work to achieve a complete operating system.

T. Field test all emergency eyewash units per ANSI Z358.1 latest edition.

U. All plumbing vents within a 10'-0" radius of exhaust vents shall be extended to a height of 3'-0" above exhaust vent crown.

V. All plumbing vents within a 10'-0" radius of any rooftop unit or intake louver shall be extended to a height of 3'-0" above fresh air intake.

W. Slopes and invert elevations of all interior piping shall be established before any piping is installed in order that proper slopes will be maintained. All piping shall be located and determined where to be run to avoid conflict with other trades.

X. Unless otherwise noted, all plumbing piping shall be routed as high as possible between bottom of roof joists and above ceiling to allow proper installation of ductwork, fire protection piping, conduits, etc.

Y. Coordinate with Architectural Drawings before roughing in plumbing.

Z. All openings in ceilings and plenum walls for plumbing shall be sealed air tight and protected with fire stop.

AA. See site plan for extent of all piping leaving and entering building.

BB. See domestic water riser diagrams for location of valves, shock absorbers, etc.

CC. Make proper hot water, cold water, hot water recirculating, waste, and vent connections to all fixtures and equipment even though all branch main, elbows and connections are not shown.

DD. Unless otherwise noted, sanitary waste piping shown is below floor and all other piping is overhead, above ceiling. Domestic hot, cold and recirculating water piping shall be installed between ceiling and attic insulation.

EE. Unless otherwise noted, horizontal sanitary piping shall be pitched 1 percent.

FF. Unless otherwise noted, all domestic water piping and fire protection piping shall be installed on heated side of ceiling insulation.

GG. All piping and installation shall comply with all local and national plumbing codes. Test piping as required by plumbing code and authority having jurisdiction.

HH. For sizes of all domestic water piping see plumbing fixture schedule and domestic water riser diagrams.

II. For sizes of all sanitary and vent piping see plumbing fixture schedule and sanitary/vent riser diagrams.

3.2. PLUMBING SPECIALTY INSTALLATION REQUIREMENTS

A. General: Install plumbing specialty components, connections, and devices according to manufacturer's written instructions.

B. Fasten recessed, wall-mounting plumbing specialties to reinforcement built into walls.

C. Secure supplies to supports or substrate.

D. Install individual stop valve in each water supply to plumbing specialties. Use ball, gate, or globe valve if specific valve as appropriate is not indicated.

E. Install water-supply stop valves in accessible locations.

F. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.

G. Include wood-blocking reinforcement for recessed and wall-mounting plumbing specialties.

3.3. FITTINGS FOR FIXTURES SUPPLIED BY OTHERS

A. Fixtures such as built-in-sink in counters and equipment may be provided under other divisions of the specifications and are complete with strainer and tailpiece. Fittings, accessories and connection of these fixtures to the plumbing system are provided under this section.

B. Rough-in and final connection includes but is not limited to all domestic water, waste, vent, dental vacuum and dental compressed air systems. Furnish stops, strainers, vacuum breakers, and under counter insulation where not furnished under another Division of these specifications.

3.4. TESTING

A. After plumbing fixtures are connected, all piping and fixtures shall be tested for operation and a smoke or peppermint test shall be made on all soil, waste and vent piping.

B. After the building has been occupied and the various equipment is in actual use, the Contractor shall make an operating test of all equipment at a time directed by

the Engineer to determine that all contract requirements are met.

3.5. CLEANING AND STERILIZATION

A. After final testing for leaks, all potable water lines shall be thoroughly flushed, by plumbing contractor, to remove foreign material. Before placing the systems in service, sterilize the new water lines in accordance with local health department codes and at a minimum according to the following procedure:

B. Through a 3/4-inch hose connection in each branch main and building main, pump in sufficient sodium hypochlorite to produce a free available chlorine residual of not less than 200 ppm. Plumbing Contractor shall provide plumbing connections and power for pumping chlorine into system.

C. Proceed upstream from the point of chlorine application opening all faucets and taps until chlorine is detected. Close faucets and taps when chlorine is evident.

D. When chlorinated water has been brought to every faucet and tap with a minimum concentration of 200 ppm chlorine, retain this water in the system for at least three (3) hours.

E. CAUTION: Over-concentration of chlorine and more than three (3) hours of retention may result in damage to piping system. It is not necessary to retain chlorine in any system for twenty-four hours to achieve sterilization. AWWA states that 200 ppm chlorine for three hours is sufficient.

F. At the end of the retention period, no less than 100 ppm of chlorine shall be present at the extreme end of the system.

G. Proceed to open all faucets and taps and thoroughly flush all new lines until the chlorine residual in the water is less than 1.0 ppm.

H. Obtain representative water sample from the system for analysis by an independent and recognized bacteriological laboratory.

I. If the sample tested for coliform organisms is negative, a letter and laboratory report shall be submitted by the service organization to the Contractor, certifying successful completion of the sterilization. Additionally, this report shall be forwarded to the Owner as well as be included in the O&M Manual.

J. If any samples tested indicate the presence of coliform organisms, the entire sterilization procedure shall be repeated.

K. Take precautions to avoid use of plumbing fixtures and domestic water systems during sterilization period. Place signs on all plumbing fixtures and outlets during sterilization period.

3.6. EXAMINATION

A. Verify that walls and floor finishes are prepared and ready for installation of fixtures.

B. Verify that electric power is available and of the correct characteristics.

3.7. PREPARATION

A. Review the equipment cut sheets. Confirm rough-in location and size of fixtures and openings prior to commencing work.

B. Rough-in fixture piping connections in accordance with minimum sizes indicated in fixture rough-in schedule for particular fixtures.

3.8. INTERFACE WITH OTHER PRODUCTS

A. Review millwork shop drawings. Confirm location and size of fixtures and openings before rough-in and installation.

3.9. ADJUSTING

A. Adjust stops, valves, infrared fixtures for intended water flow rate to fixtures without splashing, noise, or overflow.

B. Test the time it takes to achieve hot water at all Plumbing Fixtures and adjust thermostatic mixing valves to deliver 105°F water at all faucets. Submit test results.

3.10. CLEANING

A. At completion, clean plumbing fixtures and equipment. Polish all chrome plated faucets, accessories, equipment, and piping.

B. All electric water cooler coils shall be cleaned of all construction dust and debris prior to building occupation by Owner.

3.11. FIXTURE HEIGHTS

A. Install fixtures to heights above finished floor as required by local Plumbing Code, Americans with Disabilities Act (A.D.A.), Authority Having Jurisdiction, and Architectural Contract Drawings. In the absence of a local code requirements, install fixtures to heights above finished floor as follows.

B. Water Closet

a. Standard 15 inches to top of bowl rim.
b. Handicapped 18 inches to top of seat.

C. Lavatory

a. Standard 31 inches to top of basin rim.
b. Handicapped 34 inches to top of basin rim.

D. Water Closet Flush Valves

a. Standard 11 inches min above bowl rim.
b. Recessed 10 inches min. above bowl rim.

E. Emergency Eye Wash

a. Handicapped 38-inches to receptor rim.

END OF SECTION 224000

SECTION 224005 - PLUMBING EQUIPMENT

PART 1 - GENERAL

1.1 GENERAL

A. For General Mechanical Requirements, see Division 22 Section, Common Work Results for Plumbing & Division 01, General Requirements.

B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 specifications apply to this Section.

C. All exposed bolts, screws, etc., shall be vandal proof.

D. All plumbing materials and equipment shall be new and of best grade, free of defects and complete with all required appurtenances and accessories.

E. Piping and insulation are specified under other sections.

F. Provide all materials, equipment and perform all labor required to install plumbing system complete as specified, as drawings indicated and as required by the State of Delaware, Town of Georgetown Code, the local code, and all other authorities have jurisdiction.

G. Provide stops for all plumbing equipment. Stops are to be accessible.

H. Provide pumps with manufacturer's name, model number, and rating/capacity identified.

I. Ensure products and installation of specified products are in conformance with recommendations and requirements of the following organizations:

1. American Gas Association (AGA).

2. National Sanitation Foundation (NSF).

3. American Society of Mechanical Engineers (ASME).

4. National Electrical Manufacturers' Association (NEMA).

5. Underwriters Laboratories (UL).

1.2 REFERENCES

A. ANSI/ASSE 1011 - Hose Connection Vacuum Breakers.

B. ANSI/ASSE 1012 - Backflow Preventers with Immediate Atmospheric Vent.

C. ANSI/ASSE 1013 - Backflow Preventers, Reduced Pressure Principle.

D. ANSI/ASE 1019 - Wall Hydrants, Frost Proof Automatic Draining Anti-Backflow Types.

E. ANSI A112.21.1 - Floor Drains.

F. ANSI A112.26.1 - Water Hammer Arrestors.

G. AWWA C506 - Backflow Prevention Devices - Reduced Pressure Principle and Double Check Valve Types.

H. PDI WH-201 Water Hammer Arresters.

I. ANSI/ASHRAE 90A - Energy Conservation in New Building Design.

J. ASME Section VIIID - Pressure Vessels; Boiler and Pressure Vessel Codes.

K. ANSI/NFPA 70 - National Electrical Code.

L. ANSI/NEMA 250 - Enclosure for Electrical Equipment (1000 Volts Maximum).

M. IBC - International Building Code

1.3 DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, protect and handle products to site under provisions of General Requirements.

B. Accept equipment on site in factory packaging. Inspect for damage.

C. Protect installed equipment from damage by securing areas and by leaving factory packaging in place to protect equipment and prevent use.

1.4 FIELD MEASUREMENTS

A. Verify that field measurements are as indicated on shop drawings and per the manufacturer.

1.5 ALTERNATES

A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1 CLEANOUTS

A. Provide cleanouts in sanitary and storm drainage systems at ends of runs, at changes in direction, near the base of stacks, every 50 feet in horizontal runs, of 4-inch diameter or less, every 100 feet in horizontal runs over 4-inches, and where indicated.

B. Cleanouts shall be full size of pipe up to 4-inches and shall be 4-inches for larger sizes. Where installed in finished floors inserts shall match adjacent floor construction.

C. Materials and Approved Manufacturers: Josam, J.R. Smith, Zurn, Wade or Ancon, Mifab, Watts, equal to Josam numbers given below:

1.	Concealed Piping	C.I. Pipe
2.	Unfinished Areas	C.I. Pipe
3.	Floors	57000-Z-CI
4.	Walls	58600-PLG
5.	Finished Areas – Floors	57000-Z-CI
6.	Terrazzo	56040-13
7.	Composition Tile	57000-X-12
8.	Ceramic Tile	57000-X
9.	Carpet	56070-14
10.	Carpet insert to match adjacent carpet in type, color and grade.	
11.	Finished Areas – Walls	58600-PLG
12.	Plaster/Dry Wall	58640-COT
13.	Tile/CMU	58600-COT

2.2 SHOCK ABSORBERS

A. Provide shock absorbers equal to Josam Shokstops at all fast closing valves, at the top of all cold water risers, at each flush valve or battery of flush valves, and where indicated. Sizes and locations shall be in accordance with PDI Standard WH 201.

B. Shock absorbers shall conform to ANSI A112.26.1, precharged suitable for operation in temperature range -100 to 300 degrees F and maximum 250 psig working pressure.

C. Approved Manufacturers: Josam, Wade, Zurn, J.R. Smith, Sioux Chief, Watts, or approved equal.

2.3 VACUUM BREAKERS

A. Provide vacuum breakers on water connections to fixtures and equipment where minimum air gaps required by Plumbing Code are not possible and on hose bibbs and other outlets to which hoses can be attached.

B. Vacuum breakers not subject to back pressure, Watts No. 288A; vacuum breakers subject to back pressure, Watts Series 9D or for hose threads, Watts Series 8A.

C. Hose connection backflow preventers shall be ASSE 1052, suitable for at least 5 gpm flow and applications with up to 10 foot head back pressure. Include two (2) check valves, intermediate atmospheric vent, and non-removable, ASME B1.20.7 garden-hose thread on outlet.

D. Hose connection vacuum breakers shall be ASSE 1011, nickel plated, with nonremovable and manual drain features, and ASME B1.20.7 garden-hose threads on outlet. Units attached to rough-bronze finish hose connections may be rough bronze.

E. Approved manufacturers: Watts, Beeco, B&K Industries, Zurn, Sparco, Conbraco or approved equal.

2.4 TRAP PRIMING STATION-LARGE AUTOMATIC TRAP PRIMER

A. Trap priming stations shall be Precision Plumbing Products, Inc., Electronic Trap Priming manifold Model PT, MIFAB, Sioux Chief, Watts, or approved equal. The manifold shall supply a minimum of 2 ounces of potable water per opening at 20 PSIG once in each 24 hour period. The Electronic Trap Priming Manifold must be capable of equally priming from 4 through 30 individual floor drain traps.

B. The unit shall be factory assembled and prepiped, and shall include a bronze body 3/4-inch female NPT WOG rated ball valve 3/4-inch, Water Hammer Arrestor, copper barrel with brass piston and type "L" copper sweat connection, electronic brass body 3/4-inch solenoid valve, and type "L" copper manifold with brass 2-inch compression fitting and orifice opening for precision water distribution to each floor drain trap. Unit shall be pre-piped with atmospheric vacuum breaker.

C. Electronic components shall include single point power connection at 120 volt 1 phase 60 hertz, manual over-ride switch, minimum 5 amp breaker, 24 hour geared timer with relay and 5 second dwell function. Separate water hammer arrestor can be provided outside station if integral arrestor is not available.

D. All components shall be factory assembled, tested and supplied in a 16 gauge steel
NEMA 1 enclosure suitable for surface or recess mounting, as indicated on contract drawings. In addition, all components must comply with nationally recognized standards. The Precision Plumbing Products Electronic Trap Priming Manifold shall be fully warranted for the life of the plumbing system.

E. When only a single trap primer is required, as in the case of a restroom with one floor drain in a toilet (or similar) the contractor may submit, in lieu of an electronic multiple station, a single station for review by the Engineer. The fixture serving the trap primer must be within 10' of the trap. Components shall be brass, bronze, and chrome, of the highest quality.

F. Access door shall be finished with a prime coat and fire rated where installed in a rated wall. Access door latch shall be Allen key type.

2.5 BACKFLOW PREVENTER (DOUBLE CHECK VALVE ASSEMBLY TYPE)

A. Furnish and install double check valve assembly backflow preventers at all cold water make-up connections to washdown for dental vacuum and where else indicated on contract documents.

B. The assembly shall consist of two positive seating check modules with captured springs and rubber seat discs. The check module sets and seat discs shall be replaceable.

C. Service of all internal components shall be through a single access cover secured with stainless steel bolts. The assembly shall include two resilient seated isolation valves and four top mounted, resilient seated test cocks.

1. Furnish each backflow preventer with the following accessories and options:

a. bronze strainer
b. quarter turn, full port, resilient seated ball valve shut-off
c. union connections

D. Provide minimum 18-inch clearance for servicing and testing.

E. The assembly shall meet the requirement of ASSE Std 1015 and AMCA Std C510.

F. Double check valve backflow preventers shall be Watts No. 007, Conbraco, Wilkens, Ancon, or approved equal.

G. Furnish test kit for field testing units. Watts Model TK-9A Analog Differential Gauge or approved equal.

PART 3 - EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

A. Install all equipment in accordance with manufacturer's instructions.

B. Install components plumb and level.

C. Cleanouts in vertical pipes shall be installed in tees near floor. Cleanouts in horizontal pipes shall be installed with wyes on long sweep quarter beds. Cleanouts punching water proofing membranes shall have flashing clamps. Cleanout access covers in dry wall or gypsum board shall be painted to match walls.

D. Extend cleanouts to finish floor or wall surface. Lubricate threaded cleanout plugs with mixture of graphite and linseed oil. Ensure clearance at cleanout for rodding of drainage system.

E. Encase exterior cleanouts in concrete flush with grade.

F. All plumbing, vents in exterior walls shall be offset a minimum of 3'-0" in ceiling at roof before penetration.

G. All plumbing vents within a 10'-0" radius of exhaust vents shall be extended to a height of 3'-0" above exhaust vent crown.

H. All plumbing vents within a 10'-0" radius of any rooftop unit or intake louver shall be extended to a height of 3'-0" above fresh air intake.

I. Slopes and invert elevations of all interior piping shall be established before any piping is installed in order that proper slopes will be maintained. All piping shall be located and determined where to be run to avoid conflict with other trades.

J. Unless otherwise noted, all plumbing piping shall be routed as high as possible between bottom of roof joists and above ceiling to allow proper installation of ductwork, fire protection piping, conduits, etc.

K. Coordinate with Architectural Drawings before roughing in plumbing.

L. All openings in ceilings and plenum walls for plumbing shall be sealed air tight and protected with fire stop.

M. See site plan for extent of all piping leaving and entering building.

N. See domestic water riser diagrams for location of valves, shock absorbers, balance valves, etc.

O. Make proper Hot Water, Cold Water, Hot Water recirculating, waste, and vent connections to all equipment even though all branch main, elbows and connections are not shown.

P. Cleanouts shall be provided near base of each vertical waste or solid stack. Provide 18" minimum clearance for access.

Q. Domestic hot, cold, and HW recirculating water piping shall be installed between ceiling and roof insulation.

R. Unless otherwise noted, horizontal sanitary piping pitches shall be 1 percent.

S. Unless otherwise noted, all domestic water piping and fire protection piping shall be installed on heated side of ceiling insulation.

T. All piping and installation shall comply with all local and national plumbing codes. Test piping as required by plumbing code and authority having jurisdiction.

U. For sizes of all domestic water piping see plumbing fixture schedule and domestic water riser diagrams.

V. For sizes of all sanitary and vent piping see plumbing fixture schedule and sanitary/vent riser diagrams.

3.2 PLUMBING SPECIALTY INSTALLATION REQUIREMENTS

A. General: Install plumbing specialty components, connections, and devices according to manufacturer's written instructions.

B. Install backflow preventers of type, size, and capacity indicated, at each water supply connection to mechanical equipment and systems, and to other equipment and water systems as indicated. Comply with authorities having jurisdiction. Locate backflow preventers in same room as connected equipment. Install air gap fitting on units with atmospheric vent connection and pipe relief outlet drain to nearest floor drain. Do not install bypass around backflow preventer. Label all piping downstream of backflow preventers as "non-potable" water.

C. Field test all backflow preventers and submit test reports to Engineer. Furnish test kits as required for field testing.

D. Install pressure regulators with inlet and outlet shutoff valves and balance valve bypass. Install pressure gages on inlet and outlet.

E. Install strainers on supply side of each control valve, pressure regulator, and solenoid valve, and where indicated.

F. Install hose bibbs with integral or field installed vacuum breaker.

G. All hose bibs shall be mounted 18" above finished floor, unless otherwise specified.

H. Install trap priming stations plumb and level with adequate access for servicing and maintenance.

I. For all trap primer pipes label the same as to the location of the floor drain served.

J. Install trap priming stations plumb and level with adequate access for service and maintenance.

K. Fasten recessed, wall mounting plumbing specialties to reinforcement built into walls.

L. Secure supplies to supports or substrate.

M. Install individual stop valve in each water supply to plumbing specialties. Use ball, gate, or globe valve if specific valve as appropriate is not indicated.

N. Install water supply stop valves in accessible locations.

O. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep pattern escutcheons if required to conceal protruding pipe fittings.

P. Include wood blocking reinforcement for recessed and wall mounting plumbing specialties.

Q. Install ball valves at all shock absorbers to allow removal for service/replacement.

3.3 FITTINGS FOR FIXTURES SUPPLIED BY OTHERS

A. Fixtures such as built in sink in counters are provided under other divisions of the specifications and are complete with strainer and tailpiece. Fittings, accessories and connection of these fixtures to the plumbing system are provided under this section.

B. Rough-in and final connection includes but is not limited to all domestic water, waste, and vent, and dental compressed air/vacuum systems. Furnish stops, strainers, vacuum breakers, and under counter insulation where not furnished under another Division of these specifications.

3.4 TESTING

A. After plumbing fixtures are connected, all piping and fixtures shall be tested for operation and a smoke or peppermint test shall be made on all soil, waste and vent piping.

B. After the building has been occupied and the various equipment is in actual use, the Contractor shall make an operating test of all equipment at a time directed by the Engineer to determine that all contract requirements are met.

3.5 CLEANING AND STERILIZATION

A. After final testing for leaks, all potable water lines shall be thoroughly flushed, by plumbing contractor, to remove foreign material. Before placing the systems in service, sterilize the new water lines in accordance with local health department codes and at a minimum according to the following procedure:

1. Through a 3/4-inch hose connection in each branch main and building main, pump in sufficient sodium hypochlorite to produce a free available chlorine residual of not less than 200 ppm. Plumbing Contractor shall provide plumbing connections and power for pumping chlorine into system.

2. Proceed upstream from the point of chlorine application opening all faucets and taps until chlorine is detected. Close faucets and taps when chlorine is evident.

3. When chlorinated water has been brought to every faucet and tap with a minimum concentration of 200 ppm chlorine, retain this water in the system for at least three (3) hours.

4. CAUTION: Over-concentration of chlorine and more than three (3) hours of retention may result in damage to piping system. It is not necessary to retain chlorine in any system for twenty-four hours to achieve sterilization. AWWA states that 200 ppm chlorine for three hours is sufficient.

5. At the end of the retention period, no less than 100 ppm of chlorine shall be present at the extreme end of the system.

6. Proceed to open all faucets and taps and thoroughly flush all new lines until the chlorine residual in the water is less than 1.0 ppm.

7. Obtain representative water sample from the system for analysis by an independent and recognized bacteriological laboratory.

8. If the sample tested for coliform organisms is negative, a letter and laboratory report shall be submitted by the service organization to the Contractor, certifying successful completion of the sterilization. Additionally, this report shall be forwarded to the Owner as well as be included in the O&M Manual.

9. If any samples tested indicate the presence of coliform organisms, the entire sterilization procedure shall be repeated.

10. Take precautions to avoid use of plumbing fixtures and domestic water systems during sterilization period. Place signs on all plumbing fixtures and outlets during sterilization period.

3.6 EXAMINATION

A. Verify that walls and floor finishes are prepared and ready for installation of fixtures.

B. Verify that electric power is available and of the correct characteristics.

3.7 PREPARATION

A. Review the equipment cut sheets. Confirm rough-in location and size of fixtures and openings prior to commencing work.

B. Rough-in fixture piping connections in accordance with minimum sizes indicated in fixture rough-in schedule for particular fixtures.

3.8 INTERFACE WITH OTHER PRODUCTS

A. Review millwork shop drawings. Confirm location and size of fixtures and openings before rough-in and installation.

3.9 CLEANING

A. At completion, clean plumbing equipment.

3.10 BACKFLOW PREVENTER (DOUBLE CHECK VALVE ASSEMBLY TYPE)

A. Furnish and install double check valve assembly backflow preventers at all cold water make-up connections to washdown for dental vacuum and where else indicated on contract documents.

B. The assembly shall consist of two positive seating check modules with captured springs and rubber seat discs. The check module sets and seat discs shall be replaceable.

C. Service of all internal components shall be through a single access cover secured with stainless steel bolts. The assembly shall include two resilient seated isolation valves and four top mounted, resilient seated test cocks.

1. Furnish each backflow preventer with the following accessories and options:

    a. bronze strainer
    b. quarter turn, full port, resilient seated ball valve shut-off
    c. union connections

D. Provide minimum 18-inch clearance for servicing and testing.

E. The assembly shall meet the requirement of ASSE Std 1015 and AMCA Std C510.

F. Double check valve backflow preventers shall be Watts No. 007, Conbraco, Wilkens, Ancon, or approved equal.

G. Furnish test kit for field testing units. Watts Model TK-9A Analog Differential Gauge or approved equal.

END OF SECTION 224005

PAGE LEFT INTENTIONALLY BLANK

SECTION 226113 - COMPRESSED-AIR PIPING FOR DENTAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Dental compressed-air piping, designated "dental air."
2. Gas-powered-tool compressed-air piping, designated "instrument air."
3. Shape-memory-metal couplings.
4. Pressure-seal fittings.
5. Flexible pipe connectors.
6. Ball valves.
7. Check valves.
8. Gas safety valves.
9. Compressed-air service connections.

B. Related Requirements:

1. Section 226119 "Compressed-Air Equipment for Dental Systems" for air compressors and specialties.

1.3 DEFINITIONS

A. Compressed-Air Piping Systems: Include dental air.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and testing agency.

B. Seismic Qualification Data: Certificates, for compressed-air manifolds, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Material Certificates: Signed by Installer, certifying that dental compressed-air piping materials comply with requirements in NFPA 99 for positive-pressure dental gas systems.

D. Brazing certificates.

E. Field Quality-Control Reports: Brazing certificates.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For dental compressed-air piping specialties to include in emergency, operation, and maintenance manuals.

1.7 QUALITY ASSURANCE

A. Installer Qualifications:

1. Dental Air Piping Systems for Healthcare Facilities: In accordance with ASSE Standard #6010 and NFPA 99 for medical-gas-system installers.
2. Shape-Memory-Metal Coupling Joints: An authorized representative who is trained and approved by manufacturer in accordance with ASSE Standard #6040 and NFPA 99.

B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.

1. Qualify testing personnel in accordance with ASSE Standard #6020 and NFPA 99 for dental-gas-system inspectors and ASSE Standard #6030 and NFPA 99 for dental-gas-system verifiers.

C. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code, Section IX, "Welding and Brazing Qualifications," or AWS B2.2/B2.2M.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Dental air operating at 80 to 100 psig (550 to 690 kPa).

2.2 PIPES, TUBES, AND FITTINGS

A. Comply with NFPA 99 for dental air piping materials.

1. All positive-pressure dental compressed-air piping, tubing, and fittings shall be manufacturer cleaned, purged, and sealed as for oxygen service, in accordance with CGA G-4.1.

a. Each length of tubing shall be delivered plugged or capped by the manufacturer and kept sealed until prepared for installation.
b. Fittings and other components shall be delivered manufacturer sealed and labeled, and kept sealed until prepared for installation.

B. Comply with ASME B31.1 for dental air piping operating at more than 150 psig (1035 kPa).

C. Comply with ASME B31.9 for dental air piping operating at 150 psig (1035 kPa) or less.

D. Copper Dental Gas Tube: ASTM B819, Type K, seamless, drawn temper. Include standard color marking "Dental Compressed Air" in green for Type K tube and in blue for Type L tube.

E. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type.

F. Copper Unions: ASME B16.22 or MSS SP-123, wrought-copper or cast-copper alloy.

G. Cast-Copper-Alloy Flanges: ASME B16.24, Class 150.

1. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch (3-mm) maximum thickness, full-face type.
2. Flange Bolts and Nuts: ASME B18.2.1 carbon steel.

H. Shape-Memory-Metal Couplings:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Aerofit, Inc.
b. CAMERON; A Schlumber Co.
c. Motion Industries.

d. Smart Tap; Smart Technology, Inc.

2. Description: Cryogenic compression fitting made of nickel-titanium, shape-memory alloy.

I. Pressure-Seal Fittings:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Apollo Valves; a part of Aalberts Integrated Piping Systems.
b. FNW; Ferguson Enterprises, Inc.
c. Viega LLC.

2. NPS 2 (DN 50) and Smaller: Wrought-copper fitting with EPDM O-ring seal in each end.
3. NPS 2-1/2 to NPS 4 (DN 65 to DN 100): Bronze fitting with stainless steel grip ring and EPDM O-ring seal in each end.

J. Flexible Pipe Connectors:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Flex-Hose Co., Inc.
b. Flexicraft Industries.
c. Hyspan Precision Products, Inc.
d. Mercer Rubber Co.
e. Metraflex Company (The).
f. Proco Products, Inc.
g. Universal Metal Hose.

2. Description: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.

a. Working-Pressure Rating: 200 psig (1380 kPa) minimum.
b. End Connections: Plain-end copper tube.

2.3 JOINING MATERIALS

A. Brazing Filler Metals: AWS A5.8M/A5.8, BCuP Series, copper-phosphorus alloys.

B. Threaded-Joint Tape: PTFE.

2.4 VALVES

A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged in accordance with CGA G-4.1 for oxygen service.

B. Ball Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   a. Amico Corporation.
   b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
   c. BeaconMedaes.
   d. Marwin Valve; Richards Industries.
   e. NIBCO INC.
   f. Ohio Medical Corporation.
   g. Oxequip Health Industries; a division of Allied Healthcare Products Inc.
   h. Tri-Tech Medical.
2. Standard: MSS SP-110.
3. Description: Three-piece body, brass or bronze.
4. Pressure Rating: 300 psig (2070 kPa) minimum.
5. Ball: Full-port, chrome-plated brass.
6. Seats: PTFE or TFE.
7. Handle: Lever type with locking device.
8. Stem: Blowout proof with PTFE or TFE seal.
9. Ends: Manufacturer-installed ASTM B819, copper-tube extensions and manufacturer-installed ASTM B819, copper-tube extensions with pressure gage on one copper-tube extension.
10. Positive-pressure dental air valves shall be manufacturer cleaned, purged, and sealed as for oxygen service, in accordance with CGA G-4.1.

    a. Valves shall be delivered sealed and labeled and kept sealed until prepared for installation.

C. Check Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Amico Corporation.
   b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
   c. BeaconMedaes.
   d. Marwin Valve; Richards Industries.
   e. NIBCO INC.
   f. Ohio Medical Corporation.
   g. Oxequip Health Industries; a division of Allied Healthcare Products Inc.
   h. Tri-Tech Medical.

2. Description: In-line pattern, bronze.
3. Pressure Rating: 300 psig (2070 kPa) minimum.
4. Operation: Spring loaded.
5. Ends: Manufacturer-installed, ASTM B819, copper-tube extensions.

6. Positive-pressure dental compressed-air valves shall be manufacturer cleaned, purged, and sealed as for oxygen service, in accordance with CGA G-4.1.

    a. Valves shall be delivered sealed and labeled and kept sealed until prepared for installation.

D. Gas Safety Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Amico Corporation.
    b. Apollo Valves; a part of Aalberts Integrated Piping Systems.
    c. CEODEUX Meditec.
    d. UCSF Health Environment of Care.

2. Bronze body.
3. ASME-construction, poppet, pressure-relief type.
4. Settings to match system requirements.
5. Positive-pressure dental compressed-air valves shall be manufacturer cleaned, purged, and sealed as for dental service, in accordance with CGA G-4.1.

    a. Valves shall be delivered sealed and labeled and kept sealed until prepared for installation.

E. Dental Compressed-Air Safety Valves:

1. Bronze body.
2. ASME-construction, poppet, pressure-relief type.
3. Settings to match system requirements.
4. Positive-pressure compressed-air valves shall be manufacturer cleaned, purged, and sealed as for oxygen service, in accordance with CGA G-4.1.

    a. Valves shall be delivered sealed and labeled and kept sealed until prepared for installation.

F. Pressure Regulators:

1. Bronze body and trim.
2. Spring-loaded, diaphragm-operated, relieving type.
3. Manual pressure-setting adjustment.
4. Rated for 250-psig (1725-kPa) minimum inlet pressure.
5. Capable of controlling delivered air pressure within 0.5 psig for each 10-psig (5.0 kPa for each 100-kPa) inlet pressure.
6. Positive-pressure dental air regulators shall be manufacturer cleaned, purged, and sealed as for dental service, in accordance with CGA G-4.1.

a. Valves shall be delivered sealed and labeled and kept sealed until prepared for installation.

PART 3 - EXECUTION

3.1 PREPARATION

A. Cleaning of Dental Air Tubing: If manufacturer-cleaned and -capped fittings or tubing is not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:

1. Clean dental air tube and fittings, valves, gauges, and other components of oil, grease, and other readily oxidizable materials as required for dental compressed air service in accordance with CGA G-4.1.
2. Wash dental air tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb (0.453 kg) of chemical to 3 gal. (11.3 L) of water.

    a. Scrub to ensure complete cleaning.
    b. Rinse with clean, hot water to remove cleaning solution.

3.2 PIPING INSTALLATION

A. General Location and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of compressed-air piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, air-compressor sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.

B. Install seismic restraints on dental compressed-air piping.

C. Comply with NFPA 99 for installation of dental compressed-air piping.

D. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.

E. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

F. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.

G. Install piping adjacent to equipment and specialties to allow service and maintenance.

H. Install piping with 1 percent slope downward in direction of flow.

I. Install nipples, unions, special fittings, and valves with pressure ratings same as or higher than system pressure rating used in applications specified in "Piping Schedule" Article unless otherwise indicated.

J. Install eccentric reducers, if available, where compressed-air piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.

K. Install branch connections to mains from top of main. Provide drain leg at end of each main and branch at low points.

L. Install piping to permit valve servicing.

M. Install piping free of sags and bends.

N. Install fittings for changes in direction and for branch connections.

O. Install dental air piping to dental air service connections in equipment specified in Section 226119 "Compressed Air Equipment for Dental Systems," and to equipment specified in other Sections requiring dental air service.

P. Piping Restraint Installation: Install seismic restraints on compressed-air piping. Seismic-restraint devices are specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."

Q. Install service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.

R. Connect piping to dental air compressors and to compressed-air outlets and equipment requiring compressed-air service.

S. Install unions in copper tubing adjacent to each valve and at final connection to each machine, specialty, and piece of equipment.

T. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Division 22 Section 220500 “Common Work Results for Plumbing.”

U. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Division 22 Section 220500 “Common Work Results for Plumbing.”

V. Connect to dental chair equipment per dental chair equipment manufacturer’s requirements.

W. Insulate all below grade compressed air piping.

3.3 VALVE INSTALLATION

A. Install shutoff valve at each connection to and from dental compressed-air equipment and specialties.

B. Install check valves to maintain correct direction of compressed-air flow from compressed-air equipment.

C. Install pressure regulators on dental compressed-air piping where reduced pressure is required.

D. Install flexible pipe connectors in discharge piping and in inlet air piping from remote air-inlet filter of each air compressor.

3.4 JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs.

B. Remove scale, slag, dirt, and debris from inside and outside of cleaned tubing and fittings before assembly.

C. Threaded Joints: Apply appropriate tape to external pipe threads.

D. Brazed Joints: Join copper tube and fittings in accordance with CDA's "Copper Tube Handbook," Ch. "Brazed Joints." Do not use flux. Continuously purge joint with oil-free dry nitrogen during brazing.

E. Soldered Joints: Apply ASTM B813, water-flushable flux to tube end. Join copper tube and fittings in accordance with ASTM B828.

F. Extruded-Tee Outlets: Form branches in copper tube in accordance with ASTM F2014, with tools recommended by tube manufacturer.

G. Flanged Joints:

1. Copper Tubing: Install flange on copper tubes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts in accordance with ASME B31.9 for bolting procedure.

H. Shape-Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of shape-memory-metal coupling joints.

3.5 DENTAL COMPRESSED-AIR SERVICE COMPONENT INSTALLATION

A. Install dental compressed-air pressure-control panel in walls. Attach to substrate.

3.6 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements for seismic-restraint devices specified in Division 23 Section 230548, “Vibration Controls for HVAC, Plumbing & Fire Protection Equipment.”

B. Comply with requirements for hangers, supports, and anchor devices specified in Division 22 Section 220500 “Common Work Results for Plumbing.”

C. Vertical Piping: MSS Type 8 or Type 42 clamps.

D. Individual, Straight, Horizontal Piping Runs:

1. 100 Feet (30 m) and Less: MSS Type 1, adjustable, steel, clevis hangers.
2. Longer Than 100 Feet (30 m): MSS Type 43, adjustable, roller hangers.

E. Multiple, Straight, Horizontal Piping Runs 100 Feet (30 m) or Longer: MSS Type 44 pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.

F. Base of Vertical Piping: MSS Type 52 spring hangers.

G. Install hangers for copper tubing with maximum horizontal spacing and minimum rod diameters to comply with MSS SP-58, NFPA 99, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

H. Support horizontal piping within 12 inches (300 mm) of each fitting and coupling.

I. Support vertical runs of copper tubing to comply with MSS SP-58, NFPA 99, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.7 IDENTIFICATION

A. Install identifying labels and devices for dental compressed-air piping, valves, and specialties. Comply with requirements in Division 22 Section 220500 “Common Work Results for Plumbing.”

B. Install identifying labels and devices for dental compressed-air piping systems in accordance with NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:

1. Dental Air: Black letters on yellow background.

3.8 FIELD QUALITY CONTROL FOR DENTAL COMPRESSED-AIR

A. Testing Agency:

1. Owner will engage a qualified testing agency to perform tests and inspections.
2. Engage a qualified testing agency to perform tests and inspections.

B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

C. Perform tests and inspections with the assistance of a factory-authorized service representative.

D. Tests and Inspections:

1. Dental Compressed-Air Testing Coordination: Perform tests, inspections, verifications, and certification of dental compressed-air piping systems concurrently with tests, inspections, and certification of dental compressed air piping systems.
2. Preparation: Perform the following Installer tests in accordance with requirements in NFPA 99 and ASSE Standard #6010:

    a. Initial blowdown.
    b. Initial pressure test.
    c. Cross-connection test.
    d. Piping purge test.
    e. Standing pressure test for positive-pressure dental compressed-air piping.
    f. Repair leaks and retest until no leaks exist.

3. System Verification: Perform the following tests and inspections in accordance with NFPA 99, ASSE Standard #6020, and ASSE Standard #6030:

    a. Standing pressure test.
    b. Individual-pressurization cross-connection test.
    c. Valve test.
    d. Piping purge test.
    e. Piping particulate test.
    f. Piping purity test.
    g. Final tie-in test.
    h. Operational pressure test.
    i. Dental compressed air-purity test.
    j. Verify correct labeling of equipment and components.

4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed, and certify report results. Include the following:

    a. Inspections performed.
    b. Procedures, materials, and gases used.
    c. Test methods used.

d. Results of tests.

E. Piping will be considered defective if it does not pass tests and inspections.

F. Prepare test and inspection reports.

G. Test all piping at 100 psig.

3.9 PROTECTION

A. Protect tubing from damage.

B. Retain sealing plugs in tubing, fittings, and specialties until installation.

C. Clean tubing not properly sealed, and where sealing is damaged, in accordance with "Preparation" Article.

3.10 PIPING SCHEDULE

A. Flanges may be used where connection to flanged equipment is required.

B. Dental Air Piping, NPS 3 (DN 80) and Smaller Shall Operate between 15 psig (103 kPa) and 50 psig (345 kPa): Type L copper tubing: wrought copper fittings; and brazed joints.

3.11 VALVE SCHEDULE

A. Zone Valves: Ball valve with manufacturer-installed ASTM B819, copper-tube extensions with pressure gauge on one copper-tube extension.

END OF SECTION 226113

SECTION 226119 - COMPRESSED-AIR EQUIPMENT FOR DENTAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Dental air compressors.
2. Dental air-compressor control panels.

1.3 DEFINITIONS

A. Actual Air: Air delivered at air-compressor outlet. Flow rate is compressed air delivered and measured in acfm (actual L/s).

B. Medical air equipment includes dental air compressors and accessories for healthcare facilities.

C. Standard Air: Free air at 68 deg F (20 deg C) and 1 atmosphere (29.92 in. Hg) before compression or expansion and measured in scfm (standard L/s).

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For air compressors and compressed-air dryers.

1. Include plans, elevations, sections, and mounting details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
4. Include diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and testing agency.

B. Seismic Qualification Certificates: For air compressors, accessories, and components from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculations.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For compressed-air equipment to include in operation and maintenance manuals.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Air-Compressor, Inlet-Air Filter Elements: Equal to 25% percent of quantity installed, but no fewer than two (2) units.
2. Belts: Two (2) for each belt-driven compressor.

1.8 QUALITY ASSURANCE

A. Installer Qualifications:

1. Laboratory Air Equipment for Nonmedical Laboratory Facilities: An employer of workers trained and approved by manufacturer.
2. Medical Air Equipment for Healthcare Facilities: Qualify installers according to ASSE 6010.

B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the compressed-air equipment testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL and that is acceptable to authorities having jurisdiction.

1. Qualify testing personnel according to ASSE 6020 for inspectors and ASSE 6030 for verifiers.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design compressed-air equipment mounting.

B. Seismic Performance: Air compressors and accessories shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

1. The term "withstand" means "the air compressor and receiver will remain in place without separation of any parts when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
2. Component Importance Factor: 1.5.

2.2 GENERAL REQUIREMENTS FOR AIR COMPRESSORS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with UL 544, "Medical and Dental Equipment," for medical compressed-air equipment.

C. Description: Factory-assembled, -wired, -piped, and -tested; electric-motor-driven; air-cooled; continuous-duty air compressors and receivers that deliver air of quality equal to intake air.

D. Control Panels: Automatic control station with load control and protection functions. Comply with NEMA ICS 2 and UL 508.

1. Enclosure: NEMA ICS 6, Type 12 control panel unless otherwise indicated.
2. Motor Controllers: Full-voltage, combination-magnetic type with undervoltage release feature and motor-circuit-protector-type disconnecting means and short-circuit protective device.
3. Control Voltage: 120-V ac or less, using integral control power transformer.
4. Motor Overload Protection: Overload relay in each phase.
5. Starting Devices: Hand-off-automatic selector switch in cover of control panel, plus pilot device for automatic control.
6. Automatic control switches to alternate lead-lag air compressors for duplex air compressors.
7. Instrumentation: Include discharge-air and receiver pressure gages, air-filter maintenance indicator, hour meter, air-compressor discharge-air and coolant temperature gages, and control transformer.

8. Alarm Signal Device: For connection to alarm system to indicate when backup air compressor is operating.

E. Receivers: Steel tank constructed according to ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.

1. Pressure Rating: At least as high as highest discharge pressure of connected air compressors and bearing appropriate code symbols.
2. Interior Finish: Corrosion-resistant coating.
3. Accessories: Include safety valve, pressure gage, automatic drain, and pressure regulator.

F. Mounting Frame: Fabricate base and attachment to air compressor and components with reinforcement strong enough to resist movement during a seismic event when base is anchored to building structure.

2.3 INLET-AIR FILTERS

A. Description: Combination inlet-air filter-silencer, suitable for remote installation, for each air compressor.

1. Construction: Weatherproof housing for replaceable, dry-type filter element, with silencer tubes or other method of sound reduction.
2. Capacity: Match capacity of air compressor, with collection efficiency of 99 percent retention of particles larger than 10 micrometers.

B. Description: Combination inlet-air filter-silencer, suitable for remote installation, for multiple air compressors.

1. Construction: Weatherproof housing for replaceable, dry-type filter element, with silencer tubes or other method of sound reduction.
2. Capacity: Match total capacity of connected air compressors, with collection efficiency of 99 percent retention of particles larger than 10 micrometers.

2.4 COMPRESSED-AIR FILTER ASSEMBLIES

A. Compressed-Air Filter Assemblies:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Arrow Pneumatics, Inc.
b. Dollinger; Celeros Flow Technology.
c. Donaldson Company, Inc.
d. EMSE Corporation.
e. Ingersoll Rand.
f. Parker (Parker Hannifin).

g. Pioneer Air Systems, Inc.
h. SPXFLOW, Air Treatment.
i. Van Air Systems, Inc.
j. Zeks Compressed Air Solutions.

2. Description: Filter assemblies suitable for compressed air, in parallel duplex arrangement. Size each assembly for maximum capacity of connected equipment and operating pressure of compressed-air system. Include automatic ejection of condensate from airstream, inlet and outlet pressure gages, and shutoff valves.

   a. Option: Factory-fabricated filter system consisting of three air filters equivalent to those specified, pipe, fittings, valves, differential pressure switch, and enclosure; and with additional automatic drain traps and gages.

3. Size filter assemblies for 5-psig (34.5-kPa) maximum air-pressure drop when filters are new and clean, at system rated capacity, and at 100-psig (690-kPa) pressure.
4. Differential Pressure Switch: Adjustable, diaphragm type, with electrical connections for alarm system, to indicate when air-pressure drop through filters rises to more than 2 psig (13.8 kPa) greater than when new and clean.
5. Particulate Filters: Collection efficiency of 98 percent retention of particles 1 micrometer and larger.
6. Odor and Taste Filters: Vapor-absorbing, activated charcoal.
7. Coalescing Filters: Collection efficiency of 99.9 percent retention of particles 0.3 micrometer and smaller.
8. Include automatic drain trap for each filter.

2.5 DENTAL AIR COMPRESSORS

A. Dental Air Compressors

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. A-dec.

2. Description: Factory-assembled, -tested, and -packaged; automatic, dental compressed-air system that will deliver air of quality at least equal to intake air; suitable for dental applications and capable of producing air at 80 psig (550 kPa).
3. Air Compressor(s): Oilless reciprocating type.

   a. Option: Construction may be oil-free, sliding-vane or scroll type.

4. Compressor Controls: Adjustable, tank-mounted, pressure switches and alternator for duplex air compressors.
5. Check Valves: In discharge piping of each air compressor.
6. Air Filter: Integral with air compressor or separate unit for field installation in compressed-air piping.
7. Dryer: Desiccant type integral with air compressor.
8. Receiver: Steel tank rated for at least 100 psig (690 kPa) with rubber isolators on feet.

    a. Pressure Regulator: Adjustable.
    b. Safety Valve: ASME relief valve with setting of 100 psig (690 kPa) or less.
    c. Drain: Automatic valve.

9. Cabinet: Enameled steel, with control panel with manual on-off switch, on light, and pressure gage.

B. Capacities and Characteristics: As indicated on the Dental Equipment Vendor Contract Drawings.

C. Dental air compressor shall be provided by Dental Equipment Vendor.

2.6 DENTAL AIR-COMPRESSOR CONTROL PANELS

A. Dental Air-Compressor Control Panels:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. A-dec.

2. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
3. Comply with UL 544, "Medical and Dental Equipment," for medical vacuum equipment.
4. Description: Wall-mounted type with visual indicators to indicate equipment in operation and to perform the following:

    a. Shut off dental air equipment.
    b. Shut off water supply to dental air equipment. Include solenoid-operated valve for installation in water piping.
    c. Remote switch with timer.

B. Control panels may be combined with dental vacuum pump control panels in single dental equipment control panels.

2.7 MOTORS

A. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Division 22 Section 220500, “Common Work Results for Plumbing.”

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean compressed-air equipment, accessories, and components that have not been cleaned for oxygen service and sealed or that are furnished unsuitable for dental air applications, according to CGA G-4.1, "Cleaning Equipment for Oxygen Service."

3.2 COMPRESSED-AIR EQUIPMENT INSTALLATION

A. General Requirements for Compressed-Air Equipment Installation:

1. Install compressed-air equipment to allow maximum headroom unless specific mounting heights are indicated.
2. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces unless otherwise indicated.
3. Install mechanical equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
4. Install equipment to allow right of way for piping installed at required slope.
5. Install the following devices on compressed-air equipment:

    a. Thermometer, Pressure Gage, and Safety Valve: Install on each compressed-air receiver.
    b. Pressure Regulators: Install downstream from air compressors, dryers, purification units, and filter assemblies.
    c. Drain Valves: Install on aftercoolers, receivers, and dryers. Discharge condensate over nearest floor drain.
    d. Concrete filled inertia base.
    e. Main line pressure switch and interlock to alarm panel.

B. Dental Air System Equipment Installation:

1. Install according to ASSE 6010 and NFPA 99.
2. Install dental air system units on cast-in-place concrete equipment bases. Comply with requirements for equipment bases and foundations specified in Division 22 Section 220500, “Common Work Results for Plumbing.”

3. Comply with requirements for vibration isolation and seismic control devices specified in Section 230548 “Vibration Controls for HVAC, Plumbing & Fire Protection Equipment”
4. Maintain manufacturer's recommended clearances for service and maintenance.
5. Install control panels for dental compressed-air equipment on wall near equipment.

3.3 CONNECTIONS

A. Comply with requirements for water-supply piping specified in Division 22 “Plumbing Piping, Fittings, and Valves.” Drawings indicate general arrangement of piping, fittings, and specialties.

B. Comply with requirements for drain piping specified in Division 22 “Plumbing Piping, Fittings, and Valves.” Drawings indicate general arrangement of piping, fittings, and specialties.

C. Comply with requirements for compressed-air piping specified in Section 226113 "Compressed-Air Piping for Dental Systems." Drawings indicate general arrangement of piping, fittings, and specialties.

D. Where installing piping adjacent to equipment, allow space for service and maintenance.

E. Connect compressed-air piping to compressed-air equipment, accessories, and specialties with shutoff valve and union or flanged connection.

3.4 IDENTIFICATION

A. Identify dental compressed-air equipment system components. Comply with requirements for identification specified in Division 22 “Common Work Results for Plumbing” and with NFPA 99.

3.5 FIELD QUALITY CONTROL FOR DENTAL COMPRESSED-AIR EQUIPMENT

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

C. Perform the following tests and inspections with the assistance of a factory-authorized service representative.

1. Dental Compressed-Air Equipment Testing Coordination: Perform tests, inspections, verifications, and certification of dental compressed-air

equipment concurrently with tests, inspections, and certification of dental compressed-air piping systems.

2. Preparation: Perform dental compressed-air equipment tests according to requirements in NFPA 99 for the following:

    a. Air-quality purity test.
    b. System operation test.

3. Equipment Verification: Comply with requirements in ASSE 6020, ASSE 6030, and NFPA 99 for verification of dental compressed-air equipment.
4. Replace damaged and malfunctioning controls and equipment.
5. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:

    a. Inspections performed.
    b. Procedures, materials, and gases used.
    c. Test methods used.
    d. Results of tests.

D. Components will be considered defective if they do not pass tests and inspections.

E. Prepare test and inspection reports.

3.6 STARTUP SERVICE

A. A factory-authorized service representative shall perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Check for lubricating oil in lubricated-type equipment.
3. Check belt drives for proper tension.
4. Verify that air-compressor inlet filters and piping are clear.
5. Check for equipment vibration-control supports and flexible pipe connectors and verify that equipment is properly attached to substrate.
6. Check safety valves for correct settings. Ensure that settings are higher than air-compressor discharge pressure, but not higher than rating of system components.
7. Check for proper seismic restraints.
8. Drain receiver tank(s).
9. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
10. Test and adjust controls and safeties.

B. Prepare written report documenting testing procedures and results.

3.7 DEMONSTRATION

A. A factory-authorized service representative shall train Owner's maintenance personnel to adjust, operate, and maintain air compressors, compressed-air dryers and compressed-air filter assemblies.

END OF SECTION 226119

SECTION 226213 - VACUUM PIPING FOR DENTAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Dental vacuum piping, designated "dental vacuum."

B. Related Requirements:

1. Section 226219 "Vacuum Equipment for Dental Facilities" for vacuum producers and accessories.

1.3 DEFINITIONS

A. Vacuum Piping Systems: Include dental vacuum.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and testing agency.

B. Seismic Qualification Data: Certificates, for accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Material Certificates: Signed by Installer, certifying that dental vacuum piping materials comply with requirements in NFPA 99 for dental vacuum systems.

D. Brazing certificates.

E. Field quality-control reports.

F. Source Quality Control Reports:

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For vacuum piping specialties to include in emergency, operation, and maintenance manuals.

1.7 QUALITY ASSURANCE

A. Installer Qualifications:

1. Medical Vacuum Piping Systems for Healthcare Facilities: In accordance with ASSE Standard #6010 and NFPA 99 for dental vacuum-gas-system installers.
2. Pressure-Seal Joining Procedure for Copper Tubing: An authorized representative who is trained and approved by manufacturer.
3. Extruded-Tee Outlet Procedure: An authorized representative who is trained and approved by manufacturer.
4. Shape-Memory-Metal Coupling Joints: An authorized representative who is trained and approved by manufacturer in accordance with ASSE Standard #6040 and NFPA 99.

B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.

1. Qualify testing personnel in accordance with ASSE Standard #6020 and NFPA 99 for medical-gas-system inspectors and ASSE Standard #6030 and NFPA 99 for medical-gas-system verifiers.

C. Brazing: Qualify processes and operators in accordance with ASME Boiler and Pressure Vessel Code, Section IX, "Welding and Brazing Qualifications," or AWS B2.2/B2.2M.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Dental vacuum operating at 10-12 in. Hg (305 mm Hg).

2.2 PIPES, TUBES, AND FITTINGS

A. Comply with NFPA 99 for dental vacuum piping materials.

B. Piping shall be either Copper Dental Gas Tube: ASTM B819, Type L, seamless, drawn temper that has been manufacturer cleaned, purged, and sealed for dental vacuum gas service or PVC pressure fittings ASTM D2467 schedule 80 socket type. Include standard color marking in blue.

C. Copper Water Tube: ASTM B88/ASTM B88M, Type M, seamless, drawn temper that has been manufacturer cleaned, purged, and sealed for medical gas service.

D. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type that has been manufacturer cleaned, purged, and sealed for medical gas service or in accordance with CGA G-4.1 for oxygen service.

E. Copper Unions: ASME B16.22 or MSS SP-123, wrought-copper or cast-copper alloy.

F. Cast-Copper-Alloy Flanges: ASME B16.24, Class 150.

1. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch (3.2-mm) maximum thickness, full-face type.
2. Flange Bolts and Nuts: ASME B18.2.1 carbon steel.

G. Shape-Memory-Metal Couplings:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Aerofit, Inc.
    b. CAMERON; A Schlumber Co.
    c. Motion Industries.
    d. Smart Tap; Smart Technology, Inc..

2. Description: Cryogenic compression fitting made of nickel-titanium, shape-memory alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service in accordance with CGA G-4.1.

H. Pressure-Seal Fittings:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. FNW; Ferguson Enterprises, Inc.
    b. NIBCO INC.
    c. Viega LLC.

2. NPS 2 (DN 50) and Smaller: Wrought-copper fitting with EPDM O-ring seal in each end.

3. NPS 2-1/2 to NPS 4 (DN 65 to DN 100): Bronze fitting with stainless steel grip ring and EPDM O-ring seal in each end.

I. Extruded-Tee Outlets: ASTM F2014 procedure for making branch outlets in copper tube.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. T-DRILL Industries Inc.

J. Flexible Pipe Connectors:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Flex-Hose Co., Inc.
b. Flexicraft Industries.
c. Hyspan Precision Products, Inc.
d. Mercer Rubber Co.
e. Metraflex Company (The).
f. Proco Products, Inc.
g. Universal Metal Hose.

2. Description: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.

a. Working-Pressure Rating: 200 psig (1380 kPa) minimum.
b. End Connections: Plain-end copper tube.

2.3 JOINING MATERIALS

A. Solder Filler Metals: ASTM B32, lead-free alloys. Include water-flushable flux in accordance with ASTM B813.

B. Brazing Filler Metals: AWS A5.8M/A5.8, BCuP Series, copper-phosphorus alloys.

C. Threaded-Joint Tape: PTFE.

D. For PVC Tubing: Solvent cement for joining PVC pipe: ASTM D2564, include primer complying with ASTM F656.

2.4 VALVES

A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged in accordance with CGA G-4.1 for oxygen service.

B. Metal Ball Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Tri-Tech Medical.
    b. Allied Healthcare Products Inc.
    c. Amico Corporation.
    d. Apollo Valves; a part of Aalberts Integrated Piping Systems.
    e. BeaconMedaes.
    f. Marwin Valve; Richards Industries.
    g. NIBCO INC.
    h. Ohio Medical Corporation.

2. Standard: MSS SP-110.
3. Description: Three-piece body, brass or bronze.
4. Pressure Rating: 300 psig (2070 kPa) minimum.
5. Ball: Full-port, chrome-plated brass.
6. Seats: PTFE or TFE.
7. Handle: Lever type with locking device.
8. Stem: Blowout proof with PTFE or TFE seal.
9. Ends: Manufacturer-installed ASTM B819, copper-tube extensions and manufacturer-installed ASTM B819, copper-tube extensions with pressure gauge on one copper-tube extension.

C. Check Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Tri-Tech Medical.
    b. Allied Healthcare Products Inc.
    c. Amico Corporation.
    d. Apollo Valves; a part of Aalberts Integrated Piping Systems.
    e. BeaconMedaes.
    f. Marwin Valve; Richards Industries.
    g. NIBCO INC.
    h. Ohio Medical Corporation.

2. Description: In-line pattern, bronze.
3. Pressure Rating: 300 psig (2070 kPa) minimum.
4. Operation: Spring loaded.
5. Ends: Manufacturer-installed ASTM B819, copper-tube extensions.

D. PVC Ball Valves: MSS SP-122, with union ends and 150-psig (1035-kPa) minimum working-pressure rating and suitable for vacuum service.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Valve, Inc.
b. Asahi/America.
c. Colonial Valve; a div. of Colonial Engineering, Inc.
d. George Fischer Inc.
e. Hayward Industrial Products, Inc.
f. IPEX Inc.
g. Jomar International Ltd.
h. NIBCO INC.
i. Plast-O-Matic Valves, Inc.
j. Sloane, George Fischer, Inc.
k. Spears Manufacturing Co.
l. Thermoplastic Valves Inc.

E. PVC Butterfly Valves: Lug type with lever handle and 150-psig (1035-kPa) minimum working-pressure rating and suitable for vacuum service.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Valve, Inc.
b. Asahi/America.
c. Colonial Valve; a div. of Colonial Engineering, Inc.
d. George Fisher Inc.
e. Hayward Industrial Products, Inc.
f. IPEX Inc.
g. NIBCO INC.
h. Sloane, George Fischer, Inc.
i. Spears Manufacturing Co.
j. Thermoplastic Valves Inc.

F. PVC Check Valves: Ball-, in-line-, piston-, or swing-check design with flanged or union ends and 100-psig (690-kPa) minimum working-pressure rating and suitable for vacuum service.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. American Valve, Inc.
b. Asahi/America.
c. Colonial Valve; a div. of Colonial Engineering, Inc.
d. George Fisher Inc.
e. NIBCO INC.
f. Sloane, George Fischer, Inc.
g. Spears Manufacturing Co.
h. Thermoplastic Valves Inc.

G. Automatic Drain Valves: Stainless-steel body and internal parts, rated for 200-psig (1380-kPa) minimum working pressure, capable of automatic discharge of

collected condensate. Include mounting bracket where wall mounting is indicated.

PART 3 - EXECUTION

3.1 PREPARATION

A. Cleaning of Dental Vacuum Tubing: If manufacturer-cleaned and -capped fittings or tubing is not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:

1. Clean dental vacuum tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service in accordance with CGA G-4.1.
2. Wash vacuum tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb (0.453 kg) of chemical to 3 gal. (11.3 L) of water.

    a. Scrub to ensure complete cleaning.
    b. Rinse with clean, hot water to remove cleaning solution.

3.2 PIPING INSTALLATION

A. General Location and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of dental vacuum piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, vacuum producer sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.

B. Comply with NFPA 99 for installation of dental vacuum piping.

C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.

D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.

F. Install piping adjacent to equipment and specialties to allow service and maintenance.

G. Install piping with 1 percent slope downward in direction of flow.

H. Install nipples, unions, special fittings, and valves with pressure ratings same as or higher than piping pressure rating used in applications specified in "Piping Schedule" Article unless otherwise indicated.

I. Install eccentric reducers, if available, where vacuum piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.

J. Provide drain leg and drain trap at end of each main and branch and at low points.

K. Install piping to permit valve servicing.

L. Install piping free of sags and bends.

M. Install fittings for changes in direction and for branch connections. Extruded-tee branch outlets in copper tubing may be made where specified.

N. Install vacuum piping from vacuum service connections specified in this Section, to equipment specified in Section 226219 "Vacuum Equipment for Dental Systems," and to equipment specified in other Sections requiring dental vacuum service.

O. Install vacuum service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.

P. Install vacuum bottle bracket adjacent to each wall-mounted vacuum service connection suction inlet.

Q. Connect vacuum piping to vacuum producers and to equipment requiring vacuum service.

R. Install unions in copper vacuum tubing adjacent to each valve and at final connection to each machine, specialty, and piece of equipment.

S. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Division 22 “Common Work Results for Plumbing.”

T. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Division 22 “Common Work Results for Plumbing.”

U. Connect to dental chair/equipment as required by dental chair manufacturer.

V. Install pipe insulation on dental vacuum exhaust piping with minimum 1 inch thick insulation.

W. Comply with ASSE Standard #6010 for installation of vacuum piping.

X. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.

Y. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

Z. Install piping adjacent to equipment and specialties to allow service and maintenance.

AA. Install vacuum piping with 2 percent slope downward in direction of flow.

BB. Insulate all below grade vacuum piping.

CC. Install nipples, unions, and special fittings, and valves with pressure ratings same as or higher than piping pressure rating used in applications below unless otherwise indicated.

DD. Install eccentric reducers, if available, where vacuum piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.

EE. Provide drain leg and drain trap at end of each main and branch and at low points.

FF. Install thermometer and vacuum gage on inlet piping to each vacuum producer and on each receiver and separator. Comply with requirements in Division 22 Section, Plumbing Piping, Fittings, and Valves.

GG. Install piping to permit valve servicing.

HH. Install piping free of sags and bends.

II. Install medical vacuum service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.

JJ. Install unions, in PVC vacuum piping NPS 2 (DN 50) and smaller, adjacent to each valve and at final connection to each piece of equipment, machine, and specialty.

KK. Install flanges, in PVC vacuum piping NPS 2-1/2 (DN 65) and larger, adjacent to flanged valves and at final connection to each piece of equipment, machine, and specialty.

3.3 VALVE APPLICATIONS

A. Valves for Copper Vacuum Tubing: Use copper alloy ball and bronze check types.

B. Valves for PVC Vacuum Piping:

1. NPS 4 (DN 100) and Smaller: Use copper alloy ball and bronze or PVC ball, butterfly, and check types.

3.4 VALVE INSTALLATION

A. Install shutoff valve at each connection to and from vacuum equipment and specialties.

B. Install check valves to maintain correct direction of vacuum flow to vacuum-producing equipment.

C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.

D. Install zone valves and gages in valve boxes. Rotate valves to angle that prevents closure of cover when valve is in closed position.

E. Install flexible pipe connectors in suction inlet piping to each vacuum producer.

3.5 JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs.

B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

C. Threaded Joints: Apply appropriate tape to external pipe threads.

D. Brazed Joints: Join copper tube and fittings in accordance with CDA's "Copper Tube Handbook," Ch. "Brazed Joints." Do not use flux. Continuously purge joint with oil-free dry nitrogen during brazing.

E. Soldered Joints: Apply ASTM B813, water-flushable flux to tube end. Join copper tube and fittings in accordance with ASTM B828.

F. Extruded-Tee Outlets: Form branches in copper tube in accordance with ASTM F2014, with tools recommended by tube manufacturer.

G. Flanged Joints:

1. Copper Tubing: Install flange on copper tubes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts in accordance with ASME B31.9 for bolting procedure.

H. Pressure-Sealed Joints: Join copper tube and copper and copper-alloy fittings with tools recommended by fitting manufacturer.

I. Shape-Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of shape-memory-metal coupling joints.

J. Solvent-Cemented Joints: Clean and dry joining surfaces. Join PVC pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. Apply primer and join according to ASME B31.9 for solvent-cemented joints and to ASTM D 2672.

3.6 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements for hangers, supports, and anchor devices specified in Division 22 “Common Work Results for Plumbing.”

B. Vertical Piping: MSS Type 8 or Type 42, clamps.

C. Individual, Straight, Horizontal Piping Runs:

1. 100 Feet (30 m) and Less: MSS Type 1, adjustable, steel, clevis hangers.
2. Longer Than 100 Feet (30 m): MSS Type 43, adjustable, roller hangers.

D. Multiple, Straight, Horizontal Piping Runs 100 Feet (30 m) or Longer: MSS Type 44 pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.

E. Base of Vertical Piping: MSS Type 52 spring hangers.

F. Install hangers for copper tubing with maximum horizontal spacing and minimum rod diameters to comply with MSS SP-58, NFPA 99, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

G. Support horizontal piping within 12 inches (300 mm) of each fitting and coupling.

H. Support vertical runs of copper tubing to comply with MSS SP-58, NFPA 99, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

I. Install vinyl coated hangers for PVC piping with a minimum horizontal spacing of 30 inches with 3/8 inch rods.

3.7 IDENTIFICATION

A. Install identifying labels and devices for laboratory vacuum piping, valves, and specialties. Comply with requirements in Division 22 “Common Work Results for Plumbing.”

B. Install identifying labels and devices for dental vacuum piping systems in accordance with NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:

1. Dental Vacuum: Black boxed letters on white-and-black diagonal stripe background.

3.8 FIELD QUALITY CONTROL FOR DENTAL VACUUM PIPING

A. Testing Agency:

1. Owner will engage a qualified testing agency to perform tests and inspections.
2. Engage a qualified testing agency to perform tests and inspections.

B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

C. Perform tests and inspections with the assistance of a factory-authorized service representative.

D. Tests and Inspections:

1. Dental Vacuum Testing Coordination: Perform tests, inspections, verifications, and certification of dental vacuum piping systems concurrently with tests, inspections, and certification of dental compressed-air piping systems.
2. Preparation: Perform the following Installer tests in accordance with requirements in NFPA 99 and ASSE Standard #6010:

a. Initial blowdown.
b. Initial pressure test.
c. Cross-connection test.
d. Piping purge test.
e. Standing pressure test for vacuum systems.
f. Repair leaks and retest until no leaks exist.

3. System Verification: Perform the following tests and inspections in accordance with NFPA 99, ASSE Standard #6020, and ASSE Standard #6030:

a. Standing pressure test.
b. Individual-pressurization or pressure-differential cross-connection test.
c. Valve test.
d. Piping purge test.
e. Final tie-in test.
f. Operational vacuum test.

g. Verify correct labeling of equipment and components.

4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed, and certify report results. Include the following:

a. Inspections performed.
b. Procedures, materials, and gases used.
c. Test methods used.
d. Results of tests.

E. Piping will be considered defective if it does not pass tests and inspections.

F. Prepare test and inspection reports.

3.9 PROTECTION

A. Protect tubing from damage.

B. Retain sealing plugs in tubing, fittings, and specialties until installation.

C. Clean tubing not properly sealed, and where sealing is damaged, in accordance with "Preparation" Article.

3.10 PIPING SCHEDULE

A. Connect new copper tubing to existing copper tubing with memory-metal couplings.

B. Connect PVC pipe to copper tube with transition fittings.

C. Flanges may be used where connection to flanged equipment is required.

D. Dental Vacuum Piping: Use copper water tube, wrought-copper fittings, and joints or schedule 80 PVC pipe, PVC fittings and solvent cemented joints.

E. Drain piping: Wrought copper fittings and sealed joints.

3.11 VALVE SCHEDULE

A. Shutoff Valves:

1. Copper Tubing: Copper-alloy ball valve with manufacturer-installed ASTM B819, copper-tube extensions.

B. Zone Valves: Copper-alloy ball valve with manufacturer-installed ASTM B819, copper-tube extensions with pressure gage on one copper-tube extension.

END OF SECTION 226213

SECTION 226219 - VACUUM EQUIPMENT FOR DENTAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Dental vacuum pumps.
2. Dental vacuum pump control panels.

1.3 DEFINITIONS

A. Actual Air: Air delivered at vacuum producer inlet. Flow rate is air measured in acfm (actual L/s).

B. Dental Vacuum Equipment: Includes dental vacuum producers and accessories for healthcare facilities.

C. Standard Air: Free air at 68 deg F (20 deg C) and 1 atmosphere (29.92 in. Hg) before compression or expansion and measured in scfm (standard L/s).

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For vacuum producers.

1. Include plans, elevations, sections, and mounting details.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
4. Include diagrams for power, signal, and control wiring.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and testing agency.

B. Seismic Qualification Certificates: For vacuum producers, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For vacuum equipment to include in operation and maintenance manuals.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Belts: Two for each belt-driven vacuum producer.

1.8 QUALITY ASSURANCE

A. Installer Qualifications:

1. Medical Vacuum Equipment for Healthcare Facilities: Qualify installers according to ASSE 6010.

B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum equipment testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.

1. Qualify testing personnel according to ASSE 6020 for inspectors and ASSE 6030 for verifiers.

PART 2. PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Seismic Performance: Vacuum producers and accessories shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

1. Component Importance Factor: 1.5.

2.2 GENERAL REQUIREMENTS FOR VACUUM PUMPS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with NFPA 99, "Health Care Facilities," for vacuum equipment and accessories for dental vacuum systems.

C. Comply with UL 544, "Medical and Dental Equipment," for medical vacuum equipment.

D. Description: Factory-assembled, -wired, -piped, and -tested; electric-motor-driven; air-cooled; continuous-duty vacuum pumps and receivers.

E. Control Panels: Automatic control station with load control and protection functions. Comply with NEMA ICS 2 and UL 508.

1. Enclosure: NEMA ICS 6, Type 12 control panel unless otherwise indicated.
2. Motor Controllers: Full-voltage, combination-magnetic type with undervoltage release feature and motor-circuit-protector-type disconnecting means and short-circuit protective device.
3. Control Voltage: 120-V ac or less, using integral control power transformer.
4. Motor Overload Protection: Overload relay in each phase.
5. Starting Devices: Hand-off-automatic selector switch in cover of control panel, plus pilot device for automatic control.
6. Automatic control switches to alternate lead-lag vacuum pumps for duplex vacuum pumps.
7. Instrumentation: Include vacuum pump inlet and receiver vacuum gages, hour meter, vacuum pump discharge-air and coolant temperature gages, and control transformer.
8. Alarm Signal Devices: For connection to alarm system to indicate when backup vacuum pump is operating.

F. Receivers: Steel tank constructed according to ASME Boiler and Pressure Vessel Code, Section VIII, Division 1; bearing appropriate code symbols.

1. Interior Finish: Corrosion-resistant coating.

2. Accessories: Include vacuum relief valve, vacuum gage, and drain.

G. Mounting Frames: Fabricate base and attachment to vacuum pump and components with reinforcement strong enough to resist movement during a seismic event when base is anchored to building structure.

2.3 DENTAL VACUUM PUMPS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. A-dec

B. Dental Vacuum Pumps:

1. Description: Factory-assembled, -tested, and -packaged; automatic, dental vacuum system; suitable for dental applications and capable of producing not less than 12 in. Hg (305 mm Hg).
2. Vacuum Pumps: For mounting on concrete base.

a. Vacuum Pumps: Brass water-injection or liquid-ring type with rubber isolators on feet. Include fitting and tubing for circulation of approximately 80 percent of water through vacuum pump.
b. Cabinet: Enameled steel; open construction with sound-insulated cover. Include control panel with alternator, adjustable vacuum control for each vacuum pump, manual on-off switches, on light, and vacuum gage.

C. Capacities and Characteristics: Refer to Dental Equipment Vendor Drawings.

D. Dental Vacuum shall be provided by Dental Equipment Vendor.

2.4 DENTAL VACUUM PUMP CONTROL PANELS

A. Dental Vacuum Pump Control Panels:

1. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
2. Comply with UL 544, "Medical and Dental Equipment," for dental vacuum equipment.
3. Description: Wall-mounted type with visual indicators to indicate equipment in operation and to perform the following:

a. Shut off dental vacuum equipment.
b. Shut off water supply to dental vacuum equipment. Include solenoid-operated valve for installation in water piping.
c. Remote switch with timer.

B. Control panels may be combined with dental air compressor control panels in single dental equipment control panels.

2.5 MOTORS

A. Comply with NEMA designation, temperature rating, service factor, and efficiency requirements for motors specified in Division 22 “Common Work Results for Plumbing."

PART 3. EXECUTION

3.1 PREPARATION

A. Clean vacuum equipment, accessories, and components that have not been cleaned for oxygen service and sealed or that are furnished unsuitable for dental vacuum applications, according to CGA G4.1, "Cleaning Equipment for Oxygen Service."

3.2 VACUUM EQUIPMENT INSTALLATION

A. Install vacuum equipment for healthcare facilities according to ASSE 6010 and NFPA 99.

B. Equipment Mounting:

1. Install vacuum producers on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in Division 22 “Common Work Results for Plumbing.”
2. Comply with requirements for vibration isolation and seismic control devices specified in Section 230548 “Vibration Controls for HVAC, Plumbing and Fire Protection Equipment.”
3. Comply with requirements for vibration isolation devices specified in Section 230548 “Vibration Controls for HVAC, Plumbing and Fire Protection Equipment.”

C. Install vacuum equipment anchored to substrate.

D. Orient equipment so controls and devices are accessible for servicing.

E. Maintain manufacturer's recommended clearances for service and maintenance.

F. Install the following devices on vacuum equipment:

1. Thermometer, Vacuum Gage, and Pressure Relief Valve: Install on each vacuum pump receiver.

2. Drain Valves: Install on receivers and separators. Discharge receiver condensate over nearest floor drain. Discharge separator oral evacuation fluids by direct connection into sanitary waste piping system.
3. Concrete filled inertia base.
4. Mainline pressure (vacuum) switch and interlock to alarm panel.

G. Dental Vacuum System Equipment Installation:

1. Install according to ASSE 6010 and NFPA 99.
2. Install dental vacuum system units on concrete bases with elastomeric mounts with a minimum deflection of 2 inches. Vibration isolation devices and installation requirements are specified in Section 230548 “Vibration Controls for HVAC, Plumbing and Fire Protection Equipment.”
3. Maintain manufacturer's recommended clearances for service and maintenance.
4. Install control panels for dental vacuum equipment on wall near equipment.

3.3 CONNECTIONS

A. Comply with requirements for water-supply piping specified in Division 22 “Plumbing Piping, Fittings and Valves.” Drawings indicate general arrangement of piping, fittings, and specialties.

B. Comply with requirements for drain piping specified in Division 22 “Plumbing Piping, Fittings and Valves.” Drawings indicate general arrangement of piping, fittings, and specialties.

C. Comply with requirements for vacuum piping specified in Section 226213 "Vacuum Piping for Dental Systems." Drawings indicate general arrangement of piping, fittings, and specialties.

D. Where installing piping adjacent to equipment, allow space for service and maintenance.

E. Connect vacuum piping to vacuum equipment, accessories, and specialties with shutoff valve and union or flanged connection.

F. Connect water supply to vacuum equipment that requires water. Include backflow preventer.

3.4 IDENTIFICATION

A. Identify dental vacuum equipment system components. Comply with requirements for identification specified in Division 22 Section 220500, “Common Works Results for Plumbing” and with NFPA 99.

3.5 FIELD QUALITY CONTROL FOR DENTAL VACUUM EQUIPMENT

A. Testing Agency: A qualified testing agency shall perform tests and inspections.

B. Manufacturer's Field Service: A factory-authorized service representative shall test and inspect components, assemblies, and equipment installations, including connections.

C. Perform the following tests and inspections with the assistance of a factory-authorized service representative:

1. Preparation: Perform dental vacuum equipment tests according to requirements in NFPA 99 for the following:

    a. System operation test.

2. Equipment Verification: Comply with requirements in ASSE 6020, ASSE 6030, and NFPA 99 for verification of dental vacuum equipment.
3. Replace damaged and malfunctioning controls and equipment.

D. Components will be considered defective if they do not pass tests and inspections.

E. Prepare test and inspection reports.

F. Test all piping at 50 psig.

3.6 STARTUP SERVICE

A. A factory-authorized service representative shall perform startup service.

1. Complete installation and startup checks according to manufacturer's written instructions.
2. Check for lubricating oil in lubricated-type equipment.
3. Check belt drives for proper tension.
4. Verify that vacuum producer outlet piping is clear.
5. Check for equipment vibration-control supports and flexible pipe connectors and verify that equipment is properly attached to substrate.
6. Check safety valves for correct settings.
7. Check for proper seismic restraints.
8. Drain receiver and separator tank(s).
9. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
10. Test and adjust controls and safeties.

B. Verify that vacuum equipment is installed and connected according to the Contract Documents.

C. Verify that electrical wiring installation complies with manufacturer's submittal and written installation requirements in electrical Sections.

D. Prepare written report documenting testing procedures and results.

3.7 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain vacuum producers.

END OF SECTION 226219

SECTION 230500 - COMMON WORK RESULTS FOR HVAC

PART 1 - GENERAL

1.1. SUMMARY

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

B. Provide all labor, materials, equipment, and services necessary for and incidental to the complete installation and operation of all mechanical work.

C. Unless otherwise specified, all submissions shall be made to, and acceptances and approvals made by the Architect and the Engineer.

D. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange piping, ductwork, equipment, and other work generally as shown on the contract drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed shop drawings for approval in accordance with Submittals specified below. The right is reserved to make reasonable changes in location of equipment, piping, and ductwork, up to the time of rough-in or fabrication.

E. Conform to the requirements of all rules, regulations and codes of local, state and federal authorities having jurisdiction.

F. Coordinate the work under Division 23 with the work of all other construction trades.

G. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the contract documents.

1.2. PERMITS AND FEES

A. Obtain all permits and pay taxes, fees and other costs in connection with the work. File necessary plans, prepare documents, give proper notices and obtain necessary approvals. Deliver inspection and approval certificates to Owner prior to final acceptance of the work.

B. Permits and fees shall comply with the Division 01, General Requirements of the specification.

1.3. EXAMINATION OF SITE

A. Examine the site, determine all conditions and circumstances under which the work must be done, and make all necessary allowances for same. No additional cost to the Owner will be permitted for contractors' failure to do so.

B. Examine and verify specific conditions described in individual specifications sections.

C. Verify that utility services are available, of the correct characteristics, and in the correct locations.

1.4. CONTRACTOR QUALIFICATION

A. Any Contractor or Subcontractor performing work under Division 23 shall be fully qualified and acceptable to the Architect/Engineer and Owner. Submit the following evidence when requested:

1. A list of not less than five comparable projects which the Contractor completed.

2. Letter of reference from not less than three registered professional engineers, general contractors or building owners.

3. Local and/or State License, where required.

4. Membership in trade or professional organizations where required.

B. A Contractor is any individual, partnership, or corporation, performing work by contract or subcontract on this project.

C. Acceptance of a Contractor or Subcontractor will not relieve the Contractor or subcontractor of any contractual requirements or his responsibility to supervise and coordinate the work, of various trades.

1.5. MATERIALS AND EQUIPMENT

A. Materials and equipment installed as a permanent part of the project shall be new, unless otherwise indicated or specified, and of the specified type and quality. Existing items of equipment are being relocated under another Division of these specifications. The Contractor shall be responsible for connecting all utilities as shown on the drawings, to equipment identified as existing.

B. Where material or equipment is identified by proprietary name, model number and/or manufacturer, furnish named item, or its equal, subject to approval by Engineer. Substituted items shall be equal or better in quality and performance and must be suitable for available space, required arrangement, and application. Submit all data necessary to determine suitability of substituted items, for approval.

C. The suitability of named item only has been verified. Where more than one item is named, only the first named item has been verified as suitable. Substituted items, including items other than first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement and application. Contractor, by providing other than the first named manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation. Adjustments and modifications shall include but not be limited to electrical, structural, support, and architectural work.

D. Substitution will not be permitted for specified items of material or equipment where noted.

E. All items of equipment furnished shall have a service record of at least five (5) years.

1.6. FIRE SAFE MATERIALS

A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA and ASTM standards for fire safety with smoke and fire hazard rating not exceeding flame spread of 25 and smoke developed of 50.

1.7. REFERENCED STANDARDS, CODES AND SPECIFICATIONS

A. Specifications, Codes and Standards listed below are included as part of this specification, latest edition.

B. AABC Associated Air Balance Council

C. ACCA - Air Conditioning Contractors of America

D. ADC Air Diffusion Council

E. AMCA Air Movement and Control Association

F. ANSI - American National Standards Institute

G. ARI - Air Conditioning and Refrigeration Institute

H. ASHRAE - American Society of Heating, Refrigerating and Air Conditioning Engineers

I. ASME - American Society of Mechanical Engineers

J. ASPE - American Society of Plumbing Engineers

K. ASTM - American Society for Testing and Materials

L. AWWA - American Water Works Association

M. CAGI - Compressed Air and Gas Institute

N. CS - Commercial Standard

O. DNREC - Delaware Department of Natural Resources

P. FM - Factory Mutual

Q. IBC - International Building Code

R. IBR - Institute of Boiler and Radiator Manufacturers

S. IEEE - Institute of Electrical and Electronics Engineers

T. MSSP - Manufacturers Standards Society of the Valve and Fittings Industry

U. NEC - National Electrical Code

V. NEMA - National Electrical Manufacturers Association

W. NFPA - National Fire Protection Association

X. NSF - National Sanitation Foundation

Y. SMACNA - Sheet Metal and Air Conditioning Contractors National Association

Z. TEMA - Tubular Exchanger Manufacturers Association

AA. UL - Underwriters' Laboratories

BB. State of Delaware Fire Protection Regulations.

CC. All mechanical equipment and materials shall comply with the codes and standards listed in the latest edition of ASHRAE HVAC Applications Handbook, Chapter entitled Codes and Standards.

1.8. SUBMITTALS, REVIEW AND ACCEPTANCE

A. Equipment, materials, installation, workmanship and arrangement of work are subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Architect to be in best interest of Owner.

B. After acceptance of Material and Equipment List, submit three (3) copies or more as required under General Conditions of complete descriptive data for all items. Data shall consist of specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, wiring diagrams, installation instructions, and any other information

necessary to indicate complete compliance with Contract Documents. Edit submittal data specifically for application to this project.

C. Thoroughly review and stamp all submittals to indicate compliance with contract requirements prior to submission. Coordinate installation requirements and any electrical requirements for equipment submitted. Contractor shall be responsible for correctness of all submittals.

D. Submittals will be reviewed for general compliance with design concept in accordance with contract documents, but dimensions, quantities, or other details will not be verified.

E. Identify submittals, indicating intended application, location and service of submitted items. Refer to specification sections or paragraphs and drawings where applicable. Clearly indicate exact type, model number, style, size and special features of proposed item. Submittals of a general nature will not be acceptable. For substituted items, clearly list on the first page of the submittal all differences between the specified item and the proposed item. The contractor shall be responsible for corrective action and maintaining the specification requirements if differences have not been clearly indicated in the submittal.

F. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Call attention, in writing, to deviation from contract requirements.

G. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted. Use only final or corrected submittals and data prior to fabrication and/or installation.

H. For any submittal requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.

I. For resubmissions, the Contractor must address in writing all of the Engineer’s comments on the original submission to verify compliance.

1.9. SHOP DRAWINGS

A. Prepare and submit shop drawings for all mechanical equipment, specially fabricated items, modifications to standard items, specially designed systems where detailed design is not shown on the contract drawings, or where the proposed installation differs from that shown on contract drawings.

B. Submit data and shop drawings including but not limited to the list below, in addition to provisions of the paragraph above. Identify all shop drawings by the name of the item and system and the applicable specification paragraph number and drawing number.

C. Every submittal including, but not limited to the list below, shall be forwarded with its own transmittal as a separate, distinct shop drawing. Grouping of items/systems that are not related shall be unacceptable.

D. Items and Systems

1. Access Doors/Panels including layouts and locations
2. Air Distribution Systems
3. Automatic Air Vents
4. Automatic Temperature Control Systems and Equipment
5. Existing Baseboard Radiation - Hot Water
6. Carbon Monoxide Detectors
7. Central Control and Monitoring Systems (CCMS) and Equipment
8. Coordinated Drawings
9. Drip Pans
10. Duct Materials
11. Exterior Equipment/Duct/Piping Supports
12. Fans
13. Filters
14. Finned Tube Radiation
15. Fire Stopping - Methods and Materials
16. Flowmeter and Primary Elements (Flow Fittings)
17. Grilles, Registers, Diffusers
18. Identification Systems
19. Material and Equipment Lists
20. Motor Operated Dampers/Actuators
21. Operations and Maintenance Manuals
22. Pete’s Plugs
23. Pipe Enclosures

24. Pipe Materials Including Itemized Schedules
25. Preliminary Testing and Balancing Reports
26. Pressure Independent Control Valves
27. Refrigerant Mitigation Controls
28. Refrigerant Monitoring Systems
29. Roof Curbs
30. Screen shots of ATC System Graphics
31. Ductless Split System Heat Pump Units
32. Static Pressure Sensors
33. Strainers
34. Test Certificates
35. Thermal Insulation Materials Include Table Summaries
36. Thermometers and Gauges
37. Variable Air Volume Boxes
38. Venturi Flow Meters
39. Vibration Isolation Materials
40. Weatherproof Assembly Components
41. Wiring Diagrams, Flow Diagrams and Operating Instructions

E. Contractor, additionally, shall submit for review any other shop drawings as required by the Architect. No item shall be delivered to the site, or installed, until the Contractor has received a submittal from the Engineer marked Reviewed or Comments Noted. After the proposed materials have been reviewed, no substitution will be permitted except where approved by the Architect.

F. For any shop drawing requiring more than two (2) reviews by the Engineer (including those caused by a change in subcontractor or supplier) the Owner will withhold contractor's funds by a change order to the contract to cover the cost of additional reviews. One review is counted for each action including rejection or return of any reason.

1.10. SUPERVISION AND COORDINATION

A. Provide complete supervision, direction, scheduling, and coordination of all work under the Contract, including that of subcontractors.

B. Coordinate rough-in of all work and installation of sleeves, anchors, and supports for piping, ductwork, equipment, and other work performed under Division 23.

C. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.

D. Coordinate electrical work required under Division 23 with that under Division 26. Coordinate all work under Division 23 with work under all other Divisions.

E. Supply services of an experienced (10 year minimum) and competent Project Manager to be in constant charge of work at site.

F. Where a discrepancy exists within the specifications or drawings or between the specifications and drawings, the more stringent (or costly) requirement shall apply until clarification can be obtained from the Engineer. Failure to clarify such discrepancies with the Engineer will not relieve the Contractor of the responsibility of conforming to the requirements of the Contract.

G. Failure of contractor to obtain a full and complete set of contract documents (either before or after bidding) will not relieve the contractor of the responsibility of complying with the intent of the contract documents.

1.11. CUTTING AND PATCHING

A. Accomplish all cutting and patching necessary for the installation of work under Division 23. Damage resulting from this work to other work already in place, shall be repaired at Contractor's expense. Where cutting is required, perform work in neat and work¬manlike manner. Restore disturbed work to match and blend with existing construction and finish, using materials compatible with the original. Use mechanics skilled in the particular trades required.

B. Do not cut structural members without approval from the Architect or Engineer.

1.12. PENETRATION OF WATERPROOF CONSTRUCTION

A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls, and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary curbs, sleeves, flashings, fittings and caulking to make penetrations absolutely watertight.

B. Where pipes penetrate roofs, flash pipe with Stoneman Stormtite, Pate or approved equal, roof flashing assemblies with skirt and caulked counter flashing sleeve.

C. Furnish and install pitch pockets or weather tight curb assemblies where required.

D. Furnish and install roof drains, curbs, vent assemblies, and duct sleeves specifically designed for application to the particular roof construction, and install in accordance with the manufacturer's instructions. The Contractor shall be responsible for sleeve sizes and locations. All roof penetrations shall be installed in accordance with manufacturer’s instructions, the National Roofing Contractors Association, SMACNA, and as required by other divisions of these specifications.

E. All work associated with the existing roof shall be performed so as to maintain the existing roof warranty.

1.13. CONCRETE AND MASONRY WORK

A. Furnish and install concrete and masonry work for equipment foundations, supports, pads, and other items required under Division 23. Perform work in accordance with requirements of other applicable Divisions of these specifications.

B. Concrete shall test not less than 3,000 psi compressive strength after 28 days.

C. Grout shall be non-shrink, high strength mortar, free of iron of chlorides and suitable for use in contact with all metals, without caps or other protective finishes. Apply in accordance with manufacturer's instructions and standard grouting practices.

D. Paint the perimeter of all housekeeping pads safety yellow.

1.14. CONNECTIONS AND ALTERATIONS TO EXISTING WORK

A. Unless otherwise noted on the drawings, where existing mechanical work is removed, pipes, valves, ductwork, etc., shall be removed, including hangers, to a point below finished floors or behind finished walls and capped. Such point shall be far enough behind finished surfaces to allow for installation of normal thickness of required finish material.

B. Where work specified in Division 23 connects to existing equipment, piping, ductwork, etc., Contractor shall perform all necessary alterations, cuttings, fittings, etc., of existing work as may be necessary to make satisfactory connections between new and existing work, and to leave completed work in a finished and workmanlike condition.

C. Where the work specified under Division 23, or under other Divisions, requires relocation of existing equipment, piping, ductwork, etc., Contractor shall perform all work and make necessary changes to existing work as may be required to leave completed work in a finished and workmanlike condition. Where existing insulation is disturbed, replace insulation where removed or damaged equal to existing, in type, thickness, density, finish and thermal resistance (R-value) value.

D. Where the relocation of existing equipment is required for access or the installation

of new equipment, the contractor shall temporarily remove and/or relocate and re-install as required to leave the existing and new work in a finished and workman like condition.

1.15. DEMOLITION

A. Unless otherwise noted all existing equipment, piping, ductwork, etc., shall remain.

B. Where existing equipment is indicated to be removed, all associated piping, conduit, power, controls, control panels, sensors, tubing, insulation, hangers, ductwork, supports and housekeeping pads, etc., patch, paint and repair walls/roof/floor to match existing and/or new finishes.

C. Provide necessary piping, valves, traps, temporary feeds, drips, etc., as required. Drain and refill piping systems as often as necessary to accommodate phasing and to minimize time lengths of outages.

D. The Contractor shall be responsible for visiting the site and determining the existing conditions in which the work is to be performed.

E. Where any abandoned pipes in existing floors, walls, ceilings, etc., conflict with new work, remove abandoned pipes as necessary to accommodate new work.

F. The location of all existing equipment, piping, ductwork, etc., indicated is approximate only and shall be checked and verified. Install all new mechanical/plumbing/fire protection work to connect to or clear existing work as applicable.

G. Maintain egress at all times. Coordinate egress requirements with the State Fire Marshal, the Owner and the authorities having jurisdiction.

H. Make provisions and include in bid all costs associated with confined entry/space requirements in crawl spaces and all other applicable OSHA regulations.

I. Where required to maintain the existing systems in operation, temporarily backfeed existing systems from new equipment. Contractor shall temporarily extend existing piping systems to new piping systems with the appropriate shut-off valves.

J. At completion of project all temporary piping, valves, controls, etc., shall be removed in their entirely.

K. Existing piping, equipment, ductwork, materials, etc., not required for re-use or re-installation in this project, shall be removed from the project site.

L. Deliver to the Owner, on the premises where directed, existing equipment and materials which are removed and which are desired by the Owner or are indicated to remain the property of the Owner.

M. All other materials and equipment which are removed shall become property of the Contractor and shall be promptly removed, from the premises, and disposed of by

the Contractor, in an approved manner. Contractor shall be responsible for proper disposal of all removed equipment containing refrigerants. Contractor shall include in his bid all cost associated with the evacuation, removal and disposal of all existing equipment containing refrigerants in accordance with EPA and Health Department requirements.

N. Where piping and/or ductwork is removed, remove all pipe or ductwork hangers which were supporting the removed piping or ductwork. Patch the remaining penetration voids with like materials and paint to match existing construction.

O. Where required, provide and coordinate removal and re-installation of existing equipment. Take care to protect materials and equipment indicated for reuse. Contractor shall repair or replace items which are damaged. Contractor shall have Owner's representative present to confirm condition of equipment prior to demolition.

P. Before demolition begins, and in the presence of the Owners representative, test and note all deficiencies in all existing systems affected by demolition but not completely removed by demolition. Provide a copy of the list of system deficiencies to the Owner and the Engineer. Videotape existing conditions in each space prior to beginning demolition work.

Q. The Owner shall have the first right of refusal for all fixtures, devices and equipment removed by the Contractor.

R. All devices and equipment designated by the Owner to remain the property of the Owner shall be moved and stored by the Contractor at a location on site as designated by the Owner. It shall be the Contractor's responsibility to store all devices and equipment in a safe manner to prevent damage while stored.

S. All existing equipment refused by the Owner shall become the property of the Contractor and shall be removed from the site by the Contractor in a timely manner and disposed of in a legal manner.

T. Work Abandoned in Place: Cut and remove underground pipe a minimum of 2 inches beyond face of adjacent construction. Cap and patch surface to match existing finish.

U. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.

V. Terminate services and utilities in accordance with local laws, ordinances, rules and regulations.

W. Where hydronic system piping and equipment is removed, Contractor shall be responsible for proper disposal of all contained fluids containing glycol (ethylene or propylene), hazardous waste and water treatment chemicals. Contractor shall include in his bid all associated costs with the removal, testing, and disposal of hydronic system fluid in accordance with EPA, Health Department, and the Local Authority Having Jurisdiction.

1.16. DRIVE GUARDS

A. Provide safety guards on all exposed belt drives, motor couplings, and other rotating machinery. Provide fully enclosed guards where machinery is exposed from more than one direction.

B. When available, guards shall be factory fabricated and furnished with the equipment. Otherwise fabricate guards of heavy gauge steel, rigidly braced, removable, and finish to match equipment served. Provide openings for tachometers. Guards shall meet local, State and O.S.H.A. requirements.

1.17. VIBRATION ISOLATION

A. Furnish and install vibration isolators, flexible connections, supports, anchors and/or foundations required to prevent transmission of vibration from equipment, piping or ductwork to building structure. See Division 23 Section, “Vibration Control for HVAC, Plumbing and Fire Protection Equipment”.

1.18. ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

1.19. REFRIGERANT SYSTEM CAPS

A. For all exterior grade and roof mounted equipment containing refrigerant install lockable caps on service valves to prevent tampering. Lockable caps shall be Model NPR as manufactured by Rector Seal or approved equal. Provide Model NPR Novent screwdriver tool with swiveling tip. Caps shall be suitable and specific for the refrigerant type utilized.

1.20. DEFINITIONS

A. Approve - to permit use of material, equipment or methods conditional upon compliance with contract documents requirements.

B. Furnish and install or provide means to supply, erect, install, and connect to complete for readiness for regular operation, the particular work referred to.

C. Contractor means the mechanical contractor and any of his subcontractors, vendors, suppliers, or fabricators.

D. Piping includes pipe, all fittings, valves, hangers, insulation, identification, and other accessories relative to such piping.

E. Ductwork includes duct material, fittings, hangers, insulation, sealant, identification and other accessories

F. Concealed means hidden from sight in chases, formed spaces, shafts, hung ceilings, or embedded in construction.

G. Exposed means not installed underground or concealed as defined above.

H. Invert Elevation means the elevation of the inside bottom of pipe.

I. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceiling, and unexcavated spaces.

J. Review - limited observation or checking to ascertain general conformance with design concept of the work and with information given in contract documents. Such action does not constitute a waiver or alteration of the contract requirements.

K. Building Line: Exterior wall of building.

1.21. MINIMUM EFFICIENCY REQUIREMENTS

A. All heating, ventilating, and air conditioning equipment shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.

B. All piping, ductwork, and equipment insulation shall comply with ASHRAE Standard 90.1, latest edition.

C. All mechanical devices, controls, accessories, and components shall be manufactured to provide the minimum efficiency requirements as specified in ASHRAE Standard 90.1, latest edition.

D. Where Energy Star certification exists for equipment utilized on this project, the equipment must be Energy Star certified. Provide Energy Star certification with submittals.

1.22. SYSTEM INTEGRATION

A. For all HVAC equipment specified to be provided with packaged controls and interfaced with the automatic temperature control system, provide system integration between the equipment manufacturer and the automatic temperature control subcontractor.

B. HVAC equipment submittals requiring system integration as defined above must identify all required system integration points.

C. HVAC equipment manufacturers must coordinate with ATC subcontractor regarding system integration prior to submitting on the equipment.

D. A system integration meeting must be arranged by the Mechanical Contractor and include, but not be limited to the systems integrator for the HVAC equipment

manufacturer and the ATC Subcontractor. This portion of systems integration must occur prior to HVAC equipment being delivered to the project.

E. Once the HVAC equipment is on site, a second systems integration meeting must be arranged by the Mechanical Contractor to coordinate the packaged controls with the ATC system. The HVAC equipment manufacturer's representative familiar with system integration and the ATC subcontractor familiar with programming must be present.

F. A final system integrations meeting shall occur once all equipment is in place and ready for operation. The Mechanical Contractor, the HVAC equipment systems' integrator, and the ATC Subcontractor shall meet on site to jointly program, schedule, verify points, interlock devices, and fully set up all systems integration components.

G. All systems integration coordination, programming, and graphics must be completed prior to requesting commissioning and/or inspections by the Engineer of Record.

1.23. COORDINATION WITH DTCC I.T. DEPARTMENT

A. All equipment that interfaces with the internet shall be coordinated with the Delaware Technical and Community College I.T. Department to verify that the same is suitable for use on the Delaware Technical and Community College I.T. infrastructure. Coordinate with the Delaware Technical and Community College I.T. Department regarding the allowable frequency bands to avoid interference with the Delaware Technical and Community College I.T. infrastructure.

1.24. A2L REFRIGERANT REQUIREMENTS

A. All refrigerants utilized on this project shall be lower flammability and lower toxicity refrigerants as defined by ASHRAE Standard 34-Designation and Safety Classification of refrigerants. Per ASHRAE 34-2019, this project shall only utilize A2L refrigerants in HVAC equipment such as R-32 and R-454B.

B. Refrigerants classified as B-1, B2i, A2, B2, A3, and B3 shall not be utilized.

C. All scroll compressor products shall be manufactured in compliance with UL-60335-2-40.

D. All equipment including installations shall comply with ASHRAE 15-2022 requirements and International Mechanical Code requirements whichever is more stringent.

E. The installing contractor shall submit a declaration to the authority having jurisdiction that the refrigerant systems have been installed and tested per ASHRAE 15-2022.

F. Provide equipment with U.L listed refrigerant mitigation controls per ASHRAE 15-

2022 requirements.

G. HVAC equipment manufacturer shall submit calculations indicating compliance with ASHRAE 15-2022.

H. Furnish units with factory installed U.L. listed refrigeration mitigation controls per ASHRAE-15.

PART 2 - ELECTRICAL REQUIREMENTS

2.1. GENERAL MOTOR AND ELECTRICAL REQUIREMENTS

A. Furnish and install control and interlock wiring for the equipment furnished. In general, power wiring and motor starting equipment will be provided under Division 26. Carefully review the contract documents to coordinate the electrical work under Division 23 with the work under Division 26. Where the electrical requirements of the equipment furnished differ from the provisions made under Division 26, make the necessary allowances under Division 23. Where no electrical provisions are made under Division 26, include all necessary electrical work under Division 23.

B. All electrical work performed under Division 23 shall conform to the applicable requirements of Division 26 and conforming to the National Electrical Code. All wiring, conduit, etc., installed in ceiling plenums must be plenum rated per NFPA and the International Building Code.

C. Provide wiring diagrams with electrical characteristics and connection requirements.

D. Test Reports: Indicate test results verifying nominal efficiency and power factor for three phase motors larger than five (5) horsepower.

E. Protect motors stored on site from weather and moisture by maintaining factory covers and suitable weatherproof covering. For extended outdoor storage, remove motors from equipment and store separately.

F. All motors shall be furnished with visible nameplate indicating motor horsepower, voltage, phase, cycles, RPM, full load amps, locked rotor amps, frame size, manufacturer’s name and model number, service factor, power factor and efficiency.

G. Motors located in exterior locations, wet air streams, air cooled condensers, and outdoors shall be totally enclosed weatherproof epoxy-treated type.

H. Nominal efficiency and power factor shall be as scheduled at full load and rated voltage when tested in accordance with IEEE 112.

I. Brake horsepower load requirement at specified duty shall not exceed 85 percent of nameplate horsepower times NEMA service factor for motors with 1.0 and 1.15

service factors.

J. All single phase motors shall be provided with thermal protection: Internal protection shall automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature ratings of motor insulation. Thermal protection device shall automatically reset when motor temperature returns to normal range, unless otherwise indicated.

K. Where a motor disconnect is indicated downstream of a variable frequency drive (VFD) provide interlock wiring from the auxiliary contacts on the disconnect to the VFD to de-energize when the disconnect is turned “off”.

L. Where equipment under this Division is specified with integral disconnecting means, the same shall be a single disconnecting means for disconnecting all ungrounded main power supply conductors that is capable of being locked in the open (“off”) position in accordance with the National Electrical Code and the local electrical inspector.

2.2. MOTORS AND CONTROLS

A. Motors and controls shall conform to the latest requirements of IEEE, NEMA, NFPA-70 and shall be UL listed. Motor sizes are specified with the driven equipment. Motor starting and control equipment is specified either with the motor which is controlled or in an electrical specification section. The Contractor is advised to consult all specification sections to determine responsibility for motors and controls.

B. Motors shall be designed, built and tested in accordance with the latest revision of NEMA Standard MG I.

C. Motors used with variable-frequency controllers shall have ratings, characteristics, and features coordinated with and approved by the variable frequency controller (drive) manufacturer. As a minimum the following shall apply to variable frequency controlled motors:

1. Motors shall be manufactured to withstand peak voltages of 1600 volts with .1 microsecond rise time per NEMA MG-1.

2. Critical vibration frequencies of motor shall not be within operating range of variable frequency controller output.

3. Temperature rise: Match rating for Class B insulation.

4. Insulation: Class F.

5. Thermal Protection: Conform to MG1 requirements for thermally protected motors.

D. Motors shall be suitable for use under the conditions and with the equipment to which applied, and designed for operation on the electrical systems specified or

indicated.

1. Motor capacities shall be such that the horsepower rating and the rated full-load current will not be exceeded while operating under the specified operating conditions. Under no condition shall the motor current exceed that indicated on the nameplates.

2. Motor sizes noted in the individual equipment specifications are minimum requirements only. It is the responsibility of the equipment manufacturers and of the Contractor to furnish motors, electrical circuits and equipment of ample capacity to operate the equipment without overloading, exceeding the rated full-load current, or overheating at full-load capacity under the most severe operating service of this equipment. Motors shall have sufficient torque to accelerate the total WR2 of the driven equipment to operating speed.

3. Motors shall be continuous duty type and shall operate quietly at all speeds and loads.

4. Motors shall be designed for operation on 60 hertz power service. Unless otherwise specified or shown, motors less than ½ horsepower shall be single phase, and motors ½ horsepower and larger shall be 3 phase unless otherwise noted.

5. Motors shall be mounted so that the motor can be removed without removing the entire driven unit.

E. Single phase motors, smaller than 1/20 horsepower shall be ball or sleeve bearing; drip-proof, totally enclosed or explosion proof, as specified; 120 volts; permanent-split capacitor or shaded pole type. These motors shall not be used for general power purposes, and shall only be provided as built-in components of such mechanical equipment as fans, unit heaters, humidifiers and damper controllers. When approved by the Engineer, deviations from the specifications will be permitted as follows:

1. Open motors may be installed as part of an assembly where enclosure within a cabinet provides protection against moisture.

2. Motors used in conjunction with low voltage control systems may have a voltage rating less than 115 volts.

F. Single phase motors, greater than 1/20 horsepower and less than ½ horsepower shall be ball bearing; drip-proof, totally enclosed or explosion proof, as specified, with Class A or B insulation, as standard with the motor manufacturer; 115 or 120/208/240 volts as required; capacitor start-induction run, permanent split capacitor, or repulsion start-induction run type with minimum efficiency of 70 percent and a minimum full load power of 77 percent.

G. Except as otherwise specified in the various specification sections, 3 phase motors 60 horsepower and smaller shall be NEMA design B squirrel cage induction type

meeting the requirements of this paragraph. Motors shall be drip-proof, totally enclosed or explosion proof, as specified or indicated. Insulation shall be Class B or F, at 40 degrees C ambient temperature. Drip-proof motors shall have a 1.15 service factor and totally enclosed and explosion proof motors shall have a service factor of 1.00 or higher. Motors specified for operation at 480, 240, and 208 volts shall be nameplated 460, 230, 200 volts, respectively. Efficiencies and percent power factor at full load for three phase motors shall be not less than the values listed below for premium efficiency motors:

MOTOR NAMEPLATE	MINIMUM PERCENT EFFICIENCY AT NOMINAL SPEED AND RATED LOAD	MINIMUM PERCENT POWER FACTOR
1HP and above to	85.5 percent	84 percent
1-½ HP	86.5 percent	85 percent
2HP	86.5 percent	85 percent
3HP	89.5 percent	86 percent
5HP	89.5 percent	87 percent
7½ HP	91 percent	86 percent
10HP	91.7 percent	85 percent
15HP	93.0 percent	85 percent
20HP	93.0 percent	86 percent
25HP	93.6 percent	85 percent

H. Three phase motors ½ HP or greater shall be the Duty Master XE by Reliance Electric Company, Super-E Premium Efficiency of Baldor Motor and Drives, E-plus Efficient Standard Duty Motor of the Electric Motor Division of Gould, Inc., the MAC II High Efficiency motor of Westinghouse Electric Corp., the equivalent product of General Electric, or approved equal.

I. For motors serving equipment being controlled by a variable speed drive, motor shall be premium efficiency inverter duty rated.

J. Motor frames shall be NEMA Standard T-Frames of steel, aluminum, or cast iron with end brackets of cast-iron or aluminum with steel inserts.

K. Control of each motor shall be manual or automatic as specified for each in the

various mechanical sections. In general, and unless otherwise specified for a particular item in the various mechanical sections of the specifications, motor starters and controls shall be specified and provided under the various electrical sections of these specifications.

L. Provide manufacturer's warranty for all motors for minimum of 5 years including all labor and materials.

2.3. MOTOR INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Install securely on firm foundation. Mount ball bearing motors to support shaft regardless of shaft position.

C. Check line voltage and phase and ensure agreement with nameplate. Check that proper thermal overloads have been installed prior to operating motors.

D. Use adjustable motor mounting bases for belt-driven motors.

E. Align pulleys and install belts.

F. Tension belts according to manufacturer's written instructions.

2.4. WIRING DIAGRAMS

A. The Contractor is responsible for obtaining and submitting wiring diagrams for all major items of equipment.

B. Wiring diagrams shall be provided with shop drawings for all equipment requiring electric power.

C. Provide wiring diagrams for all major mechanical items of equipment to electrical contractor and ATC subcontractor for coordination.

2.5. ENCLOSURES

A. Electrical enclosures including factory provided enclosures, field provided and installed enclosures, and automatic temperature control system enclosures shall be as follows:

1. Dry Interior Locations: NEMA 1.

2. Damp/Wet Locations, Including Exterior Locations: NEMA 3R.

3. Corrosive Locations, Including Laboratories, Janitor's Closets, Chemical Storage Rooms and Similar Space: NEMA 4X.

PART 3 - EXECUTION

3.1. EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

A. Install equipment to provide maximum possible headroom, if mounting heights are not indicated.

B. Install equipment according to approved submittal data. Portions of the work are shown only in diagrammatic form. Refer conflicts to Architect.

C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.

D. Install mechanical equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.

E. Install equipment giving right of way to piping installed at required slope.

F. Install flexible connectors on equipment side of shutoff valves, horizontally and parallel to equipment shafts if possible.

G. Do not install equipment, ductwork, or piping over electrical gear, electrical panels, motor controllers, and similar electrical equipment. Install equipment, ductwork, and piping to maintain clear space above and in front of all electrical components per the National Electric Code.

3.2. SUPPORTS, HANGERS AND FOUNDATIONS

A. Provide supports, hangers, braces, attachments and foundations required for the work. Support and set the work in a thoroughly substantial and workman-like manner without placing strains on materials, equipment, or building structure, submit shop drawings for approval. Coordinate all work with the requirements of the structural division.

B. Supports, hangers, braces, and attachments shall be standard manufactured items or fabricated structural steel shapes. All interior hangers shall be galvanized or steel with rust inhibiting paint. For un-insulated copper piping provide copper hanger to prevent contact of dissimilar metals. All exterior hangers shall be constructed of stainless steel utilizing stainless steel rods, nuts, washers, bolts, etc.

C. Concrete housekeeping pads and foundations shall be not less than 4 inches high and shall extend a minimum of 6 inches beyond equipment bases. Provide wire-mesh reinforcement; chamfer exposed edges and corners; and finish exposed surfaces smooth.

D. Where new concrete housekeeping pads are placed on existing concrete, saw cut

the existing concrete to the perimeter dimension of the new pad to a depth of ½ inch. Break out the top ½ inch area of the existing concrete. Add stubs of #4 rebar angled into the existing concrete at a depth of approximately 50 percent of the existing slab thickness. The top portion of the rebar stub shall extend into the new pad by approximately 50 percent of its thickness. Furnish one rebar stub per every two square feet of new pad. Chemically bond the new concrete to the existing concrete.

3.3. PROVISIONS FOR ACCESS

A. The contractor shall provide access panels and doors for all concealed equipment, valves, strainers, dampers, filters, controls, control devices, cleanouts, fire dampers, damper operators, traps, and other devices requiring maintenance, service, adjustment, balancing or manual operation.

B. Where access doors are necessary, furnish and install manufactured painted steel door assemblies consisting of hinged door, key locks, and frame designed for the particular wall or ceiling construction. Properly locate each door. Door sizes shall be a minimum of 12 inches x 12 inches for hand access, 18 inches x 18 inches for shoulder access and 20 inches x 30 inches for full body access where required. Review locations and sizes with Architect prior to fabrication. Provide U.L. approved and labeled access doors where installed in fire rated walls or ceilings. Doors shall be Milcor Metal Access Doors as manufactured by Inland-Ryerson, Mifab, or approved equal.

1. Acoustical or Cement Plaster: Style B

2. Hard Finish Plaster: Style K or L

3. Masonry or Dry Wall: Style M

C. Where access is by means of liftout ceiling tiles or panels, mark each ceiling grid using small color-coded and numbered tabs. Provide a chart or index for identification. Place markers within ceiling grid not on ceiling tiles.

D. Access panels, doors, etc. described herein shall be furnished under the section of specifications providing the particular service and to be turned over to the pertinent trade for installation. Coordinate installation with installing contractor. All access doors shall be painted in baked enamel finish to match ceiling or wall finish. Label inside of access door as to what it serves.

E. Submit shop drawings indicating the proposed location of all access panels/doors. Access doors in finished spaces shall be coordinated with air devices, lighting and sprinklers to provide a neat and symmetrical appearance.

F. Where access doors are installed in wet locations (i.e. toilet rooms, and similar spaces, etc…) provide aluminum access doors/frames.

3.4. PAINTING AND FINISHES

A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc. shall be stainless steel.

B. Clean surfaces prior to application of insulation, adhesives, coatings, paint, or other finishes.

C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pretreatment.

D. Protect all finishes and restore any finishes damaged as a result of work under Division 23 to their original condition.

E. The preceding requirements apply to all work, whether exposed or concealed.

F. Remove all construction marking and writing from exposed equipment, ductwork, piping and building surfaces. Do not paint manufacturer's labels or tags.

G. All exposed ductwork, piping, equipment, etc. shall be painted. Colors shall be as stated in this division or as selected by the Architect and conform to ANSI Standards.

H. All exposed ductwork, piping, equipment, etc. in finished spaces shall be painted. Colors shall be as selected by the Architect and conform to ANSI Standards.

I. All exposed ductwork, piping, equipment, etc., in Mechanical Rooms, and Storage where PVC jacketed shall not require painting. Label and identify and color code as specified.

3.5. CLEANING OF SYSTEMS

A. Thoroughly clean systems after satisfactory completion of pressure tests and before permanently connecting fixtures, equipment, traps, strainers, and other accessory items. Blow out and flush piping until interior surfaces are free of foreign matter.

B. Flush piping in re-circulating water systems to remove cutting oil, excess pipe joint compound, solder slag and other foreign materials. Do not use system pumps until after cleaning and flushing has been accomplished to the satisfaction of the Engineer. Employ chemical cleaners, including a non-foaming detergent, not harmful to system components. After cleaning operation, final flushing and refilling, the residual alkalinity shall not exceed 300 parts per million. Submit a certificate of completion to Engineer stating name of Service Company used.

C. Maintain strainers and dirt pockets in clean condition.

D. Clean fans, ductwork, enclosures, registers, grilles, and diffusers at completion of work.

E. Install filters of equal efficiency to those specified in permanent air systems operated for temporary heating during construction. Replace with clean filters as specified prior to acceptance and after cleaning of system.

F. Pay for labor and materials required to locate and remove obstructions from systems that are clogged with construction refuse after acceptance. Replace and repair work disturbed during removal of obstructions.

G. Leave systems clean, and in complete running order.

H. All HVAC piping/equipment strainers must be pulled and cleaned prior to substantial completion. In addition six (6) months after substantial completion all HVAC piping/equipment strainers must be pulled and cleaned a second time. Document and submit verification of strainer cleaning to Engineer, Owner, and Construction Manager.

3.6. COLOR SELECTION

A. Color of finishes shall be as selected by the Architect.

B. Submit color of factory-finished equipment for acceptance prior to ordering.

3.7. PROTECTION OF WORK

A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.

B. Cover temporary openings in piping, ductwork, and equipment to prevent the entrance of water, dirt, debris, or other foreign matter. Deliver pipes and tubes with factory applied end caps.

C. Cover or otherwise protect all finishes.

D. Replace damaged materials, devices, finishes and equipment.

E. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, where stored inside.

F. Provide moisture protection for ductwork in areas which are not under roof or where ductwork would be exposed to rainwater.

3.8. OPERATION OF EQUIPMENT

A. Clean all systems and equipment prior to initial operation for testing, balancing, or

other purposes. Lubricate, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.

B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment. Where factory start-up of equipment is not specified, provide field start-up by qualified technician.

C. Submit factory start-up sheets or field start-ups sheets for all equipment prior to the commencement of testing and balancing work. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.

D. Do not use mechanical systems for temporary services or temporary conditioning during construction, unless approved by Owner in writing. Refer to Division 01 Section "Temporary Facilities and Controls" for temporary heating/cooling during construction.

E. Upon completion of work, clean and restore all equipment to new conditions; replace expendable items such as filters.

3.9. DEMONSTRATION AND TRAINING VIDEO RECORDINGS

A. General: Record demonstration and training video recordings. Record each training module separately.

1. At beginning of each training module, record each chart containing learning objective and lesson outline.

B. Video Recording Format: Provide high-quality color video recordings with menu navigation in format acceptable to Engineer

C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to show area of demonstration and training. Display continuous running time.

D. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.

E. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.

3.10. IDENTIFICATIONS, FLOW DIAGRAMS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS

A. Contractor shall submit for approval schematic piping diagrams of each piping system installed in the building. Diagrams shall indicate the location and the identification number of each valve in the particular system. Following approval by all authorities, the diagrams shall be framed, mounted under safety glass and hung in each Mechanical Room where directed. Contractor shall deliver the tracing or sepia from which the diagrams were reproduced to the Owner.

B. All valves shall be plainly tagged. For any bypass valves, install sign indicating valve position as “Normally Open” or “Normally Closed” as required.

C. All items of equipment, including motor starters, disconnects and ATC panels shall be furnished with white on black plastic permanent identification cards. Lettering shall be a minimum of ¼ inch high. Identification plates shall be secured, affixed to each piece of equipment, starters, disconnects, panels by screw or adhesive (tuff bond #TB2 or as approved equal).

D. Provide three (3) copies of operating and maintenance instructions for all principal items of equipment furnished. This material shall be bound as a volume of the Record and Information Booklet as hereinafter specified.

E. All lines piping and ductwork installed under this contract shall be stenciled with direction of flow arrows and with stenciled letters naming each pipe and ductwork and service. Refer to Division 23 Section, “HVAC Piping, Fittings, Valves, Etc.” and Division 23 Section, “HVAC Air Distribution”. Color-code all direction of flow arrows and labels. In finished spaces omit labeling and direction of flow arrows. Paint in color as selected by Architect.

F. Submit list of wording, symbols, letter size, and color coding for mechanical identification. Submit samples of equipment identification cards, piping labels, ductwork labels, and valve tags to Engineer for review prior to installation.

G. Provide at least 8 hours of straight time instruction to the operating personnel. Time of instruction shall be designated by the Owner. Additional instruction time for the automatic temperature control (ATC) system is specified in Division 23 Section, “Instrumentation & Controls of HVAC & Plumbing Systems”.

H. Contractor shall demonstrate Sequences of Operation of all equipment in presence of Owner’s representative, Engineer, and ATC subcontractor.

3.11. WALL AND FLOOR PENETRATION

A. All penetrations of partitions, ceilings, roofs and floors by ducts, piping or conduit under Division 23 shall be sleeved, sealed, and caulked airtight for sound and air transfer control. Penetrations of mechanical room partitions, ceilings, and floors shall be as specified in Division 23 Section, “Vibration Control for HVAC, Plumbing and Fire Protection Equipment”.

B. All penetration of fire rated assemblies shall be sleeved, sealed, caulked and protected to maintain the rating of the wall, roof, or floor. Fire Marshal approved U.L. assemblies shall be utilized. See Division 07 Section, “Fire Protection, HVAC & Plumbing Penetration Firestopping”.

C. Where piping extends through exterior walls or below grade, provide waterproof pipe penetration seals, as specified in another division of these specifications.

D. Provide pipe escutcheons and duct flanges for sleeved pipes and ducts in finished areas.

E. Piping sleeves:

1. Galvanized steel pipe, standard weight where pipes are exposed and roofs and concrete and masonry walls. On exterior walls provide anchor flange welded to perimeter.

2. Twenty-two (22) gauge galvanized steel elsewhere.

F. Ductwork sleeves: 20 gauge galvanized steel.

G. Extend all floor sleeves through floor at least 3/4-inches above finished floor, caulk sleeve the entire depth and furnish and install floor plate.

H. For renovation projects where new pipes or ducts penetrate existing floors, furnish ground penetrating radar to properly map out acceptable locations for pipe/duct penetrations. Review penetrations with Structural Engineer.

3.12. RECORD DRAWINGS

A. Upon completion of the mechanical installations, the Contractor shall deliver to the Architect one complete set of prints of the mechanical contract drawings which shall be legibly marked in red pencil to show all changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.

B. Contractor shall incorporate all sketches, addendums, value engineering, change orders, etc., into record drawings prior to delivering to Architect.

3.13. WARRANTY

A. Contractor's attention is directed to warranty obligations contained in the GENERAL CONDITIONS.

B. The above shall not in any way void or abrogate equipment manufacturer’s guarantee or warranty. Certificates of equipment manufacturer’s warranties shall be included in the operations and maintenance manuals.

C. The Contractor guarantees for a two (2) year period from the time of final

acceptance by the Owner.

1. That the work contains no faulty or imperfect material or equipment or any imperfect, careless, or unskilled workmanship.

2. That all work, equipment, machines, devices, etc. shall be adequate for the use to which they are intended, and shall operate with ordinary care and attention in a satisfactory and efficient manner.

3. That the contractor will re-execute, correct, repair, or remove and replace with proper work, without cost to the Owner, any work found to be deficient. The contractor shall also make good all damages caused to their work or materials in the process of complying with this section. Contractor shall repair and/or replace any/all damage to finishes and furniture resulting from their corrective work.

4. That the entire work shall be water-tight and leak-proof.

3.14. LUBRICATION

A. All bearings, motors, and all equipment requiring lubrication shall be provided with accessible fittings for same. Before turning over the equipment to the Owner, the Contractor shall fully lubricate each item of equipment, shall provide one year's supply of lubricant for each, and shall provide Owner with complete written lubricating instructions, together with diagram locating the points requiring lubrication. Include this information in the Record and Information Booklet.

B. In general, all motors and equipment shall be provided with grease lubricated roller or ball bearings with Alemite or equal accessible or extended grease fittings and drain plugs.

3.15. OPERATIONS AND MAINTENANCE MANUALS

A. The Contractor shall have prepared three (3) hardcopies and one (1) electronic copy of the Operations and Maintenance Manuals and deliver these copies of the booklet to the Owner. The booklet shall be as specified herein. The booklet must be approved and will not be accepted as final until so stamped.

B. The booklet shall be bound in a three ring loose-leaf binder similar to National No. 3881 with the following title lettered on the front: Operations and Maintenance Manuals –DTCC Carter Partnership Dental Suite - HVAC. No sheets larger than 8-1/2 inches x 11 inches shall be used, except sheets that are neatly folded to 8-1/2 inches x 11 inches and used as a pull-out. Provide divider tabs and table of contents for organizing and separating information.

C. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of Volume 1 (if applicable) of hard copies of the manual.

D. Provide the following data in the booklet:

1. As first entry, an approved letter indicating the starting/ending time of Contractor’s warranty period.

2. Maintenance, operation, and lubrication instructions on each piece of equipment furnished.

3. Complete catalog data on each piece of heating and air conditioning equipment furnished including approved shop drawing.

4. Manufacturer's extended limited warranties on equipment including but not limited to variable frequency drives, air conditioning compressors, and heat pumps.

5. Chart form indicating frequency and type of routine maintenance for all mechanical equipment. The chart shall also indicate model number of equipment, location and service.

6. Provide sales and authorized service representatives names, address, and phone numbers of all equipment and subcontractors.

7. Provide supplier and subcontractor’s names, address, and phone number.

8. Catalog data of all equipment, valves, etc. shall include wiring diagrams, parts list and assembly drawing.

9. Provide and install in locations as directed by the Owner, valve charts including valve tag number, valve type, valve model number, valve manufacturer, style, service and location. Each valve chart shall be enclosed in a durable polymer based frame with a cover safety glass.

10. Copy of the approved balancing report including duct leakage data.

11. Pre-Testing Air and Fluid Flow Rate Results (where required for existing buildings).

12. ATC systems including as-built ATC drawings of systems including internal of all panels.

13. Access panel charts with index illustrating the location and purpose of access panels.

14. Approved Health Department, HVAC Inspector, and Electrical Inspector Certificates.

15. Start-up reports for equipment.

16. Provide and install in locations as directed by Owner, filter charts, including filter type, size, model number, manufacturer, quantity and size for each filter utilized on the project. Filter charts shall be enclosed in a durable

polymer based frame with a cover safety glass.

17. Insert color graphic with embedded parameters for ATC system into record and information booklet.

18. Filter charts indicating equipment served, size, and type of filter required.

19. Documentation of strainer pulling and cleaning.

20. Certificate of ASHRAE 15 compliance for A2L refrigerants.

21. Pipe Pressure Test Logs/Reports.

E. Electronic copies of the manual shall be saved on USB flash drives, and shall be in searchable PDF format with interactive index tabs. Approved electronic copies shall be stored in flash drive zipper cases in front of volume 1 (if applicable) of hard copies of the manual.

F. Submit Record and Information Booklets prior to anticipated date of substantial completion for Engineer review and approval. Substantial completion requires that Record and Information booklets be reviewed and approved.

3.16. INSTALLATION AND COORDINATION DRAWINGS

A. Prepare, submit, and use composite installation and coordination drawings to assure proper coordination and installation of work. Drawings shall include, but not be limited, to the following:

1. Complete Ductwork, Plumbing, Sprinkler and HVAC Piping Drawings showing coordination with lights, electrical equipment, HVAC equipment and structural amenities.

B. Draw plans to a scale not less than 3/8-inch equals one foot. Include plans, sections, and elevations of proposed work, showing all equipment, piping and ductwork in areas involved. Fully dimension all work including lighting fixtures, conduits, pullboxes, panelboards, and other electrical work, walls, doors, ceilings, columns, beams, joists and other architectural and structural work.

C. Identify all equipment and devices on wiring diagrams and schematics. Where field connections are shown to factory-wired terminals, include manufacturer's literature showing internal wiring.

D. Refer to Division 01 Section “Project Management and Coordination” for additional requirements related to coordination drawings.

3.17. PIPING SYSTEMS TESTING

A. The entire new HVAC piping systems shall be tested hydrostatically before insulation covering is applied and proven tight under the following gauge pressures

for a duration of twenty-four (24) hours. Testing to be witnessed by Owner's representative and documented in writing.

SYSTEM	TEST PRESSURE
Heating Water Supply & Return Piping	100 psig
Refrigerant Piping	600 psig with Nitrogen

B. Ductwork pressure testing shall be as specified in another division of these specifications.

C. Testing and acceptance thereof shall be in accordance with local requirements and shall meet approval of authority having jurisdiction. Submit certificates and approved permits and insert one (1) copy in the Operations and Maintenance Manuals.

D. Refrigerant piping shall be tested utilizing nitrogen per equipment manufacturer’s requirements.

E. All testing shall be witnessed by Construction Manager.

F. All refrigerant piping shall be installed and tested per ASHRAE 15-Safety Standard for Refrigerant Systems.

3.18. EQUIPMENT BY OTHERS

A. This Contractor shall make all system connections required to equipment furnished and installed under other divisions or furnished by the Owner. Connections shall be complete in all respects to render this equipment functional to its fullest intent.

B. It shall be the responsibility of the supplier of this equipment to furnish complete instructions for connections. Failure to do so will not relieve this contractor of any responsibility for improper equipment operation.

3.19. ADDITIONAL FILTERS AND BELTS

A. One complete set of additional filters and belts shall be turned over to the owner upon final acceptance of the building by the owner. Provide correspondence to the Engineer (copy) documenting that additional filters and belts have been turned over to Owner.

B. All filters and belts shall be tagged and identified for equipment served. Furnish filters in protection wrap.

3.20. STRAINER CLEANING

A. All equipment strainers must be pulled and cleaned at substantial completion.

Document in writing and via digital photographs that all strainers have been pulled and cleaned.

B. One year after project substantial completion all strainers shall be pulled again and cleaned. Document in writing and via digital photographs that all strainers were pulled and clean at the one year after project substantial completion data.

C. Insert documentation that the strainers have been pulled and cleaned in the Record and Information Books.

D. Re-purge hydronic systems of all air after strainers are pulled and cleaned.

3.21. OUTAGES

A. Provide a minimum of fourteen (14) days notice to schedule outages. The Contractor shall include in their bid outages and/or work in occupied areas to occur on weekends, holidays, or at night. Coordinate and get approval of all outages with the Owner.

B. Submit Outage Request form, attached at end of this Section, to Owner for approval.

END OF SECTION 230500

OUTAGE REQUEST

DATE APPLIED: _____ BY: _____

DATE FOR OUTAGE: _____ FIRM: _____

START OUTAGE-TIME: _____ DATE: _____

END OUTAGE -- TIME: _____ DATE: _____

AREAS AND ROOMS: _____

FLOOR(S): _____

AREA(S): _____

ROOM(S): _____

WORK TO BE PERFORMED: _____

SYSTEM(S): _____

REQUEST APPROVED BY: _____

(FOREMAN OR OTHER PERSON IN CHARGE)

(FOR OWNER'S USE ONLY):

APPROVED: _____

YES ____ NO ___ BY: _____ DATE: _____

DATE/TIME-AS REQUESTED: _____ OTHER : _____

OWNER'S PRESENCE REQUIRED: _____

YES: ____ NO: ___ NAME: _____

POINT OF CONTACT: _____ PHONE: _____

SECTION 230505 - HVAC PIPING, FITTINGS AND VALVES

PART 1 - GENERAL

1.1. SUMMARY

A. The conditions of the contract and other general requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 23 Section, Common Work Results for HVAC and Division 01, General Requirements.

B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SYSTEM DESCRIPTION CONDITIONS

A. Provide all labor and materials necessary to furnish and install all piping systems on this project as herein specified and/or shown on the drawings. Final connections to equipment furnished in other sections of the specifications shall be included under this section.

B. All piping and insulation installed in ceiling plenums must be plenum rated and comply with NFPA and International Building Code (IBC).

C. Where more than one piping system material is specified, ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

D. Use unions, flanges, and couplings downstream of valves and at equipment or apparatus connections. Do not use direct welded or threaded connections to valves, equipment or other apparatus.

E. Use non-conducting dielectric connections whenever jointing dissimilar metals in open systems.

F. Provide pipe hangers and supports in accordance with ASTM B31.9 and MSS SP69 unless indicated otherwise.

G. Use 3/4 inch (20 mm) ball valves with cap and chain for drains at main shut-off valves, low points of piping, bases of vertical risers, and at equipment. Pipe to nearest floor drain.

H. At all runout piping serving equipment, use swing joints with elbows to prevent excessive movement of piping due to expansion.

1.3. QUALITY ASSURANCE

A. Valves: Manufacturer's name and pressure rating marked on valve body.

B. Welding Materials and Procedures: Conform to ASME Code and applicable state labor regulation. Provide certificate of compliance from authority having jurisdiction indicating approval of welders.

C. Welders Certification: In accordance with ASME Section 9.

D. All grooved joint couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be of the same manufacturer as the grooved components.

1. All castings used for coupling housings, fittings, and valve bodies shall be date stamped for quality assurance and traceability.

E. Maintain one copy of each document on site.

1.4. DELIVERY, STORAGE AND HANDLING

A. Deliver, store, protect and handle products to site under as hereinbefore specified.

B. Accept valves on site in shipping containers with labeling in place. Inspect for damage.

C. Provide temporary protective coating on cast iron and steel valves.

D. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

E. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed systems.

1.5. ENVIRONMENTAL REQUIREMENTS

A. Do not install underground piping when bedding is wet or frozen.

1.6. ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1. PIPE MATERIALS

A. All materials, unless otherwise specified, shall be new and of the best quality of their respective kinds, and shall conform to the requirements and ordinances of local, state and insurance authorities having jurisdiction.

1. Heating Water Supply & Return Piping (Inside of Building):

a. Manufactures: Victaulic, Grinnell, or Sure-Joint.
b. Pipe: Schedule 40 Black steel pipe, ASTM A53
1-1/2 inch and smaller - Type F, ASTM A53 steel (CW) with threaded joints
2 inch and larger - Grade B, Type E, ASTM A53 steel (ERW) with welded, flanged or grooved joints.
c. Fittings & Joints: 2-1/2 inches & larger, schedule 40 wrought steel ASTM A234 Grade WPB or Std. B16.9 long radius welding; factory-fabricated from ASTM A53 pipe; or ASTM A536 ductile iron; 2 inches & smaller 125 lb. std. cast iron screwed, ASTM Standard B16.4; or Vic-Press precision, cold drawn, stainless steel with elastomer O-ring seals. Joints shall be threaded or AWS D1.1 welded. Victaulic, Appollo/Shurjoint, or approved equal grooved joints shall be acceptable.
d. Flanges: Wrought steel Class 150 welding neck. ASTM Standard B16.5.
e. Grooved Joint Couplings: Two ductile iron housings, pressure responsive elastomer gasket, and ASTM A449 zinc electroplated steel bolts and nuts. Couplings shall comply with ASTM F1476 Standard Specification for the Performance of Gasketed Mechanical Couplings for Use in Piping Applications.
i. Rigid Type: Coupling housings shall be cast with offsetting, angle-pattern bolt pads to provide joint rigidity and support and hanging in accordance with ASNI B31.1 and B31.9.
1) Victaulic Style 107H, Apollo/Shurjoint Z-07, Installation-Ready or approved equal, for direct stab installation without field disassembly, with grade EHP gasket, suitable for water service to +250 degrees F.
ii. Flexible Type: For use in locations where vibration attenuation and stress relief are required, and for the elimination of flexible connectors. Victaulic Installation-Ready Style 177 or Style 77, or approved equal.
iii. 14” and Larger: AGS Series, two segment coupling with lead-in chamfer on housing key and wide width FlushSeal gasket. Victaulic Style W07 (rigid) and Style W77 (flexible), Apollo/Shurjoint 7707/7707N, or approved equal.
iv. Flange adapters shall be suitable for direct connection to ANSI Class 125 or 150 flanged components. Victaulic Style

741/W741, Apollo/Shurjoint 7041, or approved equal.

v. Rolled form grooves only. Cut grooves are prohibited.

vi. Verify gasket compatibility on Chemical Treatment piping.

f. Gate Valves: 2-1/2 inches & larger - IBBM, 150 lb. OS&Y grooved end or flanged; 2 inches & smaller - 150 lb. Bronze body bronze trim. Basis of Design: Victaulic Series 771V or approved equal. For valves 4 inch and larger located in mechanical equipment spaces 10 feet-0 inch or greater above finished floor, valve shall have chain wheel operators with chains extending to within 6 feet-0 inch above finished floor. Chain wheels and guides shall be galvanized.

g. Ball Valves: Shut-off valves 2 inches and smaller shall be ball valves. Ball valves shall be 600cwp, 150swp full port, with RPTFE seats, chrome plated ball and stem 2 ½ and larger, class 125 cast iron OS&Y IBBM gate valve, brass or bronze body, standard port, 2 piece body. Ball valves shall be VicPress end, threaded end or solder end as required to accommodate piping. Ball valves shall be as manufactured by Victaulic, Crane, Apollo, Nibco, Watts or engineer approved equal.

h. Globe Valves: 2-1/2 inches & larger – IBBM 125 lb.std. flanged, with No. 1 disc; 2 inches & smaller - bronze 150 lb. std. screw ends, with #1 disc.

i. Check Valves: 2-1/2 inches & larger – IBBM or stainless steel trim, 125 lb.std. grooved end or flanged spring-assisted swing check suitable for vertical or horizontal installation, with metal disc; 2 inch & smaller - 125 lb. std. screwed. Provide "silent" spring loaded check valves at all pump discharges. Victaulic Series 716/W715 or approved equal.

j. Balancing Valves: Victaulic Series 377/365, DeZurik Series 100, Fig. 118 or approved equal, ductile iron or cast iron construction, stainless steel bearings, nickel seats (3 inches and larger) non-lubricated, eccentric plug with EPDM, chlorobutyl rubber or Bunz-N resilient faced plugs suitable for 230 degrees F, semi-steel screwed with fig. 159, removable lever and open. nut for valves 3 inches and smaller.

k. Butterfly Valves: Victaulic Vic300 MasterSeal/ AGS-Vic300, DeZurik, Apollo 215L series, high performance, Milwaukee High Performance Valve, or Keystone K-Loc, type with infinite position lever (for 3-inches and smaller) and pressure-responsive seat or double seat type and memory stop. Provide gear operator on valves 4-inches and larger.

i. Valve stem shall be stainless steel, and shall be offset from the disc centerline to provide complete 360 degree circumferential seating.

ii. Valve shall be rated to +250 deg F in sizes through 12-inches.

iii. Seat shall be elastomer, of a grade suitable for the intended service. The seat shall be pressure responsive in sizes through 12 inches.

iv. For valves 4 inches and larger located 10 feet-0 inches or

more above finished floor shall be provided with chain operators with chains extending to within 6 feet-0 inches above finished floor. Chain wheel and guide shall be galvanized.

l. Extended Valve Stems: Provide and install round collar type extended valve stems on all valves installed in insulated piping. Valve stem and collar shall be selected to suit insulation thickness and maintain valve handles outside of insulation.

m. Alternate:

i. At contractors option all HVAC water supply and return lines may be copper type L (ASTM Std. B88) with wrought copper fittings (ASTM Std. B 16.22) with brazed or 95-5 silver solder joints lead and antimony based solders are prohibited and all bronze valves may be used on piping 2 inches and less in size.

ii. At Contractors option, copper press fittings may be utilized as manufactured by Viega Pro Press/ Mega Press, Apollo Press/Apollo Power Press, or Mueller Streamline Co. Viega, ProPress, and Mueller Streamline Co. Pressure Seal Fittings: Bronze or copper shall conform to ASME B16.51, ICC LC 1002, and IAPMO PS 117. ProPress fittings ½-inch thru 4- inch for use with ASTM B88 copper tube type L and ½-inch up to 1-1/4-inch annealed copper tube. ProPress fittings shall have an EPDM sealing element and Smart Connect (SC) feature. 2-1/2-inch thru 4-inch shall have a 420 stainless steel grip ring, PBT separator ring, EPDM sealing element and leak detection feature.

2. Refrigeration Piping:

a. Concealed: Tube Size ¾ -inch & Smaller:
ASTM B280, copper tube; Type ACR, soft annealed temper fittings; cast copper-alloy fittings for flared copper tubes; flared joints. Fittings shall be ASME B16.22, wrought copper. Joints shall be brazed, AWS A5.8, BCUP silver/phosphorous/copper alloy with melting range 1190 to 1480 degrees F.

b. Concealed: Tube Size 7/8 inch through 4-1/8inches:
Copper tube, Type ACR, soft annealed temper; wrought-copper, brazed-joint fittings; brazed joints.

c. Exposed: Tube Size ¾ Inch and Smaller:
Copper pipe, Type ASTM B88, Type K with brazed wrought-copper fittings conforming to ASME B16.22. Filler metal shall be brazing type conform to AWS A5.8.

d. Exposed: Tube Sizes 7/8 Inch and Larger:
Copper pipe, Type ASTM B88, Type K with brazed wrought-copper fittings conforming to ASME B16-22. Filler metal shall be brazing type conforming to AWS A5.8.

e. Brazed Joints: Braze joints using American Welding Society (AWS) classification BCuP-4 for brazing filler metal.

f. Flexible connectors: 500-psig (3450-kPa) minimum operating

pressure; stainless-steel core and high-tensile stainless-steel-braid covering; dehydrated, pressure tested, minimum 7 inches (180 mm) long.

g. Diaphragm Packless Valves:
500-psig (3450-kPa) working pressure and 275 degrees Fahrenheit (135 degrees C) working temperature; globe design with straight-through or angle pattern; forged-brass or bronze body and bonnet, phosphor bronze and stainless-steel diaphragms, rising stem and handwheel, stainless-steel spring, nylon seat disc, and with solder-end connections.

h. Packed-Angle Valves:500-psig (3450-kPa) working pressure and 275 degrees Fahrenheit (135 degrees C) working temperature; forged-brass or bronze body, forged-brass seal caps with copper gasket, back seating, rising stem and seat, molded stem packing, and with solder-end connections.

i. Check Valves: Smaller than NPS 1 (DN 25): 400-psig (2760-kPa) operating pressure and 285 degrees Fahrenheit (141 deg Celsius) operating temperature; cast-brass body, with removable piston, polytetrafluoroethylene seat, and stainless-steel spring; globe design. Valve shall be straight-through pattern, with brazed-end connections.

j. Check Valves: NPS 1 (DN 25) and Larger: 400-psig (2760-kPa) operating pressure and 285 degrees Fahrenheit (141 deg Celsius) operating temperature; cast-bronze body, with cast-bronze or forged-brass bolted bonnet; floating piston with mechanically retained polytetrafluoroethylene seat disc. Valve shall be straight-through or angle pattern, with solder-end connections.

k. Service Valves: 500-psig (3450-kPa) pressure rating; forged-brass body with copper stubs, brass caps, removable valve core, integral ball check valve, and with brazed-end connections.

3. Cooling Coil A/C Condensate Drain and Floor Drain Piping that is Collecting A/C Condensate Piping:

a. Pipe & Fittings: All A/C condensate drain piping, including floor drain piping that is collecting A/C condensate, shall be constructed of Type L copper tubing, with sweat fittings made with 95-5 solder. Washout plugs (cleanouts) shall be strategically located to allow periodic flush out of system. At a minimum, provide washout plugs at equipment connections and at direction changes of 90 degrees F or greater. Also install cleanout at all equipment traps for cleaning and service.

b. Provide backwater valve (ball float type) at connections of condensate piping to stormwater piping and air gap fitting. Backwater valve shall be Model Z1099 as manufactured by Zurn or approved equal. Backwater valve shall have drain coated cast iron body, plastic ball float, bronze backwater bushing and replaceable neoprene seat.

c. Exterior condensate pipe penetrations must exit exterior wall above flashing. Extend discharge away from exterior walls as detailed.

B. Steel pipe shall be similar and equal to National Tube Company, Grinnell, Republic, or Bethlehem black or zinc-coated (galvanized) as hereinafter specified. Pipe shall be free from all defects which may affect the durability for the intended use. Each length of pipe shall be stamped with the manufacturer's name.

C. Copper pipe shall be Revere, Anaconda or Chase with approved solder fittings.

2.2. PIPE HANGERS

A. All hangers for metallic piping shall be adjustable, wrought clevis type, or adjustable malleable split ring swivel type, having rods with machine threads. Hangers shall be Grinnell Company's Figure 260, Victaulic, or Shurjoint for pipe ¾-inch and larger, and Figure 65 for pipe 2-inches and smaller, or approved equal Victaulic, Shurjoint, Carpenter Patterson, or approved equal. Adjustable pipe stanchion with U-bolt shall be Grinnell Company's Figure 191. Pipe roller supports shall be Grinnell's Figure 181 or Figure 271 Victaulic or Shurjoint. Exterior pipe hangers shall be galvanized or stainless steel construction. For copper piping in direct contact with the hanger, hanger construction shall be copper coated to prevent contact of dissimilar metals similar to Grinnell's Figure CT-65. Hanger spacing and rod sizes for steel and copper pipe shall not be less than the following:

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
3/4 & 1	6	5	3/8
1 - ½	6	8	3/8
2	8	8	3/8
2 – ½	10	9	½

NOMINAL PIPE SIZE IN	STD. STEEL PIPE	MAXIMUM SPAN FT. COPPER TUBE	MINIMUM ROD DIAMETER INCHES OF ASTM A36 STEEL THREADED RODS
3	12	10	½
4	14	12	5/8
5	14	12	5/8
6	16	14	3/4
8	18	16	7/8
10	20	18	7/8
12	20	18	7/8

B. Anchors, guides, and roller supports shall be installed in accordance with the contract drawings and manufacturer's recommendations to provide pipe support and control pipe movement for all piping systems. Anchors and guides shall be securely attached to the pipe support structure. Submit shop drawing for proposed pipe support structure for guides and anchors for approval of the Structural Engineer. Pipe alignment guides shall be Fig. 255 Grinnell, or as approved equal. Guides shall be sized to accommodate the pipe with insulation. Guides shall be steel factory, fabricated, with bolted two section outer cylinder and base for alignment of piping and two section guiding spider for bolting to pipe.

C. Hangers for pipe sizes ½ to 1 ½ inch (13 to 38 mm): Carbon steel, adjustable swivel, split ring.

D. Hangers for cold pipe sizes 2 inches (50 mm) and over: Carbon steel, adjustable,

clevis.

E. Hangers for cold pipe sizes 2 to 4 inches (50 to 100 mm): Carbon steel, adjustable, clevis.

F. Hangers for cold pipe sizes 6 inches (150 mm) and over: adjustable steel yoke, cast iron roll, double hanger.

G. Multiple or Trapeze hangers: Steel channels with welded spacers and hanger rods.

H. Multiple or Trapeze hangers for hot pipe sizes 6 inches (150 mm) and over: Steel channels with welded spacers and hanger rod, cast iron roll.

I. Wall support for pipe sizes to 3 inches (76 mm): cast iron hook

J. Wall support for pipe sizes 4 inches (100 mm) and over: Welded steel bracket and wrought steel clamp.

K. Wall support for hot pipe sizes 6 inches (150 mm) and over: welded steel bracket and wrought steel clamp with adjustable steel yoke and cast iron roll.

L. Vertical Support: Steel riser clamp.

M. Floor support for cold pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

N. Floor support for hot pipe sizes to 4 inches (100 mm): Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

O. Floor support for hot pipe sizes 6 inches (150 mm) and over: Adjustable cast iron roll and stand, steel screws, and concrete pier or steel support.

P. Copper pipe support: Carbon steel ring, adjustable, copper plated.

Q. Hanger rods: Mild steel threaded both ends, threaded one end, or continuous threaded.

R. Inserts: Malleable iron case of galvanized steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

S. For exterior pipe supports provide stainless steel, supports, brackets, hardware and anchors.

T. For pipe hangers installed in corrosive environments such as chemical storage rooms, janitor’s closets…etc. the same shall (including hardware) shall be finished with on Electro-Galvanized Finish such as Galv-Krom® or approved equal.

2.3. VALVES

A. Provide parts list and assembly drawings (exploded view) for all valves in shop drawing submittals. Provide valves of the same type by the same manufacturer.

2.4. STRAINERS

A. Strainers shall be of the basket or "Y" type and shall be heavy and durable, constructed of ductile iron to ASTM A536 or the best grade gray iron with the bottoms drilled and plugged. Bodies shall have arrows clearly cast on the sides to show flow direction. Strainers shall be equipped with easily removable covers and brass sediment baskets made of stainless steel or brass not less than #22 gauge in thickness. Total area of basket perforations shall be not less than four times the cross section of the entering pipe. Flow shall be into basket, and then out through the perforations. Strainers shall be suitable for water or the intended fluid. Strainers 2 inches and smaller shall have threaded or solder ends, 2 inches and larger shall have flanged ends.

B. Strainer screens shall be stainless steel with perforations and shall be 1/16-inch for pipe sizes 5 inches and less, 1/8-inch (40 percent open area) perforations for pipe sizes 6-inch and greater.

C. Provide valved and capped (with chain) blowdowns in each strainer. Blowdown valves shall be Apollo 78-100/200 series or as approved equal.

D. Strainers shall be manufactured by Victaulic Style 732/W732, Watts, Mueller, Armstrong, Yarway, Spirax/Sarco, Apollo/Shurjoint 726, or as approved equal.

2.5. UNIONS, FLANGES, AND COUPLINGS

A. Unions in steel pipe 2-inches and smaller shall be malleable iron with brass inserted seats designed for a working pressure of 150 psig.

B. Unions in copper pipe 2-inches and smaller shall be sweat fittings with bronze seats designed for a working pressure of 125 psig.

C. Unions in stainless steel pipe 2-inches and smaller shall be hexagonal threaded type stainless steel unions, with VicPress ends. Basis of Design: Victaulic Style P584.

D. Flanges for steel pipe over 2 inches shall be 150 psig, forged steel, slip on. Gaskets shall be 1/16 inch thick pre-formed neoprene.

E. Flanges for copper pipe over 2 inches shall be bronze. Gaskets shall be 1/16 inch thick preformed neoprene.

2.6. MANUAL AIR VENTS

A. Manual air vents shall be similar to the hereinafter specified gauge valves. Provide 1/4-inch size on ¾-inch pipe and smaller, ½ -inch size on 1-inch pipe and larger. Install at all high points of piping. Valves shall be Crane No. 88, or as approved equal, with threaded ends, bronze body, bronze or brass bonnet and bronze stem.

2.7. THERMOMETERS

A. Unless otherwise indicated, thermometers shall be ASTM E1, in a glass type, organic filled, 9-inch scale size, corrosion-resistant metal case, with "any-angle" mounting with positive locking device. Trerice Industrial Thermometers, Weksler Instruments, Ernst Gage Co., Miljoco, or approved equal. Insertion stem length shall suite the pipe size and configuration. Thermometer wells shall be brass with brass union hubs in copper and in ferrous piping. Where piping is insulated or otherwise covered, use wells with lagging extension. Where wells are installed in pipe tees at turns, increase pipe size so that well does not restrict flow. Accuracy shall be 2 percent.

B. Unless otherwise indicated, thermometer ranges shall be as follows:

1. Heating Water: 30 degrees Fahrenheit to 240 degrees Fahrenheit, 2 degrees Fahrenheit Division.

C. Provide heat conducting compound in wells.

2.8. PRESSURE GAUGES

A. Unless otherwise indicated, pressure gauges shall be the bronze bourdon tube type, 4-1/2-inch dial, stem mounting, cast aluminum adjustable pointer, 1 percent accuracy over middle half of scale range, 1-1/2 percent over balance: Trerice Model 600C; Weksler Instruments, Ernst Gage Co., Miljoco, or as approved equal.

B. Gauges shall have pressure, vacuum, compound, or retard ranges as required, select ranges so that the normal readings are at the approximate midpoint and maximum system pressures do not exceed full scale.

C. Furnish and install a gauge valve at each pressure gauge. Gauge valves shall be Crane Model No. 88, Needle Valve, Ernst Gage Co. FLG 200, Wexler Instrument Corp. Type BBV4, or approved equal, rated for pressure intended.

D. Gauge connections for pressure gauges, thermometers, or control instruments shall be made using tee fittings, except that gauge connections up to 1-inch size in steel may be using threaded extra heavy pipe couplings welded directly to the main, provided that the main is at least 2-inch size for 2-inch connections, 3-inch size for 3/4-inch connections, and 4-inch size for 1-inch connections. Minimum gauge connection shall be 2-inch ips.

E. Provide snubbers on all gauges. Snubbers shall be No. 872 by Trerice, RS1/RS6

by Wexler Instruments, Miljoco or as approved equal.

2.9. FLOW METER FITTINGS

A. Griswold or Bell & Gossett Venturi disturbed flow measurement quickset flow meter fittings shall be utilized for hydronic flow measurement. Units shall consist of a spun steel venturi welded into the pipe. Disturbed fluid shall be channeled through the throat of the venturi with a multi-point Piezo Ring. Accuracy shall be ± 1% PSID with no straight pipe run required.

2.10. ESCUTCHEONS

A. Provide chromium plated escutcheons properly fitted and secured with set screws on all exposed piping which passes through walls, floors or ceilings of finished spaces.

B. All escutcheon plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface. Plastic escutcheon plates will not be accepted.

2.11. DIELECTRIC CONNECTIONS:

A. Furnish and install electrically insulated dielectric waterway fittings, unions or flanges, as manufactured by Victaulic Company Style 47, EPCO Sales, Inc., or approved equal at the following locations:

1. Where steel piping systems join copper piping.

2. Where copper tube connects to expansion tanks and other steel vessels.

3. Avoid the installation of steel nipples, cast iron or steel valves and specialties, or other ferrous components in predominately copper piping systems. Where such installation is necessary, isolate the component with dielectric connections. Do not mix steel pipe and copper tube in the same run of pipe or in the same section of a piping system.

4. Dielectric Waterway: Copper silicon casting conforming to UNS C87850 with grooved and/or threaded ends. UL classified in accordance with NSF-61 for potable water service, and shall meet the low-lead requirements of NSF-372. Basis of Design: Victaulic Series 647.

2.12. SLEEVES

A. Sleeves shall be provided around all pipes through walls, floors, ceilings, partitions, roof structure members or other building parts. Sleeves shall be standard weight galvanized iron pipe two sizes larger than the pipe or insulation so that pipe or insulation shall pass through masonry or concrete walls or floors. Provide 20

gauge galvanized steel sheet or galvanized pipe sleeves for all piping passing through frame walls.

B. Sleeves through floors shall be flush with the floor except for sleeves passing through Equipment Rooms which shall extend ¾-inch above the floor. Refer to Division 23 Section, Vibration Controls for HVAC, Plumbing and Fire Protection Equipment for mechanical equipment room penetrations additional requirements. Space between the pipe and sleeve shall be caulked. Escutcheon plates shall be constructed to conceal the ends of sleeves. Each trade shall be responsible for drilling existing floors and walls for necessary sleeve holes. Drilling methods and tools shall be as hereinbefore specified.

C. Sleeves through walls and floors shall be sealed with a waterproof caulking compound.

D. Firestop at sleeves that penetrate smoke barriers smoke partitions and/or rated walls/floors.

2.13. TEST PLUGS

A. Where indicated, furnish and install P/T plugs or Pete's Plugs as manufactured by IMAC Systems or approved equal.

B. Description: Nickel-plated, brass-body test plug in NPS 2 (DN15) fitting. Test plugs shall be as manufactured by Trerice, Watts, Natural Meter, Apollo Brass Test Plugs, or approved equal. Test-station fitting made for insertion in piping tee fitting.

C. Body: Length as required to extend beyond insulation. Brass or stainless steel with core inserts and gasketed and threaded cap. Include extended stem on units to be installed in insulated piping.

D. Thread Size: NPS ¼ (DN 8) or NPS ½ (DN15) as required, ASME B1.20.1 pipe thread.

E. Pressure Rating: 500 psig minimum.

F. Minimum Pressure and Temperature Rating: 500 psig at 200 deg F.

G. Core Inserts: One or two self-sealing valves, suitable for inserting 1/8 inch OD probe from dial-type thermometer or pressure gage. Chlorosulfonated polyethylene synthetic and EPDM self-sealing rubber.

H. Core Insert: Self-sealing valve, suitable for inserting 1/8 inch OD probe from dial-type thermometer or pressure gage.

I. Core Material for Air, Water, Oil, and Gas: 20 to 300 degrees F chlorosulfonated polyethylene synthetic rubber.

J. Test-Plug Cap: Gasketed and threaded cap, with retention chain or strap.

K. Self-closing valves with caps and retaining straps.

2.14. TRANSITION FITTINGS

A. General Requirements:

1. Same size as pipes to be joined.

2. Pressure rating at least equal to pipes to be joined.

3. End connections compatible with pipes to be joined.

B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.

C. Plastic-to-Metal Transition Fittings:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Charlotte Pipe and Foundry Company.
b. Harvel Plastics, Inc.
c. Spears Manufacturing Company.

2. Description: PVC or CPVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions; one end with threaded brass insert and one solvent-cement-socket end.

D. Plastic-to-Metal Transition Unions:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Colonial Engineering, Inc.
b. NIBCO INC.
c. Spears Manufacturing Company.

2. Description: PVC or CPVC four-part union. Include brass threaded end, solvent-cement-joint plastic end, rubber O-ring, and union nut.

PART 3 - EXECUTION

3.1. GENERAL PIPING INSTALLATION REQUIREMENTS

A. All pipes shall be cut accurately to measurements established at the building, and shall be worked into place without springing or forcing, properly clearing all windows, doors and other openings. Excessive cutting or other weakening of the building structure to facilitate piping installation will not be permitted. All pipes shall

be so installed as to permit free expansion and contraction without causing damage. All horizontal mains shall pitch down in the direction of flow with a grade of not less than 1 inch in 40 feet. All open ends of pipe lines, equipment, etc., shall be properly capped or plugged during installation to keep dirt or other foreign material out of the system. All pipes shall be run parallel with the lines of the building and as close to walls, columns and ceilings as may be practical, with proper pitch. All piping shall be arranged so as not to interfere with removal of other equipment on devices not to block access to doors, windows, manholes, or other access openings. Flanges or unions, as applicable for the type of piping specified, shall be provided in the piping at connections to all items of equipment, coils, etc., and installed so that there will be no interference with the installation of the equipment, ducts, etc. All valves and specialties shall be placed to permit easy operation and access and all valves shall be regulated, packed and glands adjusted at the completion of the work before final acceptance. All piping shall be installed so as to avoid air or liquid pockets throughout the work. Ends of pipe shall be reamed so as to remove all burrs.

B. All piping shall be graded to convey entrained air to high points where automatic air vents shall be provided. The size of supply and return pipes for each piece of equipment shall in no case be smaller than the outlets in the equipment.

C. All piping shall be run to provide a minimum clearance of 2-inches between finished covering on such piping and all adjacent work. Group piping wherever practical at common elevations.

D. All valves, strainers, caps, and other fittings shall be readily accessible.

E. Drain valves with hose connections shall be provided at low points for drainage of piping systems. Blow down valves shall be provided at the ends of all mains and branches so as to properly clean by blowing down the lines throughout in the direction of normal flow.

F. Discharge lines from all relief valves shall be piped to within 4-inches of floor and extend to floor drains wherever floors are not pitched to drains. Pitch the relief valve piping away from the relief valve to issue that no fluid can be trapped in valve discharge. Support all relief valve piping to prevent exerting strain on the relief valve body. The end of the relief valve discharge piping shall not be threaded to prevent capping or plugging.

G. All branches from water mains shall be taken from the top of the supply mains at an angle of forty-five (45) degrees above the horizontal, unless otherwise directed. Branches feeding down shall be taken from the side or bottom of the main on water mains only. All connections shall be carefully made to insure unrestricted circulation, eliminate air pockets or trapped condensate, and permit the complete drainage of the system.

H. Cutoff valves shall be provided on each branch line from the mains on all heating/air conditioning lines.

I. Shut-off valves shall be installed at the inlet and outlet of each coil and piece of

equipment to permit isolation for maintenance and repair. Units having multiple coils shall have separate valves for each coil.

J. Balancing valves shall be installed in all heating/air conditioning water branches and at all pumps, and where indicated on the drawings.

K. Unions shall be installed on all bypasses, ahead of all traps, at all connections to equipment, where shown on drawings or where required to facilitate removal of equipment whether shown or not.

L. Spring clamp plates (escutcheons) shall be provided where pipes are exposed in the building and run through walls, floors, or ceilings. Plates shall be chrome plated spun brass of plain pattern, and shall be set tight on the pipe and to the building surface.

M. If the size of any piping is not clearly evident in the drawings, the Contractor shall request instructions for the Engineer as to the proper sizing. Any changes resulting from the Contractor's failure to request clarification shall be at his expense. Where pipe size discrepancies or conflicts exist in the drawings, the larger pipe size shall govern.

N. Install all valves with stem upright or horizontal, not inverted.

O. Where pipe support members are welded to structural building framing, scrape, brush clean, weld and apply one coat of zinc rich primer.

P. Provide clearance for installation of insulation and access to valves and fittings.

Q. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.

R. Provide manual air vents at top of piping systems.

S. Due to phased construction and the fact that we are connecting to the existing piping systems in various locations, all new and existing piping shall be cleaned, flushed, and purged of air. All new and existing strainers shall be pulled and cleaned. Document strainer cleaning with digital photographs and include in the Operation and Maintenance Manuals.

3.2. THERMOMETER AND PRESSURE GAGE INSTALLATION REQUIREMENTS.

A. Install thermometers and adjust vertical and tilted positions.

B. Install separable sockets in vertical position in piping tees where fixed thermometers are indicated.

1. Install with socket extending to one-third diameter of pipe.

2. Fill sockets with oil or graphite and secure caps.

C. Install pressure gages in piping tees with pressure-gage valve located on a pipe at most readable location.

D. Adjust faces of thermometer and gages to proper angle for best visibility.

E. Clean windows of thermometer and gages and clean factory-finished surfaces. Replace cracked and broken window, and repair scratched and marred surfaces with manufacturer's touch up paint.

3.3. VALVE INSTALLATION REQUIREMENTS

A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.

B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

C. Operate valves from fully open to fully closed positions. Examine guides and seats made accessible by such operation.

D. Examine threads on valve and mating pipe for form and cleanliness.

E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.

F. Do not attempt to repair defective valves; replace with new valves.

G. Install valves as indicated, according to manufacturer's written instructions.

H. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.

I. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.

J. Locate valves for easy access and provide separate support where necessary.

K. Install valves in horizontal piping with stem at or above the center of the pipe.

L. Install valves in a position to allow full stem movement.

M. For chain wheel operators, extend chains to 60 inches above finished floor elevation.

N. Adjust or replace packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if leak persists.

O. Install flow control valves with clearances from center line of valve to ceiling to allow servicing as required by manufacturer.

P. Furnish and install Pete's plugs at all coils, pumps, pressure gauges, and hydronic equipment.

3.4. REFRIGERANT PIPING AND ACCESSORIES INSTALLATION REQUIREMENTS

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems; indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Shop Drawings.

B. Install and test refrigerant piping according to ASHRAE 15.

C. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise. All exposed piping shall be hard copper tubing with brazed joints. Refer to Architectural Contract Documents to determine exposed areas.

E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

F. Install piping adjacent to units to allow service and maintenance.

G. Install piping free of sags and bends. Install VEE clevis hangers and VEE troughs on pipes less than ¾"inch in diameter.

H. Install fittings for changes in direction and branch connections.

I. Select system components with pressure rating equal to or greater than system operating pressure.

J. Install piping as short and direct as possible, with a minimum number of joints, elbows, and fittings.

K. Arrange piping to allow inspection and service of refrigeration equipment. Install valves and specialties in accessible locations to allow for service and inspection. Install access doors or panels as specified if valves or equipment requiring maintenance is concealed behind finished surfaces.

L. Install refrigerant piping in protective conduit where installed below ground.

M. Install refrigerant piping in rigid or flexible conduit in locations where exposed to mechanical injury.

N. Slope refrigerant piping as follows:

1. Install horizontal hot-gas discharge piping with a uniform slope downward away from compressor.

2. Install horizontal suction lines with a uniform slope downward to compressor.

3. Install traps and double risers to entrain oil in vertical runs.

4. Liquid lines may be installed level.

O. When brazing, remove solenoid-valve coils and sight glasses; also remove valve stems, seats and packing, and accessible internal parts of refrigerant specialties. Do not apply heat near expansion-valve bulb.

P. Install piping with adequate clearance between pipe and adjacent walls and hangers or between pipes for insulation installation.

Q. Identify refrigerant piping and valves.

R. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Division 23 Section, “Common Work Results for HVAC”.

S. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Division 23 Section, “Common Work Results for HVAC”.

T. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Division 23 Section, “Common Work Results for HVAC”.

U. Install the following pipe attachments:

1. Adjustable steel clevis hangers for individual horizontal runs less than 20 feet (6m) long.

2. Roller hangers and spring hangers for individual horizontal runs 20 feet (6m) or longer.

3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet (6m) or longer, supported on a trapeze.

4. Spring hangers to support vertical runs.

5. Copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.

V. Install hangers for copper tubing with the following maximum spacing and minimum rod sizes:

1. NPS ½ (DN 15): Maximum span, 60 inches (1500mm); minimum rod size, ¼ inch (6.4mm).

2. NPS 5/8 (DN 18): Maximum span, 60 inches (1500mm); minimum rod size, ¼ inch (6.4mm).

3. NPS 1 (DN 25): Maximum span, 72 inches (1800mm); minimum rod size, ¼ inch (6.4mm).

4. NPS 1-1/4 (DN 32): Maximum span, 96 inches (2400mm); minimum rod size, 3/8 inch (9.5mm).

5. NPS 1-1/2 (DN 40): Maximum span, 96 inches (2400mm); minimum rod size, 3/8 inch (9.5mm).

6. NPS 2 (DN 50): Maximum span, 96 inches (2400mm); minimum rod size, 3/8 inch (9.5mm).

7. NPS 2-½ (DN 65): Maximum span, 108 inches (2700mm); minimum rod size, 3/8 inch (9.5mm).

8. NPS 3 (DN 80): Maximum span, 10 feet (3m); minimum rod size, 3/8 inch (9.5mm).

9. NPS 4 (DN 100): Maximum span, 12 feet (3.7m); minimum rod size, 1/2 inch (13mm).

W. For all interior refrigerant pipe/tubing that is less than 3/4inch in diameter, utilize VEE type clevis hanger Model 200 V and VEE type trough Model 200 VT; as manufactured by Carpenter and Patterson or approved equal. VEE trough materials shall be carbon steel with pre-galvanized finish. Install as required to maintain maximum hanger spacing requirements.

X. Support multifloor vertical runs at least at each floor.

Y. Furnish and install complete refrigerant piping systems between the indoor units and outdoor units. Support piping in accordance with Division 23 Section, HVAC Piping, Fittings, Valves, Etc. Piping shall be sized as recommended by unit manufacturer taking into account length of vertical and horizontal runs, and refrigerant type. Provide and install dual sets of refrigerant piping on all units required to have dual independent circuits.

Z. Furnish and install all required piping accessories including, but not limited to, thermal expansion valves, Sporlan, or approved equal; Packless isolation valves at condenser and evaporator coil, Henry or approved equal, charging valve with chained seal cap, Henry or approved equal, sight glasses, Henry or approved equal; filter dryer with replaceable cartridge, Sporlan, or approved equal, liquid line solenoid valve l20V/1/60 Hz., Sporlan, or approved equal. Contractor shall provide traps and double suction risers if required by equipment manufacturer. Pitch piping for proper oil return. Submit shop drawings on all components, and piping arrangements.

AA. All accessories shall be ARI rated. Furnish required nitrogen and refrigerant to fully test and charge system. Flood piping system with nitrogen when brazing.

BB. Refrigerant piping shall be Type 1 hard temper (ACR) copper tubing with wrought copper brazed fittings. Make joints with brazed wrought copper fittings.

CC. Refrigerant piping shall be cleaned, dehydrated and evacuated. Piping shall be evacuated and held to less than 2.5 mm Hg vacuum for a period of not less than 12 hours without appreciable pressure rise. Vacuum shall then be broken with refrigerant or dry nitrogen and re-evacuated to 2.5 mm Hg vacuum for an additional 12 hours. Piping test to be witnessed by Owner's representative and documented in writing. Submit results of tests to Architect/Engineer.

DD. All refrigerant/suction lines sets shall be fully insulated. Exterior pipe insulation shall be fully jacketed as specified in Division 23 Section, “HVAC Insulation”. Exposed interior pipe insulation shall be fully jacketed as specified in Division 23 Section, “HVAC Insulation”.

EE. Follow ASHRAE 15, latest edition procedures for charging and purging of systems and for disposal of refrigerant.

FF. Provide replaceable cartridge filter-driers, with isolation valves and valved bypass.

GG. Locate expansion valve sensing bulb immediately downstream of evaporator on suction line.

HH. Provide external equalizer piping on expansion valves with refrigerant distributor connected to evaporator.

II. Install flexible connectors at right angles to axial movement of compressor, parallel to crankshaft.

JJ. Fully charge completed system with refrigerant after tested.

KK. Provide electrical connection to solenoid valves.

LL. Refrigerant monitoring piping shall be connected to refrigerant monitoring equipment and piped per the Manufacturer's requirements.

MM. Install liquid indicators in liquid line leaving condenser, in liquid line, and on leaving side of liquid solenoid valves.

NN. Install strainers immediately upstream from each automatic valve, including expansion valves, solenoid valves, hot-gas bypass valves, and compressor suction valves.

OO. Install strainers in main liquid line where multiple expansion valves with integral strainers are used.

PP. Install moisture-liquid indicators in liquid lines between filter-dryers and thermostatic expansion valves and in liquid line to receiver.

QQ. Install flexible connectors at or near compressors where piping configuration does not absorb vibration.

RR. Test and inspect refrigerant piping according to ASME B31.5, Chapter VI.

1. Test refrigerant piping, specialties. Isolate compressor, condenser, evaporator, and safety devices from test pressure.

2. Test high- and low-pressure side piping of each system at not less than the lower of the design pressure or the setting of pressure relief device protecting high and low side of system.

    a. System shall maintain test pressure at the manifold gage throughout duration of test.
    b. Test joints and fittings by brushing a small amount of soap and glycerin solution over joint.
    c. Fill system with nitrogen to raise a test pressure of 150 psig (1035 kPa) or higher as required by authorities having jurisdiction.
    d. Remake leaking joints using new materials, and retest until satisfactory results are achieved.

SS. Adjust thermostatic expansion valve to obtain proper evaporator superheat requirements.

TT. Adjust high- and low-pressure switch settings to avoid short cycling in response to fluctuating suction pressure.

UU. Adjust set-point temperature of the conditioned air controllers to the system design temperature.

VV. Perform the following adjustments before operating the refrigeration system, according to manufacturer's written instructions:

1. Open shutoff valves in condenser water circuit.

2. Check compressor oil level above center of sight glass.

3. Open compressor suction and discharge valves.

4. Open refrigerant valves, except bypass valves that are used for other purposes.

5. Check compressor-motor alignment, and lubricate motors and bearings.

WW. Before installing copper tubing other than Type ACR, clean tubing and fittings with trichloroethylene.

XX. Replace core of filter-dryer after system has been adjusted and design flow rates and pressures are established.

YY. Charge system using the following procedures:

1. Install core in filter-dryer after leak test but before evacuation.

2. Evacuate entire refrigerant system with a vacuum pump to a vacuum of 500 micrometers (67 Pa). If vacuum holds for 12 hours, system is ready for charging.

3. Break vacuum with refrigerant gas, allowing pressure to build up to 2 psig (14 kPa).

4. Charge system with a new filter-dryer core in charging line. Provide full-operating charge.

3.5. PIPE JOINTS INSTALLATION REQUIREMENTS

A. Grooved Joints: Grooved joint shall be installed in accordance with the manufacturer's written recommendations. Grooved ends shall be clean and free from indentations, projections, or roll marks. The gasket shall be molded and produced by the coupling manufacturer of an elastomer suitable for the intended service. The coupling manufacturer's factory trained representative shall provide on-site training for the contractor's field personnel in the use of grooving tools and installation of product. The representative shall periodically visit the job site to ensure best practices in grooved product installation are being followed. (A distributor's representative is not considered qualified to conduct the training.)

B. Screwed Joints: All screwed joints shall be made with tapered threads properly cut. Screwed joints shall be made perfectly tight with a stiff mixture of graphite and oil, applied with a brush to the male threads on the fittings.

C. Brazed Joints and Copper Piping: Joints in copper piping shall conform to the following minimum standards.

1. The pipes shall be cut to a length making certain that the ends are square, using a fins hacksaw blade or tube cutter. The ends of all pipes shall be reamed and all burrs removed.

2. The outside end of the pipe and the cut end of the fitting shall be cleaned with steel wool, sand cloth, or steel wire brush. All dark spots shall be removed.

3. The flux shall be applied evenly and sparingly to the outside end of the pipe and the inside of the outer end of the fitting until all surfaces to be jointed are completely covered. The piping and fitting shall be slipped together and reworked several times to insure an even distribution of the flux.

4. The correct amount of brazing material per joint for each size pipe shall be used in accordance with the manufacturer's recommendations.

5. Brazed joints shall be made by using a direct flame from a torch.

6. On pipe sizes larger than ¼-inch, the fittings and valves in the pipe shall be

moved or tapped with a hammer when the brazing material starts to melt to insure an even distribution of the brazing material.

7. The excess brazing material shall be removed while it is still in the plastic state leaving a fillet around the cup of the fitting.

8. Brazed joints shall be suitable for working pressure of 550 psig and for working temperature of not less than 250 degrees F. The type of brazing material and flux used will be submitted for approval. Type 95-5 shall be the minimum standard.

9. Lead and antimony-based solders shall not be used for potable water systems. Brazing and silver solders are acceptable.

D. Where copper piping joins steel piping, approved bronze adapters shall be used.

E. Prohibited Connections: No direct weld or brazed connections without unions or flanges, shall be made to valves, strainers, apparatus, or related equipment. Right and left couplings, long threads, or caulking of pipe threads or gasket joints will not be permitted.

3.6. HANGERS, SUPPORTS, ANCHORS, GUIDES INSTALLATION REQUIREMENTS

A. General: All hangers shall be of an approved type arranged to maintain the required grading and pitching of lines to prevent vibration and to provide for expansion and contraction. Provide protection saddles between hangers and insulation on heating water insulated pipe. Saddles shall be Grinnells Figure 173/273 or approved equal. Provide approved spacers between saddles and pipe where flexible insulation is specified. Provide insulation protection shields for insulated piping without saddles. Shield shall be Grinnell Figure 167 or as approved equal.

B. Spacing: Regardless of spacing, hangers shall be provided at or near all changes in direction, both vertical and horizontal, for all piping.

C. Vertical Lines: Shall be supported at their bases, using either a suitable hanger placed in a horizontal line near the riser, or a base type fitting set on a pedestal, foundation or support. All vertical lines extending through more than one floor level shall be supported at each floor with a riser clamp. Riser clamp shall be Grinnell Co.'s Figure 261, or approved equal. All vertical drops to pump suction elbows shall be supported by floor posts.

D. Racks and Brackets: All horizontal piping on vertical walls shall be properly supported by suitable racks securely anchored into the wall construction. Where not practical to obtain ceiling anchorage, all piping near walls shall be supported by approved brackets securely anchored into the wall construction. Washer plates (Fib. 60, 60L) and other miscellaneous attachments, fasteners, etc., shall be Grinnell or as approved equal. All exterior hanger and bracket systems in their entirety shall be galvanized.

E. Pipe Hangers and supports shall be attached to the panel point at the top chord of bar joist or at a location approved by the structural engineer.

F. Select hangers and components for loads imposed. Secure rods with double nuts.

G. Support of horizontal piping shall allow for vertical adjustment after installation of piping.

H. Support overhead piping with clevis hangers.

I. Do not support all parallel piping from the same joist. Stagger all supports in accordance with the structural engineer's recommendations.

J. Refer to structural documents for appropriate connection/attachment materials to building.

3.7. AIR VENTING INSTALLATION REQUIREMENTS

A. The top of each hydronic water supply and return piping and other points as indicated or where necessary for the removal of air from the system or equipment, shall be vented using an approved type of manual air vent.

B. In addition to manual air vents at high points of system, each item of water heat transfer equipment shall be manually vented using an approved type manual air vent. All air vents shall be accessible.

3.8. EXPANSION LOOPS AND SWING CONNECTION INSTALLATION REQUIREMENTS

A. Connect risers and branch connections to mains with at least five pipe fittings, including tee in main.

B. Connect risers and branch connections to terminal units with at least four pipe fittings, including tee in riser.

C. Connect mains and branch connections to terminal units with at least four pipe fittings, including tee in main.

3.9. PIPING IDENTIFICATION INSTALLATION REQUIREMENTS

A. All piping shall be identified with painted background marked with the name of the service with arrows to indicate flow direction. Color code and system identification shall comply with ANSI Standards and piping identification system shall comply with ASME A13.1-81., scheme for the identification of piping systems and ASHRAE Fundamentals Handbook, latest edition.

B. Markings shall be plain block letters, stenciled on pipes, and shall be located near each branch connection, near each valve, and at least every 10 feet on straight runs of pipe. Where pipes are adjacent to each other, markings shall be neatly

lined up. All markings shall be located in such manner as to be easily legible from the floor. Pipe identification schedule shall be as follows:

OUTSIDE DIAMETER OF PIPE OR COVERING (INCHES)	LENGTH OF COLOR FIELD (INCHES)	SIZE OF LETTERS (INCHES)
½ to 1 ¼	8	½
1-½ to 2	8	¾
2 ½ to 6	12	1 ¼
8 to 10	24	2 ½
Over 10	32	3 ½

3.10. VALVE IDENTIFICATION REQUIREMENTS

A. All valves shall be tagged with a numbered tag.

B. The tags shall be made of 1-inch diameter brass tags fastened to the valve by means of brass chains. Numbers shall agree with valve numbers on diagrammatic herein before specified.

C. Provide a minimum of three (3) valve charts with valve numbers indicating valve type, size, manufacturer and service.

D. Additional valve charts shall be mounted behind glazed wooden frames and be hung in each mechanical equipment room including each air handling unit mechanical equipment room. Additional copies shall be provided in each copy of the O&M manuals.

3.11. CLEANING PIPING AND EQUIPMENT

A. All condensate, heating water, and HVAC systems shall be cleaned by filling with

a solution of one (1) pound of trisodium phosphate to each 50 gallons of water and circulating this solution for a period of six (6) hours during which time the system shall reach operating temperature. The systems shall then be flushed with fresh water and refilled with fresh water and/or where indicated antifreeze solution and purged of all air.

B. New and existing piping systems shall be cleaned, flushed, and purged.

C. All heating water, and pumped condensate piping systems shall be flushed clean with fresh water. See Division 22 Sections, Plumbing Fixtures and Plumbing Equipment for domestic potable water cleaning and sterilization.

D. Any equipment, such as coils that have small tubing, shall be bypassed to prevent deposition of debris from the piping. Water balancing shall not be scheduled until the completion of the cleaning and treatment process.

E. All new and existing strainers shall be inspected and cleaned prior to testing and balancing. In addition, prior to substantial completion, contractor must inspect and clean all new and existing strainers.

F. Where new equipment is connected to existing piping systems, install temporary bypasses as required for flushing new equipment piping.

3.12. PRESSURE SEAL FITTING INSTALLATION REQUIREMENTS

A. Viega, ProPress Pressure Seal bronze or copper fittings: Sealing element shall be verified for the intended use. Tube ends shall be cut on a right angle (square) to the tube. Tube ends shall be reamed and chamfered, all grease, oil or dirt shall be removed from the tube end with a clean rag. Visually examine the fitting sealing element to ensure there is no damage, and it is properly seated into the fitting. Utilizing a Viega Insertion Depth Inspection Gauge mark the tube wall, with a felt tip pen, at the appropriate location, or insert the tube fully into the fitting and mark the tube wall at the face of the fitting. Always examine the tube to ensure it is fully inserted into the fitting prior to pressing the joint. ProPress fittings ½-inch thru 4-inch shall be installed according to the most current edition of the Viega installation guidelines, using appropriate sized rigid ProPress tools. Installers shall attend a Viega ProPress installation training class.

B. After ProPress Pressure Seal fittings have been installed a “two step test” shall be followed. Pressurize the system with application appropriate test medium, water between 15 and 85 psi, or air/dry nitrogen between .5 and 45 psi. Check the pressure gauge for pressure loss. If the system does not hold pressure, walk the system and check for un-pressed fittings. Should you identify an un-pressed fitting ensure the tube is fully inserted into the fitting, and properly marked, prior to pressing the joint. After appropriate repairs have been made, retest the system per specification requirements, not to exceed 600 psi with water.

3.13. CLEANING/FLUSHING/PURGING PIPING AND EQUIPMENT

A. The Contractor shall submit a detailed written flushing plan including shop drawings depicting locations of temporary bypasses, strainers, vents, drains, isolation valves and temporary spool pieces for review and approval by the Engineer of Record.

B. All hot water systems shall be cleaned by filling with a solution of one (1) pound of trisodium phosphate to each 50 gallons of water and circulating this solution for a period of five (5) days during which time the system shall reach operating temperature. The systems shall then be flushed with fresh water and refilled with fresh water and antifreeze and purged of all air.

C. Any equipment, such as coils that have small tubing, shall be bypassed to prevent deposition of debris from the piping. Water balancing shall not be scheduled until the completion of the cleaning and treatment process.

D. All strainers shall be inspected and cleaned prior to testing and balancing. In addition, prior to substantial completion, contractor must inspect and clean all strainers.

E. Flushing & Treatment:

1. The hot water systems shall be thoroughly flushed and treated.

2. Flushing and Treatment shall be witnessed by representatives of the Mechanical Contractor, Chemical Treatment Contractor, Engineer of Record, and Owner.

3. The phasing layout and complexity of the piping system may require the system to be separately flushed in sections.

F. Chemical Water Treatment Contractor:

1. The Contractor shall submit to the Engineer of Record the Proposed Chemical Treatment Contractor Company information and Qualifications along with the proposed chemical cleaning, dispersant, & inhibitor brands and concentrations of the chemicals for review and approval.

G. Pumps:

1. Temporary Pump System:

a. The incorporation and use of temporary pump systems is recommended for the flushing & cleaning process. The Contractor shall size the temporary pump system to ensure a fluid velocity of 6 FPS through the largest pipe diameter in the system.
b. The Contractor shall submit documentation to the Engineer of Record for approval of the proposed temporary pump system. This shall include pump curves, flow meters to prove the required velocity, pressure gauges, connection details and temporary power

requirements along with a written description and photos of the proposed temporary pump system.

2. Permanent Facility Pump Systems:

   a. In the event temporary pumps cannot be utilized for the flushing and cleaning process, the existing permanent facility pump systems may be used only with prior approval of the Engineer of Record. The Contractor shall submit documentation to the Engineer of Record for approval of the proposed use of the Permanent Facility pump system. This shall include verification that the permanent facility pump system is capable of achieving the required fluid velocity of 6 FPS through the largest pipe diameter in the system, pump curves, flow meters to prove the required velocity, pressure gauges, connection details and power requirements along with a written description and photos of the proposed Permanent Facility pump system.
   b. In exchange for the use of the permanent facility pump system, The Contractor shall engage the Pump Manufacturer at the end of the cleaning/flushing process to disassemble the pump bodies and fully inspect the condition of the impellers, seals, bearings, wear rings, and motors for any damage caused by the flushing process. The Pump Manufacturer shall provide a written report with documenting photos of the condition of the pump system to the Engineer of Record. The permanent facility pumps must be in new condition and unconditionally warranted for a period of 2 years from the date of Project Substantial Completion. In the event a pump or pumps fail and is proven to be a result of the cleaning/flushing process during the 2 year warranty period the Contractor shall provide an additional 2 year extended warranty from the date of repair/replacement on the failed pump system.

H. Bypasses, Vents, Drains, Strainers, Isolation Valves, Temporary Spool Pieces & Hoses:

The Contractor shall prepare the piping system to ensure equipment and fragile devices are protected from damage caused by the flushing process.

1. The Contractor shall isolate & bypass all major equipment, coils, ancillary equipment, control valves, check valves, insertion type & inline flow meters and any other fragile device that may be damaged as a result of the cleaning/flushing process. The Contractor shall incorporate the use of Line Size temporary flanged / union spool pieces in locations where fragile devices were removed.

2. The Contractor shall install high point air vents and low point drains where required. The layout of the piping system may require additional secondary high point vents and low point drains to ensure the system can be fully vented and drained during the cleaning/flushing process. The Contractor shall depict on the Flushing procedure shop drawings all required and

secondary vents & drains. Secondary vents and drains shall be at No additional costs to the Owner.

3. The Contractor shall provide and install strainers where required.

I. Flushing Operation:

1. Pre Flush - Bypass loops should be installed at all equipment components. Strainers can be removed when a self-contained purge unit is used in conjunction with on board filtration. Flush ports should be identified along with the type of high pressure hose or piping that will be used to connect to the system. The water source should be identified and must be adequate to fill and make up water in a timely manner to the system during the flush process.

2. Clear Water Flush – Fill the piping system with clean potable water. The first flush is a clear- water flush intended to circulate water through the system and force loose debris to low point drains and the flush cart filtration system. This flush should be at minimum velocity throughout the system of 5 to 7 ft/sec. Filtration size shall be 25 micron.

3. Cleaning & Passivation - The second flush cycle is a combined flushing cycle where cleaning and passivation chemicals are introduced into the system to clean the oils and treat the inside wall of the piping system. This process will be monitored by the chemical treatment company to meet the chemical specifications of the water. The cleaning velocity should be between 3 to 5 ft/sec and the circulation time will be based on the chemical testing but will typically be up to 48 hours.

4. A circulation pump shall be sized to meet a fluid velocity of 6 FPS in the largest pipe main. Add by-pass piping for continuous circulation at each end where required.

5. The system shall be filled from the lowest available point; all vents and high point connections shall be open during this operation to allow the air in the system to vent off. Fill system with fresh water and circulate for 12-24 hours and flush to remove large sediment first.

6. Drain system from all lowest possible points and refill with fresh water.

7. Add a System Cleaner/Dispersant: Liquid alkaline compound with emulsifying agents and detergents to remove grease and petroleum products, similar to Bond - 8050 Closed System Cleaner, at a dosage of 15 gallons per 1000 gallons of system volume, and circulate for 24 hours.

8. All new installed equipment (such as water source heat pumps, HX’s, expansion tanks, etc.) which are not to be subjected to chemical cleaning and flushing, shall be disconnected from the piping. Add by-pass loops at each branch pipe to ensure continuous circulation of flushing fluids. Circulating pump must run continuously during the entire cleaning and

flushing procedure to assure proper cleaning.

9. Drain system from all of the lowest points until the pH is equal to fresh potable water make-up (< 8.0).

10. Circulate the system water again after flushing for 12 hours, then drain system again if water is still turbid.

11. If system water is clean at test valves on lower section of system proceed to step 13. If the system is still turbid fill circulate for another 12 hours and flush until it is clear.

12. Refill system with fresh water and add corrosion inhibitor, similar to Bond-5010 Molybdum, to system water to achieve the desired residual (50-150ppm).

13. The system must be tested after 2-3 weeks of operation to ensure the chemical residual is adequate and maintained.

14. Submit Piping System Flushing report of cleaning and flushing. Report is to include largest main, circulation pump sizing (flow and head), system volume (in gal), amount of cleaning agent added (in gal), flush start date and time and end date and time, amount of chemical added, water quality parameters and chemical residual after 2 week operation period.

15. Treatment – After cleaning and before adding chemical initial charge, system must be flushed to meet these minimum requirements:

    a. Conductivity no higher than 20 micromhos above domestic water level
    b. No foam
    c. Copper level less than 0.5 ppm
    d. Iron level less than 1.0 ppm
    e. pH 9.4 or less
    f. Less than 1 ppm phosphates (ortho-phosphate PO4)

16. Final Clear Water Flush – The system will be continuously flushed while discharging chemicals into the sanitary system as approved locally. As the existing or new treated water is being discharged a fresh water make-up source will be utilized to ensure air is not introduced into the system. Continue to drain the system while adding domestic water to dilute the treated water. The chemical treatment company will monitor the outgoing water composition and compare the composition with the incoming water. Flush with fresh water until the conductivity is reduced to that of the make-up water and iron level is 1.0 ppm or less the final system water should be approved by the chemical treatment company. Filtration should be 5 micron.

17. Final Chemical Fill – Once the chemical treatment company has determined the system has been brought back to the correct composition,

the chemical treatment company will inject the final chemicals into the system. Once the system is filled with the final chemicals it is important that the water is not to be left stagnant.

18. Verify satisfactory completion of clean pipe and a final flushing and chemical treatment report should be signed by field personnel and submitted.

19. Treat and test hot water systems monthly for the entire 24 month warranty period.

END OF SECTION 230505

SECTION 230548 - VIBRATION CONTROLS FOR HVAC, PLUMBING AND FIRE PROTECTION EQUIPMENT

PART 1 - RELATED DOCUMENTS

1.1. GENERAL

A. Drawings and General Provisions of Contract, including General and Supplementary Conditions and Division 01 Specification Sections apply to work of this section.

B. All work under this section shall also be subject to the requirements of Division 23 Section, Common Work Results for HVAC.

1.2. SUMMARY

A. Provide all labor and materials necessary to furnish and install vibration control systems on this project as herein specified and/or shown on the drawings.

B. Mount all mechanical equipment on suitable vibration isolators so as to prevent transmission of vibration into or through the building structure. Isolators shall be as manufactured by Mason Industries, Inc., Korfund, Inc., Amber Booth, Vibration Mounting and Controls, or approved equal, and shall be selected by the isolator manufacturer for each item of equipment in accordance with requirements hereinafter specified.

C. The equipment manufacturer shall supply all pump and motor bases, fan and motor bases, cradles, isolation pipe/duct hangers, spring and/or neoprene isolators, neoprene pads, flexible connectors, etc. as a coordinated package by a single manufacturer.

D. Select isolators for uniform static deflections according to distribution of weight; and for not less than the indicated isolation efficiency with the lowest rotational speed of equipment as the disturbing frequency.

E. Isolators and bases shall be stable during stopping and starting of equipment without transverse or eccentric movement of equipment, and shall be designed to resist horizontal forces of equipment which may operate unbalanced.

F. In general, select isolators on the basis of criteria as specified in the ASHRAE Applications Handbook, Latest Edition.

1.3. SUBMITTALS

A. Shop Drawings: Indicate inertia bases and locate vibration isolators, with static and dynamic load on each.

B. Product Data: Provide schedule of vibration isolator type with location and load on each.

C. Manufacturer's Installation Instructions: Indicate special procedures and setting dimensions.

D. Manufacturer's Certificate: Certify that isolators are properly installed and adjusted to meet or exceed specified requirements.

1.4. PROJECT RECORD DOCUMENTS

A. Record actual locations of hangers including attachment points.

1.5. COLOR CODING

A. All springs shall be color coded for load carrying capacity.

1.6. ALTERNATES

A. Refer to Division 01 Section, Alternates - Alternates for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1. MANUFACTURERS

A. Isolators shall be the equivalent of the following types by Mason Industries, Inc., Korfund, Inc., Kinetic Noise Control, Inc., Vibro Acoustics or approved equal.

2.2. CORROSION PROTECTION FOR STEEL PARTS

A. Where steel parts are exposed to weather or humid environments provide hot-dipped galvanized coating of at least 2 ounces of zinc per square foot of surface. Coat springs with neoprene.

2.3. SPRING MOUNTS AND SOUND PADS

A. Provide all spring mounts with leveling devices, minimum .25 inch thick neoprene sound pads, and zinc chromate plated hardware.

B. All sound pads shall be size for minimum deflection of .05 inch; meet requirements for neoprene pad isolators.

2.4. SPRINGS

A. All springs shall have minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between .3 and .6 of maximum deflection.

2.5. NEOPRENE

A. Grade durometer 40, 50 OR 60 AND OIL RESISTANT.

2.6. FLOOR MOUNTED ISOLATORS:

A. Neoprene Isolation Pads: Provide pads at least ¼ " thick with cross-ribbed or waffle design. For concentrated loads provide steel bearing plates bonded or cold cemented to the pads. Neoprene isolation pads shall be Type Super W.

B. Neoprene Isolators: Rubber (neoprene)-in-shear mounting: Provide molded neoprene isolators having steel base plates with mounting holes and, at the top, steel mounting plates with mounting holes or threaded inserts. Provide elements of type and size coded with molded letters or color-coded for capacity identification. Embed metal parts completely in neoprene. Double deflection neoprene mountings shall have a minimum static deflection of 0.35". Bolt holes shall be provided for these areas where bolting is required. On equipment such as small vent sets and close coupled pumps, steel rails shall be used above the mounting to compensate for the over-hang. Mountings shall be type ND or rails type DNR.

2.7. SPRING ISOLATORS

A. General: Provide spring isolators or protected spring isolators that are adjustable and laterally stable with free-standing springs of horizontal stiffness at minimum 80 percent of the vertical (axial) stiffness. For machine-attached and floor-attached restraining elements, separate from metal-to-metal contact by neoprene cushions 1/8-inch thick minimum. Provide neoprene acoustic friction pads at least ¼ inch thick.

B. Spring Isolator: Spring type isolators shall be free standing and laterally stable without any housing and complete with ¼ " neoprene acoustical friction pads between the baseplate and the support. All mountings shall have leveling bolts that must be rigidly bolted to the equipment. Spring diameters shall be no less than 0.8 of the compressed height of the spring at rated load. Springs shall have a minimum additional travel to solid equal to 50% of the rated deflections, compressed spring height and solid spring height. Mountings shall be type SLF as manufactured by Mason Industries, Inc. or as approved equal.

2.8. SUSPENSION ISOLATORS

A. General: Provide hangers with suspension isolators encased in open steel brackets. Isolate hanger rods from isolator steel brackets with neoprene-lined

opening.

B. Suspension Neoprene Isolators: Provide double-deflection elements with minimum 3/8 inch deflection.

C. Suspension Spring Isolators: Vibration hangers shall contain a steel spring and 0.3" deflection neoprene element in series. The neoprene element shall be molded with a rod isolation bushing that passes through the hanger box. Spring diameters and hanger box lower hole sizes shall be large enough to permit the hanger rod to swing thru a 30° arc before contacting the hole and short circuiting the spring. Springs shall have a minimum additional travel to solid equal to 50% of the rated deflection. Submittals shall include a scale drawing of the hanger showing the 30° capability. Hangers shall be type 30N.

D. Precompressed Suspension Spring Isolators: Vibration hangers shall be as described in "C" above, but they shall be precompressed to the rated deflection so as to keep the piping or equipment at a fixed elevation during installation. The hangers shall be designed with a release mechanism to free the spring after the installation is complete and the hanger is subjected to its full load. Deflection shall be clearly indicated by means of a scale. Submittals shall include a scale drawing of the hanger showing the 30° capability. Hangers shall be type PC30N.

2.9. INERTIA BASES

A. Structural Bases: Vibration isolator manufacturer shall furnish integral structural steel bases. Bases shall be rectangular in shape for all equipment other than centrifugal refrigeration machines and pump bases which may be "T" or "L" shaped. Pump bases for split case pumps shall include supports for suction and discharge base ells. All perimeter members shall be beams with a minimum depth equal to 1/10th of the longest dimension of the base. Beam depth need not exceed 14" provided that the deflection and misalignment is kept within acceptable limits as determined by the manufacturer. Height saving brackets shall be employed in all mounting locations to provide a base clearance of one inch- bases shall be type WF.

B. Structural Rails: Vibration isolator manufacturer shall provide steel members welded to height saving brackets to cradle machines having legs or bases that do not require a complete supplementary base. Members shall be sufficiently rigid to prevent strains in the equipment. Inverted saddles shall be type ICS.

C. Concrete Bases: Vibration isolator manufacturer shall furnish rectangular structural beam or channel concrete forms for floating foundations. Bases for split case pumps shall be large enough to provide support for suction and discharge base ells. The base depth need not exceed 12" unless specifically recommended by the base manufacturer for mass or rigidity. In general, bases shall be a minimum of 1/12th of the longest dimension of the base, but not less than 6". Forms shall include minimum concrete reinforcement consisting of half inch bars or angles welded in place on 6" centers running both ways in a layer 1-1/2" above the bottom, or additional steel as is required by the structural conditions. Forms

shall be furnished with steel members to hold anchor-bolt sleeves when the anchor bolts fall in concrete locations. Height saving brackets shall be employed in all mounting locations to maintain a 1" clearance below the base. Concrete shall be 3,000 psi concrete. Mass of concrete inertia bases shall be minimum of 2 times weight of isolated equipment. Bases shall be type K.

2.10. FLEXIBLE CONNECTORS FOR PIPING

A. General: Straight or elbow flexible connectors rated for temperatures, pressures, and fluids to be conveyed. Provide flexible connectors with the strength 4 times operating pressure at highest system operating temperature. Provide elbow flexible connectors with a permanently set angle.

B. Elastomeric Flexible Connectors: Flexible neoprene connectors shall be manufactured of multiple plys of nylon tire cord fabric and neoprene both molded and cured in hydraulic rubber presses. No steel wire or rings shall be used as pressure reinforcement. Straight connectors shall have two spheres. Connectors up to and including 1 ½ " diameter may have threaded ends. Connectors 2" and larger shall be manufactured with floating galvanized flanges recessed to lock the connector's raised face neoprene flanges. Hoses shall be installed on the equipment side of the shut-off valves. Connectors shall be rated a minimum of 150 psi at 220°F. Flanged equipment shall be directly connected to neoprene elbows in the size range 2 ½ " through 12" if the piping makes a 90o turn at the equipment. All straight through connections shall be made with twin-spheres properly pre-extended as recommended by the manufacturer to prevent additional elongation under pressure. 12" and larger sizes operating above 100 psi shall employ control cables with end fittings isolated by means of ½ " thick bridge bearing neoprene washer bushings designed for a maximum of 1000 psi.

C. Submittals shall include two test reports by independent consultants showing minimum reductions of 20 DB in vibration accelerations and 10 DB in sound pressure levels at typical blade passage frequencies.

D. Elbows shall be Mason-Flex type MFNEC, straight connectors Mason-Flex type MFTFU or MFTNC, and control cable assemblies type ACC.

E. Metal Flexible Connectors: Fabricated of Grade E phosphor bronze, monel or corrugated stainless steel tube covered with comparable bronze or stainless steel braid restraining and pressure cover. Sizes 3" and larger shall be flanged. Sizes 2 ½ " and smaller shall have male nipples. Lengths shall be as indicated:

Nominal Diameter (Inches)	Length (Inches)
½ "	12"
3/4"	12"

1 ½ "	12"
1 ½ "	12"
2"	12"
2 ½ "	12"
3"	18"
4"	18"
5"	24"
6"	24"

F. Hoses shall be installed on the equipment side of the shut-off valves horizontally and parallel to the equipment shafts wherever possible. Hoses shall be type BSS.

2.11. NEOPRENE PAD ISOLATORS

A. Rubber or neoprene waffle pads.

1. 30 durometer

2. Minimum 2 inch (13mm) thick

3. Maximum loading 40 psi (275 kPa)

4. Height of ribs shall not exceed 0.7 times width.

B. Configuration: ½ inch (13mm) thick waffle pads bonded each side of ¼ inch (6 mm) thick steel plate.

2.12. RUBBER MOUNTS

A. Molded rubber designed for 0.6 inches (13 mm) deflection with threaded insert.

PART 3 - EXECUTION

3.1. GENERAL PROVISIONS

A. Install vibration-and-noise isolation materials and equipment as indicated and in accordance with machinery manufacturer's instructions.

B. Where neoprene elements of vibration isolator may be subjected to high pipe

temperatures above 160°F, provide metal heat shields or thermal isolators.

C. A minimum of 4" thick reinforced concrete housekeeping pads shall be provided under all floor mounted equipment. Rest subbases on structural floor and reinforce with steel rods interconnected with floor reinforcing bars by tie bars hooked at both ends. Provide at least one (1) inch clearance between subbases and inertia bases, steel bases, and steel saddles with machinery in operation.

D. All vibration isolators exposed to weather or humid environment shall be hot dipped galvanized with springs coated with neoprene in accordance with paragraph hereinbefore described.

E. Concrete inertia bases shall be a minimum of two (2) times the weight supported. Clearance between the underside of the inertia base and the housekeeping pad below shall not be less than 1 inch. Concrete shall be 3000 psi. Install inertia bases in accordance with the recommendations of the machinery manufacturer and the inertia base manufacturer.

F. Anchor Bolts and Grout: Secure machinery to foundations and inertia bases with anchor bolts. Grout equipment with baseplates, the full area under baseplates with premixed non-shrinking grout. After grout has set, remove wedges, shims, and jack bolts and fill spaces with grout.

G. Common Machinery Foundations: Mount electrical motors on the same foundations as driven machinery. Support piping connections, strainers, valves,

H. Machinery: Provide vibration isolators, flexible connectors and seismic snubbers in accordance with manufacturer's recommendations. Machinery with spring isolators or protected spring isolators shall rock or move freely within limits of stops or seismic snubber restraints.

I. Stability: Isolators shall be stable during starting and stopping of machinery without traverse and eccentric movement of machinery that would damage or adversely affect the machinery or attachments.

J. Lateral Motion: The installed vibration isolation systems for each piece of floor or ceiling mounted machinery shall have a maximum lateral motion under machinery start up and shut down conditions of not more than ¼ -inch. Restrain motions in excess by approved spring mountings.

K. Unbalanced Machinery: Provide foundation suspension systems specifically designed to resist horizontal forces for machinery with large unbalanced horizontal forces. Vibration isolator systems shall conform to the machinery manufacturer's recommendations.

L. Nonrotating Machinery: Mount nonrotating machinery in systems which includes rotating or vibrating machinery on isolators having the same deflection as the hangers and supports for the pipe connected to.

M. Roof and Upper Floor Mounted Machinery: On the roof or upper floors, mount machinery on isolators with vertical stops. Rest isolators on beams or structures

designed and installed in accordance with the SMACNA ASMM Plate 61.

N. Vibration isolation ceiling hangers shall be installed so that the hanger rods do not touch the sides of the isolator housing, thereby seriously degrading the vibration isolation performance. Vibration isolation ceiling hangers shall be located so that the hanger housing may rotate 360 degrees without touching any object.

O. Electrical Connections: Provide flexible conduit or multiple conductor cable connections for machinery with sufficient extra length to permit 2 inch minimum displacement in any direction without damage.

P. Systems Not To Be Vibration Isolated: Do not provide vibration isolation for electrical raceways and conduits or for fire protection, storm, sanitary, and domestic water piping systems which do not include pumps or other vibrating, rotating, or pulsating equipment including control and pressure reducing valves.

Q. Install in accordance with manufacturer's instructions.

R. Install isolation for motor driven equipment.

S. Bases:

1. Set steel bases for one inch (25mm) clearance between housekeeping pad and base.

2. Set concrete inertia bases for 2 inch (50mm) clearance between housekeeping pad and base.

3. Adjust equipment level.

T. Install spring hangers without binding.

U. On closed spring isolators, adjust so side stabilizers are clear under normal operating conditions.

V. Prior to making piping connections to equipment with operating weights substantially different from installed weights, block up equipment with temporary shims to final height. When full load is applied, adjust isolators to load to allow shim removal.

W. Connect wiring to isolated equipment with flexible hanging loop.

3.2. FLEXIBLE PIPE CONNECTORS

A. Provide flexible connectors in accordance with manufacturers instructions where piping systems serving vibration isolated equipment and as shown on the drawings. Flexible connectors shall be installed near the connection to the equipment. Where liquid pulsation dampening is required, flexible connectors with spherical configuration may be used. Provide restraints for pipe connectors at pumps to prevent connector failure upon pump start-up.

B. Provide flexible connectors at connections of dental air compressors and dental vacuum pumps where they connect to piping systems.

3.3. ISOLATION FOR SPECIFIC EQUIPMENT

A. The vibration isolator manufacture shall provide isolators for all pieces of equipment provided for the job. Isolator shall be selected by the isolator manufacturer on the basis of criteria as specified in the ASHRAE Applications Handbook, latest edition, unless a more stringent requirement is indicated on the drawings.

B. Dental Air Compressors and Dental Vacuum Pumps:

1. All dental air compressors and dental vacuum pumps shall be mounted on 1” thick ribbed neoprene pads and shall be anchored to concrete housekeeping pad.

2. Provide flexible pipe connections at pump suction and discharge. Mason Industries Type BSS or MFTNC/MFTFU with control rods type ACC or as approved equal.

C. All VAV boxes shall be suspended using hangers incorporating steel springs in series with neoprene selected for not less than 1" static deflection under full load (Mason Industries Type 30N or equivalent).

D. Conventional Ductless Units: Indoor ductless units shall be supported with rubber grommet type suspension isolators. Outdoor ductless units shall be supported on ribbed neoprene pads resting on roof curbs (roof application).

3.4. MANUFACTURER’S FIELD SERVICES

A. Inspect isolated equipment after installation and submit report. Include static deflections.

END OF SECTION 230548

SECTION 230593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC AND PLUMBING

PART 1 - GENERAL

1.1 GENERAL

A. This section covers performance testing, adjusting and balancing of heating, ventilating, air conditioning and domestic re-circulating systems as specified in Division 23 Section, Heating, Ventilating, and Air Conditioning Equipment and in Division 22 Sections, Plumbing Fixtures and Plumbing Equipment.

B. For Common Work Results of HVAC, See Division 23. See Division 01 for General Requirements.

C. The mechanical contractor shall select and employ an impartial, independent balancing agency to provide testing and balancing services for the heating, ventilating and air conditioning (HVAC) systems, plumbing systems, and other specified systems of this project.

D. The work included in this section consists of furnishing labor, instruments, and tools required in testing, adjusting and balancing the HVAC and plumbing systems, as described in these specifications or shown on accompanying drawings. Services shall include checking equipment performance, taking the specified measurements, and recording and reporting the results. Where balance valves and/or flow meter fittings are not indicated utilize ultrasonic flow meter to record fluid flow rates in gallons per minute.

1. Perform all work required to prepare the building HVAC and Plumbing systems for testing, adjusting, and balancing indicated by the Contract Documents as follows:

    a. Verify the air systems are ready for balancing.
    b. Verify the hydronic systems are ready for balancing.
    c. Verify the control systems are ready for balancing.
    d. Notify appropriate parties the system is ready for balancing.

2. Scope of work.

    a. Testing, adjusting, and balancing (TAB) of the HVAC systems, Plumbing Systems, and related ancillary equipment will be performed by an independent, third party, AABC Certified Agency, selected and employed directly by the Contractor. The preparation and corrections necessary for the testing and balancing of these systems, as described herein, are the responsibility of the Contractor.
    b. As part of the project Construction Contract, the Contractor shall make any changes or replacements to the sheaves, belts, dampers, valves, or other components required for correct balance as

advised by the TAB Agency, at no additional cost to the Owner.

c. The Contractor shall provide and coordinate the services of qualified, responsible subcontractors, suppliers and personnel as required to correct, repair, and/or replace any and all deficient items or conditions found during the course of this project, including the testing, adjusting, and balancing period.

d. In order that all systems may be properly tested, adjusted and balanced as required herein by these Specifications, the Contractor shall operate the systems at their expense for the length of time necessary to properly verify their completion and readiness for TAB, and the entire duration required for the TAB process.

e. Project Contract completion schedules shall allow for sufficient time to permit the completion of TAB services prior to Owner occupancy. The Contractor shall allow adequate time for the testing and balancing activities of the Owner-provided services during the construction period and prior to Substantial Completion, as defined in the AIA General Conditions and Supplementing Condition of this Construction Document.

f. The Drawings and Specifications indicate valves, dampers, and miscellaneous adjustment devices to be adjusted to obtain optimum operating conditions. It is the responsibility of the Contractor to install these devices in a manner that will leave them accessible and readily adjustable. Should any such device not be readily accessible, the Contractor shall provide access, as requested by the TAB Agency. Any malfunction encountered by TAB personnel and reported to the Contractor shall be corrected by the Contractor immediately so that the balancing work can proceed with a minimum of delays.

g. The scope of work, as defined herein, is to advise the Contractor of the coordination, adjustment, and system modifications that will be required under the project work to complete Owner requirements for final TAB. The Contractor's original bid shall allow for the costs of all work which may be required in the TAB phases, and which may be necessary for the completion of the TAB work as defined by the TAB Agency.

3. Submittals. The TAB Agency shall submit an agenda that will include:

a. Field observation reports.
b. An overview of system TAB procedures.
c. System testing which will include where ducts will be traversed, which instrumentation will be used, how correction factors for grille and diffuser will be obtained, how measurements will be verified at maximum and minimum, and how control components will be verified.
d. Report forms with each system's components identified and numbered.

E. The items requiring testing, adjusting, and balancing include, but are not limited to, the following:

Air Systems:
1. Existing Air Handling Unit #3
2. Coils (Air Temperatures, Fluid Temperatures, Fluid Pressure Drops, & Static Pressure Drops)
3. Diffusers, Registers and Grilles
4. Ductless Split System Units (Indoor and Outdoor units)
5. Exhaust Fans
6. Pressure Independent Control Valves
7. Static Pressure Sensors
8. Supply Fan AHU
9. Unit Heaters
10. VAV Boxes
11. Ventilation Fans
12. Zone Branch and Main Ducts

Hydronic Systems:
1. Existing Air Handling Unit #3
2. Coils
3. Condensate overflow safety switches
4. Domestic Re-circulating Systems
5. Emergency Fixture Mixing Valves
6. Flow Meter Fittings
7. In-line Pumps
8. Pumps
9. System Mains and Branches
10. Thermostatic Mixing Valves
11. Unit Heaters
12. VAV Box Hot Water Coils
13. In addition, any existing fans, pumps equipment or air devices specified to be re-used under this project shall be tested and balanced, similar to new fans.

1.2 ALTERNATES

A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

1.3 GENERAL COMMISSIONING REQUIREMENTS

A. Refer to Division 01 Section, “General Commissioning Requirements” for description of work under this Division affected by General Commissioning.

1.4 PRELIMINARY EXAMINATION

A. Verify that systems are complete and operable before commencing work. Ensure the following conditions:

1. Systems are started and operating in a safe and normal condition.
2. Temperature control systems are installed complete and operable.
3. Proper thermal overload protection is in place for electrical equipment.
4. Final filters are clean and in place. If required, install temporary media in addition to final filters.
5. Duct systems are clean of debris.
6. Fans are rotating correctly.
7. Volume dampers are in place and open.
8. Air coil fins are cleaned and combed.
9. Access doors are closed and duct end caps are in place.
10. Air outlets are installed and connected.
11. Duct system leakage is minimized.
12. Hydronic systems are flushed, filled, and vented.
13. Pumps are rotating correctly.
14. Proper strainer baskets are clean and in place.
15. Service and balance valves are open.

B. Submit field reports. Report defects and deficiencies noted during performance of services which prevent system balance.

C. Beginning of work means acceptance of exiting conditions.

1.5 QUALIFICATIONS OF THE BALANCE AGENCY

A. The balancing agency shall be a member of the Associated Air Balance Council (AABC).

B. The certified test and balance engineer shall be responsible for supervision and certification for the total work herein specified.

C. All final reports shall be signed by the certified test and balance engineer.

D. All personnel used on the project will be employees of an AABC Certified Agency. All work will be performed under the direct supervision of the AABC Certified Test and Balance Engineer (TBE). All work will be performed with AABC Certified Test and Balance Technicians (TBT) Resumes including education, experience, and certification of each person on the project shall be submitted.

E. Warranty. The AABC Agency shall submit a National Project Performance Guaranty.

1.6 PERSONNEL

A. All personnel used on the project will be employees of an AABC Certified Agency. All work will be performed under the direct supervision of the AABC Certified Test and Balance Engineer (TBE). All work will be performed with AABC Certified Test and Balance Technicians (TBT). Resumes including education, experience, and certification of each person on the project shall be submitted as informational

submittals.

1.7 WARRANTY

A. The AABC Agency shall submit a National Project Performance Guaranty.

1.8 PRE-BALANCING CONFERENCE

A. Convene a conference one week prior to commencing work of this Section with all appropriate individuals.

1.9 STANDARDS

A. The balancing agency shall perform the services specified herein in accordance with the Associated Air Balance Council's National Standards, including revisions, to the date of the contract.

B. All terms in this specification shall have their meaning defined as stated in the National Standards.

C. ADC: Test Code for grilles, registers, and diffusers.

D. ASHRAE III: Practice for measurement, testing, adjusting and balancing of building heating, ventilation, air conditioning, and refrigeration systems.

E. NEBB: Procedure standards for testing, adjusting, and balancing of environmental systems.

F. SMACNA: HVAC systems testing, adjusting, and balancing.

G. AABC: Associated Air Balance Council

1.10 COORDINATION

A. It will be necessary for the balancing agency to perform its services in close coordination with the mechanical contractor.

B. The plans and specifications have indicated meters, valves, dampers, and other devices for the purpose of adjusting the system to obtain optimum operating conditions. It will be the responsibility of the mechanical contractor to install these devices in a manner that will leave them accessible and readily adjustable. The balancing agency shall provide guidance if there is a questionable arrangement of a control or balancing device.

C. The general contractor/construction manager, mechanical contractor, temperature control contractor and suppliers of the HVAC equipment shall all cooperate with the balancing agency to provide all necessary data on the design and proper

application of the system components.

D. For heat pumps, the manufacturer's start-up agency and Test and Balance Engineer shall assist each other with obtaining proper flow rates and refrigerant pressures.

1.11 INSTALLATION TOLERANCE

A. Unless otherwise indicated, all air devices shall be adjusted to within plus or minus 10 percent of design. All fans shall be adjusted to within plus or minus 5 percent of design. All pumps and Hydronic equipment shall be adjusted to within plus or minus 5 percent of design.

1.12 RESPONSIBILITIES OF THE TAB AGENCY

A. Liaison and Early Inspection. The following reviews, observations, and tests shall be performed by the TAB Agency:

1. Review the mechanical drawings and specifications for balanceability and provide commentary. Verify proper types and locations of all Test and Balance devices.
2. During construction, review all approved HVAC submittals such as control diagrams, air handling devices, hydronic devices, and other components that pertain to TAB work and balanceability. Assist the commissioning agent with all Functional Performance Testing.
3. Perform construction observations and submit a written report:

    a. On the ductwork prior to insulation and/or ceiling cover-up.
    b. On the piping prior to insulation and/or ceiling cover-up.

4. Witness duct pressure test as defined in the specifications, and submit a written report.
5. Perform a pre-balance site review, and submit a written report.
6. During the balancing process, abnormalities and malfunctions of equipment or components may be discovered by the TAB personnel. The Construction Inspector, Architect, Engineer, and Owner shall be advised in writing so that the condition(s) can be corrected by the Contractor. The written document need not be formal, but shall be understandable and legible. The TAB Agency shall not instruct or direct the Contractor in any of the work, but will make reports to the appropriate parties.

B. Final Air Balance. When systems are complete and ready for operation, the TAB Agency will perform a final air balance for all air systems and record the results. The volume of air for the supply, return, exhaust, and outside air equipment and terminals will be tested and balanced within the tolerances of the AABC Standard, or as specified, whichever is more stringent. Air handling unit and fan volumes shall be adjusted by changing fan speed. Air distribution device volumes shall be adjusted using the duct dampers and not the grille face. Air distribution devices

shall be balanced with air patterns as specified. Duct volume dampers shall be adjusted to provide air volume to branch ducts where such dampers are shown. The general scope of balancing by the TAB Agency will include, but is not limited to, the following:

1. Filters: Check air filters and filter media. Balance systems with essentially clean filters and filter media.
2. Fan Speed: Measure and record RPM for each fan. Provide Controls Contractor with drive parameters for variable speed drives.
3. Voltage and Amperage Readings: Measure and record the final operating voltage and amperage for each motor.
4. Static Pressure Profile: Static pressure profiles shall be measured and recorded across each supply fan, cooling coil, heating coil, heat of rejection equipment fans, return air fan, air handling unit filter, exhaust fan, and at the furthest air device or terminal unit from the air handler supplying that device.
5. Equipment Air Flow: Adjust and record supply, return, outside and exhaust air CFM and temperatures, as applicable, at each fan and coil.
6. Coil Temperatures: Set controls for full cooling and for full heating loads. Read and record entering and leaving dry bulb and wet bulb (cooling only) temperatures at each cooling coil, heating coil, and HVAC terminal unit. At the time of reading, record water flow and entering and leaving water temperatures and pressure drops. In variable flow systems, adjust the air and water flow to design for all the above readings.
7. Zone Air Flow: Adjust each HVAC terminal unit and each air-handling unit for design CFM.
8. Outlet Air Flow: Adjust each supply diffuser, register and grille, and each exhaust inlet to within the tolerance per the AABC Standard.
9. Pitot Tube Traverses: For use in future troubleshooting by maintenance personnel, all main supply, return, outside air, and exhaust ducts shall have air velocity and volume measured and recorded by the Pitot tube traverse method shown in the AABC Standard. Locations of these traverse test stations shall be described on the sheet containing the data. All Pitot tube traverses shall be clearly identified on the outside of the duct insulation with the traverse identified and duct size. Submit half scale drawings showing the locations of all duct traverses.
10. Terminal Boxes: Maximum and minimum airflow on terminal boxes shall be adjusted, measured, and recorded.

C. Final Water Balance. When systems are complete and ready for operation, the TAB Agency will perform a final water balance for each hydronic HVAC system. The general scope of balancing by the TAB Agency will include, but not be limited to, the following:

1. Adjusted System Tests: Adjust balancing valves at each coil and heat exchanger for design flow per the AABC Standard. Adjust balancing valves at pumps to obtain design water flow. Record pressure rise across pumps, and obtain GPM flow from the pump curve. Permanently mark the balanced position for each valve. If discharge valves on the pumps are used for balancing, record the head being restricted by the valves. Test and record

autoflow valve differential pressures and adjust pump speed to optimize and minimize autflow differential pressure.

2. Temperature Readings: Read and record entering and leaving water temperature at each water coil, converter, heat rejection equipment and heat exchanger at design flow. Adjust as necessary to secure design operating conditions. Provide final readings at all thermometer well locations.
3. Pressure Readings: Water pressure shall be recorded at all gauge connections. Pressure readings at coils and pumps shall be related to coil and pump curves in terms of GPM flow and through flow measuring stations, where provided and installed, at each hydronic unit. The flow of water through all water coils shall be adjusted by balancing valves until the rated pressure drop across each coil is obtained and total water flow is verified by flow measuring station. For coils equipped with three-way valves, the rated pressure drop shall first be adjusted through the coils. The bypass valve shall then be adjusted on each coil until the pressure drop between supply and return connections is the same as with the flow through the coil.
4. Voltage and Amperage Readings: Read and record the final operating voltage and amperage for each pump motor.
5. Pump Speed: Measure and record RPM for each pump. Provide Controls Contractor with drive parameters for variable speed pumps.

D. Testing of Temperature Control Systems as applicable to the project.

1. Air Handling Units

a. Start each air handling unit; verify and document:
- Dampers modulate properly and in the correct sequence.
- Fan(s) VFD or ECM motors ramps to design speed or proper controlled speed.
- All terminal boxes open and/or start in the correct sequence.
- All coil valves operate in response to the controlled temperature.
- All interlocked fans and/or devices energize.
- All alarms and safeties are operational and will alarm or shut down the unit.
- All operating scenarios are tested; e.g.: economizer cycle, minimum/maximum airflows, outside airflows at unit minimum/maximum volume, and special sequences.
- All end switches and positioners are properly set.
- All pressure controllers respond to increases or decreases in system pressure.
- All temperature and pressure sensors are calibrated.
- Airflow monitors report the correct airflow and control devices respond correctly to a change in airflow; e.g.: outside air control.
- Reset control sequences operate in response to changes in system temperatures, flows, or pressures.
- Correct operation of fan sequences when multiple fans are

installed.
- Emergency mode operation; e.g.: power outage, freeze protection.
- Test all static pressure sensors and controls and calibrate the same.

b. Shut down each air handling unit; verify and document:
- Dampers respond properly (open, close, or modulate), and in the correct sequence.
- All fan systems ramp down and stop.
- Correct operation of fan sequences when multiple fans are installed.
- Emergency mode operation; e.g.: freeze protection.
- Interlocked devices turn off.
- System starts for setback temperature control.
- System starts on a temporary occupancy override.
- All terminal boxes close and/or stop in the correct sequence.
- All coil/heat exchanger valves go to their specified position.
- All alarms and safeties remain operational.

2. Fan Systems

a. Start each fan or fan system; verify and document:
- Interlocks and lockouts operate in accordance with the sequence.
- Fan(s) VFD or ECM motor ramps to design speed or proper controlled speed.
- All alarms and safeties are operational and will alarm or shut down the fan.
- Dampers modulate properly and in the correct sequence.
- All terminal boxes open and/or start in the correct sequence.
- All interlocked fans and/or devices energize.
- All end switches and positioners are properly set.
- All pressure controllers respond to increases or decreases in system pressure.
- All temperature and pressure sensors are calibrated.
- Airflow monitors report the correct airflow and that control devices respond correctly to a change in airflow; e.g.: outside air control.
- Correct operation of fan sequences when multiple fans are installed.
- Emergency mode operation; e.g.: power outage, freeze protection.

b. Shut down each fan or fan system; verify and document:
- Dampers respond properly (open, close, or modulate) and in the correct sequence.
- All fan systems ramp down and stop.

- Correct operation of fan sequences when multiple fans are installed.
- Emergency mode operation; e.g.: purge air.
- Interlocked devices turn off.
- All terminal boxes close and/or stop in the correct sequence.
- All alarms and safeties remain operational.

3. Hydronic Systems

a. Start hydronic systems; verify and document:
- Valves modulate properly and in the correct sequence.
- Pump(s) VFD ramps to design speed or proper controlled speed.
- All isolation valves go to their “system on” position.
- All coil/valves operate in response to the controlled temperature.
- All reset and changeover valves operate in response to the control system.
- All interlocked devices energize.
- All alarms and safeties are operational and will alarm or shut down the system.
- All operating scenarios are tested; e.g.: minimum/maximum water flows, minimum/maximum pressure, and special sequences.
- All end switches and positioners are properly set.
- All pressure controllers respond to increases or decreases in system pressure.
- All temperature and pressure sensors are calibrated.
- Flow meters report the correct water flow and that control devices respond correctly to a change in water flow.
- Reset control sequences operate in response to changes in system temperatures, flows or pressures.
- Differential pressure across all autoflow valves, flow meters, PIC valves, coils, equipment.
- Correct operation of pump, HVAC equipment, and/or heat exchangers sequences when multiples are installed.
- Emergency mode operation; e.g.: power outage, freeze protection.
- The controls have time delay strategy to avoid excessive cycling of pumps, coils and heat exchangers.

b. Shut down hydronic systems; verify and document:
- Valves modulate properly and in the correct sequence.
- Pump(s) VFD ramps down to off position.
- All isolation valves go to their “system off” position.
- All coil valves go to their normal off position.
- All interlocked devices de-energize.
- All changeover valves go to the normal position.

- All alarms and safeties remain operational.
- Correct shutdown of pump, HVAC equipment, and/or heat exchangers.
- Emergency mode operation: e.g., freeze operation.

4. Component Calibration
   All temperature, airflow, fluid flow, pressure, and flow measuring components shall be measured and compared to the control system readout; verify and document:

   - The air temperature sensors for each coil, heat exchanger. If the temperature is not reading within tolerance, the sensor will be reported to the control contractor for calibration.
   - The room temperature, relative humidity, $C0_2$ sensors. If the sensors are not reading within tolerance, the sensors shall be reported to the control contractor for calibration.
   - The water temperature sensors for each coil, heat exchanger. If the temperature is not reading within tolerance, the sensors shall be reported to the control contractor for calibration.
   - All air and water pressure sensor readouts. If the pressure is not reading within tolerance, the sensor shall be reported to the control contractor for calibration.
   - All flow measuring device readouts. If the flow readout is not recording within tolerance, the sensor shall be reported to the control contractor for calibration.

5. Point Verification

   - Point verification for the digital control system documents that every point is operational and the setpoint, flow, temperature, or pressure is reporting correctly to the graphic interface. Verify and document all points.

6. Dynamic Testing

   - Dynamic testing involves making a change of value at the sensor in order to observe the system's reaction and how it regains the original setpoint. Verify and document the system's response.

1.13 REPORTS

A. The report shall be a complete record of the HVAC system performance, including conditions of operation, items outstanding, and any deviations found during the process. The final report also provides a reference of actual operating conditions for the owner and/or operations personnel. The report summary is a project narrative describing the outcome of the testing and balancing and shall include a list of items that document all system variations deviating from design tolerances. Information can also be included that suggests possible resolutions.

B. All measurements and recorded readings that appear in the reports shall be certified by the Agency's Test and Balance Engineer.

C. Submit reports on forms approved by the Engineer. Hard and/or electronic copies of the final report shall be submitted in accordance with the Contract Requirements. The report shall indicate a summary of actual operating data and any abnormal operating conditions. The report shall contain all required information as described within this specification, including the information formatted and shown in the AABC Standard.

D. For phased projects, submit a final, complete, and comprehensive TAB report with index for all phases.

E. When the Engineer reviews TAB reports and provides comments, address each comment in writing for all re-submitted TAB reports.

1.14 TAB FINAL ACCEPTANCE INSPECTION

A. At the time of TAB final acceptance inspection, the TAB agency shall recheck, in the presence of the Owner's representative, specific and random selections of data recorded in the certified test and balance report.

B. Points and areas for recheck shall be selected by the Owner's representative.

C. Measurements shall be verified at the same test conditions as the submitted and approved test and balance agenda.

D. Selections for verification shall not exceed 10% of the total number tabulated in the report, except where special air systems require a complete recheck for safety reasons.

E. If 10% of the random verification tests demonstrate a measured flow deviation of 10%, or more from that recorded in the certified test and balance report, the report shall be automatically rejected. In the event the report is rejected, all systems shall be readjusted and tested, new data recorded, a new certified test and balance submitted, and a new inspection test made. There shall be no additional cost to the Owner for this work.

F. Final acceptance shall occur after successful completion of the TAB verification process.

1.15 RESPONSIBILITIES OF THE MECHANICAL CONTRACTOR

A. The mechanical contractor shall sufficiently complete the installation and start all HVAC and plumbing systems to insure they are working properly and shall perform all other items as described hereinafter to assist the balancing agency in performing the testing and balancing of the HVAC system.

B. Record equipment manufacturer's standard start-up information and submit to

Engineer for review. Testing and balancing work shall not commence on any equipment until start-up reports have been completed, reviewed by Engineer, and forwarded to Testing and Balancing Agency.

C. The Contractor shall:

1. Have the building, air conditioning systems, heating systems, and plumbing systems in complete operational readiness for TAB work to begin.
2. The Contractor shall allow sufficient time for the TAB Agency to perform their contracted work within the construction schedule. The Contractor shall complete work by systems or floors, whichever is the most efficient for testing systems. After award of the contract and the completion of the construction schedule by the Contractor, a TAB coordination meeting shall be held with the TAB Agency, the Contractor and primary subcontractors, including but not limited to mechanical, electrical, and building automation subcontractors to develop a testing schedule for the project. The Contractor shall submit copies of the proposed schedule to the TAB Agency two weeks prior to this meeting.
3. Promptly correct deficiencies of materials and workmanship identified as delaying completion of TAB work.
4. Be responsible for any added costs to the Owner resulting from the Contractor's failure to have the building air conditioning systems and plumbing systems ready for TAB when scheduled, or from the Contractor's failure to correct deficiencies promptly.

D. Facility Operational Readiness

1. Complete operational readiness of the building requires that the building envelope be complete. This includes the installation of doors, windows, and ceilings to obtain simulated or projected operating conditions.

E. Air Distribution Systems

1. Verify installation for conformity to design.
2. Terminate all supply, return, outside air, exhaust air, relief air, ventilation air ducts, and pressure test them for leakage. Test pressure and leakage rate shall be as specified in Division 23 Section, HVAC Air Distribution System under Leakage Tests. Pressure testing shall be performed by mechanical contractor and witnessed by Test and Balance Engineer.
3. Ensure that all volume dampers and fire dampers are properly located and functional. Dampers serving requirements of minimum and maximum outside - return - relief, and exhaust air shall provide tight closure and full opening, with a smooth and free operation.
4. Verify that all supply - return - exhaust and transfer grilles; registers, and diffusers are installed, operational, and sealed tightly.
5. Ensure that air-handling systems, units, and associated apparatus, such as heating and cooling coils, filter sections, access doors, etc., are blanked and/or sealed to eliminate excessive bypass or leakage of air.
6. Ensure that all fans are operating and free of vibration. All fans and drives shall be checked for proper fan rotation and belt tension. Overload

protection shall be of proper size and rating. A record of motor current and voltage shall be made to verify that the motors do not exceed nameplate rating. Record thermal overload ratings for all motors in the Test and Balance Report.

7. Make any necessary changes to the sheaves, belts, and dampers, as required by the balancing agency, at no additional cost to the owner.
8. Install clean filters.
9. Coils shall be clean with fins straightened, bearings shall be properly greased, belts shall be aligned and tightened, and the system shall be completely operational. The Contractor shall verify that all systems are operating within the design pressure limits of the piping and ductwork.
10. All supply, return, exhaust, and relief fans shall be operating and verified for: freedom from vibration, proper fan rotation and belt tension; heater elements in motor starters to be of proper size and rating, as the as per the starter manufacturer. Record motor amperage and voltage on each phase at start-up, verifying they do not exceed nameplate ratings.
11. All terminal units shall be installed and functional. Controls commissioning shall be complete.
12. For heat pumps, provide refrigerant suction and discharge pressure to Test and Balance Engineer for inclusion in the final TAB Report.

F. Water Circulating Systems

1. Verify installation for conformity to design.
2. Check all pumps to verify pump alignment and rotation.
3. Ensure that systems are clean, with the proper strainer screens installed for normal operation.
4. Check all pump motors for current on each phase and voltage, to ensure that motors do not exceed nameplate rating.
5. Provide thermal overload protection of proper size per the starter manufacturer and rating. Record thermal overload ratings for all motors. Insert data in Test and Balance Report.
6. Ensure that all water circulating systems shall be full and free of air; that expansion tanks are set for proper water level; and that all air vents were installed at high points of systems and are operating.
7. All piping shall be terminated and pressure tested for leakage as required by the specification. All valves shall be set to their full open position, bypass stop valves shall be closed, and mixing valves shall be set to full-flow through the the system’s components. After the system is flushed and checked for proper operation, all strainers shall be removed and cleaned. The Contractor shall repeat the operation until circulating water is clean. The start-up strainers shall then be removed and hung adjacent to the pumps.
8. Chemicals shall be added to closed systems to treat piping and inhibit corrosion. The system static pressure shall be adequate to completely fill the system without operating the pumps.
9. The operating parameters of the heat exchangers, coils, pumps, and control devices shall be capable of obtaining design requirements.
10. Proper balancing devices shall be installed in the designated locations. These devices include but are not limited to flow meters, pressure taps,

thermometer wells, and balancing valves.

11. Test undercounter domestic recirculating pumps with an ultrasonic flow meter and record how long it takes for hot water to reach the faucets.

G. Notification of System Readiness

1. After completion of the work, the Contractor shall notify the Owner and TAB Agency, in writing, certifying that the work has been accomplished and that the building, air conditioning, and plumbing systems are ready for testing, adjusting, and balancing. The Contractor shall include a copy of the tabulated data of the start-up reports.
2. The Contractor shall notify the TAB Agency of the readiness for balancing and forward copies of the Contractor's certification and the tabulated data.
3. Should the TAB Agency be notified as described above and the inspection reveal the TAB services notification to have been premature, all costs of the inspection by the TAB Agency shall be reimbursed by the Contractor.

1.16 CONTRACTOR SUPPLIED ITEMS

A. As a requirement of the TAB contract, the Contractor's Project Manager shall compile and provide the TAB Agency the following:

1. One set of mechanical specifications.
2. All pertinent change orders.
3. All Request(s) for Information (RFI).
4. One complete set of MEP Drawings.
5. One copy of approved submittal data on equipment installed and controls submittal with sequences of operation.
6. All HVAC Control Communications software with the appropriate licenses and hardware interfaces.
7. All Addendums and RFI's (Requests for Information).

1.17 RESPONSIBILITIES OF THE TEMPERATURE CONTROL CONTRACTOR

A. The temperature control contractor shall complete the installation of the temperature control system, and operate and test all control systems to ensure they are functioning properly as designed. The temperature control contractor shall assist the balancing agency in testing and balancing the HVAC systems, as described hereinafter.

1. Verify that all control components are installed in accordance with project requirements and are functional, including all electrical interlocks, damper sequences, air and water reset, freeze stats, high and low temperature thermostats, safeties, and duct smoke detectors.
2. Verify that all controlling instruments are calibrated and set for design operating conditions.
3. Calibrate temperature sensors after installation, and before the temperature sensors control verification tests are performed. The

balancing agency shall prove the accuracy of final settings by taking temperature readings. The readings shall be in a typical conditional space for each separately controlled zone.

4. The temperature control contractor shall allow sufficient time in the project to provide assistance and instruction to the balancing agency in the proper use and setting of control components such as, but not limited to, computers, static pressure controllers, or any other device that may need set points changed so that the testing and balancing work can be performed.
5. The temperature control contractor shall assist the balancing agency in the testing of VAV boxes. The temperature control contractor shall make available to the balancing agency the use of a portable service terminal for use in balancing VAV boxes.
6. The Control Contractor shall schedule a meeting with the Mechanical Contractor, TAB Agency, and Owner's representative for a pre-submittal review to establish that their interpretation of the control sequence is correct.
7. The Control Contractor shall verify that all controlling instruments are calibrated and set for design operating conditions, with the exception of components that require input from the TAB Agency. A default shall be set for such components. The Control Contractor shall cooperate with the TAB Agency and provide all software and interfaces necessary to communicate with the system.
8. The Automatic Temperature Control Contractor shall thoroughly check all controls, sensors, operators, and sequences before notifying the TAB Agency that the Energy Management System is operational. The Energy Management System Contractor shall provide technical support in the form of technicians and necessary computers to the TAB Agency for a complete check of those systems.
9. The Fire Alarm (FA) Contractor shall thoroughly check all detection devices, sequences, interlocks, and other components before notifying the TAB Agency that the system is operational, including the Fireman's Override Panel. The FA Contractor shall provide all documentation that identifies all fire and smoke detection devices, all smoke zones, and all alarm and event chart devices. The FA Contractor shall certify to the Contractor that the systems are totally operational prior to the start of TAB.

B. All control sequences, software, equipment, and components shall be started-up by a qualified technician. Start-up report shall be submitted to Engineer prior to the commencement of testing and balancing work. Testing and balancing shall not commence until start-up reports are completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.

1.18 NOTIFICATION FOR TESTING AND BALANCING WORK TO BEGIN

A. The mechanical contractor shall notify the balancing agency in writing when all heating, ventilating, and air conditioning and plumbing systems are complete and ready for testing and balancing. The mechanical contractor shall attest that he has completed all items as herein described.

B. The following must be completed prior to start of system balancing:

1. All duct work and associated grilles/registers/diffusers installed and completed.
2. Piping systems completed, flushed and filled.
3. Equipment properly started by qualified personnel or start-up technicians.
4. Ceiling tiles installed.
5. Automation system (temperature controls) installed and completed for both air and water systems.
6. All equipment controlled in automatic (“Auto”) mode.
7. Access granted to the balancing contractor to the automation/controls system provided.

C. Mechanical Contractor shall notify the Construction Manager of the start date of this portion of the work.

1.19 DEFICIENCIES

A. Any deficiencies in the installation or performance of a system or component observed by the TAB agency shall be brought to the attention of the appropriate responsible person.

B. The work necessary to correct items on the deficiency listing shall be performed and verified by the affected Contractor before the TAB Agency returns to retest. Unresolved deficiencies shall be noted in the final report.

C. TAB Agency shall notify Construction Manager of all deficiencies found during initial survey.

1.20 ADJUSTING

A. Ensure recorded data represents actual measured observed conditions.

B. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.

C. After adjustment, take measurements to verify balance has not been disrupted or that such disruption has been rectified.

D. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring all sensors to specified settings.

E. At final inspection, recheck random selections of data recorded in report. Recheck points or areas as selected and witnessed by the Owner.

F. Check and adjust systems approximately six months after final acceptance and submit report.

G. Permanently mark the locations of all duct traverses on the exterior surface of the duct insulation. For exterior ductwork, the duct traverse locations must be identified with waterproof labels.

PART 2 - PRODUCTS (NOT APPLICABLE)

PART 3 - EXECUTION

3.1 GENERAL

A. Perform all testing and balancing in complete accordance with AABC National Standards for Field Measurements and Instrumentation.

B. Furnish all test instruments and equipment. All instruments must have been calibrated within twelve (12) months prior to use and shall be checked for accuracy prior to and during the work. Submit certificate for calibration of all equipment utilized on project with date of calibration clearly identified.

C. Review all systems designs and equipment, manufacturers' data, and be completely familiar with the work before proceeding.

D. Report all malfunctions or deficiencies to the contractor so that corrective action can be taken. Test and Balance Report shall not be submitted for review until all malfunctions or deficiencies are corrected. Repeat tests where required until design conditions are achieved.

E. Where systems or equipment cannot be balanced or adjusted to design conditions, determine the cause and submit a complete report to the Engineer.

F. Retest or rebalance the system as required during the warranty period.

G. Test and balance all systems under adequate load condition. If, in the opinion of the Engineer, there is insufficient load to properly test and balance the systems, perform sufficient preliminary balancing and adjustment to permit operation of the systems until such time as final testing and balancing can be done. Provide in writing the future date when systems shall be tested under sufficient load.

H. At project completion provide a complete set of ½ scale drawings indicating the locations of all duct traverses.

3.2 EXAMINATION

A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems' designs that may preclude proper TAB of systems and equipment.

B. Examine systems for installed balancing devices, such as test ports, gage cocks,

thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are accessible.

C. Examine the approved submittals for HVAC systems and equipment.

D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems' output, and statements of philosophies and assumptions about HVAC/plumbing system and equipment controls.

E. Examine ceiling plenums used for supply, return, or relief air to verify that they meet the leakage class of connected ducts and are properly separated from adjacent areas. Verify that penetrations in plenum walls are sealed and fire-stopped if required.

F. Examine equipment performance data including fan and pump curves.

1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems – Duct Design". Compare results with the design data and installed conditions.

G. Examine system and equipment installations and verify that field quality-control testing, cleaning and adjusting specified in individual Sections have been performed.

H. Examine test reports specified in individual system and equipment Sections.

I. Examine HVAC equipment and filters and verify that bearings are greased, belts are aligned and tight, and equipment with functioning controls is ready for operation.

J. Examine terminal units, and verify that they are accessible and their controls are connected and functioning.

K. Examine strainers. Verify that startup screens are replaced by permanent screens and indicated perforations.

L. Examine heat-transfer coils for correct piping connections and for clean and straight fins.

M. Examine system pumps to ensure absence of entrained air in the suction piping.

N. Examine operating safety interlocks and controls on HVAC equipment.

O. Report deficiencies discovered before and during performance of TAB procedures.

Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.3 AIR SYSTEM PROCEDURES

A. The balancing agency shall perform the following testing and balancing functions in accordance with the Associated Air Balance Council's National Standards:

1. Fan Speeds - Test and adjust fan RPM to achieve design CFM requirements.
2. Current and Voltage - Measure and record motor current and voltage. Check and record thermal overload ratings for all motors.
3. Pitot-Tube Traverse - Perform a Pitot-tube traverse of main supply, return and exhaust ducts to obtain total CFM. If a Pitot-tube traverse is not practical, the summation of the outlets or inlets may be used. An explanation why a traverse was not made must appear on the appropriate data sheet.
4. Outside Air - Test and adjust system minimum outside air by Pitot-tube traverse. If a Pitot-tube traverse is not practical, the percentage of outside air may be determined by calculations from the return air, outside air, and mixed air temperatures. Make allowances for heat of compression and motor heat where applicable.
5. Static Pressure - Test and record system static pressures, including suction and discharge static pressure of each fan. Measure static air pressure conditions on air supply units, including filter and coil pressure drops, and total pressure across the fan. Make fan RPM allowances for 50 percent loading of filters.
6. Air Temperature - Take wet-bulb and dry-bulb air temperatures on the entering and leaving side of each cooling coil and/or heat recovery coil. Dry-bulb temperature shall be taken on the entering and leaving side of each heating coil.
7. Zone Ducts - Adjust zone ducts to within design CFM requirements. At least one zone balancing damper shall be completely open.
8. Main Ducts - Adjust main ducts to within design CFM requirements and traverse for total CFM quantities.
9. Branch Ducts - Adjust branch ducts to within design CFM requirements. Multi-diffuser branch ducts shall have at least one outlet or inlet volume damper completely open.
10. Magnahelic Gauges - Static pressure at static pressure tips for Magnahelic gauges shall be recorded in Test and Balance Reports.
11. Tolerances - Test and balance each diffuser, grille, and register to within 10 percent of design requirements. Test and balance all fans to within 5 percent of design requirements.
12. Identification - Identify the location and area of each grille, diffuser, register, and terminal box. This information shall be recorded on air outlet data sheets.
13. Description - Record the size, type, and manufacturer of each diffuser, grille, and register on air outlet data sheets.
14. Minimizing Drafts - Adjust all diffusers, grilles, and registers to minimize

drafts in all areas.

15. Test and Balance Engineer shall witness and record all leakage testing of ductwork. Leakage test data shall be included in final Test and Balance Reports.
16. Set volume regulators on all terminal boxes [VAV diffusers]to meet design maximum and minimum CFM requirements. Calibrate all terminal box air flow rates with automatic temperature control system. On fan-powered VAV boxes, adjust air flow switches for proper operation.
17. Where modulating dampers are provided, take measurements and balance at extreme conditions. Balance variable air volume systems at maximum air flow rate, full cooling, and at minimum airflow rate, full heating.
18. Measure temperature conditions across outside air, return air, and exhaust dampers to check leakage.
19. For heat pumps, assist start-up organization or manufacturer's representative with start-up. Record air flow rates, and electrical characteristics prior to refrigerant pressure measurement and settings.
20. For all equipment specified with condensate overflow safety switches/floats test operation of such device and record results. Verify interlock with ATC system.
21. Outside air and exhaust/relief air measurements must be measured and submitted in all modes of operation including the following:

    a. Min Min Outside Air/Exhaust/Relief air mode (square footage outside air).
    b. Min Max Outside Air/Exhaust/Relief air mode (square footage and people outside air).
    c. Maximum outside air/exhaust/relief mode (full 100% economizer mode).

22. For all outside air modes of operation record and submit full static pressure profiles, amperage, BHP, air flow rates, external static pressure, and internal static pressure. Verify airflow rates with air flow monitoring stations and record results.

3.4 WATER SYSTEM PROCEDURES

A. The various water circulating systems shall be filled, purged of air, and put into operation before hydronic balancing by the mechanical contractor.

B. The flow of water through all coils shall be adjusted by manipulating balancing valves until the rated pressure drop through the coil or metering device is obtained. Perform balancing by measurement of temperature differential in conjunction with air balancing.

C. The balancing agency shall perform the following testing and balancing functions in accordance with the AABC National Standards.

D. All Hydronic equipment, domestic re-circulating pumps, and HVAC pumps shall be Tested and Balanced as described below:

1. Water Treatment - Examine the water in the system and determine if the water has been treated and cleaned. If it has not, request the mechanical contractor to clean and treat the water prior to TAB work
2. Strainers - Request that the mechanical contractor clean all strainers.
3. Air Vents - Check all air vents at the high points of the water system and determine if they are installed and operating.
4. Valves - Set all balancing valves to the full-open position for balancing.
5. Pumps - Adjust all pumps and domestic hot water re-circulating water pumps to meet design GPM requirements. Check pumps for proper operation. Pumps shall be free of vibration and cavitation. Measure and record operating current and voltage. Check and record thermal overloads installed on all pumps. Record in Test and Balance Report.
6. Tolerances - Proceed to balance all coils, pumps, and balance valves to within 5 percent of design requirements.
7. Marking - Mark all settings and record all data after completing the flow readings and coil adjustments.
8. Where available pump capacity (due to diversity) is less than total flow requirements or individual system parts, full flow in one part may be simulated by temporary restriction of flow to other parts.
9. Test all A/C condensate pumps for proper operation.
10. Test condensate overflow safety switches and record test results in the Test and Balance Report.

E. Coils:

1. Tolerances - Test, adjust, and balance all hydronic coils within 5 percent of design requirements.
2. Verification - Verify the type, location, final pressure drop and GPM of each coil. This information shall be recorded on coil data sheets.

3.5 DOMESTIC HOT WATER RE-CIRCULATING SYSTEMS PROCEDURES

A. The domestic hot water re-circulating system shall be tested and balanced as indicated on the contract documents including:

1. Balance of circuit setters to design quantities indicated on contract documents.
2. Balance of re-circulating pumps to meet design GPM requirements.

3.6 TESTING AND BALANCING OF EXISTING SYSTEMS

A. The balancing agency shall perform testing and balancing of existing air handling, fan and pump systems to the extent indicated. Existing air devices and terminals shall be re-tested and balanced where effected by new ductwork modifications.

B. Test and Balance Agency shall assist the mechanical contractor in selection of new sheaves and belts, if required. Re-sheaving of existing air handling units or fans shall be done at no additional cost to owner. Where required, new sheave

and belt size calculations shall be forwarded to the Engineer for review and approval.

C. The Test and Balance Agency shall perform air system procedures (here-in before specified) on the following existing systems.

1. Existing AHU #3

D. The Test and Balance Agency shall perform water system procedures (here-in before specified) on the following hydronic systems.

1. Existing AHU #3
2. Provide temperature measurements across all existing coils.
3. For variable speed pumps, adjust existing differential pressure sensor serving existing variable speed pumps as required and record setpoint in TAB report.
4. Existing finned tube radiation.
5. Existing domestic recirculating pump.
6. Existing heating water pumps.

3.7 LIFE SAFETY CONTROLS TESTING PROCEDURES

A. The TAB agency shall test and record life safety control operation on the HVAC equipment. It shall verify the installation of required smoke detectors in air handling equipment (AHE), and shall verify operation of the smoke detector by activating the smoke detector and observing air handler shutdown. With the controls and alarm contractors, the TAB agency shall verify the operation of interconnected systems such as the AHU smoke detector's activation of the fire alarm system and the alarm system's activation of the life safety control sequences. Record results of tests within TAB report.

3.8 VERIFICATION OF TEMPERATURE CONTROL

A. The balancing agency shall be assisted by the temperature control contractor in verifying the operation and calibration of all temperature control systems. The following tests shall be conducted:

1. Verify that all control components are installed in accordance with project requirements and are functional, including all electrical interlocks, damper sequences, air and water reset.
2. Verify that all controlling instruments are calibrated and set for design operating conditions.
3. Verify the accuracy of the final settings by taking temperature readings. The readings shall be in a typical conditioned space for each separately controlled zone.
4. Test and calibrate all air flow monitoring stations and VAV boxes.
5. Test and calibrate all static pressure sensors for proper set point and control.

6. Test and calibrate all fluid and airside differential pressure sensors. Record set point in Record and Information Books.

3.9 TEST AND BALANCE REPORTS

A. The test and balance report shall be complete with logs, data, and records as required herein. All logs, data, and records shall be typed on white bond paper and bound. The report shall be certified accurate and complete by the balancing agency's certified test and balance engineer.

B. Three (3) hardcopies and one (1) electronic copy of the test and balance report are required and shall be submitted to the Engineer. If, in the opinion of the Engineer, test results or portions thereof are incomplete or inconclusive, repeat necessary portions of the work to the satisfaction of the Engineer.

C. The report shall contain the following general data in a format selected by the balancing agency:

1. Project Number
2. Contract Number
3. Project Title
4. Project Location
5. Project Architect
6. Project Mechanical Engineer
7. Test & Balance Agency
8. Test & Balance Engineer
9. Construction Manager
10. Mechanical Contractor
11. Commissioning Agent
12. Dates tests were performed
13. Certification
14. Duct Leakage Tests
15. Phone Numbers of all Individuals Listed Above

D. The test and balance report shall be recorded on report forms conforming to the recommended forms in the AABC National Standards.

E. The test and balance report shall include a table of contents with numbered pages.

3.10 TEST REPORT FORMS

A. Air Moving Equipment and Fan Test Forms - Submit fan curve showing design and operating points of operation. Also, record the following on each air-handling equipment test form:

1. Manufacturer, model number, serial number, arrangement.
2. All design and manufacturer-rated data.
3. Total actual CFM by traverse if practical. If not practical, the sum of the

outlets may be used, or a combination of each of these procedures. For specific systems, such as ones with diversity, see the AABC National Standards.

4. Suction and discharge static pressure of each fan, as applicable. Include pressure drops across coils, dampers, filters, mixing boxes, and similar devices.
5. Outside-air, return-air, and exhaust air total CFM.
6. Actual operating current, voltage and brake horsepower of each fan motor. For packaged equipment, this includes supply fans, relief air fans, and condenser fans.
7. Final RPM of each fan.
8. Fan and motor sheave manufacturer, model, size, number of grooves, bore, and center distance.
9. Belt size, quantity and make.
10. Static-pressure controls final operating set points (if applicable).
11. Total and external static pressure.

B. Pump Test Forms - Submit pump curve showing design, operating, and no-flow points of operation. Also, record the following items on each pump test form:

1. Manufacturer, size, model, service and serial number.
2. All design and manufacturer's rated data.
3. Pump operating suction and discharge pressure and final total dynamic head.
4. No flow (pump discharge valve closed) suction and discharge pressure and corresponding total dynamic head. This procedure is to determine actual impeller size. Record impeller size.
5. Rated and actual operating current, voltage, and brake horsepower of each pump motor.
6. Total operating head pressure.
7. Shutoff, discharge and suction pressures.
8. Shutoff, total head pressure.
9. For variable speed pumps record the differential pressure sensor setpoint pressure.

C. Heating and Cooling-Coil Test Forms - Record the following items on each test form:

1. Manufacturer, location, service.
2. All design and manufacturer's rated data.
3. Rated and actual water pressure drop through each coil and related GPM.
4. Rated and actual static pressure drop across each coil.
5. Rated and actual entering and leaving water temperatures across each coil.
6. Wet-bulb and dry-bulb temperatures entering and leaving each cooling coil; dry-bulb temperatures entering and leaving each heating coil.
7. Air flow (Design and Actual).
8. For DX-coil, provide design and actual saturated suction temperature.
9. For DX-Coil, provide design and actual discharge pressures.

D. Electric Motors Test Forms: (Applies to all motors, including pumps, fans and HVAC equipment)

1. Manufacturer.
2. Model/Frame.
3. HP/BHP.
4. Phase, voltage, amperage; nameplate, actual, no load.
5. RPM.
6. Service factor.
7. Starter size, rating, heater elements.
8. Sheave Make/Size/Bore.
9. Thermal overload settings

E. V-Belt Drive Test Forms:

1. Identification/location.
2. Required driven RPM.
3. Driven sheave, diameter and RPM.
4. Belt, size and quantity.
5. Motor sheave diameter and RPM.
6. Center to center distance, maximum, minimum, and actual.

F. Duct Traverse Test Forms:

1. System zone/branch.
2. Duct size.
3. Area.
4. Design velocity.
5. Design air flow.
6. Test velocity.
7. Test airflow.
8. Duct static pressure.
9. Air temperature.
10. Air correction factor.

G. Duct Leakage Test Forms:

1. Description of ductwork under test.
2. Duct design operating pressure.
3. Duct design test static pressure.
4. Duct capacity, air flow.
5. Maximum allowable leakage duct capacity times leak factor.
6. Test apparatus.

    a. Blower.
    b. Orifice, tube size.
    c. Orifice size.
    d. Calibrated.

7. Test static pressure.

8. Test orifice differential pressure.
9. Leakage.

H. Terminal Unit (VAV Box) Data Test Forms:

1. Manufacturer.
2. Type, constant, variable, single, dual duct.
3. Identification/number.
4. Location.
5. Model number.
6. Size.
7. Minimum static pressure.
8. Minimum design air flow.
9. Maximum design air flow.
10. Minimum actual air flow.
11. Maximum actual air flow.
12. Inlet static pressure.

I. Air Distribution Test Forms:

1. Air terminal number.
2. Room number/location.
3. Terminal type.
4. Terminal size.
5. Area factor.
6. Design velocity.
7. Design air flow.
8. Test (final) velocity.
9. Test (final) air flow.
10. Percent of design air flow.

J. Ductless Unit Test Forms:

1. Manufacturer
2. Type, air conditioning, heat pump
3. Identification number
4. Location
5. All design and manufacturer's rated data.
6. Rated and actual entering and leaving dry bulb temperatures.
7. Rated and actual entering and leaving wet bulb temperatures.
8. Air flow (design and actual)
9. Provide actual saturated suction temperature.
10. Actual operating current, voltage and brake horsepower of each fan motor.
11. Final fan RPM.
12. Operation of refrigerant mitigation controls, fan interlock, and refrigerant leak detection sensors.

K. Existing Finned Tube Test Forms - Record the following items on each test form:

1. Manufacturer, location, service.

2. All design and manufacturer's rated data.
3. Rated and actual water pressure drop through each piece of finned tube and related GPM.
4. Rated and actual entering and leaving water temperatures across each section of finned tube.
5. Entering and leaving air temperatures across each finned tube element.

L. Thermostatic Mixing Valve Test Forms

1. Manufacturer, Model Number, Series, Arrangement
2. All manufacturer data.
3. Verify all strainers are clean.
4. Leaving temperature actual and design.

M. Condensate Over Flow Switches/Floats Test Forms

1. Manufacturer
2. Type
3. Location
4. Equipment shut down verification
5. ATC interlock verification

N. Existing Rooftop Unit Test Forms: Submit fan curve showing design and operating points of operation. Also, record the following on each air-handling equipment test form:

1. Manufacturer, model number, serial number, arrangement.
2. All design and manufacturer-rated data.
3. Total actual CFM by traverse if practical. If not practical, the sum of the outlets may be used, or a combination of each of these procedures. For specific systems, such as ones with diversity, see the AABC National Standards.
4. Suction and discharge static pressure of each fan, as applicable. Include pressure drops across coils, filters, energy wheels, and similar devices.
5. Outside-air, and exhaust air total CFM.
6. Actual operating current, voltage and brake horsepower of each fan motor.
7. Final RPM of each fan.
8. Fan and motor sheave manufacturer, model, size, number of grooves, bore, and center distance.
9. Belt size, quantity and make.
10. Total and external static pressure.
11. Rated and actual static pressure drop across each energy wheel.
12. Wet-bulb and dry-bulb temperatures entering and leaving each cooling coil, heat pipe and energy wheel. Dry-bulb temperatures entering and leaving each heating coil.
13. Rated and actual pressure entering/leaving each hydronic coil.
14. Record the supply fan and exhaust fan maximum hertz/speed, and minimum hertz/speed. Provide measurements to ATC subcontractor for fan tracking control.
15. Test minimum air flow rate, maximum air flow rate and economizer air flow

rate.

16. Submit amperage, air flow rates, RPM, hertz, and static pressure profile in all modes of operation.

END OF SECTION 230593

SECTION 230600 – HEATING, VENTILATING, AND AIR CONDITIONING EQUIPMENT

PART 1 - GENERAL

1.1 GENERAL

A. The Conditions of the Contract and other General Requirements apply to the work specified in this section. All work under this section shall also be subject to the requirements of Division 23 Section, Common Work Results for HVAC and Division 01 Section General Requirements.

1.2 DESCRIPTION

A. The work to be performed shall include all labor, materials and equipment necessary to furnish and install complete, all mechanical equipment as shown on drawings, hereinafter specified or reasonably implied, and leaving the same in satisfactory operation condition. It is the intent that systems be installed complete with all items necessary to accomplish this purpose.

1.3 SUBMITTALS

A. Shop Drawings: Indicate assembly, equipment dimensions, weight loading, required clearances, construction details, field connection details, and electrical characteristics and connection requirements.

B. Product Data:

1. Provide literature which indicates dimensions, weights, capacities, ratings, performance, gages and finishes of materials, and electrical characteristics and connection requirements.
2. Provide data of filter media, filter performance data, filter assembly, and filters frames.
3. Provide fan curves with specified operating point clearly plotted.
4. Submit sound power level data for both fan outlet and casing radiation at rated capacity. Submit sound power levels by octave band or sound pressure levels by octave band for all equipment.
5. Submit electrical requirements for power supply wiring including wiring diagrams for interlock and control wiring, clearly indicating factory-installed and field-installed wiring.

1.4 OPERATION AND MAINTENANCE DATA

A. Maintenance Data: Include instructions for lubrication, filter replacement, motor and drive replacement, spare parts lists, and wiring diagrams.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, protect, and handle products to site under provisions of General Requirements.

B. Accept products on site in factory-fabricated protective containers, with factory-installed shipping skids and lifting lugs. Inspect for damage.

C. Store all equipment in clean dry place and protect from weather and construction traffic. Handle carefully to avoid damage to components, enclosures, and finish.

D. Comply with manufacturer's installation instructions for rigging, unloading and transporting equipment.

E. Protect all motors, shafts, and bearings from weather and construction dust.

1.6 ENVIRONMENTAL REQUIREMENTS

A. Do not operate any equipment for any purpose, temporary or permanent, until ductwork/piping is clean, filters/strainers are in place, bearings lubricated, and equipment has been test run under observation.

1.7 ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

1.8 EXTRA MATERIALS

A. For each unit or air device, furnish a spare set of filters.

B. For each unit that has belts, furnish a spare set of belts.

1.9 SHORT CIRCUIT CURRENT RATINGS

A. Unless otherwise noted, all HVAC equipment shall include a nameplate that identifies the short circuit current rating (SCCR). Unless otherwise noted the SCCR rating for all HVAC equipment shall be a minimum of 65 KA.

1.10 PACKAGED EQUIPMENT BACNET CARDS

A. For all packaged units, furnish and install Bacnet cards for interface to the automatic temperature control system. Map over all Bacnet points and alarms and show on ATC system graphics. All alarms must be identified on ATC graphic.

PART 2 - PRODUCTS

2.1 CONVENTIONAL DUCTLESS SPLIT SYSTEM HEAT PUMP (INVERTER TYPE) (CEILING CASSETTE TYPE)

A. The heat pump air conditioning system shall be a Mitsubishi Electric, Sanyo, LG, Daikin, Samsung, or approved equal split system. The system shall consist of a slim silhouette, compact ceiling recessed packaged evaporator section with matching Slim Line outdoor unit. The units shall be listed by Electrical Testing Laboratories (ETL) and bear the ETL label. All wiring to be in accordance with the National Electrical Code (N.E.C.). The units shall be rated in accordance with ARI standard 240 and bear the ARI label. A full charge of R-32 or R-454B refrigerant for 100 feet of refrigerant tubing shall be provided in the condensing unit. A dry nitrogen holding charge shall be provided in the condensing unit. A dry nitrogen holding charge shall be provided in the evaporator. System SEER shall meet or exceed Federal Standards latest edition

B. The units shall have a manufacturer's warranty for a period of two (2) years from date of installation. The compressor shall have a warranty of six years from date of installation. If, during this period, any part should fail to function properly due to defects in workmanship or material, it shall be replaced or repaired at the discretion of Mitsubishi Electronics America, Inc. This warranty does not include labor. Manufacturer shall have ten years experience in the U.S. market. Capacity shall be as scheduled on the contract drawings.

C. The indoor unit shall be completely factory assembled and wired. The casing shall be galvanized sheet with grey heat insulation. This unit shall fit in the ceiling and have the capability of attaching a branch supply duct as well as a fresh air duct. The evaporator fan shall be an assembly with a high performance, fan direct driven by a single motor. The fans shall be statically and dynamically balanced and run on permanently lubricated bearings. The indoor unit shall have an adjustable air outlet system offering 4-way air flow, 3-way air flow, or 2-way air flow. The auto air swing vanes shall automatically swing up and down for uniform air distribution. Return air shall be filtered by a long-life filter to provide approximately, 2500 hours of use in a normal office environment before cleaning. The indoor unit shall be covered with a flat panel which protrudes only 1 inch below the ceiling to provide a neat and clean installation. The coils shall be of nonferrous construction with smooth plate fins bonded to copper tubing. The tubing shall have inner grooves for high efficiency heat exchange. All tubes joints shall be brazed with phoscopper or silver alloy. The coils shall be pressure tested at the factory. A condensate pan shall extend under the coil and piping. An integral drain pan pump capable of lifting condensate 12 inches shall be provided. An integral booster heater shall not be provided to supplement the unit during the heating mode. The unit variable speed compressor shall allow full heating capability and defrost without the need for a booster heater. The unit electrical power requirements shall be as scheduled on the contract drawings.

D. The control system shall consist of two (2) microprocessors interconnected by a single non-polar two wire cable as supplied. Wiring shall run from indoor unit to

controller direct. NO SPLICES. When running longer lengths or more than one set of hardwired remote controller wires together, a double insulated, two wire cable equivalent to that provided e.g. Belden 9407 cable, is mandatory or use shielded two wire cable. One microprocessor shall be factory wired and located within the indoor unit. It shall have the capability of sensing return air temperature and indoor coil temperature; receive and process commands from the hardwired remote controller provide emergency operation; control the booster heater and control the outdoor unit. The microprocessor within the wall mounted hardwired remote controller shall provide automatic cooling and heating system changeover; display set point and room temperature; a 24 hour on/off timer so that automatic operation can be set on the timer at one hour intervals from one to twenty-four hours; have self-diagnostic function display; check mode for memory of most recent problem; System shall control continued operation of the air sweep louvers; and provide on-off and system/mode function switching. The heating system shall be controlled so that only warm air is discharged whenever the fan speed exceeds the very low (VLO) speed. Normal operation of the hardwired remote controller provides individual system control in which one hardwired remote controller and one indoor unit are installed in the same room. The hardwired remote controller shall have the capability of controlling up to a maximum of 50 systems at a maximum developed control cable distance of 1650 feet. The control voltage between the hardwired remote controller and the indoor unit shall be 12 volts, D.C. The control voltage between the indoor unit and the outdoor unit shall be 12 volts D.C. Both 12 VDC shall be generated from the indoor unit microprocessor board. The system shall be capable of automatic restart when power is restored after power interruption. System shall include twenty function self-diagnostics including total hours of compressor run time.

E. The outdoor unit shall be completely factory assembled, piped, and wired. The casing shall be fabricated of galvanized steel, bonderized and finished with baked enamel. The unit shall be furnished with one (1) direct drive, propeller type fan arranged for horizontal discharge. The motors shall have inherent protection be of the permanently lubricated type, and resiliently mounted for quiet operation. Each fan shall be provided with a raised guard to prevent contact with moving parts. The variable speed compressor shall be of the high-performance, rotary type with crankcase heater, accumulator and internal thermal overloads. The variable speed compressor shall be mounted so as to avoid the transmission of vibration. The refrigeration system shall be equipped with pressure switch and have the capability to operate with a maximum height difference of 130 feet and overall refrigerant tubing length of 130 feet between indoor and outdoor sections without the need for line size changes, traps or additional oil. Refrigerant flow from the condenser to be controlled by means of a capillary tube. The condenser coil shall be of nonferrous construction with smooth plate fins bonded to copper tubing. The coil shall be protected with an integral metal guard. The unit shall be controlled by the microprocessor located in the matching indoor unit. A built-in, low-ambient controller shall allow cooling to 0 degrees F outdoor temperature. The unit electrical power requirements shall be as scheduled on the contract drawings. The outdoor unit shall be placed on vibration isolators and mounted on a concrete pad.

F. High condensate water safety shutdown: Each indoor unit’s detection unit shall

be interlocked to alarm and stop the outdoor unit if a high condensate water level is sensed.

G. Refrigeration Mitigation Controls: Furnish units with listed refrigeration mitigation controls, fan interlocks, and refrigeration leak detection equipment per ASHRAE 15 requirements.

H. Units shall provide cooling down to 0F ambient temperature. Furnish with wind baffles.

2.2 FANS

A. General

1. Provide fans as indicated on the drawings. All fans shall have been tested and their performance rated in accordance with Air Movement and Control Association, Inc., Bulletin 210-85 Test Code and shall be licensed to bear the AMCA Seal. All fans shall carry the AMCA Certified Rating Seal for air and sound. Sound power levels shall be submitted for approval. Fan curves shall be submitted with all fan shop drawings.
2. Fan manufacturer shall submit under what duct configuration (unducted, partially ducted, or ducted) the manufacturer certified the performance of a particular fan or group of fans.

B. Power Roof Ventilators

1. Belt Drive

a. Furnish and install belt driven power roof ventilators of the size, capacity, and electrical characteristics a shown on contract drawings.
b. Roof fans shall be centrifugal belt driven type.
c. The fan wheel shall be centrifugal backward inclined, constructed of aluminum and shall include a wheel cone carefully matched to the inlet cone for precise running tolerances. Wheels shall be statically and dynamically balanced.
d. The fan housing shall be constructed of heavy gauge aluminum with a rigid internal support structure. The fan shroud shall have a rolled bead for added strength.
e. Motors shall be heavy duty ball bearing type, carefully matched to the fan load, and furnished at the specified voltage, phase and enclosure. Motor and drives shall be mounted on vibration isolators, out of the airstream. Fresh air for motor cooling shall be drawn into the motor compartment from an area free of discharge contaminants. Motors shall be readily accessible for maintenance.
f. Drive frame assemblies shall be constructed of heavy gauge steel and mounted on vibration isolators.
g. Precision ground and polished fan shaft shall be mounted in

permanently sealed, lubricated pillow block ball bearings. Bearings shall be selected for a minimum (L50) life in excess of 200,000 hours at maximum cataloged operating speed. Drives shall be sized for a minimum of 150 percent of driven horsepower. Pulley shall be of the fully machined cast iron type, keyed and securely attached to the wheel and motor shafts. Motor pulleys shall be adjustable for final system balancing.

h. A disconnect switch shall be factory installed and wired from the fan motor to a junction box installed within the motor compartment. A fan conduit chase shall be provided through the curb cap to the motor compartment for ease of installation.

i. All fans shall bear the AMCA Certified Ratings Seal for sound and air performance.

j. Each fan shall bear a permanently affixed manufacturer's nameplate containing the model number and individual serial number for future identification.

k. Provide 12-inch high, fully insulated, aluminum roof curbs with each ventilator. Fan and roof curb shall be provided by the same manufacturer.

l. Provide 2-inch aluminum birdscreen with each fan.

m. Motor operated dampers shall be provided by ATC subcontractor and installed by mechanical contractor.

n. Fans shall be Model GB as manufactured by Greenheck Fan Corporation, ACME Engineering, Penn Ventilator, Cook, Twin City Fan and Blower or approved equal.

2.3 EXTERIOR EQUIPMENT/DUCT SUPPORT

A. Exterior Equipment Supports shall be Pate Model ES suitable for roof construction. Equipment supports shall be constructed of 18 gauge galvanized steel, unitized construction with integral base plate, continuous welded corner seams, pressure treated wood nailer counterflasing and lag screws. Units shall be internally reinforced. Minimum height shall be 12-inches above the finished roof or as shown on the detail(s) on the drawing(s).

2.4 EXTERIOR ROOFTOP PIPING SUPPORT (NON-PENETRATING)

A. Exterior Piping Supports shall be non penetrating roof piping supports suitable for roof construction as manufactured by RTS – Rooftop Support Systems, Eberl Iron Works, Inc., Miro Industries. Pipe supports shall be constructed of 18 gauge stainless steel, unitized construction with integral base plate. Units shall be internally reinforced. Minimum height shall be 12-inches above the finished roof or as shown on the detail(s) on the drawing(s). Provide all stainless steel hardware. Duct support shall be “double support” type with adjustable height and width. Base shall be non-penetrating type, heavy duty rubber, manufactured from 100% recycled crumb rubber.

B. Pipe Supports: The pipe supports shall be elevated pipe roller supports. To allow

for expansion and contraction the supports shall include pipe rollers, threaded rods, and supporting hardware. All supports shall be type 304 stainless steel with stainless steel hardware. Furnish with pipe straps to restrain pipes on the rollers.

2.5 STATIC PRESSURE PROBES

A. General: Provide complete static pressure probes for air handling units and return air systems as indicated on drawings. The static pressure probes shall include static pressure probes and electronic pressure transmitters. All components shall be of the same manufacturer. The manufacturer shall be Air Monitor or as approved equal. A static pressure probe shall be provided for each supply duct main as indicated on the contract drawings. Provide multiple static pressure probes where indicated.

B. Air Monitor Duct Static Pressure Traverse Probes

1. Provide where indicated duct static traverse probe capable of continuously monitoring the duct or system static pressure it serves.
2. Each duct static traverse probe shall contain multiple static pressure sensors located along the exterior surface of the cylindrical probe. Said sensors shall not protrude beyond the surface of the probe.
3. The duct static traverse probe shall be of extruded aluminum construction and (except for ¾-inch diameter probes with lengths of 24-inches or less) be complete with threaded end support rod, sealing washer and nut and mounting plate with gasket and static pressure signal fitting.
4. The static traverse probe shall be capable of producing a steady, non-pulsating signal of standard static pressure, without need for correction factors, with an instrument accuracy of 0.5 percent.
5. The duct static pressure traverse probe shall be the STAT-probe/1 as manufactured by the Air Monitor Corporation, Paragon or as approved equal.

C. Air Monitor Electronic Pressure Transmitters

1. The electronic control-instrument components shall be of industrial process control quality with operating features described herein and capable of producing the outlined performances. Commercial grade control-instruments, devices, are not acceptable.
2. The electronic pressure transmitter shall include an automatic zeroing circuit capable of automatically readjusting the transmitter zero at predetermined (adjustable) time intervals while retaining (locking in) the output signal. The electronic pressure transmitter shall be capable of receiving signals of static pressures, and of amplifying and scaling the sensed pressure into a 4-20 mADC or 0-5 (0-10) VDC output signal linear to static pressure, within the following minimum performance criteria:

Zeroing	Automatic, within 0.1 percent of operating span, on 4 to 256 minute intervals (selectable)
Spans	Factory Custom Spanned, Coordinated With System, Ranges From 0 To .01-Inch To 0 To 10.0-Inches. Field Adjustment +20 Percent Of Span.
Accuracy	+ 0.25 Percent Of Span
Deadband And Hysteresis (Combined):	Less Than 0.2 Percent Of Span
Linearity:	+ 0.2 Percent Of Span
Repeatability:	0.15 Percent Of Span
Response:	0.5 Second For 98 Percent Full Span Input
Power Supply:	24 Vac, 20 To 40 Vdc, Selectable; 4 Wire

3. Coordinate requirements with the buildings direct digital control system to perform the required sequence of operation.
4. The pressure transmitter shall be the VELTRON series 5000AZ as manufactured by the Air Monitor Corporation or as approved equal.

2.6 TERMINAL AIR UNITS – NON FAN POWERED DENTAL FACILITY TYPE WITH HOT WATER HEAT

A. VAV Boxes (Pressure Independent-Electronic Actuation)

1. Furnish and install variable air volume terminals of the sizes and capacities as indicated on the drawings. The boxes must be specifically designed and performance shall be ARI certified for medium pressure operation. Units serving Cath Lab shall be constant volume type. All other units shall vary air flow rate based on space temperature deviation from set point.
2. The entire terminal unit shall be specifically designed and built as a single unit for primary air (55°F). Units shall be provided with an insulated variable air volume damper that modulates the primary air in response to a wall mounted room thermostat. Units shall include an integral air sound attenuator with double wall metal lined insulation (suitable for critical hospital environments).
3. All interior surfaces shall be covered and protected as required for an operating room environment per ASHRAE 170.
4. Unit casing shall be a double wall minimum of 22 gauge galvanized steel, fully lined with a minimum of 1 inch thick, 1.5 pound density insulation. The insulation shall be protected with a continuous metal liner and shall comply with UL standard 181 for erosion and NFPA 90A for fire resistivity.

No cut edges of insulation shall be exposed to the moving air stream. All liners must include impervious cover to comply with ASHRAE 170 requirements.

5. The terminal casing shall have a removable bottom access door which allows removal of fan, and servicing of unit without disturbing duct connections. Casing leakage shall not exceed 2 percent of the scheduled air flow at 3.0 inches difference in static pressure from inlet to outlet. All casing joints shall be sealed with an approved sealant if required to meet the maximum casing leakage.
6. The terminal casing shall have an insulated round inlet collar for the primary air connection and a rectangular discharge air connection. Casing shall be designed for hanging by all thread rods or sheet metal straps with spring vibration isolators from structures above.
7. The control contractor shall be responsible for installation of space sensors, wiring to 120V power panel, and communication transmission bus. The controls contractor shall coordinate shipment of Terminal Control Unit, duct sensors and damper operators to the terminal box manufacturer for installation at the factory. The terminal box manufacturer shall supply and install necessary contactors, wiring, control transformers, relays and enclosures to assure terminal box functionality in accordance with this specification.
8. The Terminal Control Unit for the VAV terminal boxes, shall be furnished and shipped by the automatic temperature controls contractor to the terminal box manufacturer for installation at their factory. The cost of factory mounting, wiring, and any factory testing and programming of the Terminal Control Unit shall be included by the terminal box manufacturer. The control contractor shall coordinate with the terminal box manufacturer and sheet metal contractor to ensure the delivery of factory installed controls and proper installation according to the project schedule.
9. The terminal box manufacturer shall install the air velocity sensor mounting bracket in the inlet collar of the terminal casing. Primary inlet air flow sensor shall be multi-quadrant averaging sensor with flow sampling of both velocity pressure and flow differential pressure from four (4) quadrants.
10. The normally-open unit shall be capable of operating in an early morning warmup cycle and a night set back cycle.
11. An air damper and actuator shall vary primary air in response to a thermostat signal. Damper leakage at shutoff shall not exceed 1 percent at 3 inches W.G. pressure. The damper shall be located inside the terminal.
12. Damper connection to the operating shaft shall be a positive mechanical connection. Provide self-lubricating bearings for the shaft. Nylon is not acceptable as bearing material.
13. The terminal shall incorporate single point electrical and control connections for the entire unit. All electrical components shall be UL listed and installed in accordance with the National Electric Code. All electrical components shall be mounted in a control box and the entire terminal shall be UL or ETL listed as an assembly.
14. Boxes shall be equipped with hot water heat coils as scheduled on the drawings.

a. Hot water reheat coils shall be enclosed in a minimum 20 gauge galvanized steel casing with slip and drive construction for attachment to metal ductwork. Coils shall be factory installed on the terminal discharge. Fins shall be rippled and corrugated heavy gauge aluminum, mechanically bonded to tubes. Tubes shall be copper with minimum wall thickness of .016-inch with male solder header connections. Coils shall be leak tested to 300 psi with minimum burst pressure of 2000 psi at ambient temperature. Number of coil rows and circuits shall be selected to provide performance as required per the plans. Coil performance data shall be based on tests run in accordance with ARI Standard 410.

15. At an inlet velocity of 2000 fpm, the differential static pressure required to operate any terminal size shall not exceed 0.14-inch w.g. for the basic terminal.
16. Boxes shall be equipped with a control transformer. The box manufacturer and control manufacturer shall coordinate all requirements to assure a complete and operational system.
17. Testing Requirements: Test and rate air terminals according to ARI 880, Industry Standard for Air Terminals.
18. Identification: Label each air terminal with plan number, nominal airflow, maximum and minimum factory-set airflows, coil type, and ARI certification seal.
19. Acoustically test all VAV boxes per ARI Standard 880-83. Submit sound power data discharge, inlet and casing radiated.
20. Variable volume terminals shall be Trane Model VLWP, series TH as manufactured by Metalaire, DESV as manufactured by Titus, Environmental Technologies, Inc., Krueger, Johnson Controls, Price, or approved as equal.

2.7 REFURBISHMENT OF EXISTING AIR HANDLING UNIT

A. The existing air handling unit, supply air fan, and return/exhaust air fan shall be refurbished per the following scope of work. Provide and coordinate disposal of all job materials. In addition to below, provide all other new equipment, control valve, sensors, motors, variable frequency drives, controls, sensors, damper actuators, duct detectors, etc. as shown on Contract Documents.

B. The specific scope of work for each unit shall be as follows:

C. Existing AHU-3 Supply Air Fan and Return Air Fan

1. Existing Model/PCCB-FJCABBFOBAAB
2. Serial # K90L3569
3. Repair, lubricate and adjust return air, relief air, and outside air damper linkages. Replace all damper actuators.
4. Clean and sanitize interior including all internal components.
5. Inspect, clean and calibrate all existing automatic temperature control

system devices and sensors.
6. Pull and clean all equipment strainers.
7. Tension, align, and install new belts.
8. Remove existing filters and install new filters. Provide spare set of filter.
9. Perform factory start-up of unit and submit report.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify all dimensions by field measurements. Verify that all equipment may be installed in accordance with pertinent codes and regulations, the original design, and the referenced standards.

B. Verify structure, mounting supports and membrane installations are completed to the proper point to allow installation of roof mounted equipment, where applicable.

C. Examine rough-in requirements for all piping systems to verify actual locations of piping connections prior to installation.

D. Verify that electrical work installation is in accordance with manufacture's submittal and installation requirements of Division 26 sections. Do not proceed with equipment start-up until electrical work is acceptable to equipment installer. Coordinate sizes of all thermal overloads with Division 26.

E. Do not proceed until unsatisfactory conditions have been corrected.

F. Provide wiring diagrams of all equipment as specified in Division 23 Section, Common Work Results for HVAC.

3.2 GENERAL INSTALLATION REQUIREMENTS

A. Install all equipment in accordance with manufacturer's installation instructions, in accordance with state and local code requirements, and in accordance with the contract drawings. Install all equipment plumb and level, to tolerances as required by the manufacturer of each item of equipment. Maintain manufacturer recommended clearances around and over all equipment.

B. Coordinate vibration isolation requirements with all equipment in accordance with Division 23 Section, Vibration Controls for HVAC, Plumbing and Fire Protection Equipment.

C. Coordinate all electrical requirements with Division 26.

D. Coordinate all indoor and outdoor equipment pad locations and sizes with approved shop drawing submittals. Provide operating weights of equipment to Structural Engineer for review. Coordinate equipment pad locations and sizes

with the Concrete Contractor or General Contractor. Furnish anchor bolts which are to be inserted in concrete pads to concrete installer.

E. Verify piping arrangements of all equipment with the contract drawings. Piping details shall be strictly adhered to concerning valves, fittings, components, etc. At coils, where a rebuildable and repairable autoflow valve is installed in the line without the need for draining or shutting of the water, the same may be utilized as the isolation valve and additional shut-off valve is not required.

F. Connect all equipment, devices and components to wiring systems and to ground as indicated and instructed by manufacturer. Tighten connectors and terminals, including screws and bolts, according to equipment manufacturer's published torque tightening values for equipment connectors. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals according to tightening requirements specified in UL 486A.

G. Testing: After installing HVAC equipment, devices and components and after electrical circuitry has been energized, demonstrate product capability and compliance with requirements.

H. Remove and replace malfunctioning units with new units and retest.

I. All mechanical penetrations or terminations in exterior walls shall be flashed and caulked watertight. Furnish and installed lintels as required.

J. Arrange for equipment such as VAV boxes to be shipped to project in modules where space constraints require the same. Field erect components as required.

3.3 FIELD QUALITY CONTROL

A. Where indicated provide the services of a factory authorized service representative to examine the field assembly of components, installation, piping, electrical connections, controls, and clearances. Submit factory start-up check list to Engineer for information purposes. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer, and forwarded to Testing and Balancing Agency.

B. Where factory start-up of equipment is not specified, provide field start-up by qualified technician to examine the field assembly of components, installation, piping, electrical connections, controls and clearances. Record equipment manufacturers standard start-up information and submit to Engineer for review. Testing and balancing work shall not commence until start-up reports have been completed, reviewed by Engineer, and forwarded to Testing and Balancing Agency.

C. Charge all refrigerant systems with refrigerant and oil and test for leaks. Repair leaks and replace lost refrigerant and oil.

D. Fill all hydronic systems with water after flushing and test for leaks. Repair leaks

and replace lost water. Coordinate with owner's contractor.

E. Submit to Engineer a written table of all relief valve and make-up water valve settings for each system. Provide an additional copy in the Operations and Maintenance Manuals.

F. Verify proper motor sizes, voltages, thermal overloads, nameplate data, etc. All equipment voltages and current shall be recorded to insure that motors are operating below their service factors. Test and Balance Engineer shall record electrical data before continuous or permanent operation.

G. Verify refrigerant mitigation controls including fan interlocks, control interlocks, and refrigerant leak detectors.

3.4 DEMONSTRATION

A. Provide the services of a factory authorized service representative to provide start-up and to demonstrate and train the Owner's maintenance personnel.

B. Place equipment into operation and adjust controls and safeties. Replace damaged or malfunctioning components and controls.

C. Training:

1. Train the Owner's maintenance personnel on start-up and shut-down procedures, troubleshooting procedures, lubrication, servicing procedures and preventative maintenance schedules/procedures. Review with the Owner's personnel, the contents of the operation and maintenance data specified in Division 23 Section, Common Work Results for HVAC.
2. Submit operation and maintenance data as soon as possible prior to project close-out. Operations and maintenance data shall be submitted to the Owner for review and comment prior to submission to the Engineer.
3. Schedule training with the Owner through the Architect and/or Engineer with at least seven (7) days prior notice.

D. Contractor shall demonstrate removal and replacement of filters at all pieces of equipment with filters in the prescence of the Owners representative.

3.5 CLEANING

A. After completing installation, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes including chips, scratches, and abrasions.

B. Clean fan and equipment interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheels, cabinets, and coils' entering air face.

3.6 CONVENTIONAL DUCTLESS UNITS EQUIPMENT INSTALLATION REQUIREMENTS

A. Mount indoor and outdoor units as detailed on contract drawings.

B. Supply initial charge of refrigerant and oil as required.

C. Install all interlock and control wiring between indoor units, outdoor units thermostats, and condensate pumps.

D. Install indoor ceiling cassette on vibration isolators.

E. Install outdoor units on concrete pads or on roof curbs as indicated on drawings.

F. Comb out fins on condensing unit where deformed or bent. Replace or repair broken fins.

G. Install condensate lift pumps, float switches, alarm, unit shut down wiring and detection block units per manufacturer's recommendations.

H. Install wind baffles when required for low ambient operation. Locate wind baffles facing the predominant wind direction in winter.

I. Test refrigeration mitigation controls including fan interlocks, refrigerant leak detection devices, and refrigeration system shutdown controls.

3.7 FAN INSTALLATION REQUIREMENTS.

A. Install fans with resilient mounting and flexible electrical leads.

B. Install flexible connections and vibration isolators as specified in Division 23 Section, Common Work Results for HVAC and Division 23 Section Vibration Controls for HVAC, Plumbing and Fire Protection Equipment. Ensure metal band of connectors are parallel with minimum one inch flex between ductwork and fan while running.

C. Provide safety screens/guards on all fans and permanently mount after final testing and balancing.

D. Do not operate fans for any purpose until ductwork is clean, filters in place, bearings lubricated, and fans have been test run under operation.

E. Provide sheave required for final air balance.

F. Install fans according to manufacturer's written instructions.

G. Adjust damper linkages for proper damper operation.

H. Adjust belt tension.

I. Lubricate bearings.

J. Replace fan and motor pulleys and belts as required to achieve design conditions.

K. Mount, install, and wire speed controllers for direct drive fans. Speed controllers for direct drive fans shall be mounted adjacent to fan and wired in accordance with the NEC.

3.8 VAV EQUIPMENT INSTALLATION REQUIREMENTS

A. Provide ceiling access doors or locate VAV units above easily removable ceiling components. Support VAV units such that all access doors and panels are readily accessible.

B. Support units individually from structure. Do not support from adjacent ductwork.

C. Verify that electric power is available and of the correct characteristics.

D. Adjust minimum and maximum set points of VAV units as indicated on contract drawings.

E. Provide proper service, maintenance access around all variable frequency drives.

F. Coordinate electrical characteristics of variable frequency drives with motor served.

G. Externally insulate all air flow monitoring stations to prevent surface condensation.

H. Install VAV boxes level and plumb, according to manufacturer's written instructions, rough-in drawings, original design, and referenced standards; and maintain sufficient clearance for normal service and maintenance.

I. Connect ductwork to air terminals according to Division 23 Section, HVAC Air Distribution ductwork sections.

J. Install piping adjacent to air terminals to allow service and maintenance.

K. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

L. Verify that conditions are suitable for installation.

M. Verify that field measurements are as shown on the drawings.

N. Install the terminal units in accordance with the manufacturer's instructions.

O. Install the inlets of the air terminal units with the air flow sensors a minimum of three duct diameters from elbows, transitions, and duct takeoffs.

P. See drawings for the size(s) and duct location(s) of the air terminal units.

Q. Provide ceiling access doors or locate units above easily removable ceiling components.

R. Support the terminal units individually from the structure.

S. Embed anchors in concrete in accordance with ASTM E488/E488M.

T. Do not support the terminal units from the ductwork.

U. Connect the terminal units to the ductwork in accordance with Division 23 Section “HVAC Air Distribution”.

V. Verify that electric power is available and of the correct characteristics.

W. Ensure the damper operator attached to the assembly allows full modulation of flow range from 100 percent of design flow to zero.

END OF SECTION 230600

SECTION 230701 – HVAC INSULATION

PART 1 - GENERAL

1.1 REFERENCE

A. The Conditions of the Contract and other General Requirements apply to the work specified in this Section. All work under this Section shall be subject to the requirements of Division 23 Section, Common Work Results for HVAC.

B. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section

1.2 DESCRIPTION

A. All piping, ductwork, and equipment installed under this Contract shall be covered as specified.

1.3 SCOPE

A. The work covered by this specification consists of furnishing all labor, equipment, materials and accessories, and performing all operations required, for the correct fabrication and installation of thermal insulation applied to all piping, equipment, and duct systems, in accordance with applicable project specifications and drawings, subject to the terms and conditions of the contract.

1.4 STANDARDS

A. Thermal insulation materials shall meet the property requirements of one or more of the following specifications as applicable to the specific product or use:

1. American Society for Testing of Materials Specifications:

   a. ASTM C 547, "Standard Specification for Mineral Fiber Preformed Pipe Insulation".
   b. ASTM C 533, "Standard Specification for Calcium Silicate Pipe & Block Insulation".
   c. ASTM C 55, "Standard Specification for Mineral Fiber Blanket and Felt Insulation".
   d. ASTM E 96, “Standard Test Methods for Water Vapor Transmission of Material”.
   e. ASTM C 585, "Recommended Practice for Inner and Outer Diameters of Rigid Pipe Insulation for Nominal Sizes of Pipe and Tubing (NPS System)".

f. ASTM C 612, "Standard Specification for Mineral Fiber Block and Board Thermal Insulation".
g. ASTM C 1136, "Standard Specification for Barrier Material, Vapor, "Type 1 or 2 (Jacket only).

2. ASHRAE 90.1 "Energy efficient design of new buildings except low-rise residential buildings", latest edition.
3. International Energy Conservation Code, latest edition.

B. Insulation materials, including all weather and vapor barrier materials, closures, hangers, supports, fitting covers, and other accessories, shall be furnished and installed in strict accordance with project drawings, plans, and specifications.

1.5 SYSTEM PERFORMANCE

A. Insulation materials furnished and installed hereunder should meet the minimum economic insulation thickness requirements of the North American Insulation Manufacturers' Association (NAIMA) (formerly known as TIMA), to ensure cost-effective energy conservation performance. Alternatively, materials should meet the minimum thickness requirements of National Voluntary Consensus Standard 90.1, (latest edition) and "Energy Efficient Design of New Buildings," of the American Society of Heating, Refrigeration, and Air-Conditioning Engineers (ASHRAE), latest edition. However, if other factors such as condensation control or personnel protection are to be considered, the selection of the thickness of insulation should satisfy the controlling factor. As minimum, all insulation thicknesses shall be as hereinafter specified.

B. Insulation materials furnished and installed hereunder shall meet the fire hazard requirements of any one of the following specifications:

1. ASTM E 84 - American Society for Testing of Materials
2. UL 723 - Underwriters' Laboratories, Inc.
3. NFPA 255 - National Fire Protection Association
4. ASTM E 96 - Standard Test Methods for Water Vapor Transmission of Materials.

C. Calcium silicate products shall include a visual identification system to permit positive field determination of their asbestos-free characteristics.

1.6 QUALITY ASSURANCE

A. Insulation materials and accessories furnished and installed hereunder shall, where required, be accompanied by manufacturers' current submittal or data sheets showing compliance with applicable specifications listed in Section 1.4 above.

B. Insulation materials and accessories shall be installed in a workmanlike manner by skilled and experienced workers who are regularly engaged in commercial

insulation work.

1.7 DELIVERY AND STORAGE OF MATERIALS

A. All of the insulation materials and accessories covered by this specification shall be delivered to the job site and stored in a safe, dry place with appropriate labels and/or other product identification.

B. The Contractor shall use whatever means are necessary to protect the insulation materials and accessories before, during, and after installation. No insulation material shall be installed that has become damaged in any way. The Contractor shall also use all means necessary to protect work and materials installed by other trades.

C. If any insulation material has become wet because of transit or job site exposure to moisture or water, the Contractor shall not install such material, and shall remove it from the job site. An exception may be allowed in cases where the Contractor is able to demonstrate that wet insulation when fully dried out (either before installation, or afterward following exposure to system operating temperatures) will provide installed performance that is equivalent in all respects to new, completely dry insulation. In such cases, consult the insulation manufacturer in writing for technical assistance.

D. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements. Protect all insulation from water, construction traffic, dirt, chemical and mechanical damage.

1.8 ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1 GENERAL

A. All materials to be insulated shall be thoroughly cleaned, after completion of successful tests, and shall be covered as specified below. Fiberglass insulation shall be Owens-Corning, Manville, Armstrong, or P.P.G, or as approved equal.

2.2 PIPE INSULATION MATERIALS

A. Unless otherwise noted, insulation shall be one piece or half sectional molded fibrous glass with "K" rating of .23 at 75 degrees Fahrenheit mean temperature, for service temperatures between -60 degrees Fahrenheit and +450 degrees Fahrenheit with all service poly-encapsulated jacket. Pipe insulation shall be

fiberglass ASJMax SSL II with double closure system as manufactured by Owens Corning, Johns Manville, Knauf or approved equal.

B. Exterior refrigerant pipe insulation shall be Armacell, or approved equal, foam insulation with exterior field applied aluminum jacketing. Interior refrigerant piping shall be Armacell or approved equal foam insulation. Where interior refrigerant piping is exposed also install field applied PVC jacketing.

C. Unless otherwise noted, pipe insulation jacket shall be factory-applied vinyl coated, embossed and reinforced vapor barrier laminate, with a perm rating of not more than 0.02 perms. All hot and cold, concealed and exposed butt strips shall be of the same material as the jacket. Jacket and butt strips shall be sealed with field-applied Foster 85-20/85-60 or Childers CP-82 (5 gal cans only) adhesive. Jacket and butt strips shall be off-white color and shall be equivalent to Owens-Corning Fiberglass 25-ASJ.

D. Indoor pipe insulation shall be ASJ Max with SSL-II closure system pipe insulation as manufactured by Owens Corning or approved equal. Pipe insulation shall be composed of heavy density fiberglass insulation with an organic binder. The insulation shall include a white, factory jacketed, resilient, tough, soil resistant polymer facing that matches standard PVD fitting covers. Furnish all accessories and matching butt joints sealing tape for system closure. Insulation shall be suitable for operating temperatures between 32 degrees Fahrenheit and 220 degrees Fahrenheit. Flame spread rating of 25 or less, and smoke development rating of 50 or less to comply with building codes for installation in return air plenums. The maximum thermal conductivity (K-value) at a mean temperature of 50 shall be .22 BTU-in/hr-Ft²-degress Fahrenheit.

E. For fittings on all piping, valves and flanges, apply fiberglass molded or segmented insulation equal in thickness to the adjoining insulation and securely fasten in place using wire. Cold piping: Apply a tack coat of vapor barrier coating and reinforcing mesh. After ½ hour, apply second coat of same vapor barrier coating, UL labeled, Type C, for cold water piping, Hot piping Type H for hot water piping: Apply tack of breather mastic. Wrap fitting with fiberglass reinforcing cloth overlapping adjoining sections of pipe insulation by 2-inches. Apply a second coat of breather mastic over the reinforcing cloth, working it to a smooth finish.

1. Vapor Barrier Coating: Foster 30-65; Childers CP-34 or Vimasco 749. Permeanie shall be 0.03 perms or less at 45 mils dry as test by ASTM E96.
2. Breather mastic: Foster 46-50; Childers CP-10/11 or Vimasco WC-5
3. Reinforcing Mesh: Foster Mast a Fab; Childers Chil Glas #10 or Vimasco Elastafab

F. All pipe insulation, jackets, or facings, and adhesives used to adhere jacket or facing to the insulation, including fittings and butt strips, shall have non-combustible fire and smoke hazard system rating and label as tested by ASTM E-84, NFPA 225, and UL 73, not exceeding Flame Spread 25, Fuel Contributed 50, Smoke Developed 50. Accessories such as adhesives, mastic cements, tapes and cloth for fittings shall have the same ratings as listed above. All products or their shipping cartons shall bear the Underwriter's label indicating that flame and

smoke ratings do not exceed the above criteria.

G. For piping having a vapor barrier insulation and for all insulated piping requiring supports, hangers and supports shall be installed outside the insulation. Wherever hangers and supports are installed outside the insulation, pipe insulation protecting shields shall be provided. Where insulation is a load bearing material, of sufficient strength to support the weight of the piping, pipe shields one-third the circumference of the insulation and of a length not less than three times the diameter of the insulation (maximum length 24-inches) shall be provided. Insulation of 7-1/4 pound or greater density will be considered as load bearing for pipe sizes up to and including 2-inches. Where insulation is not of sufficient strength to support the weight of the piping, a half section of high density fiberglass or foam inserts, shall be provided. Vapor barrier and finish shall be applied as required to match adjoining insulation. In addition, shields shall be furnished as specified above.

H. For piping located outside of the building, a corrugated aluminum weatherproof jacketing system shall be provided. This system shall be Micro-Lot ML as manufactured by Manville, Polyweld by Pabco Metals Corp., Childers, or as approved equal, and installed per the manufacturer's recommendations. Where outdoor piping is receiving electric heat tape, the insulation shall be oversized so that the heat tape is not compressed tightly to the pipe. Pipe jacketing shall be corrugated (3/16-inch) deep aluminum, .016-inch thickness of H-14 temper with aluminum strapping of .75-inch width and .020 inch thickness with moisture barrier. Aluminum jacketing elbows shall be smooth, .016-inch thickness and 1100 alloy. All jacketing shall have an integrally bonded moisture barrier over the entire surface in contact with the insulation. Longitudinal joints shall be applied so they will shed water and shall be sealed completely with metal jacketing sealant. Sealant shall be Foster 95-44 or Childers CP-76. Circumferential joints shall be closed using preformed butt strips following manufacturer's recommendations for securement. Jacket seams shall be located on the bottom side of the horizontal piping.

I. All disturbed piping insulation in existing areas shall be re-insulated with insulation type, density, and thickness as specified for new piping. Insulation damaged due to new work and demolition only shall be replaced unless otherwise noted.

J. On cold systems such as refrigerant piping and cooling coil drain piping , etc. vapor barrier performance is extremely important. All penetrations and seams of the ASJ and exposed ends of insulation must be sealed with vapor barrier coating. The ASJ must be protected with either a coating or a suitable vapor retarding outer jacket. Vapor seals at butt joints shall be applied at every fourth pipe section joint and at each fitting to provide isolation of water incursion. Vapor Barrier Coating: Foster 30-65; Childers CP-34 or Vimasco 749. Permeance shall be 0.03 perms or less at 45 mils dry as test by ASTM E96.

K. Fittings and valves shall be insulated with pre-formed fiberglass fittings, fabricated sections of fiberglass pipe insulation, Fiberglass pipe and tank insulation, Fiberglass blanket insulation, or insulating cement. Thickness shall be equal to adjacent pipe insulation. Finish shall be with pre-formed PVC fitting covers or as

otherwise specified on contract drawings. Where applicable, Victaulic PVC fitting valve and coupling covers shall be utilized. Victaulic PVC covers shall be installed with matching pipe insulation jacketing material, vinyl tape solvent weld adhesive and appropriate fasteners.

1. Flanges, couplings and valve bonnets shall be covered with an oversized pipe insulation section sized to provide the same insulation thickness as on the main pipe section. An oversized insulation section shall be used to form a collar between the two insulation sections with low density blanket insulation being used to fill gaps. Jacketing shall match that used on straight pipe sections. Rough cut ends shall be coated with a suitable weather or vapor-resistant mastic as dictated by the system location and service. Finish valve installation with a Tyvac jacket with ends that secure to adjacent piping.
2. On hot systems where fittings are to be left exposed, insulation ends should be beveled away from bolts for easy access.
3. On cold systems, particular care must be given to vapor sealing the fitting cover or finish to the pipe insulation vapor barrier. All valve stems must be sealed with caulking which allows free movement of the stem but provides a seal against moisture incursion. All gauge and thermometer penetrations and extensions shall be correctly sealed and insulated to prevent surface condensation. Install oversized hangers to prevent penetrations of pipe insulation vapor barrier.

L. All piping shall be supported in such a manner that neither the insulation or the vapor/weather barrier is compromised by the hanger or the effects of the hanger. In all cases, hanger spacing must be such that the circumferential joint may be made outside the hanger. On cold systems, vapor barrier must be continuous, including material covered by the hanger saddle.

1. Piping systems 3-inches (7.5cm) in diameter or less, insulated with Fiberglass insulation, may be supported by placing saddles of the proper length and spacing, as designated in Owens-Corning Pub. 1-IN-12534, under the insulation. Hangers saddles shall be minimum 16 gauge with a saddle arc of 120 degrees minimum.
2. For hot or cold piping systems larger than 3-inches (7.5 cm) in diameter, operating at temperatures less than +200 degrees F (93 degrees C) and insulated with fiber glass, high density inserts such as foam or wood blocks with sufficient compressive strength shall be used to support the weight of the piping system. At temperatures exceeding +_200 degrees F (93 degrees C), Owens-Corning Pink Calcium Silicate, IIG, or approved equal pipe insulation shall be used for high density inserts.
3. Owens-Corning Pink Calcium Silicate pipe insulation may be used to support the entire weight of the piping system provided the hanger saddle is designed so the maximum compressive load does not exceed 100 psi (7kg/cm).
4. Where pipe shoes and roller supports are required, insulation shall be inserted in the pipe shoe to minimize pipe heat loss. Where possible, the pipe shoe shall be sized to be flush with the outer pipe insulation diameter.
5. Thermal expansion and contraction of the piping and insulation system

shall generally be taken care of by utilizing double layers of insulation and staggering both longitudinal and circumferential joints. Where long runs are encountered, expansion joints may be required where single layers of insulation are being used and should be so noted on the contract drawings.

6. On vertical runs, insulation support rings shall be used.

M. The direct buried heating water piping (PEX) serving the finned tube radiation shall be insulated with closed - cell phenolic - foam insulation. Insulation shall be in accordance with ASTM C1126 and shall exhibit low water - absorption characteristics. High density (5lb/cu.ft) shall be utilized for underground installations. Insulation shall be as manufactured by Kooltherm, Imcoa, Armstrong, Dyplast, ITW Insulation, or approved equal.

2.3 PIPING INSULATION THICKNESSES SCHEDULE

A. All piping shall be insulated with pipe insulation of the thicknesses indicted below:

PIPING INSULATION THICKNESS SCHEDULE SERVICES	THICKNESS
All Branch Runouts to Existing Fin Tube	1-inch thickness
Heating Hot Water Piping 2-inches & Larger	2 –inch thickness
Heating Hot Water Piping 1-½ -inches & Smaller	1 ½ -inch thickness
All Drain Piping from Cooling Coils/Evaporators	1-inch thickness
All Refrigerant Piping	1-inch thickness

2.4 DUCTWORK INSULATION MATERIALS AND THICKNESSES

A. Insulate all ductwork with fiberglass exterior duct insulation with factory-applied foil facing. All exposed fiberglass duct insulation shall be 2-inch rigid or non-flexible board type 3.0 pcf minimum density, 0.23 max. "K" factor at 75 degrees F mean temperature, with white vinyl A.S.J. max, polymer coating vapor barrier facing. All concealed fiberglass duct insulation shall be 2-inch flexible blanket type, 1.0 pcf minimum density. All concealed insulation shall be 0.27 max. "K" factor at 75 degrees F mean temperature with reinforced foil-scrim Kraft vapor barrier facing. Unless otherwise noted, the minimum installed R-value shall be 6.0 HR x ft2 x ºF/btu.

B. For concealed supply air ductwork from air handling units to variable air volume boxes valves insulation shall be 12 -inch flexible blanket, 12 pcf minimum density, .25 max "k" factor at 75 degrees F mean temperature.

C. Refer to Division 23 Section, HVAC Air Distribution System and contract drawings for location of all sound-lined ductwork. Sound-lined ductwork from the discharge or supply side of all air handling units, energy recovery units, and VAV boxes shall require external insulation in addition to internal lining specified hereinafter. All other ducts indicated to be provided with interior lining shall not require additional exterior insulation. Duct lining shall comply with ASHRAE 170 for Healthcare

applications.

D. Where exhaust ducts carrying moisture-laden air shower exhaust, etc. are routed in unconditioned spaces, insulation is required as described above. Insulation shall be continuous through the unconditioned area. The vapor barrier shall be tightly sealed to prevent condensation. Exhaust ducts located within conditioned spaces do not require insulation unless otherwise noted.

E. Where a vapor barrier is required, all joints, seams, tears, punctures, and other penetrations shall be closed with 3-inch (7.5cm) pressure-sensitive tape matching the facing or with vapor barrier coating reinforced with 3-inch (7.5cm) glass scrim tape.

F. Contractor-applied internal linings shall be as specified and installed as hereinafter specified.

G. For exposed Fiberglass duct insulation, tightly butt all edges and seams. Secure insulation with flush mechanical fasteners spaced not less than one per square foot. Insulation may be secured with 100 percent coverage of adhesive with mechanical fasteners on the underside of the duct only, in addition to adhesive. Adhesive shall be water based Foster 85-60 or Childers CP-127. Cover all seams, joints and fasteners with not less than 3-inch wide tape matching the insulation facing. Pre-finished white fastener caps may be left exposed if the spacing and pattern is uniform in appearance. Staples will not be permitted.

H. All VAV box hot water coils shall be insulated with fiberglass exterior duct insulation with factory applied foil facing. Insulation shall be 1½ -inches flexible blanket type, 1.0 pcf minimum density, 30 max "k" factor, with reinforced foil-scrim Kraft vapor barrier facing.

I. All disturbed ductwork insulation in existing areas shall be re-insulated with insulation type and thickness as specified for new ductwork. Duct insulation damaged due to installation of new work and demolition only shall be replaced.

J. All supply air diffusers and supply air registers shall be fully insulated on the rear exposed surface to prevent condensation. Insulation shall be 1 ½" inch flexible blanket type 1 ½ pcf minimum density with reinforced foil-scrim-Kraft vapor barrier facing, .25 max "k" factor.

K. Existing ductwork that is indicated to be re-used shall be cleaned, degreased, sealed, and insulated as specified for new ductwork.

L. Clean, seal, and insulate all existing ductwork. Insulate and jacket all existing ductwork.

M. For Healthcare and Dental Suite Applications, duct lining shall comply with ASHRAE 170 requirements.

2.5 ACCESSORY MATERIALS

A. Accessory materials installed as part of insulation work under this section shall include, but not be limited to:

1. Closure Materials - Butt strips, bands, wires, staples, mastics, adhesives; pressure-sensitive tapes.
2. Field-applied jacketing materials - sheet metal, plastic, canvas, fiber glass cloth, insulating cement; PVC fitting covers, PVC jacketing.
3. Support Materials - Hanger straps, hanger rods, saddles.
4. Fasteners, weld pins/studs, speed clips, insulation washers.
5. Metal mesh or expanded metal lagging.

B. All accessory materials shall be installed in accordance with project drawings and specifications, manufacturer's instructions, and/or in conformance with the current edition of the Midwest Insulation Contractors Association (MICA) "Commercial & Industrial Insulation Standards."

2.6 FIELD-APPLIED JACKET

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.

1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:

a. Johns Manville; Zeston.
b. P.I.C. Plastics, Inc.; FG Series.
c. Proto PVC Corporation; LoSmoke.
d. Speedline Corporation; SmokeSafe.

2. Adhesive: As recommended by jacket material manufacturer.
3. Color: High gloss white.
4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.

a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

2.7 HANGER BLOCKS

A. For all pipes larger than 3 inches in diameter the hanger blocks shall be high compressive strength foam or wood blocks. Wood blocks shall be precision cut

thickness to match specified insulation and shall include flared edge hanger saddle as manufactured by Buckaroo.

B. The wood blocks shall be suitable for temperatures from -120 degrees Fahrenheit to 200 degrees Fahrenheit. Do not utilize the wood blocks for piping systems operating outside of the indicated temperature range.

C. Wood blocks are not acceptable for use at refrigerant pipe hangers.

PART 3 - EXECUTION

3.1 WORKMANSHIP

A. The Contractor shall take special care to prevent soiling equipment below or adjacent to areas being insulated. He shall be completely responsible for removing insulation cement splashes and smears and all surfaces that he mars or otherwise soils or defaces, and he will be totally responsible for restoring these damaged surfaces to their like-new condition when delivered to the site.

3.2 SITE INSPECTION

A. Before starting work under this section, carefully inspect the site and installed work of other trades and verify that such work is complete to the point where installation of materials and accessories under this section can begin.

B. Verify that all materials and accessories can be installed in accordance with project drawings and specifications and material manufacturers' recommendations.

C. Verify, by inspecting product labeling, submittal data, and/or certifications which may accompany the shipments, that all materials and accessories to be installed on the project comply with applicable specifications and standards and meet specified thermal and physical properties.

3.3 PREPARATION

A. Ensure that all pipe and equipment surfaces over which insulation is to be installed are clean and dry.

B. Ensure that insulation is clean, dry, and in good mechanical condition with all factory-applied vapor or weather barriers intact and undamaged. Wet, dirty, or damaged insulation shall not be acceptable for installation.

C. Ensure that pressure testing of piping or duct systems has been completed prior to installing insulation.

3.4 INSTALLATION

A. Piping Systems

1. General:

   a. Install all insulation materials and accessories in accordance with manufacturer's published instructions and recognized industry practices to ensure that it will serve its intended purpose.
   b. Install insulation on piping subsequent to installation of heat tracing, painting, testing, and acceptance tests.
   c. Install insulation materials with smooth and even surfaces. Insulate each continuous run of piping with full-length units of insulation, with single cut piece to complete run. Do not use cut pieces or scraps abutting each other. Butt insulation joints firmly to ensure complete, tight fit over all piping surfaces.
   d. Maintain the integrity of factory-applied vapor barrier jacketing on all pipe insulation, protecting it against puncture, tear or other damage. Seal all tears, punctures and other penetrations of the pipe insulation vapor barrier coating.
   e. On exposed piping, locate insulation and cover seams in least visible location.

2. Fittings: Cover valves, fittings, unions, flanges, strainers, flexible connections, expansion joints, pump bodies, drain valves, strainers, blowdowns, backflow preventers, autoflow valves, flow measuring stations, and similar items in each piping system using one of the following:

   a. Mitered sections of insulation equivalent in thickness and composition to that installed on straight pipe runs.
   b. Cold pipe fittings: Apply a tack coat of vapor barrier coating and reinforcing mesh to produce a smooth surface. After ½ hour, apply a second coat of same vapor barrier coating, UL labeled, Type C, for cold water piping.
   c. Hot pipe fittings and Type H for hot water piping: Apply tack of breather mastic. Wrap fitting with fiberglass reinforcing cloth overlapping adjoining sections of pipe insulation by 2-inches. Apply a second coat of Type C or Type H breather mastic over the reinforcing cloth, working it to a smooth finish.
   d. Insulation cement equal in thickness to the adjoining insulation.
   e. PVC fitting covers insulated with material equal in thickness and composition to adjoining insulation.

3. Penetrations: Extend piping insulation without interruption through walls, floors, and similar piping penetrations, except where otherwise specified.
4. Joints:

   a. Butt pipe insulation against hanger inserts. For hot pipes, apply 3-inch (7.5cm) wide vapor barrier tape or bank over butt joints. For cold piping, apply wet coat of vapor barrier lap cement on butt joints, and seal joints with 3-inch (7.5cm) wide vapor barrier tape or band.
   b. All pipe insulation ends shall be tapered and sealed, regardless of

service.

5. Indoor piping shall be ASJ max with SSL-II closure system as manufactured by Owens Corning, Johns Manville, Knauf or approved equal.
6. Exterior above ground piping shall be insulated with ASJ max SSL-II closure system insulation. Fiberglass insulation with aluminum jacketing shall be utilized for exterior above ground applications. Seal all aluminum jacketing laps with 1/8” bead of metal jacketing sealant to prevent water entry.
7. All floor drain piping that is indicated to receive A/C condensate shall be fully insulated to prevent condensation.

B. Ductwork Insulation:

1. General:

a. Before installing insulation, ensure that all seams and joints in ductwork have been sealed and leak tested by the contractor responsible for the duct system. Before applying duct insulation, air ducts shall be clean and dry.
b. Install insulation in accordance with manufacturer's published instructions and recognized industry practice to ensure that it will serve its intended purpose.
c. Install insulation materials with smooth and even surfaces. Butt joints firmly together to ensure complete and tight fit over surfaces to be covered.
d. Maintain the integrity of factory-applied vapor barrier jacketing on all insulation, protecting it against puncture, tears or other damage. All staples used on ductwork insulation shall be coated with suitable sealant to maintain vapor barrier integrity and covered with pressure sensitive vapor barrier tape and vapor barrier coating as specified.
e. Insulate entire system including fittings, joints, flanges, fire dampers, flexible connections, and exposed joints. All portions of duct designated to receive duct wrap shall be completely covered with duct wrap.
f. To ensure installed thermal performance, duct wrap insulation shall be cut to "stretch-out" dimensions. Maintain specified duct insulation thickness and vapor barrier at all fittings, obstructions, and duct flanges.
g. A 2-inch (50mm) piece of insulation shall be removed from the facing at the end of the piece of duct wrap to form an overlapping stapling and taping flap.
h. Install duct wrap insulation with facing outside so that the tape flap overlaps the insulation and facing at the other end of the piece of duct wrap. Adjacent sections of duct wrap insulation shall be tightly butted with the 2-inch (50mm) stapling and taping flap overlapping. If ducts are rectangular or square, install so insulation is not excessively compressed at corners. Seams shall be stapled

approximately 6-inches (150mm) on center with 2-inch (13mm) (min) steel outward clinching staples.

i. Seams, joints and staples shall be sealed with pressure-sensitive tape matching the insulation facing (either plain foil or FRK backing stock) and glass fabric and vapor barrier coating. Cloth duct tape of any color or finish using reclaimed rubber adhesives shall not be utilized on duct wrap insulation. Adjacent sections of duct wrap shall be tightly butted with the 2-inch (50mm) tape flap overlapping.

j. Where rectangular ducts are 24-inch (600mm) in width or greater, duct wrap insulation shall be additionally secured to the bottom of the duct with mechanical fasteners such as pins and speed clip washers, spaced on 18-inch (425mm) centers (maximum) to prevent sagging of insulation.

k. Seal all tears, punctures and other penetrations of the duct wrap facing using one of the above methods to provide a vapor tight system.

l. Upon completion of installation of duct wrap and before operation is to commence, visually inspect the system and verify that it has been correctly installed.

m. Open all system dampers and turn on fans to blow all scraps and other loose pieces of material out of the duct system. Allow for a means for removal of such material.

n. Check the duct system to ensure that there are no air leaks through joints.

o. No ductwork insulation shall be supported utilizing tie wire or bailing wire. Penetrations of ductwork insulation vapor barrier are prohibited.

p. Bevel and terminate insulation at access doors. Paint edges with vapor barrier mastic.

q. Install insulation board between volume dampers and sheet metal standoffs.

r. Provide removable insulation section at all pitot tube traverse points. Insulation section shall contain tether that attaches to adjacent ductwork.

2. Penetrations: Extend ductwork insulation without interruption through walls, floors and similar ductwork penetrations, except where otherwise specified.

3. Ductwork Exposed to Weather: Protect outdoor insulation from weather by installing outdoor weather barrier mastic or jacketing as recommended by the insulation manufacturer.

4. Rigid Insulation:

a. Rigid duct insulation may be impaled over welded pins and secured with insulation caps and washers matching the color of the vapor barrier facing. All seams shall be firmly butted and sealed with pressure-sensitive vapor barrier tape matching the facing and vapor barrier coating.

b. Corner angles shall be installed on all external corners of rigid duct insulation in exposed finished areas before jacketing, except oven

and hood exhaust duct insulation, which shall have no corner angles.

5. Duct Wrap Insulation: Duct wrap insulation shall be applied with all joints butted firmly together. All joints in the insulation covering shall be sealed with adhesive. Duct wrap insulation shall be secured to bottom of rectangular or oval ducts over 24inches (60cm) wide with mechanical fasteners on 16-inch (40 cm) (approx.) centers to prevent sagging.
6. Duct Lining Insulation: Duct liner insulation shall be applied with all joints tightly butted using 90 percent coverage of adhesive meeting the requirements of ASTM C 916 plus mechanical fasteners spaced according to the liner manufacturer's schedule for the interior width of the plenum, housing, or air shaft. (Also refer to Division 23 Section, HVAC Air Distribution System.)

3.5 FIELD QUALITY ASSURANCE

A. Upon completion of all insulation work covered by this specification, visually inspect the work and verify that it has been correctly installed. This may be done while work is in progress, to assure compliance with requirements herein to cover and protect insulation materials during installation.

3.6 PROTECTION

A. Replace damaged insulation which cannot be satisfactorily repaired, including insulation with vapor barrier damage and moisture-saturated insulation.

B. The insulation contractor shall advise the general and/or the mechanical contractor as to requirements for protection of the insulation work during the remainder of the construction period, to avoid damage and deterioration of the finished insulation work.

3.7 SAFETY PRECAUTIONS

A. Insulation contractor's employees shall be properly protected during installation of all insulation. Protection shall include proper attire when handling and applying insulation materials, and shall include (but not be limited to) disposable dust respirators, gloves, hard hats, and eye protection.

B. The insulation contractor shall conduct all job site operations in compliance with applicable provisions of the Occupational Safety and Health Act, as well as with all state and/or local safety and health codes and regulations that may apply to the work.

3.8 INSULATION COVERING

A. Unless otherwise noted, all exposed duct and equipment insulation shall have a

field applied PVC jacket cover neatly cut and pasted over ductwork and equipment insulation. PVC shall be high gloss white and shall be 20 mils thick. Jacket all existing ductwork when new insulation is installed on the same.

B. Unless otherwise noted, all exposed pipe insulation required to be insulated shall be jacketed with a PVC Jacketing with fitting covers. PVC jacket shall be color fade resistant, white high gloss, U.S.D.A. authorized as manufactured by Proto Corporation or approved equal. PVC jacketing shall be high impact, ultraviolet resistant PVC. Minimum thickness shall be 20 mils, roll stock ready for shop or field cutting and forming.

C. Exposed areas include, but are not limited to, all mechanical equipment rooms/fan rooms, electric rooms, storage rooms, janitor closets, and piping and ductwork exposed in an occupied space.

D. Where PVC jackets are indicated, install with 1 inch overlap at longitudinal seams and end joints, for horizontal applications, install with longitudinal seams along top and bottom of vessels. Seal with manufacturers recommended adhesive.

1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

E. Exterior exposed pipe insulation required to be insulated shall be jacketed with a corrugated aluminum jacketing system as previously described. Seal all laps with 1/8” bead metal jacketing sealant.

END OF SECTION 230701

PAGE LEFT INTENTIONALLY BLANK

SECTION 230900 - INSTRUMENTATION AND CONTROLS OF HVAC AND PLUMBING SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. For General Mechanical Requirements, see Division 23 Section, Common Work Results for HVAC, and Division 01 Sections.

B. Comply with all code requirements and fire safety requirements as specified in Division 23 Section, Common Work Results for HVAC.

C. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

D. This Section includes control equipment for HVAC systems and components, including control components for terminal heating and cooling units not supplied with factory wired controls.

E. The automatic temperature control system ATC and central control and monitoring system (CCMS) shall be electric/electronic direct digital control (DDC), Alerton as installed by Albireo Energy, Johnson Controls (Metasys), Johnson Controls FX (Facility Explorer) as installed by Modern Controls, Siemens, Automated Logic Corporation, Schneider Electric as installed by Tri-M, Advanced Power, and TAC Controls by Schneider Electric installed by Automation and Control Concepts or Niagara. All work associated with the automatic temperature control system shall be performed by personnel regularly and directly employed by the Automatic Temperature Controls Contractor. Control System shall be web based, allowing the client access via a standard web browser.

F. Coordinate controls with controlled equipment. Upon completion of the work, calibrate and adjust all controls for proper function. Electric wiring, including interlock wiring for all equipment shall be furnished and installed under this section. All electrical work shall conform to the applicable requirements of Division 26.

G. All automatic temperature control dampers, valves and separable wells for immersion elements furnished by the Control Manufacturer shall be installed by the Mechanical Contractor or his sheet metal subcontractor under the Control Manufacturer's supervision.

H. Reference is hereby made for this contractor to become familiar with Division 26 of these specifications. Familiarization is for coordination purposes only. The control contractor shall provide all necessary relays, contactors, interlock wiring etc. not provided under Division 26 for the automation of the ATC and CCMS systems as required by the sequence of operation and input/output schedule. The control contractor shall coordinate all requirements with the building Fire Alarm

System. The control contractor shall provide all additional devices and interlock wiring required for the automation of the ATC system and monitoring of the CCMS system.

I. Furnish all labor, materials, software, equipment and services necessary for and incidental to furnishing and installing a complete direct digital control, automatic temperature control system to meet the requirements of the sequence of operation described on the Drawings.

J. Unless the necessary items are specified to be provided with mechanical equipment by Division 23, the ATC contractor shall coordinate with Division 23, Mechanical, and shall furnish and install all items necessary to meet the requirements of the Sequence of Operation and the Central Control and Monitoring System (CCMS) indicated on the drawings and as required in this specification.

K. The control system shall include all necessary and specified control equipment properly installed in accordance with the specifications and drawings and shall include, but not be limited to the automatic temperature control and energy management system of the following:

1. Condensate Overflow Safety Switches
2. Dampers and Actuators
3. Ductless Units
4. VAV Boxes with Hot Water Heat.
5. General Exhaust Systems
6. Heating System
7. Hot Water Coils
8. Mechanical Room Heat and Ventilation Control
9. Miscellaneous interlocks required for ventilation systems, etc.
10. Plug Load Management
11. Plumbing Systems
12. Refrigerant Monitoring Systems
13. Refrigerant Mitigation Controls (Monitoring)
14. Relief Air Dampers
15. Temperature Sensors
16. Static Pressure Controllers
17. Existing Baseboard Radiation Control
18. VAV Boxes
19. Ventilation Systems

L. All labor, material, equipment and software to meet the functional intent of the system, as specified herein and as shown on the drawings, shall be included. Drawings are diagrammatic only. Equipment and labor not specifically referred to herein or on the plans, that are required to meet the functional intent, shall be provided without additional cost to the owner.

M. Where equipment is specified to be provided by equipment manufacturer or where packaged controls are specified map out all points provided by the manufacturer so the same can be viewed by ATC system. As a minimum all points indicated in the point list and control diagram must be viewable and adjustable from the ATC

system. Coordinate with equipment manufacturer.

1.2 DEFINITIONS

A. DDC: Direct digital control.

B. I/O: Input/output.

C. LonWorks: A control network technology platform for designing and implementing interoperable control devices and networks.

D. MS/TP: Main tracking/token passing.

E. PC: Personal computer.

F. PID: Proportional plus integral plus derivative.

G. RTD: Resistance temperature detector.

H. UPS: Uninterruptible Power Supply.

I. NAE: Network Automated Engine.

1.3 SYSTEM PERFORMANCE

A. Comply with the following performance requirements:

1. Graphic Refresh: Update graphic with minimum 20 dynamic points with current data within 8 seconds.
2. Object Command: Reaction time of less than two seconds between operator command of a binary object and device reaction.
3. Object Scan: Transmit change of state and change of analog values to control units or workstation within six seconds.
4. Alarm Response Time: Annunciate alarm at workstation within 45 seconds. Multiple workstations must receive alarms within five seconds of each other.
5. Program Execution Frequency: Run capability of applications as often as five seconds, but selected consistent with mechanical process under control.
6. Performance: Programmable controllers shall execute DDC PID control loops, and scan and update process values and outputs at least once per second.
7. Reporting Accuracy and Stability of Control: Report values and maintain measured variables within tolerances as follows:

    a. Water Temperature: Plus or minus 1 deg F (0.5 deg C).
    b. Water Flow: Plus or minus 5 percent of full scale.
    c. Water Pressure: Plus or minus 2 percent of full scale.
    d. Space Temperature: Plus or minus 1 deg F (0.5 deg C).

e. Ducted Air Temperature: Plus or minus 1 deg F (0.5 deg C).
f. Outside Air Temperature: Plus or minus 2 deg F (1.0 deg C).
g. Dew Point Temperature: Plus or minus 3 deg F (1.5 deg C).
h. Temperature Differential: Plus or minus 0.25 deg F (0.15 deg C).
i. Relative Humidity: Plus or minus 5 percent.
j. Airflow (Pressurized Spaces): Plus or minus 3 percent of full scale.
k. Airflow (Measuring Stations): Plus or minus 5 percent of full scale.
l. Airflow (Terminal): Plus or minus 10 percent of full scale.
m. Air Pressure (Space): Plus or minus 0.01-inch wg (2.5 Pa).
n. Air Pressure (Ducts): Plus or minus 0.1-inch wg (25 Pa).
o. Carbon Dioxide: Plus or minus 50 ppm.
p. Electrical: Plus or minus 5 percent of reading.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Factory-Mounted Components: Where control devices specified in this Section are indicated to be factory mounted on equipment, arrange for shipping of control devices to equipment manufacturer.

B. System Software: Update to latest version of software at Project completion.

1.5 COORDINATION

A. Coordinate location of temperature sensors, relative humidity sensors, CO_2 sensors, dewpoint temperature sensors, and other exposed control sensors with plans and room details before installation.

B. Coordinate equipment with Division 28 Section, “Fire Alarm System” to achieve compatibility with equipment that interfaces with that system.

C. Coordinate supply of conditioned electrical branch circuits for control units and operator workstation.

D. Coordinate equipment with Division 26 Section, Panelboards to achieve compatibility with starter coils and annunciation devices.

1. Coordinate equipment with Division 26 Section, Motor-Controllers to achieve compatibility with motor starters and annunciation devices.

1.6 WORK BY OTHERS

A. Automatic temperature control valves, air flow stations, pipe taps, flow meters, and separable wells for immersion elements furnished by the control manufacturer shall be installed by the mechanical contractor under the control manufacturer's supervision. The control contractor shall deliver to the mechanical contractor valves and wells for installation within the various systems.

B. All automatic dampers furnished by the control manufacturer shall be installed by

the mechanical contractor under the control manufacturer's supervision.

1.7 QUALITY ASSURANCE

A. Supplier shall have an in-place support facility with technical staff, spare parts inventory and all necessary test and diagnostic equipment. The fully staffed and equipped office shall be within a 60 mile radius of the job site.

B. The systems shall be complete in all respects, and shall be installed by skilled personnel. The Control Contractor shall have a successful history in the installation and maintenance of automatic temperature control systems similar in size and performance to that specified herein.

C. Refer to Contract Drawings for sequences of operations, control diagrams, and points lists.

D. All electrical wiring in connection with the Automatic Temperature Control System shall be furnished and installed by the ATC Contractor. This shall include all interlock wiring between the existing air handling unit, fans, heating systems, switches, VAV boxes, dampers, ductless units, static pressure controllers, etc.

E. Bids by wholesalers, contractors or franchised dealers or any other firm whose principal business is not that of manufacturing or installing automatic temperature control systems, shall not be acceptable. Bid documents that are not complete in their response to these documents or take exception to any of the capabilities defined within these documents shall not be acceptable.

F. Installer Qualifications: Automatic control system manufacturer's authorized representative who is trained and approved for installation of system components required for this Project.

G. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

H. Comply with ASHRAE 135 for DDC system components.

1.8 GUARANTEE AND INSTRUCTION

A. The control system including all components, system software, parts and assemblies herein specified shall be free from defects in workmanship and materials under normal use and service. After completion of the installation, the Control Manufacturer shall regulate and adjust all thermostats, control valves, control motors, and other equipment provided under this contract. If within two (2) years from the date of acceptance by Owner any of the equipment herein described is proved to be defective in workmanship or materials, it will be replaced or repaired at no additional cost to the Owner. The Control Manufacturer shall, after completion, provide any service incidental to the proper performance of the Control System under guarantees outlined above for a period of two (2) years.

Normal maintenance of the system is not to be considered part of the guarantee. All corrective modifications made during warranty service periods shall be updated on all user documentation including "as-built" shop drawings and on user and manufacturer archived software disks.

B. The control contractor shall completely check out, calibrate and test all connected hardware to insure that the system performs in accordance with the approved specifications and sequences of operation submitted.

C. Upon completion of the work, the control drawings encased in heavy plastic shall be provided where directed. Layout shall show all control equipment and the function of each item indicated.

D. The temperature control contractor's office shall be within a 100 mile radius of the job site.

E. The contractor shall respond to the job site with qualified technicians within a 4 hour period for any emergency relating to the control system or energy management systems.

F. This agreement shall include emergency service during normal working hours.

1.9 SUBMITTALS

A. Product Data: Include manufacturer's technical literature for each control device. Indicate dimensions, capacities, performance characteristics, electrical characteristics, finishes for materials, and installation and startup instructions for each type of product indicated.

1. DDC System Hardware: Bill of materials of equipment indicating quantity, manufacturer, and model number. Include technical data for operator workstation equipment, interface equipment, control units, transducers/transmitters, sensors, actuators, valves, relays/switches, control panels, and operator interface equipment.
2. Control System Software: Include technical data for operating system software, operator interface, color graphics, and other third-party applications.
3. Controlled Systems: Instrumentation list with element name, type of device, manufacturer, model number, and product data. Include written description of sequence of operation including schematic diagram.

B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.

1. Bill of materials of equipment indicating quantity, manufacturer, and model number.
2. Schematic flow diagrams showing equipment, fans, pumps, coils, dampers, valves, and control devices.

3. Wiring Diagrams: Power, signal, and control wiring.
4. Details of control panel faces, including controls, instruments, and labeling.
5. Written description of sequence of operation.
6. Schedule of dampers including size, leakage, and flow characteristics.
7. Schedule of valves including flow characteristics.
8. DDC System Hardware:

    a. Wiring diagrams for control units with termination numbers.
    b. Schematic diagrams and floor plans for field sensors and control hardware.
    c. Schematic diagrams for control, communication, and power wiring, showing trunk data conductors and wiring between operator workstation and control unit locations.

9. Control System Software: List of color graphics indicating monitored systems, data (connected and calculated) point addresses, output schedule, and operator notations.
10. Controlled Systems:

    a. Schematic diagrams of each controlled system with control points labeled and control elements graphically shown, with wiring.
    b. Scaled drawings showing mounting, routing, and wiring of elements including bases and special construction.
    c. Written description of sequence of operation including schematic diagram.
    d. Points list.

C. Data Communications Protocol Certificates: Certify that each proposed DDC system component complies with LonWorks or Bacnet.

D. Software and Firmware Operational Documentation: Include the following:

1. Software operating and upgrade manuals.
2. Program Software Backup: On a magnetic media or compact disc, complete with data files.
3. Device address list.
4. Printout of software application and graphic screens.
5. Software license required by and installed for DDC workstations and control systems.

E. Software Upgrade Kit: For Owner to use in modifying software to suit future systems revisions or monitoring and control revisions.

F. Qualification Data: For Installer and manufacturer.

G. Field quality-control test reports.

H. Submit screen shots of ATC system graphics at substantial completion.

I. Operation and Maintenance Data: For HVAC instrumentation and control system

to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section, Operation and Maintenance Data, and Division 23 Section, Common Work Results for HVAC include the following:

1. Maintenance instructions and lists of spare parts for each type of control device.
2. Interconnection wiring diagrams with identified and numbered system components and devices.
3. Keyboard illustrations and step-by-step procedures indexed for each operator function.
4. Inspection period, cleaning methods, cleaning materials recommended, and calibration tolerances.
5. Calibration records and list of set points.

J. Upon completion of the work, provide a complete set of “as-built" drawings and application software on CD, USB, or other type of electronic storage device. Drawings shall be provided in format as acceptable to the Owner’s files. Submit as-built drawings and specification to Owner's representative for review and approval prior to final project closeout.

1.10 SOFTWARE LICENSE AGREEMENT

A. The owner shall sign a copy of the manufacturer's standard software and firmware licensing agreement as a condition of this contract. Such license shall grant use of all programs and application software to owner as defined by the manufacturer's license agreement, but shall protect manufacturer's rights to disclosure of trade secrets contained within such software. All software and hardware upgrades shall be included in two (2) year warranty period.

B. Software license agreement shall not apply on projects where existing ATC system is being extended.

C. Minimum of four (4) software license seats shall be provided. Storage of all software shall be coordinated with the DTCC’s I.T. Manager.

1.11 ELECTRICAL SURGE PROTECTION

A. It is the responsibility of the ATC/FMS contractor to provide adequate surge protection for all wall mounted control panels required for this project.

1. Devices under surge protection shall be of design that loss of memory will not occur in the event of the surge protection device being activated due to surge/spike conditions.
2. Surge protection devices will be required to be hard wired, with the exception of peripheral devices that use standard 110VAC plugs for connections (i.e. Modems).
3. Surge protection devices are to be rated for 120 VAC single phase, 20 (or greater) amps capacity.

4. Surge Protection devices to include internal fuse protection, audible surge alarm & LED indicators.
5. Surge protectors to have clamping voltage of 480V peak, maximum surge current rating of 50,000 amps. Unit to have NEMA 12 enclosure with wall mounting bracket and conduit connection.

1.12 TRAINING

A. The training time period shall be coordinated with the school system's facility Engineer. The schedule training period shall be arranged at the owner's convenience.

B. Cost shall include all training material, instruction books, and two copies of video tape with sound DVD of training session.

C. Upon completion of the work, the Control Contractor shall have completely adjusted the entire control system. He shall arrange to instruct the Owner's representative on the operation of the control system for a period of not less than four (4) hours. All training shall be by the control contractor and shall utilize specified manuals and as-built documentation.

D. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain control systems and components.

1. Train Owner's maintenance personnel on procedures and schedules for starting and stopping, troubleshooting, servicing, and maintaining equipment and schedules.
2. Provide operator training on data display, alarm and status descriptors, requesting data, executing commands, calibrating and adjusting devices, resetting default values, and requesting logs. Include a minimum of 40 hours' dedicated instructor time on-site.
3. Review data in maintenance manuals. Refer to Division 01 Section, Contract Closeout.
4. Review data in maintenance manuals. Refer to Division 01 Section, Operation and Maintenance Data.
5. Schedule training with Owner, with at least seven days' advance notice.
6. Control Contractor shall also attend and participate in separate HVAC equipment systems training in addition to ATC training.

1.13 ALTERNATES

A. Refer to Division 01 Section, Alternates for description of work under this section affected by alternates.

1.14 DTCC SPECIFIC REQUIREMENTS

A. The ATC Subcontractor shall include in his bid all costs associated with incorporating the following specific requirements:

1. All holiday schedules shall incorporate a 12 month block. Coordinate exact holidays, schedules, calendars, occupied, unoccupied periods with Owner prior to writing software. All schedules shall be reviewed and approved by the Owner.
2. Relays for ATC equipment shall not be located in ceilings. All relays shall be located in equipment control panels and/or mechanical rooms.
3. All exhaust fans shall be assigned a designated point. Utilizing relays to provide digital point for exhaust fans shall not be acceptable.
4. Graphics on ATC computer shall in addition to basic requirements indicate the percentage open or closed on all valves and dampers.
5. The ATC Computer Graphics shall incorporate the final room numbers actually utilized in the dental suite All room names utilized in the graphic display shall be reviewed and approved by the Owner.
6. The ATC Computer Graphics shall indicate for each item of equipment the “on” or “off” status and command shall be “run” or “stop”.
7. The ATC Computer Graphic shall indicate for each duct smoke detector the “on” or “off” status and command.
8. All temperature sensors, equipment, relative humidity sensors, current sensors, CO2 sensors, differential pressure sensors, etc. indicated on ATC Control Diagrams and point list shall be displayed on the ATC Computer Graphic. Measured value or status shall be displayed.
9. For any multi-stage HVAC units, the quantity of compressor stages and the quantity of electric heat stages shall be displayed on the Computer Graphics.
10. The exact space temperature set points, relative humidity set points, changeover set points. etc., shall be coordinated with Owner prior to final data entry. All items indicated in sequences of Operation as “adjustable” shall be reviewed and approved by Owner prior to implementation of the same.
11. The outside air relative humidity and outside air temperature shall be monitored on ATC system and reported on ATC Computer Graphics. See Floor plans for exact locations.
12. Provide a graphic of all floor plans indicating location of all equipment interlocked with ATC System including all control panels.
13. Graphic shall also indicate area of building served by each item of equipment. Graphics shall indicate all global sensor readings.
14. All equipment shall be labeled with name of equipment, area served, and area location (room name/number).
15. Scheduling of HVAC equipment/zones shall be such that for afterhours use the ATC system shall allow a temporary override of the pre-set occupied/unoccupied schedule by zone and for specific equipment in a zone. This must allow the dental suite staff the ability to operate as few or many zones as desired without operating entire portions of the building.
16. Provide “Loss of Heat” monitoring and alarm on ATC system if any space temperature sensor in the building drops below 50 degrees Fahrenheit (Adjustable).
17. Provide additional software package and license so that Owner can install software on Owner provided laptop. Assist owner with installation of software.
18. Scheduling of HVAC equipment/zones shall be such that for afterhours use

the ATC system shall allow a temporary override of the pre-set occupied/unoccupied schedule by zone and for specific equipment in a zone. This must allow DTCC the ability to operate as few or many zones as desired without operating entire portions of the building.

19. Alarms shall be delayed during optimal start stop to avoid nuisance alarm triggers.
20. Global unoccupied setpoints shall be 70 degrees F in heating mode and 74 degrees F in cooling mode. Coordinate/confirm with Owner all setpoints.
21. All status indicators for fans or pumps shall be provided by differential pressure sensors. Current sensors are NOT acceptable to be utilized for equipment status unless indicated on the control diagram.
22. Position of all H-O-A switches and other switches shall be reported on ATC graphic with equipment.
23. All text alarms shall clearly identify what they are within the body of the text. i.e. “freeze protection pump failure”, “Duct smoke detector trip”, etc. Coordinate all text alarms and verbiage with Owner.

1.15 GLOBAL SENSORS

A. General

1. Furnish and install global sensors and report the same on the automatic temperature control system.
2. Global sensors shall monitor and trend the following conditions:

    a. Outside air temperature.
    b. Outside air relative humidity.
    c. Graphic shall also indicate area of building served by each item of equipment.
    d. Global holiday schedules:
        i. Provide all interlock wiring and programming to allow a global holiday schedule for all equipment except the administration equipment. Global holiday schedule shall allow the Owner to shut down the entire building’s HVAC systems if an unscheduled event occurs when school is cancelled.
        ii. System shall also be capable of individual scheduling of equipment as specified or all can be globally modified at once.
    e. All equipment interlocked with ATC system shall be able to be turned on/off via ATC system as specified. Changing temperature set point alone is not acceptable method for turning equipment on/off.
    f. Where valve or damper position is indicated ATC graphic shall indicate percentage open or percentage closed.

PART 2 - PRODUCTS

2.1 BUILDING MANAGEMENT SYSTEM

A. The Building Management System (BMS) shall use an open architecture and fully support a multi-vendor environment. To accomplish this effectively, the BMS shall support open communication protocol standards and integrate a wide variety of third-party devices and applications. The system shall be designed for use on the Internet, or intranets using off the shelf, industry standard technology compatible with other owner provided networks.

B. The Building Management System shall consist of the following:

1. Standalone Network Automation Engine(s)
2. Field Equipment Controller(s)
3. Input/Output Module(s)
4. Local Display Device(s)
5. Portable Operator's Terminal(s)
6. Distributed User Interface(s)
7. Network processing, data storage and communications equipment
8. Other components required for a complete and working BMS

C. The system shall be modular in nature, and shall permit expansion of both capacity and functionality through the addition of sensors, actuators, controllers and operator devices, while re-using existing controls equipment.

D. System architectural design shall eliminate dependence upon any single device for alarm reporting and control execution. The failure of any single component or network connection shall not interrupt the execution of control strategies at other operational devices.

E. Automation Network

1. The automation network shall be based on a PC industry standard of Ethernet TCP/IP. Where used, LAN controller cards shall be standard “off the shelf” products available through normal PC vendor channels.
2. The automation network shall be capable of operating at a communication speed of 100 Mbps, with full peer-to-peer network communication.
3. Network Automation Engines (NAE) and/or system controllers shall reside on the automation network.
4. The automation network will be compatible with other enterprise-wide networks. Where indicated, the automation network shall be connected to the enterprise network and share resources with it by way of standard networking devices and practices.

F. Control Network

1. Network Automation Engines and/or system controllers shall provide supervisory control over the control network and shall support all three (3)

of the following communication protocols:

a. BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, Clause 9.
b. LonWorks enabled devices using the Free Topology Transceiver (FTT-10a).
c. The Johnson Controls N2 Field Bus or equivalent.
d. Tridium FX-40
e. Honeywell Webs
f. TAC Controls by Schneider Electric
g. Siemens P1/P2 Serial

2. Control networks shall provide either “Peer-to-Peer,” Main-Tracking, or Supervised Token Passing communications, and shall operate at a minimum communication speed of 9600 baud.
3. DDC Controllers shall reside on the control network.
4. Control network communication protocol shall be BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135.
5. A BACnet Protocol Implementation Conformance Statement shall be provided for each controller device (main or tracking) that will communicate on the BACnet MS/TP Bus.
6. The Conformance Statements shall be submitted with the BAS Submittals.

G. Integration

1. Hardwired

a. Analog and digital signal values shall be passed from one system to another via hardwired connections.
b. There will be one separate physical point on each system for each point to be integrated between the systems.

2. BACnet Protocol Integration – BACnet

a. The neutral protocol used between systems will be BACnet over Ethernet and comply with the ASHRAE BACnet standard 135-2003.
b. A complete Protocol Implementation Conformance Statement (PICS) shall be provided for all BACnet system devices.
c. The ability to command, share point object data, change of state (COS) data and schedules between the host and BACnet systems shall be provided.

H. Dedicated Web Based User Interface

1. Where required by the Owner, the BMS Contractor shall provide and install a personal computer for command entry, information management, network alarm management, and database management functions. All real-time control functions, including scheduling, history collection and alarming, shall be resident in the BMS Network Automation Engines to facilitate greater fault tolerance and reliability. Coordinate with Owner to

determine computer type (i.e. PC (Windows based) or Macintosh (Apple)).

2. Dedicated User Interface Architecture – The architecture of the computer shall be implemented to conform to industry standards, so that it can accommodate applications provided by the BMS Contractor and by other third party applications suppliers, including but not limited to Microsoft Office Applications. Specifically it must be implemented to conform to the following interface standards.

    a. Microsoft Edge Internet Explorer for user interface functions
    b. Microsoft Office Professional for creation, modification and maintenance of reports, sequences other necessary building management functions
    c. Microsoft Outlook or other e-mail program for supplemental alarm functionality and communication of system events, and reports
    d. Required network operating system for exchange of data and network functions such as printing of reports, trends and specific system summaries.

3. Computer Hardware – The personal computer(s) shall be configured as follows:

    a. Description: A tower or all-in-one computer designed for normal use at a single, semipermanent location.
    b. Performance Requirements:
        i. Performance requirements may dictate equipment exceeding minimum requirements indicated.
        ii. Energy Star compliant.
    c. Personal Computer:
        i. Minimum Processor Speed: 3 gigahertz (GHz). Dual Core Processer.
    d. RAM:
        i. Capacity: 16GB.
        ii. Speed and Type: 1333 MHz, SDRAM.
    e. Hard Drive:
        i. Media: Solid state.
        ii. Number of Hard Drives: One.
        iii. Capacity: 250GB.
    f. Optical Read and Write Drive:
        i. Include with at least 2 MB of data buffer.
        ii. Type: SCS1 CD-ROM Drive with Read/Write Capability.
        iii. Average access time of 150 ms or less.
    g. At least four expansion slots.
    h. Video Card:
        i. Resolution: 1920 by 1200 pixels.
        ii. RAM: 4 GB.
        iii. Controller Speed: 4GHz.
    i. Sound Card:
        i. At least 128 voice wavetable synthesis.
        ii. Capable of delivering three-dimensional sound effects.
        iii. High-resolution 16-bit stereo digital audio recording and

playback with user-selectable sample rates up to 48,000 Hz.

j. Two (2) Network Interface Cards: Include cards with connection, as applicable.
   i. 10-100-1000 base TX Ethernet with RJ45 connector port.
   ii. 100 base FX Ethernet with SC or ST port.
k. Wireless Ethernet, 802.11 a/b/g/n.
l. Optical Modem: Full duplex link for connection to optical fiber cable provided.
m. I/O Ports:
   i. Two USB 3.0 ports on front panel, six on back panel, and three internal on motherboard.
   ii. One serial port.
   iii. One parallel port.
   iv. Two PS/2 ports.
   v. One RJ-45.
   vi. One stereo line-in and headphone/line-out on back panel.
   vii. One microphone and headphone connector on front panel.
   viii. One IEEE 1394 on front and back panel with PCI-e card.
   ix. One ESATA port on back panel.
n. Battery: Life of at least three years to maintain system clock/calendar and ROM, as a minimum.
o. Keyboard:
   i. 101 enhanced keyboard.
   ii. Full upper- and lowercase ASCII keyset, numeric keypad, dedicated cursor control keypad, and 12 programmable function keys.
   iii. Wireless operation within up to 72 inches (1800 mm) in front of workstation.
p. Pointing Device:
   i. Either a two- or three-button mouse.
   ii. Wireless operation within up to 72 inches (1800 mm) in front of workstation.
q. Flat Panel Display Monitor:
   i. Display:
      1. Color display with 21 inches diagonal viewable area.
      2. Digital input signal.
      3. Aspect Ratio: 16 to 9.
      4. Antiglare display.
      5. Tilt adjustable base.
      6. Energy Star compliant.
      7. Resolution: 1920 by 1200 pixels at 60 Hz.
      8. Number of Displays: One.
r. Speakers:
   i. Two, with individual controls for volume, bass and treble.
   ii. Signal to Noise Ratio: At least 65 dB.
   iii. Power: At least 4 W per speaker/channel.
   iv. Magnetic shielding to prevent distortion on the video monitor.
s. I/O Cabling: Include applicable cabling to connect I/O devices.
t. Uninterruptable Power Supply.

I. User Interface Application Components

1. Operator Interface

a. An integrated browser based client application shall be used as the user operator interface program.
b. All Inputs, Outputs, Setpoints, and all other parameters as defined within Part 3 or on the drawings, shown on the design drawings, or required as part of the system software, shall be displayed for operator viewing and modification from the operator interface software.
c. The user interface software shall provide help menus and instructions for each operation and/or application.
d. All controller software operating parameters shall be displayed for the operator to view/modify from the user interface. These include: setpoints, alarm limits, time delays, PID tuning constants, run-times, point statistics, schedules, and so forth.
e. The Operator Interface shall incorporate comprehensive support for functions including, but not necessarily limited to, the following:
    i. User access for selective information retrieval and control command execution
    ii. Monitoring and reporting
    iii. Alarm, non-normal, and return to normal condition annunciation
    iv. Selective operator override and other control actions
    v. Information archiving, manipulation, formatting, display and reporting
    vi. FMS internal performance supervision and diagnostics
    vii. On-line access to user HELP menus
    viii. On-line access to current FMS as-built records and documentation
    ix. Means for the controlled re-programming, re-configuration of FMS operation and for the manipulation of FMS database information in compliance with the prevailing codes, approvals and regulations for individual FMS applications.
    x. The operation of the control system shall be independent of the user interface, which shall be used for operator communications only. Systems that rely on an operator workstation to provide supervisory control over controller execution of the sequences of operations or system communications shall not be acceptable.

2. Navigation Trees

a. The system will have the capability to display multiple navigation trees that will aid the operator in navigating throughout all systems and points connected. At minimum provide a tree that identifies all systems on the networks.
b. Provide the ability for the operator to add custom trees. The operator will be able to define any logical grouping of systems or

points and arrange them on the tree in any order. It shall be possible to nest groups within other groups. Provide at minimum 5 levels of nesting.

c. The navigation trees shall be “dockable” to other displays in the user interface such as graphics. This means that the trees will appear as part of the display, but can be detached and then minimized to the Windows task bar or closed altogether. A simple keystroke will reattach the navigation to the primary display of the user interface.

3. Alarms

a. Alarms shall be routed directly from Network Automation Engines to PCs and servers. It shall be possible for specific alarms from specific points to be routed to specific PCs and servers. The alarm management portion of the user interface shall, at the minimum, provide the following functions:
   i. Log date and time of alarm occurrence.
   ii. Generate a “Pop-Up” window, with audible alarm, informing a user that an alarm has been received.
   iii. Allow a user, with the appropriate security level, to acknowledge, temporarily silence, or discard an alarm.
   iv. Provide an audit trail on hard drive for alarms by recording user acknowledgment, deletion, or disabling of an alarm. The audit trail shall include the name of the user, the alarm, the action taken on the alarm, and a time/date stamp.
   v. Provide the ability to direct alarms to an e-mail address or alphanumeric pager. This must be provided in addition to the pop up window described above. Systems that use e-mail and pagers as the exclusive means of annunciating alarms are not acceptable.
   vi. Any attribute of any object in the system may be designated to report an alarm.

b. The FMS shall annunciate diagnostic alarms indicating system failures and non-normal operating conditions

c. The FMS shall annunciate application alarms as required.

4. Reports and Summaries

a. Reports and Summaries shall be generated and directed to the user interface displays, with subsequent assignment to printers, or disk. As a minimum, the system shall provide the following reports:
   i. All points in the BMS
   ii. All points in each BMS application
   iii. All points in a specific controller
   iv. All points in a user-defined group of points
   v. All points currently in alarm
   vi. All points locked out
   vii. All BMS schedules
   viii. All user defined and adjustable variables, schedules,

interlocks and the like.

b. Summaries and Reports shall be accessible via standard UI functions and not dependent upon custom programming or user defined HTML pages.
c. Selection of a single menu item, tool bar item, or tool bar button shall print any displayed report or summary on the system printer for use as a building management and diagnostics tool.
d. The system shall allow for the creation of custom reports and queries via a standard web services XML interface and commercial off-the-shelf software such as Microsoft Access, Microsoft Excel, or Crystal Reports.

5. Schedules

a. A graphical display for time-of-day scheduling and override scheduling of building operations shall be provided. At a minimum, the following functions shall be provided:
   i. Weekly schedules
   ii. Exception Schedules
   iii. Monthly calendars
b. Weekly schedules shall be provided for each group of equipment with a specific time use schedule.
c. It shall be possible to define one or more exception schedules for each schedule including references to calendars
d. Monthly calendars shall be provided that allow for simplified scheduling of holidays and special days for a minimum of five years in advance. Holidays and special days shall be user-selected with the pointing device or keyboard, and shall automatically reschedule equipment operation as previously defined on the exception schedules.
e. Changes to schedules made from the User Interface shall directly modify the Network Automation Engine schedule database.
f. Schedules and Calendars shall comply with ASHRAE SP135/2003 BACnet Standard.
g. Selection of a single menu item or tool bar button shall print any displayed schedule on the system printer for use as a building management and diagnostics tool.

6. Password

a. Multiple-level password access protection shall be provided to allow the user/manager to user interface control, display, and database manipulation capabilities deemed appropriate for each user, based on an assigned password.
b. Each user shall have the following: a user name (24 characters minimum), a password (12 characters minimum), and access levels.
c. The system shall allow each user to change his or her password at will.
d. When entering or editing passwords, the system shall not echo the

actual characters for display on the monitor.

e. A minimum of five levels of access shall be supported individually or in any combination as follows:
   i. Level 1 = View Data
   ii. Level 2 = Command
   iii. Level 3 = Operator Overrides
   iv. Level 4 = Database Modification
   v. Level 5 = Database Configuration
   vi. Level 6 = All privileges, including Password Add/Modify
f. A minimum of 100 unique passwords shall be supported.
g. Operators shall be able to perform only those commands available for their respective passwords. Display of menu selections shall be limited to only those items defined for the access level of the password used to log-on.
h. The system shall automatically generate a report of log-on/log-off and system activity for each user. Any action that results in a change in the operation or configuration of the control system shall be recorded, including: modification of point values, schedules or history collection parameters, and all changes to the alarm management system, including the acknowledgment and deletion of alarms.

7. Screen Manager - The User Interface shall be provided with screen management capabilities that allow the user to activate, close, and simultaneously manipulate a minimum of 4 active display windows plus a network or user defined navigation tree.
8. Dynamic Color Graphics

   a. The graphics application program shall be supplied as an integral part of the User Interface. Browser or Workstation applications that rely only upon HTML pages shall not be acceptable.
   b. The graphics applications shall include a create/edit function and a runtime function. The system architecture shall support an unlimited number of graphics documents (graphic definition files) to be generated and executed.
   c. The graphics shall be able to display and provide animation based on real-time data that is acquired, derived, or entered.
   d. Graphics runtime functions – A maximum of 16 graphic applications shall be able to execute at any one time on a user interface or workstation with 4 visible to the user. Each graphic application shall be capable of the following functions:
      i. All graphics shall be fully scalable
      ii. The graphics shall support a maintained aspect ratio.
      iii. Multiple fonts shall be supported.
      iv. Unique background shall be assignable on a per graphic basis.
      v. The color of all animations and values on displays shall indicate the status of the object attribute.
   e. Operation from graphics – It shall be possible to change values (setpoints) and states in system controlled equipment by using

drop-down windows accessible via the pointing device

f. Graphic editing tool – A graphic editing tool shall be provided that allows for the creation and editing of graphic files. The graphic editor shall be capable of performing/defining all animations, and defining all runtime binding.
   i. The graphic editing tool shall in general provide for the creation and positioning of point objects by dragging from tool bars or drop-downs and positioning where required.
   ii. In addition, the graphic editing tool shall be able to add additional content to any graphic by importing backgrounds in the SVG, BMP or JPG file formats.

g. Aliasing – Many graphic displays representing part of a building and various building components are exact duplicates, with the exception that the various variables are bound to different field values. Consequently, it shall be possible to bind the value of a graphic display to aliases, as opposed to the physical field tags.

9. Historical trending and data collection

   a. Each Automation Engine shall store trend and point history data for all analog and digital inputs and outputs, as follows:
      i. Any point, physical or calculated, may be designated for trending. Two (2) methods of collection shall be allowed:
         1. Defined time interval
         2. Upon a change of value.
      ii. Each Automation Engine shall have the capability to store multiple samples for each physical point and software variable based upon available memory, including an individual sample time/date stamp. Points may be assigned to multiple history trends with different collection parameters.
   b. Trend and change of value data shall be stored within the engine and uploaded to a dedicated trend database or exported in a selectable data format via a provided data export utility. Uploads to a dedicated database shall occur based upon one of the following: user-defined interval, manual command, or when the trend buffers are full. Exports shall be as requested by the user or on a time scheduled basis. Trend data shall be available for a minimum of twelve (12) months.

10. Trend data viewing and analysis

   a. Provide a trend viewing utility that shall have access to all database points.
   b. It shall be possible to retrieve any historical database point for use in displays and reports by specifying the point name and associated trend name.
   c. The trend viewing utility shall have the capability to define trend study displays to include multiple trends
   d. Displays shall be able to be single or stacked graphs with on-line

selectable display characteristics, such as ranging, color, and plot style.

e. Display magnitude and units shall both be selectable by the operator at any time without reconfiguring the processing or collection of data. This is a zoom capability.

f. Display magnitude shall automatically be scaled to show full graphic resolution of the data being displayed.

g. Trend studies shall be capable of calculating and displaying calculated variables including highest value, lowest value and time based accumulation.

J. Network Automation Engine (NAE)/ System Controllers

1. The Network Automation Engine (NAE)/ System Controllers or approved equal shall be a fully user-programmable, supervisory controller. The NAE shall monitor the network of distributed application-specific controllers, provide global strategy and direction, and communicate on a peer-to-peer basis with other Network Automation Engines.
2. Automation network – The NAE shall reside on the automation network and shall support a subnet of system controllers.
3. User Interface – Each NAE shall have the ability to deliver a web based User Interface (UI) as previously described. All computers connected physically or virtually to the automation network shall have access to the web based UI.

    a. The web based UI software shall be imbedded in the NAE. Systems that require a local copy of the system database on the user's personal computer are not acceptable.
    b. The NAE shall support up four (4) concurrent users.
    c. The web based user shall have the capability to access all system data through one NAE.
    d. Remote users connected to the network through an Internet Service Provider (ISP) or telephone dial up shall also have total system access through one NAE.
    e. Systems that require the user to address more than one NAE to access all system information are not acceptable.
    f. The NAE shall have the capability of generating web based UI graphics. The graphics capability shall be imbedded in the NAE.
    g. Systems that support UI Graphics from a central database or require the graphics to reside on the user's personal computer are not acceptable.
    h. The web based UI shall support the following functions using a standard version of Microsoft Edge Internet Explorer:
        i. Configuration
        ii. Commissioning
        iii. Data Archiving
        iv. Monitoring
        v. Commanding
        vi. System Diagnostics
    i. Systems that require workstation software or modified web

browsers are not acceptable.

j. The NAE shall allow temporary use of portable devices without interrupting the normal operation of permanently connected modems.

4. Processor – The NAE shall be microprocessor-based with a minimum word size of 32 bits. The NAE shall be a multi-tasking, multi-user, and real-time digital control processor. Standard operating systems shall be employed. NAE size and capability shall be sufficient to fully meet the requirements of this Specification.
5. Memory – Each NAE shall have sufficient memory to support its own operating system, databases, and control programs, and to provide supervisory control for all control level devices.
6. Hardware Real Time Clock – The NAE shall include an integrated, hardware-based, real-time clock.
7. The NAE shall include troubleshooting LED indicators to identify the following conditions:

   a. Power - On/Off
   b. Ethernet Traffic – Ethernet Traffic/No Ethernet Traffic
   c. Ethernet Connection Speed – 10 Mbps/100 Mbps
   d. FC Bus – Normal Communications/No Field Communications
   e. Peer Communication – Data Traffic Between NAE Devices
   f. Run – NAE Running/NAE In Startup/NAE Shutting Down/Software Not Running
   g. Bat Fault – Battery Defective, Data Protection Battery Not Installed
   h. Fault – General Fault
   i. Modem RX – NAE Modem Receiving Data
   j. Modem TX – NAE Modem Transmitting Data

8. Communications Ports – The NAE shall provide the following ports for operation of operator Input/Output (I/O) devices, such as industry-standard computers, modems, and portable operator's terminals.

   a. Up to two (2) USB port
   b. Up to two (2) URS-232 serial data communication port
   c. Up to two (2) RS-485 port
   d. One (1) Ethernet port

9. Diagnostics – The NAE shall continuously perform self-diagnostics, communication diagnosis, and diagnosis of all panel components. The Network Automation Engine shall provide both local and remote annunciation of any detected component failures, low battery conditions, or repeated failures to establish communication.
10. Power Failure – In the event of the loss of normal power, The NAE shall continue to operate for a user adjustable period of up to 10 minutes after which there shall be an orderly shutdown of all programs to prevent the loss of database or operating system software.

    a. During a loss of normal power, the control sequences shall go to

the normal system shutdown conditions. All critical configuration data shall be saved into Flash memory.

b. Upon restoration of normal power and after a minimum off-time delay, the controller shall automatically resume full operation without manual intervention through a normal soft-start sequence.

11. Certification – The NAE shall be listed by Underwriters Laboratories (UL).
12. Controller network – The NAE shall support the following communication protocols on the controller network:

    a. The NAE shall support BACnet Standard MS/TP Bus Protocol ASHRAE SSPC-135, Clause 9 on the controller network.
        i. A BACnet Protocol Implementation Conformance Statement shall be provided for each controller device (main or tracking) that will communicate on the BACnet MS/TP Bus.
        ii. The Conformance Statements shall be submitted 10 day prior to bidding.
        iii. The NAE shall support a minimum of 100 control devices.
    b. The NAE shall support the Johnson Controls N2, Tridium FX-40, or Honeywell Webs or approved equal Field Bus.
        i. The NAE shall support a minimum of 100 N2 control devices.
        ii. The Bus shall conform to Electronic Industry Alliance (EIA) Standard RS-485.
        iii. The Bus shall employ a main/tracking protocol where the NAE is the main.
        iv. The Bus shall employ a four (4) level priority system for polling frequency.
        v. The Bus shall be optically isolated from the NAE.
        vi. The Bus shall support the Metasys Integrator System.

2.2 WIRING

A. The multi-conductor cable for field wiring of electronic analog sensors shall be minimum No. 22 AWG, 300 volt, thermoplastic with stranded copper wire and 100 percent shield coverage. The number of conductors in each sensor cable shall be as determined by the Contractor. 2/c #22 shielded cables shall be Belden Cat. #8451 3/c #20 shielded cables shall be Belden Cat. #9770 or approved equal.

B. Conductors for digital sensors or contact control shall be the same as for the analog sensors, except the grounded shield is not required.

C. Individual conductors shall be color coded and in addition shall be numbered in the field to identify the particular terminal to which attached. Field numbering shall be performed with Brady or approved equal markers wrapped around the wire near the terminal connection. All wires shall be terminated with pressure type connectors suitable for wire size, material and terminal connection.

D. All exposed wiring or wiring concealed in partitions shall be installed in a designated conduit raceway. The conduit shall conform to Division 26 of the specification. Where wiring is installed in an air plenum the same shall be plenum rated cable.

E. All junction boxes shall have covers painted safety green, and be rigid steel.

F. All wiring between static pressure controllers and variable frequency drive fan controllers shall be shielded and grounded at the fan controller end. Directly route the variable frequency drive fan controller to the static pressure controller(s).

G. Where a motor disconnect is indicated downstream of a variable frequency drive (VFD) provide interlock wiring from the auxiliary contacts on the disconnect to the VFD to de-energize when the disconnect is turned “off”.

2.3 CONTROLLERS

A. Temperature sensor covers shall be stainless steel wire guard type with vandal proof screws. All room temperature sensors shall be mounted 4'-0 inches above the finished floor, except in stairways, corridors and toilets, which shall be 7'-0 inches. Provide insulating bases where temperature sensors are located on exterior or unconditioned walls. Each temperature sensor shall have adjustable limit stops and adjustable sensitivity. User adjustment shall be 2 degrees F above and below set points or as determined by the Owner. Room temperature sensors shall include range of 55 degrees F to 85 degrees F set point adjustment. Temperature sensors shall include set-point adjustors, U.L. approved for mounting base in air plenums, and RJ-11 jack for communications. Room temperature sensors shall be fully adjustable and shall display set point and actual temperature.

B. Space sensor wiring shall be installed concealed where possible. Should the Division 23 Contractor be unable to do so then surface metal raceway shall be utilized as specified in Division 26.

C. Room temperature sensors shall be accessible to ADA occupants.

D. All global sensors shall be monitored in accessible locations. Exterior sensors shall be provided with sun shield and be installed to prevent bird nesting.

2.4 DAMPERS

A. Control Dampers

1. The temperature control contractor shall provide all automatic control dampers of the types indicated on the plans and not specified to be integral with other equipment. Frames shall be not less than 16 gauge galvanized steel. Blades shall not be over 6 inches wide airfoil shaped double skin construction of 14 gauge equivalent thickness. Bearings shall be stainless steel sleeves with 2 inch shafts. Blade edge seals shall be vinyl blade with flexible metal compressible jamb seals of the tight-seal spring type.

Dampers and seals shall be suitable for temperature ranges of -40 to 250 degrees F.

2. All proportional or modulating control dampers shall be opposed blade type and all two-position dampers shall be parallel blade type.
3. Dampers shall be sized to meet flow requirements of the application. The sheet metal contractor shall furnish and install baffles to fit the damper to duct size. Baffles shall not exceed 6 inches.
4. Dampers shall be minimum leakage type to conserve energy and the temperature control manufacturer shall submit leakage and flow characteristic data for all control dampers with the temperature control submittal. Maximum leakage shall be 3 CFM/Sq. Ft. at static pressure of 1 inch W.C. for a damper width of 48 inches.
5. Ultra-low leakage dampers shall have blade edges shall to be fitted with replaceable, snap-on, inflatable seals to limit damper leakage to 2 percent at applied static pressure.
6. Low pressure rectangular control dampers shall be Type CD60 airfoil low leakage damper as manufactured by Ruskin or as approved equal of American Warming and Ventilating, Air Balance and Arrow.
7. Round control dampers shall be Type CERS25 with blade edge seals as manufactured by Ruskin or as approved equal.
8. Provide damper end switch for all control dampers where indicated. Damper end switch shall provide “proof of open” prior to allowing fan to energize. Damper end switch shall be Model TS-475 Mechanical Damper Arm Switch (no-mercury) as manufactured by MDI, Inc. or approved equal. Install per manufacturer’s recommendations on control damper. End switch shall have the following features:

    a. Housing Material: Glass filled PBT (polybutylene terephthalate).
    b. Bracket Material: Plated steel.
    c. Operation: Steel ball actuated sub-miniature snap action switch.
    d. Operating angle: 15 degrees. (Contact closes at 10 degrees above horizontal and contact opens at 5 degrees below horizontal).

B. Damper Operators

1. Electric damper actuators shall be properly sized to provide sufficient torque to position the damper throughout its operating range.
2. Use devices which are quiet in operation and which in the event of power failure, will "fail safe" by spring action in either the normally open or normally closed position as required for freeze, moisture, smoke, or fire protection.
3. Electric actuators requiring a 24 VAC power supply will be utilized. Motors shall be specifically designed and sized with proper torque according to requirements of the device it is to be used on (i.e.: valve, damper). Each actuator will accept the proper control input as the system is designed, (i.e.: floating, 0-10VDC, 4-20Ma etc.) without the need for any additional interface devices.
4. For all exterior damper operators provide NEMA 4X stainless steel corrosion resistant enclosure. Damper operator enclosure shall be model ZS-300 as manufactured by Belimo or approved equal.

2.5 PRESSURE INDEPENDENT HYDRONIC CONTROL VALVES

A. All automatic control valves 2 inches and smaller shall be screwed type, and valves 2 ½ inches and larger shall be flanged. Valves shall be factory-rated to withstand the pressures encountered. Valves shall have stainless-steel stems and spring loaded Teflon packing with replaceable seats and discs. All control valves must be capable of withstanding the shut-off head of the pumps, they are connected to without the valve seat lifting. Valves shall have stainless steel stems and spring loaded Teflon packing with replaceable seats and discs.

1. All modulating straight-through water valves shall be provided with equal-percentage contoured throttling plugs and shall be pressure independent type. All three-way valves shall be provided with linear throttling plugs such that the total flow through the valve shall remain constant regardless of the valve's position modulating. Valves shall be sized for a pressure drop equal to the coil they serve but not to exceed 5 psi. Valves shall have replaceable seats and discs. Pressure independent control valves shall be as manufactured by Griswold, Delta P, Warren Controls, Danfos, Bray, or approved equal.
2. Pressure Independent Actuated Ball Valves (PIC-V) for Flows up to 85 GPM

    a. The modulating control valves shall be pressure independent.
    b. Valves shall accurately control flow within +/-5% (including manufacturing tolerance) independent of system pressure fluctuation by maintaining a constant pressure differential across the control valve so that the valve only repositions on a change in load demand.
    c. The pressure independent modulating control valve shall include a Pressure Compensating Cartridge, Actuated Ball Valve, 2 PT’s, Manual Air Vent, Union, and Manual Isolation Ball in a single valve housing.
    d. The valve shall have an accuracy of +/- 5% including manufacturing tolerances and pressure variations.
    e. Valve housing shall consist of forged brass, rated at no less than 360 psi at 250°F.
    f. A venturi flow meter fitting shall be field installed so that the flow rate can be read by means of differential pressure. Valve shall include a field installed or factory installed venturi metering station so that the flow rate can be read by means of differential pressure. Venturi metering station shall not require any straight runs of piping before or after meter. Provide separate flow meter fitting if venturi flow meter is not integral to PIC valve assembly.
    g. Both the ATC and shutoff valve shall have stems that are field repairable with the valve in the line. The body design shall allow inspection or repair of the stem without disturbing piping connections or draining water. The repairable stem shall include two Teflon seals and one EPDM O-ring for protection against chemicals and modulating temperature.
    h. Valve shall have a union end connection with factory installed air

vent to allow for venting of the coil or heat pump.

i. The control valve shall accurately control the flow from 0 to 100% full rated flow.
j. The ATC portion of the valve shall use the full 90 degrees of the stroke for control. Stroke limiting of the valve shall not be acceptable.
k. A flow tag shall be furnished with each valve.
l. A universal mounting plate shall allow installation of actuators meeting the system electrical requirements and valve torque requirements as provided by Honeywell, Invensys, Johnson Controls, KMC, Schneider, Neptronic, or Siemens.
m. The actuator and plate can be rotated after mounting.
n. The actuator mounting assembly shall accommodate no less than 1 ½" of insulation.
o. Pressure Compensating Cartridge (PCC)
    i. PCC shall automatically compensate for pressure changes in valve and shall maintain a constant pressure drop across the flow limiting actuated ball.
    ii. The operating pressure range shall be available with the minimum range requiring 3 PSID to actuate the cartridge and the maximum 8 psid to actuate the cartridge
    iii. Valve internal control mechanism includes a diaphragm and full travel linear coil spring.
    iv. Valves shall include an accessible/ replaceable cartridge.
    v. Dual pressure/temperature test valves for verifying the pressure differential across the cartridge and flow limiting ball shall be standard.
p. Actuated Ball Valve
    i. Valve ball shall consist of chemically plated nickel brass or stainless steel.
    ii. Actuator stem shall be removable/ replaceable without removing valve from line.
    iii. Manufacturer shall be able to provide ball insert to limit flow to maximum flow rate with ±5% accuracy. Insert shall be constructed of a Glass-Filled Polymer. The insert shall be press fit to the inside of the ball. Clipping the insert onto the exiting side of the ball shall not be acceptable.
    iv. Each maximum flow rate selected shall use a different characterizing disc so that stroke limiting is not required.
    v. Valve shall have a minimum rangeability as follows: ½"-40:1, ¾"-160:1, 1" to 3"-400:1
    vi. Valve shall have EPDM O-rings behind Reinforced Teflon (PTFE) ball seals.
    vii. The valve shall have a minimum close-off pressure differential rating of 100 psi with 35 in-lbs of torque for 1/2" to 2" sizes.
    viii. Actuator shall provide minimum torque required for full valve shutoff position.
q. Isolation Ball Valve
    i. Valve shall include a 600 WOG manual isolation ball valve.

ii. Stem shall be removable/replaceable with the valve in the line.

r. The control valve actuator will be furnished by the controls contractor under Section 230900.

s. Pressure independent valves shall come as one complete assembly from Griswold Controls or approved equal and shall include a supply side combination shutoff/ strainer valve.

B. Control Valve Operators

1. Electric valve actuators shall be properly sized to provide sufficient torque to position valves throughout its operating range.
2. Use devices which are quiet in operation and which in the event of power failure, will "fail safe" by spring action in either the normally open or normally closed position as required for freeze, moisture, smoke, or fire protection. Spring return valves are required for all control valves where coils are exposed to outside air conditions.
3. Electric actuators requiring a 24VAC power supply will be utilized. Motors shall be specifically designed and sized with proper torque according to requirements of the device it is to be used on (i.e: valve, damper). Each actuator will accept the proper control input as the system is designed, (i.e.: floating, 0-10VDC, 4-10Ma etc.) without the need for any additional interface devices.

2.6 CONTROL PANELS

A. Furnish and install local panels for ATC devices. Control panels shall be fully enclosed cabinets, all steel construction and shall meet the requirements of NEMA 1 enclosures. Cabinet shall have piano hinged door with a locking latch. All cabinet locks shall use common key. Provide means of storing control system instructions and drawings inside cabinet for future reference. Panel shall be wall mounted or free standing and located where directed by the Contract Drawings or Engineer.

1. Each panel shall have all internal devices factory wired to a numbered terminal strip. Controllers and associated devices shall be mounted within the panel, accessible through a hinged door.
2. All ATC panels shall be provided with integral disconnect, wiring, and control transformers.
3. Any ATC control panel that is serving equipment on the emergency generator must be powered by an emergency generator fed circuit/electrical panel. Refer to electrical contract documents for all emergency powered equipment.

2.7 MISCELLANEOUS ELECTRICAL DEVICES

A. Electric Actuators. All automatically controlled devices, unless specified otherwise elsewhere, shall be provided with electric actuators which shall be sized to operate

their appropriate loads with sufficient reserve power to provide smooth modulating action or two-position action and tight close off as specified.

2.8 UNINTERRUPTIBLE POWER SUPPLY

A. Furnish, size and install uninterruptible power supplies (UPS's) at all ATC panels.

B. Provide all interlock and power wiring from U.P.S. to control panels as required such that all components are powered via the UPS. For hard-wired equipment furnished with pigtails/wire leads, e.g. control power transformers, splice pigtails/wire leads in junction box to a flexible cord with NEMA 5-15P Plug, which shall be plugged into the UPS.

C. UPS's shall be sized for the ATC panel load and shall provide at least 10 minutes of full load power in the event of a power outage.

D. UPS shall be furnished with plug and cord and shall be powered from power receptacle(s) in ATC panels.

2.9 CENTRAL CONTROL AND MONITORING SYSTEM (CCMS) (HARDWARE DESCRIPTION)

A. General

1. The Facilities Management Control System (FMCS) shall be comprised of a network of various independent, Stand-alone Digital Controllers (SDC'S), Air Handler Digital Controllers (AHDC's), Unitary Digital Controllers (UDC's), Variable Air Volume Digital Controllers (VAVDC's)]; together with Centralized Control Stations (CCS), and Centralized Host Stations (CHS) as specified, to provide centralized access and facility wide control functions. The AHDC's, UDC's and VAVDC's shall be interconnected in a communicating network to provide facility wide access and sharing of information. A Gateway Digital Controller (GDC's) shall be provided to allow interface with third party microprocessor based control systems that are specified for integration within specification. A Local Area Network (LAN) shall be provided to interconnect SDC's for high-speed data transmission.
2. Specification Nomenclature

a.	FMCS	Facility Management Control System
b.	AHDC	Air Handler Digital Controller
c.	UDC	Unitary Digital Controller
d.	VAVDC	Variable Air Volume Digital Controller
e.	GDC	Gateway Digital Controller
f.	GP	Graphical Programmer
g.	CHS	Central Host Station
h.	CCS	Central Control Station
i.	RPTR	Communications Repeater

B. Centralized Host Stations (CHS)

1. The FMCS shall include Centralized Host Stations. CHS's shall, in conjunction with the full compliment of Digital Controllers, provide the performance requirements within this specification. Each CHS shall include all hardware and software components to serve as a centralized facility operator station, providing color graphics, facility wide access, operator initiation of global control strategies, and centralized documentation.
The CHS shall be capable of simultaneously interfacing with the following:

a. -mouse pointing device
b. -two parallel printers
c. -high resolution VGA color graphics monitor
d. -seven auto answer/auto dial modems
e. -color inkjet printer
f. -two serial printers
g. -three FMCS LAN interface
h. -Alarm Graphic and Report FAX dial out service interface
i. -Mass storage tape system

As a minimum, the temperature control contractor shall provide the types and quantities of CHS, CCS, SDC, MSDC, AHDC, GDC, UDC, and VAV DC as required.

2. Computer

a. The existing FMS computer located in the Maintenance Office shall be utilized with the new CCMS System if compatible with the same. If the selected ATC contractor cannot tie into the existing computer, then a new stand-alone computer shall be furnished.
b. The existing FMS computer located in the college's Central Maintenance Office shall be utilized with the new CCMS System. Provide modem terminal, and wiring as required to interface this college's CCMS system with FMS computer. I/P data drop shall be provided adjacent to the network panels.
c. Coordinate IP address with Owners' I.T. Department for network connection. The CCMS must be fully networkable.
d. Provide fiber optic cable as required.
e. Extend Existing Building Management System (BMS) as required to accommodate all equipment on this project.

3. Operator Workstation: One PC-based microcomputer with minimum configuration as follows:

a. Uninterruptible Power Supply: 2 kVa.
b. Operating System: Microsoft Windows – Latest Version.
   i. ASHRAE 135 Compliance: Workstation shall use ASHRAE 135 protocol and communicate using ISO 8802-3 (Ethernet) datalink/physical layer protocol.
   ii. LonWorks Compliance: Control units shall use LonTalk

protocol and communicate using EIA/CEA 709.1 datalink/physical layer protocol.

c. Printer: Color, ink-jet type as follows:
   i. Print Head: 4800 x 1200 dpi optimized color resolution.
   ii. Paper Handling: Minimum of 100 sheets.
   iii. Print Speed: Minimum of 17 ppm in black and 12 ppm in color.

C. Centralized Control Stations (CCS)

1. The FMCS shall include Centralized Control Stations, as required. CCS's shall, in conjunction with the network of SDC's and additional CCS components as required, provide the performance requirements within this section of the specification. Each CCS shall include all hardware and software components to serve as a centralized facility operator station, providing facility wide access, for review and modification of global control strategies, real time system monitoring, controller database editing or creation, and centralized documentation.

D. Local Area Networks

1. The LAN shall utilize packetized transmissions, CRC 16 error checking, and distributed error recovery. Single or multiple SDC failures shall not cause loss of communication between other LAN-connected SDC's.
2. LAN connected SDC's shall be provided with a communications watchdog to assure that an individual SDC cannot permanently occupy the LAN. If an SDC is determined to be monopolizing communications, it shall be automatically shut down and an exception reported to annunciate this fact.
3. The LAN shall employ a token passing, peer-to-peer convention, same as or similar to the industry standard format IEEE 802.4. The content of messages shall be the manufacturer's standard. The Local Area Network components shall be manufacturer's standard or available from third party vendors which utilize the same chip implementation as used by the manufacturer.
4. Industry standard ANSI, RS-485 Network Communication System, Lon, or Bacnet, or Equivalent shall be utilized.
5. Trunk Wiring Practices - General

   a. The distributed communication network system shall consist of a multi-drop RS-485 bus architecture connecting SDC's, MSDC's, AHDC's, GDC's, UDC's, and VAVDC's. The trunk shall consist of:
      i. A twisted pair of wires (24 awg) completely encased in continuous metallic conduit.
      ii. A twisted shielded pair of wires (24awg) with the shield grounded in accordance with the manufacturer's wiring practices.
      iii. Or a dual channel, 62.5 micron fiber cabling system with ST type connectors.

   There shall be no power wiring, in excess of 30 VAC rms voltage, run in conduit with communications trunk wiring. In cases where

power or signal wiring is run in conduit with trunk wiring, all communications trunk wiring and power wiring shall be run using separate twisted shielded pairs (24awg) with the shields grounded in accordance with the manufacturer's wiring practices.

b. Communication Transient Protection

i. The manufacturer's catalog data sheet shall provide evidence that all FMCS products offered by the manufacturer are tested and comply with the standard for Transient Surge withstand capabilities for electrical devices ANSI C62.41, IEEE-587-1980, Categories A and B. Such testing shall have included power and communication trunk wiring. Compliance with IEEE-587 shall imply conformance with IEEE-472 transient standards based on the stated position of ANSI and IEEE regarding applicability of the rated standards.

ii. In addition, at each building entry and exit point, the wire communications trunk wiring shall be protected with a transient surge protection device providing the minimal protection specifications of the General semiconductor, Model #422E device. Transient surge protection is not necessary if the communication trunk, external to the building, is fiber optic in nature.

iii. The communications circuitry and input/output circuitry, of the SDC's, MSDC's, AHDC's, and VAVDC's shall provide protection against a 1000 volt, 3 amp transient signal, directly applied to the communication or input/output terminations. The manufacturer's catalog data sheet shall provide evidence of conformance with this requirement. Systems not complying with this requirement shall provide equivalent protection external to the FMCS controller. Protection shall be provided for the individual communications and input/output terminations for each FMCS controller. Submittal documentation shall clearly define how this requirement will be met and how the external protection will not affect the performance of the controllers.

c. RS-485 Trunk Distance and Topology

The manufacturer's RS-485 trunk shall provide operation over end to end linear distances of 4000 feet for wire connections and 6,500 feet for fiber optic connections, without repeaters, at communication data rates of up to 64 kbps. The trunk may be extended up to 20,000 feet through the use of wire repeaters or 80,000 feet through the use of fiber optic repeaters.

At data rates of up to 19.2 kbps, the trunk distance shall be extendible to distances of up to 20,000 feet using RS-485 communication wire or fiber optic repeaters. A repeater shall be used each 4,000 feet of linear distance for wire or every 6,500 feet for fiber optics. Repeating devices shall contain separate LED indication for each communication interface trunk to indicate proper operation of the repeater as well as the communications trunks.

Contractors shall provide devices which are of FMCS control

system manufacturer's design.

d. It shall be possible for the trunk to be "T" eed or "starred", at any location using a repeater, to facilitate the installation. Systems which do not provide this capability shall provide a trunk riser diagram showing end to end distances and locations of system topology necessary to meet the trunk diagram shown on the plans.

e. Fiber Optic Communication Trunk
The temperature control contractor shall provide a dual channel fiber optic data link, as required, to minimize the effects of transient surges caused by lightning or external EMI generating equipment. The data link shall be comprised of a single duplex cable containing two fibers (transmit and receive), of 62.5 micron construction, to accommodate data rates of up to 64 kbps.
The fiber optic trunk shall be connected to SDC devices using manufacturer's standard RS-485 to fiber optic data link modem. Repeating devices shall contain separate LED indication for each communication interface and the fiber modem, to indicate proper operation of all aspects of the device. Fiber modem devices shall be tested and conform with transient surge withstand tests for electrical devices, ANSI C62.41 IEEE-587 Categories A and B. Manufacturer's data sheet shall provide evidence of compliance with this requirement. Manufacturer's products which do not meet this minimum performance requirement shall not be acceptable.
Systems which require a special gateway controller to accommodate the fiber optic trunks, shall provide such a controller per point where the fiber optic cable enters and leaves the building. Gateway controllers shall not inhibit transfer of point data values between SDC controllers throughout the LAN. Such inhibitive systems shall not be acceptable.
In lieu of the above two options, the contractor may provide a fiber optic link to each SDC controller within the LAN. All controllers shall have access to the fiber optic link for LAN.
Fiber optic cable shall be fully tested and terminated by the temperature control contractor.

E. Air Handler Digital Controller (AHDC)

1. General

a. Controls shall be microprocessor based, Air Handler Digital Controllers (AHDC's). AHDC's shall be provided for air handling units and other applications as required. AHDC's shall be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the AHDC. The application control program shall be resident within the same enclosure as the input/output circuitry which translates the sensor signals. All input/output signal conversion shall be performed through a minimum of a 10 bit A to D converter. All input points shall be universal in nature allowing their individual function definition to be assigned through the application software. All unused input points

must be available as universally definable at the discretion of the owner. If the input points are not fully universal in nature, unused points must be equal in quantity between Analog Inputs and Digital Inputs.

Contractor shall provide a minimum of one AHDC controller per air handling system as shown on the drawings.

The BAS contractor shall provide and field install all AHDC's specified under this section. Mechanical equipment manufacturers desiring to provide AHDC type controls as factory mounted equipment, shall provide a separate bid for their products less all controls, actuators, valve assemblies and sensors, which are specified to be provided by the BAS/Temperature control contractor.

b. All input/output signals shall be directly hardwired to the AHDC. Troubleshooting of input/output signals shall be easily executed with a volt-ohm meter (VOM). As a result of this intent, it is specified that power line carrier systems, or other systems which command multiple outputs over a single pair of wires, shall not be utilized.

c. AHDC's shall be in continuous direct communication with the network which forms the facility wide Building Automation System. The AHDC's shall communicate with the SDC at a baud rate of not less than 19,200 baud.

2. Non-Volatile Memory

a. All control sequences programmed into the AHDC shall be stored in non-volatile memory, which is not dependent upon the presence of a battery, to be retained. Power failures shall not cause the AHDC memory to be lost, nor shall there be any need for batteries to be recharged or replaced to maintain the integrity of the controller database. The AHDC shall allow for the creation of unique application control sequences. Systems that only allow selection of sequences from a library or table, are not acceptable.

b. All control sequences shall be fully programmable at the AHDC, allowing for the creation and editing of an application control sequence, while at the unit.

c. The AHDC shall be provided with an interface port for the HHOT. The interface port shall allow the HHOT to have full functionality as described. From the interface port, the HHOT shall be able to directly access any AHDC, UDC or VAVDC in the network.

d. The AHDC shall provide an input/output point trending utility that is capable of accumulating 48 analog point samples and 10 digital point samples, per Input/Output point. Each sample shall be taken on a user defined interval, ranging from 1 second to 255 hours per sample. The digital readings shall be on a change of state occurrence for the digital points. All samples shall be recorded with the engineering units for the value, along with a time and date identifier for each sample taken. The samples shall be protected against loss due to power interruptions through a battery or capacitor backup method for a minimum of 30 days.

Systems unable to provide the above capability shall provide for the individual Input/Output point trending at the SDC. Specifics as to how each AHDC point will be trended, at the SDC, shall be provided in the submittal documents. Included in the explanation shall be the sample intervals, the memory allocation in the SDC and the number of AHDC's per SDC that can be expected.

e. The AHDC shall provide LED indication of transmit/receive communications performance, as well as for the proper/improper operation of the controller itself.

f. The AHDC shall be provided with a battery backed time clock that is capable of maintaining the time of day and calendar for up to thirty days, upon loss of power to the AHDC, without loss of setting. The battery for the time clock shall be replaceable by the customer. The AHDC shall be provided with integral time schedules; as a minimum, two seven day schedules with eight on/off periods per day shall be provided. Holiday override of weekly schedules shall be provided for pre-scheduling of holidays, for the year in advance.

3. Controller Location

a. To simplify controls and mechanical service troubleshooting, the AHDC shall be mounted directly in or on the controls compartment of the air handling system. The AHDC shall be provided in a NEMA 1 enclosure to accommodate direct mounting on the equipment to be controlled. The AHDC shall be constructed in a modular orientation such that service of the failed components can be done quickly and easily. The modular construction should limit the quantities of printed circuit boards to a maximum of two. All logic, control system, power supply and input/output circuitry shall be contained on a single plug-in circuit board. When required to replace a printed circuit board, it shall not be necessary to disconnect any field wiring. This shall allow all controls maintenance and troubleshooting to be made while at the air handling unit. The AHDC shall be directly wired to sensory devices, staging relays or modulating valves for heating and cooling.

b. For compatibility to the environment of the air handling unit, AHDC's shall have wide ambient ratings. AHDC's shall be rated for service from -40 Deg F (Degrees Fahrenheit) to 140 Deg F.

c. Contractor shall submit description of location of AHDC's on all mechanical and air handling equipment.

F. Unitary Digital Controller (UDC)

1. General

a. Controls shall be microprocessor based Unitary Digital Controllers (UDC's). UDC's shall be provided for equipment as necessary. UDC's shall be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the UDC. The application control program shall be resident within the

same enclosure as the input/output circuitry which translates the sensor signals. All input/output signal conversion shall be performed through a minimum of a 10 bit A to D converter.
Contractor shall provide a minimum of one UDC controller per unitary system as required.
The BAS contractor shall provide and install all UDC's specified under this section. Mechanical equipment manufacturers desiring to provide UDC type controls as factory mounted equipment, shall provide a separate bid for their products less all controls, actuators, valve assemblies and sensors, which are specified to be provided by the BAS/Temperature control contractor.

b. All input/output signals shall be directly hardwired to the UDC. Troubleshooting of input/output signals shall be easily executed with a volt-ohm-milli-amp meter (VOMA). As a result of this intent, it is specified that power line carrier systems, or other systems which command multiple outputs over a single pair of wires, shall not be utilized.

c. UDC's shall be in continuous, direct communication with the network which forms the facility wide building automation system. The UDC's shall communicate with the SDC at a baud rate of not less than 9,600 baud.

2. Non-Volatile Memory

a. All control sequences programmed into the UDC shall be stored in non-volatile memory, which is not dependent upon the presence of a battery, to be retained. Power failures shall not cause the UDC memory to be lost, nor shall there be any need for batteries to be recharge or replaced to maintain the integrity of the controller database. The UDC shall allow for the creation of unique application control sequences. Systems that allow only selection of sequences from a library or table are not acceptable.

b. All control sequences shall be fully configurable at the AHDC, allowing for the creation and change of a sequence while at the unit.

c. The UDC shall be provided with the ability to interface with the HHOT. The interface port shall be provided at the wall sensor or within the unitary equipment, as specified on the plans. The interface port shall allow the HHOT to have full functionality as described hereinbefore of this specification. From the interface port, the HHOT shall be able to directly access any AHDC, UDC, **or** VAVDC in the network.

d. The UDC shall provide an input/output point trending utility that is capable of accumulating 48 analog point samples and 10 digital point samples per Input/Output point. Each sample shall be taken on a user defined interval, ranging from 1 second to 255 hours per sample. The digital readings shall be on a change of state occurrence for the digital points. All samples shall be recorded with the engineering units for the value, along with a time and date identifier for each sample taken.
Systems unable to provide the above capability shall provide for the

individual input/output point trending at the SDC. Specifics as to how each UDC point will be trended, at the SDC, shall be provided in the submittal documents. Included in the explanation shall be the sample intervals, the memory allocation in the SDC and the number of UDC's per SDC that can be expected.

e. The UDC shall provide LED indication of transmit/receive communication performance, as well as for the proper/improper operation of the controller itself.

3. Controller Location

a. To simplify controls and mechanical service troubleshooting, the UDC shall be mounted directly in the controls compartment of the unitary system. The UDC shall be provided with a sheet metal or polymeric enclosure that is constructed of material allowing for the direct mounting within the primary air stream, as defined by UL-465. The direct mounting shall allow all controls maintenance and troubleshooting to be made while at the unitary equipment. The UDC shall be directly wired to sensory devices, staging relays or modulating valves for heating and cooling.

b. For compatibility to the environment of the unitary equipment, UDC's shall have wide ambient ratings. UDC's shall be rated for service from 32 Deg F (Degrees Fahrenheit) to 140 Deg F.

c. Contractor shall submit description of location of UDC's on all mechanical and unitary equipment.

G. Gateway Digital Controller (GDC)

1. General

a. Controls shall be microprocessor based, Gateway Digital Controllers (GDC's). GDC's shall be provided for the purpose of integrating microprocessor based, communicating, direct digital control systems from vendors other than the primary, selected controls manufacturer. GDC's shall be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the GDC. All communications interface control programs shall be resident within the GDC.

The BAS contractor shall provide and field install all GDC's specified under this section. Any interface requirement beyond a two wire communications wire link, shall be provided by the equipment manufacturer supplying the non-primary or third party microprocessor based, communicating, direct digital controllers.

b. All GDC's shall exist at the LAN level with the SDC's. The GDC's shall possess all capabilities described under the SDC section while additionally providing the interface to the third party systems described above. The GDC's shall communicate with the third party controllers at the highest possible baud rate offered by the third party system. As a minimum, 9,600 baud communications shall be utilized.

c. All control sequences programmed into the GDC shall be stored in non-volatile memory, which is not dependent upon the presence of a battery, to be retained. Power failures shall not cause the GDC memory to be lost, nor shall there be any need for batteries to be recharged or replaced to maintain the integrity of the controller database. The GDC shall allow the standard database information from the third party system to be integrated in standard FMCS data formats, allowing for the creation of unique application control sequences. Systems that only allow selection of data and sequences from a library or table, are not acceptable.

d. Each GDC shall be provided with manufacturer's standard built-in operator interface.
The GDC shall provide Alarming, point trending and Energy report generation capabilities. Alarming points shall be uniquely definable, with multiple alarms assignable to a single point. Such alarm shall be provided with a unique 80 character message. Systems utilizing an alarm message library, shall describe the size of the library and verify how all alarming within the GDC will be guaranteed unique 80 character messages.
The quantities of trended point values shall be limited only by total controller memory space. If necessary, a GDC may be dedicated fully to a trending task, allowing all controller memory to be available for the trend storage. Each unique trend report shall contain a minimum of 4 different points and a minimum of 128 samples per point. Trending frequency for each report shall be operator definable from a sample once a second to a sample once every 24 hours. Trend reports shall be internally formatted by the GDC and shall be reportable directly to a serial printer, a VT-100 display terminal, a CCS, CHS or any other device capable of receiving a formatted ASCII data file.

e. The energy reports shall not be limited in quantities only by available memory within the GDC. Each Energy Report shall be fully formatted and reportable to a serial printer, a VT-100 display terminal, a CCS, a CHS or any other device capable of receiving a formatted ASCII data file. As a minimum, each Energy Report shall provide a daily report and a monthly report with summary information such as outside air temperature, outside air humidity, total energy consumed and degree day calculations.

f. The GDC shall be provided with a battery backed clock that is capable of maintaining the time of day and calendar for up to thirty days, upon loss of power to the GDC, without loss of setting. The battery for the time clock shall be field replaceable by the customer.

H. Variable Air Volume Digital Controls (VAVDC)

1. General
Controls shall be microprocessor based Pressure Independent, Variable Air Volume Digital Controllers (VAVDC), as required. The VAVDC shall be based on a minimum 16 bit microprocessor working from software program memory which is physically located in the VAV DDC controller. The VAV

controller "intelligence" shall be resident within the same enclosure which translates sensor signals into digital information.

The VAVDC shall consist of a 16 bit microprocessor, power supply, enclosure, actuator (when required), differential pressure transducer, field termination, field adjustments and operation/application system software in a single integrated package. Systems not providing a single integrated package shall provide documentation supporting the use of the individual components in the application. Documentation shall include life cycle information for the actuator, sensor and control accuracy verification for the combination of the products. All input/output signals shall be directly hardwired to the VAV DDC controller. Troubleshooting of input/output signals shall be easily executed through the HHOT connected at the wall sensor location.

The VAVDC controller shall have a room sensor with integral room set point adjustment. The room sensor/set point shall be capable of being hardwired shared by up to four VAVDC's, providing coordinated control of zones containing multiple VAVDC's. The sharing of the sensor/set point shall be through hardwire connection. Systems sharing room sensor data through communications shall not be acceptable. In cases where a single room sensor is to be shared by multiple controllers and the system cannot accommodate the functions; a wall sensor with multiple sensing elements and a ganged set point adjustment, under a single sensor, shall be employed. The room sensor shall contain a push-button for override of unoccupied conditions and a plug-in communications jack for connection of the HHOT.

VAVDC's shall be provided by the BAS contractor, to the VAV box manufacturer, for factory mounting. The VAV terminal unit supplier shall include, in its price, all costs for mounting of VAVDC controller, connection of actuator to damper shaft, wiring of device power, wiring of VAVDC to fan (fan powered terminal) and wiring to reheat valve actuator as specified on drawings. Termination of re-heat valve actuator shall be done by BAS contractor in the field.

2. VAVDC's shall be in continuous, direct communication with the network which forms the facility wide building automation system, the VAVDC's shall communicate with the SDC at a data baud rate of not less than 19,200 baud.

3. The VAVDC shall be provided with the ability to interface with the HHOT. The interface port shall be provided at the wall sensor or at the controller, as specified on the plans. The interface port shall allow the HHOT to have full functionality. From the interface port, the HHOT shall be able to directly access any AHDC, UDC or VAVDC in the network.

   Through the palm top HHOT, the VAVDC shall support a fully prompted Air Balance sequence. The palm top HHOT shall, when connected to the wall sensor, automatically access the connected VAVDC unit. Systems requiring an address number or an access code to be entered, shall not be acceptable. The air balance sequence shall step the balancing contractor through the checkout and calibration of the VAVDC. Upon completion of the balancing sequence, the flow values presented by the VAVDC shall match those observed by the balancing contractor's measurement equipment. Additionally, upon completion of the air balance, the SDC shall

automatically archive the balance settings for future use if the controller were to require replacement. Systems not able to provide a formatted air balance HHOT, shall not be acceptable.
Through this specification requirement, the discrepancies between the readings at the VAVDC/SDC/CHS and the balancing contractors measurement devices, will be eliminated. As a minimum, the balancing program shall step the balancing contractor through the following functions:

a. -Check damper linking for full end to end stroke travel
b. -Verify and set maximum CFM flow valve
c. -Calibrate maximum CFM flow valve
d. -Verify and set minimum CFM flow valve
e. -Calibrate minimum CFM flow valve
f. -Verify and set reheat flow set point
g. -Calibrate reheat flow set point

4. The VAVDC shall provide LED indication of transmit/receive communications performance, as well as for the proper/improper operation of the controller itself.
5. The VAVDC shall be capable of supporting a VAVDC powered, direct plug-in communications repeater allowing for the "T"eeing or "Star"ing of the communications wiring. The plug-in communications repeater shall simplify the network topology by accommodating the various floor plan layouts of the facility.
   Systems unable to provide a plug-in communications repeater shall employ standard communications repeaters, mounting these repeaters at the VAVDC where the wiring is to be "T"eed or "Star"ed. The repeaters shall provide quick disconnect terminations for the communications and power wiring, allowing easy troubleshooting and replacement. If the repeater is to be powered from the same source as the VAVDC, the power transformer shall be adequately sized.
6. The VAVDC control algorithms shall be designed to limit the frequency of damper repositioning, to assure a minimum 10 year life from all components of the VAVDC. The VAVDC shall provide zone control accuracy of not more than +/- 1 Degree F. Systems providing control accuracies greater than +/10 degrees F, shall not be acceptable. With the submittal package, contractor shall provide performance data that verifies control accuracy of the VAVDC.
   The VAV terminal manufacturer shall provide a multi-point averaging, differential pressure sensor mounted on the inlet to each VAV box. The VAV terminal unit manufacturer shall supply a line to low voltage transformer, of sufficient capacity, to power the VAVDC plus all reheat valves and/or contactors and fan circuits associated with the VAV terminal and actuator assemblies. The BAS contractor shall provide all reheat control valves to the mechanical contractor for mounting and piping. The BAS contractor shall provide and install all wiring between the valve and VAVDC controller and between the room sensor and the VAVDC controller.

7. Non-Volatile Memory

a. All control sequences programmed in the VAV controller shall be stored in non-volatile memory, which is not dependent upon the presence of a battery to be retained. Power failures shall, therefore, not cause the VAV controller memory to be lost, nor shall there be any need for batteries to be recharged or replaced. The VAVDC shall employ global positioning strategies and actuation response times, sufficient to allow compliance with NFPA-92.

8. Controller Location

a. To simplify controls, mechanical service and troubleshooting, all components of the VAV controller shall be mounted directly at the Variable-Air-Volume terminal box. Enclosure assembly shall be mounted and positioned so that it is easily accessible to operational personnel.
b. The VAVDC shall be powered by a 24 VAC power source and shall comply with Class 2 wiring requirements.
c. For compatibility to the environment of a VAV terminal box, the VAVDC controller shall have wide ambient ratings for specified controls sequences and performance. VAVDC shall be rated for service from 40 Degrees F (Degrees Fahrenheit) to 140 Degrees F.
d. Contractor shall submit description of location of VAVDC controller on VAV terminal box.
e. For compatibility of use, in the supply or return air plenums, the VAVDC enclosure shall be constructed to comply with the requirements of UL-465.

9. Controller Point Capacity

a. Cooling Only Units
The VAVDC controller shall provide input/output points as follows:
i. Self-calibrating Velocity Pressure input (0-2 inch WC). The velocity pressure transducer shall be a continuously self-calibrating unit, which determines the zero velocity pressure point, by equalizing the pressure across the sensing element, every 10-15 seconds.
ii. Room Temperature Input
iii. Occupancy Override Input
iv. VAV Box Damper Output: Unless otherwise specified, the controller shall provide a minimum 30 lb./inch integral electric actuator, having a 90 degree stroke rotation in a time of 3 minutes maximum.
v. Occupancy or Status Input
vi. 0-100 percent Position Indication of Primary Damper Actuator - Direct feedback from damper actuator
vii. Room Set point Input
viii. Auxiliary Temperature Input
1) HHOT Interface
1) Fan Assisted, Induction, Reheat Units
In addition to the inputs and output points described above,

VAVDC controllers which are fan assisted, induction or reheat configurations shall provide the following additional control points:

ix. A minimum of 4, Form A, digital outputs for fan control, floating valve actuator control. Contact outputs shall be capable of accommodating 120 VAC pilot duty loads. Systems unable to accommodate the 120 VAC requirement shall provide interface relays for all controlled loads.

x. A 4-20mA (2-10 VDC, 1-5 VDC) proportional analog output signal for control of a proportioning hydronic reheat valve.

xi. VAV Terminals with Actuator by VAV Terminal Manufacturer
In place of the internal actuator specified in item above and in addition to the inputs and outputs specified in above, the VAVDC controller shall provide one of the two outputs below:

xii. Two additional, solid state electronic triacs to drive VAV terminal manufacturers 24 volt, synchronous, floating motor actuators.

xiii. A 4-20mA dc output for interface to VAV terminals with analog actuators.
For externally actuated controllers, the controller shall provide the commanded output position as a feedback signal.

2.10 SYSTEM SOFTWARE DESCRIPTION

A. General

1. Contractor shall provide all software for a complete and operational system as described herein. Software shall include manufacturer's standard multi-tasking, multi-user operating system for operator consoles and controllers, network communication software for dial-up and hard trunk applications, operator man-machine interface software, control application software and all other software necessary to provide the functions specified herein.
2. System software shall be as manufactured by Siebe Environmental Controls, Johnson Controls, Johnson Controls Facility Explorer, Siemens, Alerton, Reliable Controls, Schneider Electric, Advanced Power, or approved equal.

2.11 EXCEPTION REPORTING SEQUENCES

A. Alarm/COS Reports

1. For those digital points indicated on the drawings, the Contractor shall provide a unique change-of-state alarm message of up to 70 characters. The message shall report to all devices assigned to the alarm class.
2. For those points indicated on the drawings which are designated as

interrupt priority, the Contractor shall provide an interrupting process display at the CHS location which displays the current conditions for the operator.
In addition, the CHS computer shall automatically send a picture of the process graphic display to the remote locations via e-mail.

3. For those points designated in paragraph 3 above, the FMCS shall also send a history log to the system report printer of the immediate prior history of the points causing the interrupt priority. This log shall contain 1 minute samples of the previous 15 minutes of operation.
4. For those points on the drawings designed as Hard Facts points, the Contractor shall provide an alarm message to a remote facsimile location designated by the Owner. The FMCS system shall provide at the remote location, a facsimile print-out showing location, time/date of alarm and alarm message of the point. For interrupt priority fax alarms, the remote facsimile machine shall receive a hard copy of the interrupt process screen showing on-line dynamic data values of the current conditions.

B. Off Hours Exception Reporting

1. The Owner shall specify up to five sites to which off hours exceptions shall be auto-dialed and reported. This shall allow the owner to assign off hours exception responses to various facility personnel as necessary. Selection of the site to be dialed can be programmed by the Owner, and set to change automatically per time of day and day of week.

2.12 MONITORING SYSTEM, SENSORS AND WIRING

A. Sensors and other Devices for Input/Output Summary Schedule:

1. Provide all necessary sensors, relays, panels, conduits and wire for the points indicated in the input/output summary as shown on the contract drawings.
2. Analog sensing elements for remote indication shall be independent of local sensors used for local control loops.
3. Temperature sensors shall be Resistance Temperature Detector (RTD) type of 1000 ohm balco. Space (60-90 degrees F); Duct/Well (-30-250 degrees F); Averaging Duct (-30-225 degrees F) or as required under Division 26.

    a. Space temperature sensors shall be provided with blank commercial type locking satin chrome covers.
    b. Duct temperature sensors shall be rigid stem or averaging type as specified in the sequence of operation. Water sensors shall be provided with a separable copper, monel or stainless steel well. Outside air wall mounted sensors shall be provided with a sun shield.
    c. The dew point temperature sensor shall employ a non-reactive organic bobbin material to give precise dew point temperature readings with accuracy of not more than + 1.5 degrees F. The dew

point temperature sensor shall incorporate an integral draft shield as part of the instrument for air velocities in excess of 50 feet per minute. The dew point temperature sensor shall operate over a minimum dew point temperature range suitable to application.

4. Relative humidity sensors shall be capacitance type with 10 percent to 90 percent range. Duct mounted relative humidity sensors shall be provided with a sampling chamber. Wall mounted sensors shall be provided with covers identical to temperature sensors. Space 10 percent -90 percent RH; Duct 10 percent - 90 percent RH.
5. All wall mounted temperature sensors, dew point temperature, relative humidity sensors, and CO2 sensors shall be installed with stainless steel wire guard. Set point adjustment shall be achievable without removing the wire guard.
6. Differential and Static Pressure Sensors and Switches

    a. Fan proof-of-flow switches shall be U.L. listed adjustable set point and differential pressure type. Switches shall be piped to fan discharge except where fans operate at less than one inch WG, they shall be piped across the fan. For fractional horsepower and non-ducted fans, relays or auxiliary contacts may be used. Maximum pressure rating shall be at least 10 inches WG. with .05-12 inch W.C. range.
    b. Air flow and static pressure analog sensors shall be high accuracy suitable for the low velocity pressures to be encountered, be selected for approximately 50 percent overrange, and have a 4 to 20 ma output. These differential pressure sensors shall be connected to the air flow measuring station with valved lines for testing and calibration, and shall have adjustments for zero and span. 5 inch W.C. range.
    c. Water flow analog sensors shall be provided complete with flow element and shall be an all solid state precision industrial type with stainless steel meter body, maximum error of no more than .5 percent or span, and 4 to 20 ma output. Sensor shall be rated for 250 psi minimum and installed in strict accordance to the manufacturer's instructions complete with three-valve manifold for calibration and maintenance.

7. Overall system accuracy, including electronic analog sensing elements, shall be as follows:

    a. Air: Plus or minus 1.0 degrees F temperature, plus or minus 2.5 percent r.h., plus or minus 2.0 percent static pressure.
    b. Proof of fan operating status, or alarm conditions shall be through positive feedback from differential pressure switches across fan. Auxiliary dry contacts may be used for proof of fans if the motors are fractional H.P., and other non-ducted fans.

8. Digital inputs from devices with isolated, dry type contacts (no grounds, no voltage) of either normally open (N.O.) or normally closed (N.C.)

configuration shall be provided. Live contact inputs, those that have voltage present, shall be provided with isolating devices to meet dry contact requirements.

9. Start-stop relay module shall contain relays for start-stop function at the remote point, with relays mounted and factory wired to numbered terminal strips.
10. Outage Devices:

    a. Control Relays: Control relay contacts shall be rated for the application, with a minimum of two sets of Form C contacts, enclosed in a dustproof enclosure. Relays shall have silver-cadmium contacts with a minimum life-span rating of one million operations. Operating time shall be 20 milliseconds or less, with release time of 10 milliseconds or less. Relays shall be equipped with coil transient suppression limiting transients to nondamaging levels.
    b. Time Delay Relays: Time delay relay contacts shall be rated for the application with a minimum of two sets of Form C contacts enclosed in a dustproof enclosure. Relays shall have silver-cadmium contacts with a minimum life span rating of one million operations. Relays shall be equipped with coil transient suppression devices to limit transients to nondamaging levels. Delays contact opening or closing shall be adjustable from one to 60 seconds with a minimum accuracy of plus or minus 2 percent of setting.
    c. Latching Relays: Latching relay contacts shall be rated for the application with a minimum of two sets of Form C contacts enclosed in a dustproof enclosure. Relays shall have silver-cadmium contacts with a minimum life-span rating of one million operations. Operating time shall be 20 milliseconds or less, with release time of 10 milliseconds or less. Relays shall be equipped with coil transient suppression devices to limit transients to nondamaging levels.
    d. Reed Relays: Reed relays shall be encapsulated in a glass-type container housed in a plastic or epoxy case. Contacts shall be rated for the application. Operating and release times shall be one millisecond or less. Reed relays shall have a minimum life span rating of 10 million operations.
    e. Contactors: Contactors shall be of the single-coil, electrically operated, mechanically held type. Positive locking shall be obtained without the use of hooks, latches, or semi-permanent magnets. Contacts shall be double-break silver-to-silver type protected by arcing contacts. Number of contacts and ratings shall be selected for the application. Operating and release times shall be 100 milliseconds or less. Contactors shall be equipped with coil transient suppression devices to limit transients to nondamaging levels.
    f. Solid-State Relays: Input-output isolation shall be greater than 1000 megohms with a breakdown voltage of 1500 V rms or greater at 60 Hz. The contact life shall be 10 million operations or greater. The ambient temperature range shall be minus 20 degrees to plus 140 degrees F. Input impedance shall not be less than 500 ohms.

Relays shall be rated for the application. Operating and release times shall be one millisecond or less. Transient suppression shall be provided as an integral part of the relay to limit transients to nondamaging levels.

11. Audible Alarm:

a. All alarms shall annunciate on the ATC system front end computer and via pagers.

2.13 FIELD INSTALLED CONDENSATE OVERFLOW SWITCHES

A. Condensate overflow switches must be tested to comply with U.L. 508.

B. Interlock condensate overflow switches to shut-down cooling equipment and alarm on ATC system where overflow condition exists.

PART 3 - EXECUTION

3.1 GENERAL

A. The Automatic Temperature Control System and Central Control and Management System, shall be designed, installed, and commissioned in a turnkey fully implemented and operational manner.

3.2 BMS SPECIFIC REQUIREMENTS

A. Graphic Displays

1. Provide a color graphic system flow diagram display for each new and existing system with all points as indicated on the point list. All terminal unit graphic displays shall be from a standard design library.
2. User shall access the various system schematics via a graphical penetration scheme and/or menu selection.

B. Custom Reports:

1. Provide custom reports as required for this project:

3.3 INSTALLATION & SUPERVISION

A. All wiring and tubing shall be properly supported and run in a neat and workmanlike manner. All wiring and tubing exposed and in equipment rooms shall run parallel to or at right angles to the building structure. All piping and wiring within enclosures shall be neatly bundled and anchored to prevent restriction to devices and terminals.

B. The control contractor shall be responsible for all electrical installation required for a fully functional control and automation system and not shown on the electrical plans or required by the electrical specifications. All wiring shall be in accordance to all local and national codes.

1. All line voltage wiring, all wiring exposed, and all wiring in equipment rooms shall be installed in conduit in accordance to the electrical specifications.
2. All electric and electronic wiring shall be minimum #20 AWG minimum THHN and shielded if required.
3. All wiring in the central control room shall be concealed in an approved manner.

C. Verify locations of temperature sensors, relative humidity sensors, CO2 sensors, dewpoint temperature sensors, and other exposed control sensors with plans and Owner prior to installation.

D. The installation and supervision of this project shall be carried out by factory trained personnel who are employed by the Contractor and licensed for this type of work.

E. Install control units and other hardware in position on permanent walls where not subject to excessive vibration.

F. Install software in control units and in operator work station. Implement all features of programs to specified requirements and appropriate to sequence of operation.

G. Install in accordance with manufacturer’s instructions.

H. Check and verify location of space temperature sensors and other exposed control sensors with plans and room details before installation. Align with lighting switches and relative humidity sensors, and dewpoint temperature sensors.

I. Mount freeze protection thermostats using flanges and element holders.

J. Mount outdoor reset thermostats and outdoor sensors indoors, with sensing elements outdoors with sun shield.

K. Provide separable sockets for liquids and flanges for air bulb elements.

L. Mount control panels adjacent to associated equipment on vibration free walls or free standing angle iron supports. One cabinet may accommodate more than one system in same equipment room. Provide engraved plastic nameplates for instruments and controls inside cabinet and engraved plastic nameplates on cabinet face.

M. Install equipment plumb and level.

N. Install all equipment to be accessible for service and maintenance.

3.4 ACCEPTANCE TESTING

A. Point Verification

To verify end-to-end operation of the system the Contractor shall provide a hard copy of an All Points Summary Listing to the Owner of each part or system to be placed in warranty by the Owner. For CHS systems, the Contractor shall additionally provide a print screen of the process display showing real time dynamic point information for all points on the subsystem(s) to be accepted.

B. Sequence Verification

1. The Contractor shall notify the Owner's representative of systems which perform all specified sequences.
2. The warranty acceptance test shall be of 5 days duration and the system shall perform as follows:

   a. During the five days, the FMCS system shall not report any system diagnostics from the subsystem under test.
   b. The subsystem shall be performance verified as operational using temporary trends of each control loop located in the SDC or MSDC.
   c. During the occupied periods, BAS control loops, under test, shall maintain control of the process variable within the following scales:
      i. Duct Static Pressure +/-0.3 inch WC
      ii. Pump Head Pressure +/-10 percent of control range
      iii. Duct Temperature Loops +/-2 degrees F
      iv. Room Temperature Loops +/-1degrees F
      v. Pipe Temperature Loops +/-2 degrees F
   d. The contractor shall provide a hard copy printout of the process variable, process variable set point and control loop output percent for the period of 2 hours prior to occupancy to 2 hours after occupancy with samples taken every 15 minutes.

3.5 VARIABLE AIR VOLUME AIR BALANCING

A. The air balance of the system shall be conducted by an independent AABC certified test and balance contractor.

B. The test and balance contractor shall verify that duct static pressure and scheduled VAV box flows +/-5 percent are present at each VAV terminal and supply air system. The air balance contractor shall make such adjustments as necessary to verify air flows meet design requirements.

C. The BAS contractor shall provide the air balance contractors via loan, palm top HHOT with an air balance test program. The HHOT shall plug into each wall sensor location and provide the air balancer a prompted display to properly set the minimum and maximum flow of each VAV terminal.

3.6 COORDINATE WITH TAB AGENCY

A. Verify that all control components are installed in accordance with project requirements and are functional, including all electrical interlocks, damper sequences, air and water reset, freeze stats and duct smoke detectors.

B. Verify that all controlling instruments are calibrated and set for design operating conditions prior to commencement of TAB work.

C. Calibrate sensors after installation, and before the sensor control verification tests are performed. Prove the accuracy of final settings by taking temperature readings. The readings shall be in a typical conditional space for each separately controlled zone.

D. Allow sufficient time in the project to provide assistance and instruction to the balancing agency in the proper use and setting of control components such as, but not limited to, computers, static pressure controllers, or any other device that may need set points changed so that the testing and balancing work can be performed.

E. Assist the balancing agency in the testing of VAV boxes. Make available to the balancing agency the use of a portable service terminal for use in balancing VAV boxes.

F. All control sequences, software, equipment, and components shall be started-up by a qualified technician. Start-up report shall be submitted to Engineer prior to the commencement of testing and balancing work. Testing and balancing shall not commence until start-up reports are completed, reviewed by Engineer and forwarded to Testing and Balancing Agency.

3.7 EXAMINATION

A. Verify existing conditions before starting work.

B. Verify that systems are ready to receive work.

C. Beginning of installation means installer accepts existing conditions.

D. Sequence work to ensure installation of components is complementary to installation of similar components in other systems.

E. Coordinate installation of system components with installation of mechanical systems equipment such as air handling units and air terminal units.

F. Verify that conditioned power supply is available to the control units and to the operator work station. Verify that field end devices, wiring, and tubing is installed prior to installation proceeding.

3.8 INTERLOCK REQUIREMENTS

A. The fan and equipment interlock requirements are as scheduled on the contract drawings.

B. Furnish and install all necessary relays, transformer, contactors, wiring, conduit, and accessories to perform fan, pumps, equipment, and damper interlocks.

C. Unless otherwise noted, fan interlocks shall be arranged such that dampers associated with fan shall be open when fan starts and close when fan stops.

D. In projects with heat pumps, the evaporator fans shall be hard wired interlocked with the condensing unit/heat pumps so that if evaporator fan fails, the heat pump shall de-energize.

3.9 SUBMITTALS AT PROJECT CLOSEOUT

A. Project Record Documents: Record actual locations of components and set points of controls, including changes to sequences made after submission of shop drawings.

3.10 CONNECTIONS

A. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.

1. Install piping adjacent to machine to allow service and maintenance.

B. Ground equipment.

1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

C. Connect hand-off-auto selection switches to override automatic interlock controls when switch is in hand position.

3.11 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections, and to assist in field testing. Report results in writing.

B. Perform the following field tests and inspections and prepare test reports:

1. Operational Test: After electrical circuitry has been energized, start units to confirm proper unit operation. Remove and replace malfunctioning units and retest.
2. Test and adjust controls and safeties.
3. Test calibration of electronic controllers by disconnecting input sensors and stimulating operation with compatible signal generator.
4. Test each point through its full operating range to verify that safety and

operating control set points are as required.

5. Test each control loop to verify stable mode of operation and compliance with sequence of operation. Adjust PID actions.
6. Test each system for compliance with sequence of operation.
7. Test software and hardware interlocks.
8. Test all end switches and verify status is reported on the ATC system.

C. DDC Verification:

1. Verify that instruments are installed before calibration, testing, and loop or leak checks.
2. Check instruments for proper location and accessibility.
3. Check instrument installation for direction of flow, elevation, orientation, insertion depth, and other applicable considerations.
4. Check flow instruments. Inspect tag number and line and bore size, and verify that inlet side is identified and that meters are installed correctly.
5. Check pressure instruments, piping slope, installation of valve manifold, and self-contained pressure regulators.
6. Check temperature instruments and material and length of sensing elements.
7. Check control valves. Verify that they are in correct direction.
8. Check DDC system as follows:

    a. Verify that DDC controller power supply is from emergency power supply, if applicable.
    b. Verify that wires at control panels are tagged with their service designation and approved tagging system.
    c. Verify that spare I/O capacity has been provided.
    d. Verify that DDC controllers are protected from power supply surges.

D. Replace damaged or malfunctioning controls and equipment and repeat testing procedures.

E. All temperature control and interlock wiring shall be installed in conduit unless otherwise noted on the plans. Power or interlock wiring shall be run in separate conduit from sensor and communications wiring.

3.12 ADJUSTING

A. Calibrating and Adjusting:

1. Calibrate instruments.
2. Make three-point calibration test for both linearity and accuracy for each analog instrument.
3. Calibrate equipment and procedures using manufacturer's written recommendations and instruction manuals. Use test equipment with accuracy at least double that of instrument being calibrated.
4. Control System Inputs and Outputs:

a. Check analog inputs at 0, 50, and 100 percent of span.
b. Check analog outputs using volt-ohm-milli-amp meter (VOMA) at 0, 50, and 100 percent output.
c. Check digital inputs using jumper wire.
d. Check digital outputs using ohmmeter to test for contact making or breaking.
e. Check resistance temperature inputs at 0, 50, and 100 percent of span using a precision-resistant source.

5. Flow:

a. Set differential pressure flow transmitters for 0 and 100 percent values with 3-point calibration accomplished at 0, 50, 90, and 100 percent of span.

6. Pressure:

a. Calibrate pressure transmitters at 0, 50, and 100 percent of span.
b. Calibrate pressure switches to make or break contacts, with adjustable differential set at minimum.

7. Temperature:

a. Calibrate resistance temperature transmitters at 0, 50, and 100 percent of span using a precision-resistance source.
b. Calibrate temperature switches to make or break contacts.

8. Stroke and adjust control valves and dampers.
9. Provide diagnostic and test instruments for calibration and adjustment of system.
10. Provide written description of procedures and equipment for calibrating each type of instrument. Submit procedures review and approval before initiating startup procedures.

B. Adjust initial CO_2, temperature, static pressure, differential pressure, and relative humidity set points.

C. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to three visits to Project during other than normal occupancy hours for this purpose.

3.13 ON-SITE ASSISTANCE

A. Occupancy Adjustments: Within one year of date of Substantial Completion, provide up to three Project site visits, when requested by Owner, to adjust and calibrate components and to assist Owner's personnel in making program changes and in adjusting sensors and controls to suit actual conditions.

3.14 SCHEDULING

A. Submit spreadsheet to Owner indicating occupied/unoccupied times for each item controlled by ATC system. Incorporate all scheduling requirements into sequence of operation.

3.15 STAGING

A. Coordinate staging requirements with equipment being controlled. Where multistage units are scheduled or specified, provide all devices, controllers, wiring to control and sequence all stages.

END OF SECTION 230900

PAGE LEFT INTENTIONALLY BLANK

SECTION 233000 - HVAC AIR DISTRIBUTION

PART 1 - GENERAL

1.1 SUMMARY

A. For General Mechanical Requirements, see Division 23 Section, “Common Work Results for HVAC” and Division 01, “General Requirements”.

B. The fabrication and installation of all ductwork, together with related equipment, shall comply with the standards of the National Fire Protection Association, as set forth in NFPA Standard No. 90A, as well as with the requirements of the Sheet Metal and Air Conditioning Contractors' National Association, Inc., and the latest edition of the ASHRAE Guide.

C. All duct sizes shown are net inside clear dimensions. Where internal duct lining is used, increase duct sizes accordingly to provide the indicated net free area. Unless otherwise indicated size runouts, drops, and connections to air handling equipment, grilles, registers, dampers, fire dampers, diffusers, fans, coils, louvers, filters, and other equipment to the full size of the equipment connection.

D. Minor changes may be made in duct sizes where required to fit the available space, provided the indicated net free area and approximate aspect ratio are maintained. Size round ducts installed in place of rectangular ducts in accordance with ASHRAE/SMACNA Table of equivalent rectangular and round ducts.

E. Smoothly transition all ductwork to prevent excessive or unnecessary turbulence or pressure loss.

F. All exposed ductwork in finished areas shall be painted in color as indicated by Architect. All ductwork requiring paint shall be constructed of paint grade galvanized sheet steel with a paintable finish.

1.2 REFERENCES

A. ASTM A 36 - Structural Steel

B. ASTM A 90 - Weight of coating on Zinc-Coated (Galvanized) Iron or Steel Articles

C. ASTM A 167 - Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip

D. ASTM C 916 Type II – Standard Specification for Adhesives for Duct Thermal Insulation

E. ASTM A 366 - Steel, Sheet, Carbon, Cold Rolled, Commercial Quality

F. ASTM A 480 - General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet, and Strip

G. ASTM A 525 - General Requirements for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process

H. ASTM A 527 - Steel Sheet, Zinc-Coated (Galvanized) by Hot-Dip Process, Lock Forming Quality

I. ASTM A 568 - Steel, Sheet, Carbon, and High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled

J. ASTM A 569 - Steel, Carbon (0.15 Maximum, Percent), Hot-Rolled Sheet and Strip, Commercial Quality

K. ASTM B209 - Aluminum and Aluminum-Alloy Sheet and Plate

L. NFPA 90A - Installation of Air Conditioning and Ventilating Systems

M. NFPA 90B - Installation of Warm Air Heating and Air Conditioning Systems

N. SMACNA - HVAC Air Duct Leakage Test Manual

O. UL 181 - Factory-Made Air Ducts and Connectors.

P. NFPA 90A - Installation of Air Conditioning and Ventilating Systems

Q. NFPA 70 - National Electrical Code

R. SMACNA - HVAC Duct Construction Standards - Metal and Flexible

S. UL 33 - Heat Responsive Links for Fire-Protection Service.

T. UL 555 - Fire Dampers

1.3 QUALIFICATIONS

A. Manufacturer: Company specializing in manufacturing the projects specified in this section with minimum five (5) years documented experience.

B. Installer: Company specializing in performing the work of this section with minimum five (5) years' experience.

1.4 REGULATORY REQUIREMENTS

A. Construct ductwork to NFPA- 90A, and NFPA-90B Standards.

B. For dental suite application, all ductwork soundlining shall comply with ASHRAE 170 requirements.

1.5 ENVIRONMENTAL REQUIREMENTS

A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturer.

B. Maintain temperatures during and after installation of duct sealants.

1.6 ALTERNATES

A. Refer to Division 01 Section, “Alternates” for description of work under this section affected by alternates.

PART 2 - PRODUCTS

2.1 DUCTWORK

A. Unless otherwise indicated or specified, fabricate ductwork of galvanized sheet steel, stainless steel, or aluminum conforming to Commercial Designation 3003 Temper H14 and Duct Sheet. Duct gages, jointing and reinforcement shall conform to Tables 4, 5, 6 and 7, as applicable, Chapter I of the latest ASHRAE Guide and Data Book. Construction details shall conform to Section I and Section II, as applicable, of Duct Manual and Sheet Metal Construction for Ventilation and Air Conditioning Systems as published by Sheet Metal and Air Conditioning Contractors' Association, Inc.

B. Erect sheet metal ductwork in a first-class, workmanlike manner secured in place rigidly and permanently. Provide suitable hangers, securely attached to building construction with bolts, clips or inserts. Hangers shall be structural shapes, unistrut, kindorf or channel; strap hangers or the use of wire will not be permitted. All thread hangers shall not pass through or be inside duct. Hangers shall not penetrate the duct insulation vapor barrier. Support vertical ducts passing through floors by angles riveted to duct and resting either on floor or on brackets secured to building construction. All space around ducts where they pass through any walls, floors, ceilings, or roofs shall be sealed tight with incombustible inert material. Do not arrange ducts so as to impair the effectiveness of fireproofing around structural members. Provide sheet metal flanged collars around exposed ducts passing through walls, floors, or ceilings to provide finished appearance. Seal all duct joints and seams including supply, return, outside air, combustion air, relief air, ventilation air and exhaust ductwork with Hardcast Sealing System as manufactured by Hardcast, Inc., Foster, Childers, or approved equal.

C. Flexible connections of neoprene, excelon, or other NFPA approved non-inflammable fabric shall be provided in the duct system at all fan inlet and outlet

connections. Flexible duct connectors shall be Durodyne or approved equal.

D. Provide cut turning vanes in all duct turns where centerline radius is located. Turning vanes shall be air-foil type with extended trailing edges. Fabricate to comply with SMACNA Sheet Metal Construction for Ventilation and Air Conditioning Systems Manual.

E. Provide duct collars and angle iron framework for mounting of automatic dampers.

F. Fabricate and support in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated. Provide duct material, gauges, reinforcing, and sealing for operating pressures indicated.

G. Construct T's, bends, and elbows with radius of not less than 1-1/2 times width of duct on centerline. Where not possible and where rectangular elbows are used, provide air foil turning vanes. Where acoustical lining is indicated, provide turning vanes of perforated metal with glass fiber insulation.

H. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever possible; maximum 30 degrees divergence upstream of equipment and 45 degrees convergence downstream.

I. Fabricate continuously welded round and oval duct fittings two gauges heavier than duct gauges indicated in SMACNA Standard. Joints shall be minimum 4-inch (100 mm) cemented slip joint, brazed or electric welded. Prime coat welded joints.

J. Provide standard 45 degree lateral wye takeoffs unless otherwise indicated where 90 degree conical tee connections may be used.

K. Fasteners: Rivets, bolts, or sheet metal screws.

L. Hanger Rods: ASTM A36 - Galvanized steel; threaded both ends, threaded one end, or continuously threaded.

2.2 DUCT SYSTEMS

A. Supply duct systems from existing air handling unit #3 to new variable air volume boxes shall be constructed for medium pressure service (6 inch W.G.) and ductwork from the variable air volume box to diffusers shall be constructed for low pressure service (2 inch W.G.). All other supply, return, exhaust, fresh air intake, relief, ventilation, and outside air ductwork shall be constructed for low pressure service (2 inch W.G.).

2.3 DUCT CONSTRUCTION

A. Rectangular and/or Round Ductwork (Low Pressure):

1. Galvanized Steel Ducts: ASTM A525 and ASTM A527 galvanized steel sheet, lock-forming quality, having G-90 Zinc coating in conformance with ASTM A90.
2. Make allowance for internal duct lining where required. Sizes shown on the drawings are inside clear dimensions.
3. Determine duct gauges for the longest duct side and use for all four sides. Joints and reinforcing requirements apply to the longest duct side.
4. Reinforce all ducts to prevent buckling, vibration, or noise as recommended in the referenced construction standards, and as required to suit the installed conditions.
5. Do not cross break duct which will receive rigid insulation covering.
6. Where tap sizes of divided-flow fittings are not indicated, make branch and main/connection sizes proportional to their respective air flows and maintain uniform transverse velocities in the fitting.
7. Make radius elbows and radius tee connection with throat radius equal to or greater than the width of the duct. Use vaned elbows where shown and where radius elbows will not fit the space, and in all square bends.
8. Turning vanes shall be the air-foil type with extended trailing edges, 36-inch maximum vane length. Where longer vanes are required, use two or more sets of vanes with intermediate runners securely fastened together.
9. Bolt, screw, rivet, or spot weld reinforcing members securely to the duct on not less than 6-inch centers.
10. Where ducts are open-ended without grilles, registers, or other means of stiffening, reinforce and stiffen the open end with standing seams or an angle frame. Provide rolled edges to prevent any exposed sharp edges.
11. Paint all cut ends on galvanized angles, rods, and other uncoated surfaces with aluminum paint.
12. Where ductwork is not painted or otherwise finished, remove all exposed traces of joint sealers, manufacturer's identification and other markings.
13. Aluminum sheet shall be 3003 H14 alloy or duct sheet, 16,000 psi minimum tensile strength, and capable of being formed to a Pittsburgh lock seam.
14. Reinforcing members for aluminum ductwork shall be galvanized steel or aluminum unless otherwise indicated. Where aluminum reinforcing is used, size the member in accordance with ASHRAE recommendations to have rigidity equivalent to listed mild steel angle sizes.
15. Where aluminum ductwork is used, make allowance for increased thermal expansion. Particularly avoid direct contact between aluminum and concrete or masonry walls subject to dampness.
16. Determine duct gauges per SMACNA based on duct size and pressure indicated.

B. Round/Flat Oval and/or Rectangular Ductwork (Single Wall Medium Pressure):

1. Galvanized Steel Ducts: ASTM A525 and ASTM A527 galvanized medium pressure sheet steel, lock forming quality, having G90 Zinc coating in conformance with ASTM A90.
2. Determine duct gauges based on duct diameter or duct size and pressures indicated.
3. Round and flat oval duct shall be spiral seam type.

4. All branch ducts shall connect to the main duct with a 45 degree conical lateral, or low loss fittings as shown on the drawings where possible. Where not possible, a 90 degree conical connection shall be used.
5. All elbows shall be long radius.
6. All seams and joints of fittings shall be welded by gas fusion with rod material same as duct material.
7. Connections to equipment shall be flexible material, NEMA approved, having adequate reinforcing to be compatible with internal pressure of system.
8. Paint all cut ends and welded joints with aluminum paint.
9. Make allowance for internal duct lining where required. Sizes shown on the drawings are inside clear dimensions. Rectangular lined ductwork shall have perforated metal liner, similar to that hereinafter specified.
10. Determine duct gauges for the longest duct side and use for all four sides. Joints and reinforcing requirements apply to the longest duct side.
11. Reinforce all ducts to prevent buckling, vibration, or noise as recommended in the referenced construction standards and as required to suit the installed conditions.
12. Do not cross-break duct which will receive rigid insulation covering.
13. Where tap sizes of divided-flow fittings are not indicated, make branch and main connection sizes proportional to their respective air flows and maintain uniform transverse velocities in the fitting.
14. Make radius elbows and radius tee connection with throat radius equal to or greater than the width of the duct. Use vaned elbows where shown and where radius elbows will not fit the space, and in all square bends.
15. Turning vanes shall be the airfoil type with extended trailing edges, 36-inch maximum vane length. Where longer vanes are required, use two or more sets of vanes with intermediate runners securely fastened together.
16. Bolt, screw, rivet, or spotweld reinforcing members securely to the duct on not less than 6-inch centers
17. Where ducts are open-ended without grilles, registers, or other means of stiffening, reinforce and stiffen, and open end with standing seams or an angle frame.
18. Remove all exposed traces of joint sealers, manufacturer's identification and other markings.

2.4 AIR TRANSFER OPENINGS

A. Furnish and install metal sleeves or frames, of the same material as the duct or air terminals attached thereto, in all air transfer openings through walls, partitions, floors and other building construction, extending completely through the opening. Securely fasten the sleeves or frames in place and provide face flanges on both sides. Where grilles or registers are required, attach them to the sleeve or frame, or extend ductwork where shown on the drawings. If no grilles, registers or duct connections are required, furnish and install ½ inch x ½ inch removable galvanized wire mesh on one face.

2.5 AIR VOLUME CONTROLS

A. Furnish and install air volume control devices where indicated and where required to adjust and balance air flow in the systems, whether indicated or not. Volume dampers shall be provided in all branch ducts serving air outlets and inlets. For existing air devices install a new volume damper and where required for access, a new access door to allow access and adjustment.

B. Manual volume dampers in ductwork shall be factory-assembled units with rigid frame, opposed-blade action, and locking quadrant operator. Mark the extended damper shaft and align the operating handle to indicate the blade position. Dampers shall be as manufactured by Ruskin, American Warming and Ventilating, Inc., Arrow, Vent Products Company, or approved equal. Rectangular dampers shall be Type MD35, with steel channel frame, 16 gauge steel blades, 9 inch maximum blade spacing, low pressure, nylon bearings, galvanized finish with aluminum paint touch up. Round manual balancing dampers shall be Type MDRS25 manufactured by Ruskin, Arrow, American Warming and Ventilating, Inc., or as approved equal. When external insulation is to be applied, provide sheet metal standoffs on all manual volume dampers. Provide blade stops to minimize air gaps around damper blades when closed.

C. Motor-operated dampers shall be as hereinafter specified under Division 23 Section, “Instrumentation and Controls of HVAC & Plumbing System”.

D. Duct turning vanes shall be Tuttle & Bailey Ducturns, or approved equal.

E. Furnish and install duct collars and angle iron frames for the installation of ATC dampers.

F. Where volume dampers are installed in exposed finished spaces locate damper handle on top of duct.

G. Where volume dampers are installed above ceilings attach a colored piece of tape so that Test and Balance Engineer can easily locate for air flow adjustment.

H. Where existing air devices do not contain manual volume dampers in the run-out ductwork, install manual volume damper at each existing air device duct runout.

2.6 INSTRUMENT TEST PORTS

A. Furnish and install instrument test ports in the ductwork to allow use of pitot tube length. Equip holes with Ventlok #699 instrument ports. Fittings shall extend beyond duct covering and insulation.

2.7 FLEXIBLE DUCT

A. Where indicated, flexible ductwork shall be Type SLR-25C as manufactured by General Flex Corporation, or as approved equal, insulated fully, UL listed as Class 1 Air Ducts, Standard 181, NFPA 90A and NFPA 90B with scuff-resistant

polyethylene connector jacket and suitable for use in return air plenums. Flex duct tape shall be UL-181 listed and marked “181B-FX”.

B. Limit flexible duct runs to 5 feet maximum. Install flexible ducts, using all recommended fittings, couplings, and accessories. Support ducts with wide straps spaced so that horizontal runs do not sag more than 2-1/2 inches in 5 feet. Internally seal all joints and connections, cover with duct tape, and fasten with metal duct strap clamps. Bends of 180 degrees in flexible duct are prohibited.

2.8 DUCT ACCESS DOORS

A. Furnish and install adequately sized duct access doors at air measuring devices, motor-operated dampers, duct coils, and other locations where indicated and required for duct access. Doors shall be the continuous piano-hinged type with approved latches and neoprene compression-type gaskets with 1 inch thick fiberglass double skin and shall be Ruskin Model ADH22, Air Balance, Inc., FSA-100 or as approved equal. Stiffen ductwork at door openings. Where doors are installed in insulated ductwork, provide equivalent insulation in the door assembly. Where access doors are installed in the fire-rated partitions, provide Fire Seal access doors as manufactured by Air Balance, Inc., or approved equal, UL approved, meeting the rating of the enclosure in which the access door is installed.

B. Where duct access doors are installed in medium pressure ductwork, they shall be as manufactured by Ruskin, Type ADHP-3, or approved equal, with six latches continuous gasket and insulated core.

C. Seal around frame attachment to duct and door to frame with neoprene or foam rubber.

2.9 SPIN-IN FITTINGS

A. Furnish and install spin-in fittings where indicated on the contract drawings, Model SM-20G, as manufactured by General Environment Corporation, or an approved equal.

2.10 DUCT LINING (LOW PRESSURE DUCTWORK)

A. All low pressure supply and return ductwork within 10 feet of air handling units, rooftop units, and as additionally shown on Contract Drawings, shall be lined on the interior for sound attenuation and thermal insulation.

B. All low pressure supply ductwork within 10 feet of variable air volume boxes and as shown on Contract Drawings shall be lined on the interior for sound attenuation and thermal insulation.

C. All low pressure ductwork within 10 feet of exhaust air fans and as additionally shown on Contract Drawings shall be lined on the interior for sound attenuation

and thermal insulation.

D. All internal duct lining for low pressure duct systems shall be provided with an interior galvanized perforated liner.

E. Provide additional exterior insulation where required and as indicated in Division 23 Section, “HVAC Insulation”.

F. The lining insulation shall be 1 inch thick, 3.0 pcf density, Aeroflex plus Duct Liner Type 300, Owens Corning Quiet R Rotary Duct Liner, Manville, Knauf, or approved equal. The material shall be specifically designed for this application, shall have a black, fire-resistant coating, shall meet NFPA Standards 90A and 90B and shall have a UL Fire Hazard Classification of Flame Spread 25 or less and smoke developed of 10 or less. The black-coated surface shall face the air stream.

G. All exposed edges and the leading edge of all cross joints of the liner shall be coated with the same adhesive used to secure the duct liner to metal surface. All air stream surfaces shall be treated with EPA registered fungicide Foster 40-20. Coating shall meet ASTM D 5590 with 0 growth rating.

H. The duct liner shall be adhered to the metal with 100 percent coverage of adhesive. Adhesive shall conform to Adhesive and Sealant Council Standards for adhesives for duct liner; ASTM C916, Type II (ASC-A-7001-A-1971). Adhesive shall be Foster 85-60, Childers CP-127 or approved equal.

I. The duct liner shall be additionally secured with mechanical fasteners, which shall compress the duct liner sufficiently to hold it firmly in place. Mechanical fasteners shall conform to Mechanical Fastener Standard MF-1-1971, available from Sheet Metal and Air Conditioning Contractors National Association.

J. All duct lining shall be installed in complete accordance with the Sheet Metal and Air Conditioning Contractors National Association (SMACNA) Duct Liner Application Standard, First Edition and Green Guard Indoor Air Quality certification program requirements.

K. Dimensions on drawings indicate inside clear opening of rectangular ductwork. Increase duct dimensions 2 inches each way for accommodating insulation on all shop or field-fabricated rectangular ductwork where lining is specified.

2.11 AIR DEVICE REQUIREMENTS

A. Furnish and install air supply, return, exhaust devices of sizes and capacities as scheduled on the drawings. Catalog numbers shown are Titus, Inc., products for equipment which have been found suitable for the application. Other manufacturers listed below or approved equal will be considered only if performance characteristics including throw, drop, pressure loss, sound pressure level, etc., are equal to or better than the performance characteristics of the specified products. All air devices shall be ADC certified. Ductwork behind

registers, grilles, open ended ducts, and diffusers shall be given two coats of flat black paint. Perimeter of all ceiling diffusers shall be caulked to provide a neat, aesthetic appearance.

B. Where air terminal devices are installed in duct collars or branches, furnish and install air extractors. Furnish and install control grids, volume dampers, and/or other accessories necessary to ensure uniform air flow across the terminal devices. Accessories shall be of the same material as the terminal device. Install fixed blade terminals so that blades block the normal line of vision. Furnish three (3) of each type of removable key operators.

C. Contractor shall determine frame and mounting type as per type of ceiling as shown on Architectural drawings.

D. Air devices and accessories that are installed in a finished, non-white ceiling shall be of a color as selected by the Architect.

E. Noise Criteria: All air devices shall be sized and selected to limit maximum NC (Noise Criteria) levels to 20.

2.12 SUPPLY AIR DEVICES

A. SD1 Diffuser, Square/Rectangular

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Titus Model TDCA-AA
   b. Metal-Aire
   c. Price
   d. Tuttle & Bailey
   e. Anemostat
   f. Carnes
   g. Nailor
   h. Krueger

2. Construction:

   a. Material: Aluminum
   b. Finish: Baked enamel, color selected by Architect
   c. Face Style: Louvered
   d. Mounting: Lay-in or Gypboard
   e. Pattern: Adjustable core style
   f. Damper: Integral, Opposed Blade type

3. Accessories:

   a. Square to round neck adaptor
   b. Adjustable pattern vanes

4. Provide auxiliary panel for lay-in tile installation.
5. The diffuser shall be tested in accordance with ANSI/ASHRAE Standard 70-1991.

2.13 RETURN/EXHAUST/TRANSFER GRILLES

A. RG1 Return/Exhaust/Transfer Grille, Square/Rectangular

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Titus Model 350FS
   b. Metal-Aire
   c. Price
   d. Tuttle & Bailey
   e. Anemostat
   f. Carnes
   g. Nailor
   h. Krueger

2. Construction:

   a. Material: Aluminum
   b. Finish: White Baked Enamel
   c. Ceiling Type: Lay-in, Gypboard, Sidewall
   d. Blades: Fixed, 35° Angle, 3/4” Spacing

3. Accessories:

   a. Face: Grille
   b. Damper: Integral, Opposed Blade type

4. Provide auxiliary panel for lay-in tile installation.
5. The register shall be tested in accordance with ANSI/ASHRAE Standard 70-1991.

B. RG2 Return/Exhaust/Transfer Grille, Square/Rectangular with Filter, Aluminum

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Titus Model 350FSF
   b. Metal-Aire
   c. Price
   d. Tuttle & Bailey
   e. Anemostat
   f. Carnes
   g. Nailor
   h. Krueger

2. Construction:

   a. Material: Aluminum
   b. Finish: White Baked Enamel
   c. Ceiling Type: Lay-in, Gypboard, Sidewall
   d. Blades: Fixed, 35° Angle, 3/4” Spacing

3. Accessories:

   a. Face: Grille
   b. Damper: Integral, Opposed Blade type

4. Provide auxiliary panel for lay-in tile installation.
5. Provide return air filter racks and 1” thick filters.
6. The register shall be tested in accordance with ANSI/ASHRAE Standard 70-1991.
7. Furnish spare filters with each air device.

2.14 OPEN END DUCTS (OED)

A. Whether indicated on plans or not, all open-ended ducts shall be provided with a protective screen.

B. All open-ended ducts shall be furnished with a 12 gauge ½ inch x ½ inch aluminum mesh screen. Screens shall be permanently installed in a removable frame, and the frame shall be attached to the open-ended duct in a neat, workmanship-like manner without any exposed edges or sharp surfaces.

C. Screen shall be attached to a ¾ inch x 1/8 inch continuous galvanized perimeter frame. Install duct stiffeners greater than 16 inches in any direction at open-ended ducts.

D. Behind all open end ducts, paint ductwork and dampers with two (2) coats of flat black paint.

2.15 DRIP PANS

A. Furnish and install suitable watertight, aluminum drip pans where water or drain piping is routed over electrical switchgear, transformers, computers, elevator machine equipment, dry storage rooms, etc. Each drip pan shall have a 1 inch copper type M drain piped to discharge where shown on drawings; or, if not shown, to discharge over nearest available open drain. Size and arrangement shall be as approved by Engineer. Sides shall be minimum 1.5 inches deep.

B. Drain pans shall be of 16 gauge welded construction. Provide drawings of typical drain pan construction for approval before construction. See Submittals in Division 01 Section, “Product Requirements”.

2.16 DUCT SEALANTS AND ADHESIVES

A. All ductwork shall be sealed, including low pressure exhaust systems. Transverse joints and longitudinal seams in duct systems shall be sealed with a duct sealant of the type specified hereinafter in Section 1, 2, or 3, or with a tape sealing system as specified in Section 4. Spiral lockseams are not longitudinal seams and do not require duct sealant. All seams and joints shall require duct sealant suitable for the pressure rating and installation application. All sealants shall exceed 500 hours without becoming brittle under ASTM-D572 test conditions (oxygen bomb), unless specified otherwise. No surface preparation or solvent cleaning shall be necessary to remove light coatings of oil and dust before applying sealant unless specified otherwise. Flanged joints shall be sealed according to Section 5. Construction joints that are not fully welded shall be sealed according to Section 6. Adhesive to secure insulation to metal surfaces shall be that specified in Section 7.

1. Assembly joints to be installed indoors or outdoors shall be sealed with Foster 32-19, Childers CP-146, United Duct Sealer WB, or equivalent, which is a water-based sealant formulated to withstand service temperatures from 20 degrees F to +200 degrees F. Sealant shall have a UL Classification marking with a flame spread of 15 and smoke developed of 0 when applied to inorganic reinforced cement board, both at a coverage of 31 square feet per gallon. Store and apply between 40°F (4°C) and 100°F (38°C); protect from freezing.
2. Assembly joints to be installed indoors shall be sealed with Foster 32-19, childers CP-146, UNI-GRIP™ duct sealer or equivalent, which is a water-based (vinyl-acrylic polymer) sealant formulated to withstand temperatures from –20 degrees to +200 degrees Fahrenheit. Surfaces to be sealed should be clean, dry, and free from oil, grease, and dirt. Sealant shall be nonflammable (wet) and fire retardant. Sealant shall have a UL Classification marking with a flame spread of 5 and smoke developed of 5 when applied to 18-gauge galvanized steel and a flame spread of 0 and smoke developed of 0 when applied to inorganic reinforced cement board, both at a coverage of 40 square feet per gallon.
3. Assembly joints shall be sealed with UNI-CAST® tape sealing system or equivalent, which is a combination of an adhesive activator and woven-fiber tape impregnated with a gypsum mineral compound. Modified acrylic/silicone activator (MTA-20 for indoor use) reacts exothermically with the tape to form a hard, airtight seal. Sealant shall be formulated to withstand temperatures from –40 degrees F to +200 degrees Fahrenheit. Combination of tape and MTA-20 adhesive shall have a flame spread and smoke developed of 0. Do not use for outdoors.
4. Flanged joints to be installed indoors shall be sealed with UNI-GASKET™ flange sealer or equivalent, which has a synthetic elastomer base and is formulated to withstand temperatures from –20 degrees F to +150 degrees F. Sealant shall have a UL Classification marking with a flame spread of 5 and smoke developed of 5 when applied to 18-gauge galvanized steel and a flame spread of 0 and smoke developed of 5 when applied to inorganic reinforced cement board, both at a coverage of 80 square feet per gallon.

5. Where duct fittings are constructed with standing seam or spot-welded techniques, all construction joints shall be sealed with UNI-WELD™ metal cement or equivalent, which is composed of neoprene rubber, resins, and inert reinforcing material dispersed in a petroleum distillate. Sealant shall be formulated to withstand temperatures from –20 degrees F to +225 degrees F. Sealant shall have a UL Classification marking with a flame spread of 0 and smoke developed of 0 when applied to 18-gauge galvanized steel and a flame spread of 0 and smoke developed of 0 when applied to inorganic reinforced cement board, tested as applied in two 1/8 inch beads 8 inches on center.
6. Where insulation is to be secured to metal surfaces, the adhesive used shall be Foster 85-60, Childers CP-127, UNI-TACK™ duct liner adhesive or equivalent, which are water-based, vinyl-acrylic copolymer adhesives formulated to withstand temperatures from –20 degrees Fahrenheit to +200 degrees Fahrenheit. Adhesive shall have a UL Classification marking with a flame spread of 0 and smoke developed of 0 when applied to 18-gauge galvanized steel and a flame spread of 0 and smoke developed of 0 when applied to inorganic reinforced cement board, both at a coverage of 267 square feet per gallon. Adhesive shall conform to ASTM C916, Type II.

B. Manufacturers: Duct Mate, United McGill, MKT Metal Manufacturers, Semco, Elgen, Childers, Foster, or as approved equal.

2.17 FILTER MEDIA DURING CONSTRUCTION

A. Filter media installed during construction: Minimum MERV 8.

PART 3 - EXECUTION

3.1 DUCT INSTALLATION REQUIREMENTS

A. Coordinate ductwork with other work and install ducts at proper elevations and locations to maintain indicated ceiling heights and clearances. Provide all elbows, transitions, offsets, connections, and other fittings necessary to fit the work into place or to connect to equipment or diffusers. Method of duct support connection to structure and slabs shall be approved by Structural Engineer, and Shop Drawings shall be submitted.

B. Substantially support ductwork with structural shapes, flat bars, or formed strap hangers securely attached to the building structure by means of bolts, clamps, or inserts. Support vertical ducts by angles attached to the duct and resting on the floor or supported by brackets or hangers attached to the building structure. Strap hangers shall be 16-gauge minimum galvanized steel formed under the bottom edge of duct. Use square ¼ inch thick washers tight against the bend on upper strap attachments to horizontal surfaces. Place all supports external to the ductwork and out of the air stream. Provide additional supports at coils and other

concentrated loads. Arrange supports so that duct weight is not transmitted to ceilings, fans or other equipment.

C. Prevent direct contact between ductwork and building surfaces or other equipment. Where ducts pass through walls, partitions, floors, ceilings, or roofs, pack and seal the space around the duct with an approved fire-safe inert material. Provide flanged duct escutcheons at all exposed ducts that pass through walls, partitions, floors, and ceilings.

D. Use galvanized (compatible) corrosion-resistant hangers, supports, brackets, and hardware.

E. Furnish and install NFPA-approved duct connections where shown and at all connections to fans, air handling units, and similar rotating equipment. Use glass-reinforced neoprene fabric, roll-formed to sheet metal strips or flanges. Support adjacent ductwork to provide sufficient slack in the connection.

F. See NFPA 90A, and latest publication of SMACNA. Prevent direct contact between ductwork and building surfaces or other equipment. The opening in the construction around the duct shall not exceed one-inch average clearance on all sides. Where ducts pass through walls, partitions, floors, ceilings, or roofs, pack and seal the space around the duct with an approved fire-safe inert material capable of preventing the passage of flame and hot gases sufficiently to ignite cotton waste when subjected to the same NFPA 251 Time-Temperature Conditions required for fire barrier penetration. All exposed duct penetrations shall be finished with a sheet metal field erected flange escutcheon to form a neat appearance.

G. Coordinate duct installation with the requirements of Division 23 Section, “Vibration Controls for HVAC, Plumbing & Fire Protection Equipment”.

H. Install in accordance with manufacturer’s instructions.

I. Install and seal ducts in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible.

J. Duct Sizes are inside clear dimensions. For lined ducts, maintain sizes inside lining.

K. Provide openings in ductwork where required to accommodate thermometers and controllers. Provide pitot tube openings where required for testing of systems, complete with metal can with spring device or screw to ensure against air leakage. Where openings are provided in insulated ductwork, install insulation material inside a metal ring.

L. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.

M. Use crimp joints, with or without bead, for joining round duct sizes eight (8) inches and smaller with crimp in direction of air flow.

N. Use double nuts and lock washers on threaded rod supports.

O. Set plenum doors 6 to 12 inches (150 to 300 mm) above floor. Arrange door swings so that fan static pressure holds door in closed position.

P. During construction, provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork systems. Also provide temporary closures of metal or taped polyethylene at all air handling equipment openings to prevent dust from entering equipment openings.

Q. Paint behind all air devices, louvers, and open end ducts with 2 coats of flat black paint.

3.2 ACCESSORY INSTALLATION REQUIREMENTS

A. Install accessories in accordance with manufacturer's instruction, NFPA 90A, and SMACNA HVAC Duct Construction Standards - Metal and Flexible. Also provide temporary closures of metal or taped polyethylene at all air handling equipment openings to prevent dust from entering equipment openings.

B. Provide duct access doors for inspection and cleaning before and after filters, coils, fans, automatic dampers, at fire dampers, duct-mounted equipment, duct coils, and elsewhere as indicated. Provide minimum 10 x 10 inch size for hand access and 18 x 18 inch size for shoulder access. Review locations prior to fabrication.

C. Provide duct test holes where required for testing and balancing purposes. Review locations with Test and Balance Engineer prior to installation.

D. For all motor operated dampers, mark the shaft so operators know the position of the damper.

E. Provide fire dampers at locations indicated, where ducts and outlets pass through fire-rated components, and where required by authorities having jurisdiction. Install with required perimeter mounting angles, sleeves, breakaway duct connections, corrosion-resistant springs, bearings, bushings and hinges.

F. Demonstrate re-setting of fire dampers to Owner's representative.

G. Provide flexible connections immediately adjacent to equipment in ducts associated with fans and motorized equipment and supported by vibration isolators. Refer to Division 23 Section, "Vibration Control for HVAC and Plumbing Systems".

H. Provide balancing dampers at points on supply, return, and exhaust systems where branches are taken from larger ducts as required for air balancing. Install minimum duct widths from duct take-off.

I. Use splitter dampers only where indicated.

J. Provide balancing dampers on duct take-off to diffusers, grilles, and registers, regardless of whether dampers are specified as part of the diffuser, grille, or register assembly.

K. Install diffusers, registers, and grilles to ductwork with airtight construction.

L. Check location of all air outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangements.

M. Install duct thermometer support flanges in wall of duct. Attach to duct with screws. Locate duct mounted thermometers, minimum 10 feet downstream of mixing dampers, coils or other devices causing air turbulence.

N. Install remote - reading duct dial thermometers in control panels with tubing connecting panel and thermometer bulb supported to prevent kinks. Use minimum tubing length. Mount control panel 60 inches above finished floor and label each dial thermometer.

O. Install duct accessories according to applicable details shown in SMACNA's HVAC Duct Construction Standards Metal and Flexible for metal ducts.

P. Install volume dampers in lined duct; avoid damage to and erosion of duct liner.

Q. Provide test holes at fan inlet and outlet and elsewhere as indicated.

R. Install fire dampers according to manufacturer's UL approved written instructions.

1. Install fusible links in fire dampers. Label access doors according to equipment served.

S. Adjust duct accessories for proper settings.

T. Coordinate the locations of all cable operational volume damper operation stations with ducted mounted volume dampers. For stations label all cable operations as to the volume damper served. Cover plates shall be finished in a color to match ceiling per the Architect.

3.3 DUCT LINING INSTALLATION REQUIREMENTS

A. All portions of duct designated to receive duct liner shall be completely covered with duct liner. Transverse joints shall be neatly butted and there shall be no interruptions or gaps. The black pigmented or mat faced surface of the duct liner shall face the airstream.

B. Duct liner shall be adhered to the sheet metal. with 90 percent coverage of adhesive complying with requirements of ASTM C916. All exposed leading edges and transverse joints shall be factory coated or coated with adhesive during fabrication. Install perforated galvanized inner liner where indicated

C. Duct liner shall be additionally secured with mechanical fasteners, either weld-secured or impact-driven, which shall compress the duct liner sufficiently to hold it firmly in place. Adhesive bonded pins are not permitted due to long term adhesive aging characteristics. Spacing of mechanical fasteners with respect to duct liner interior width shall be in accordance with SMACNA HVAC DGS. Maximum spacing for mechanical fasteners shall be as follows:

Velocity = 0 to 2,500 feet per minute (0 to 12.8m/s):	
From transverse end of liner	3: (75mm)
Across width of duct	12 inches (300 mm) O.C.
From corners of duct	4 inches (100mm)
Along length of duct	18 inches (450mm) O.C.

D. Acoustical Duct Liner shall be cut to assure overlapping and compressed longitudinal corner joints.

E. Upon completion of installation of duct liner and before operation is to commence, visually inspect the system and verify that the duct liner insulation has been correctly installed.

F. Open all system dampers and turn on fans to blow all scraps and other loose pieces of material out of the duct system. Allow for a means of removal of such material.

G. Check the duct system to ensure that there are no air leaks through joints.

3.4 CLEANING

A. Clean duct system and force air at high velocity through ducts to remove accumulated dust. To obtain sufficient air, clean half the system at a time. Protect equipment which may be harmed by excessive dirt with temporary filters, or bypass during cleaning.

B. Clean duct systems with high power vacuum machines. Protect equipment which may be harmed by excessive dirt with filters, or bypass during cleaning. Provide adequate access into ductwork for cleaning purposes.

C. Ductwork shall be cleaned in accordance with “Duct Cleanliness for New Construction (SMACNA 2000)”, and shall achieve a “Basic” cleanliness level.

3.5 LEAKAGE TESTS

A. All low pressure sheet metal ductwork shall undergo leakage tests at 2 inch W.G. Tests shall be accomplished under this section and witnessed as specified under

Division 23 Section, “Testing, Adjusting, and Balancing for HVAC and Plumbing”.

B. All medium pressure sheet metal ductwork shall undergo leakage tests at 5 inch W.G. Tests shall be accomplished under this section and witnessed as specified under Division 23 Section, “Testing, Adjusting, and Balancing for HVAC and Plumbing”.

C. Leakage from each duct system shall not exceed 5 percent for low pressure systems and 1 percent for medium pressure systems of the normal air handling capacity of the system. If the system ductwork is tested in sections, the leakage shall not exceed ½ of 1 percent of the CFM to be handled by that section, and the total leakage of the system shall not exceed 1 percent of the total system CFM. Test pressure shall not exceed the pressure limits of the duct construction as defined in SMACNA High Pressure Duct Construction Standards. Repair all leaks which are audible, regardless of the leakage rate of the duct system as a whole, by remaking the entire defective joint or seam. Spot sealing of ducts in place will not be acceptable.

D. All duct accessories, including but not limited to volume dampers, ATC sensors, motor operated dampers, duct access doors, duct smoke detectors, and duct coils shall be installed prior to duct leakage testing.

E. Submit a complete report of the ductwork leakage tests to the Architect and include final approved copies in test and balance reports.

3.6 DUCTWORK IDENTIFICATION

A. Degrease and clean surfaces to receive adhesive for identification materials.

B. All ductwork shall be identified with painted background marked with the name of the service with arrows to indicate flow direction. Color Code and System Identification shall comply with ANSI Standards.

C. Marking shall be plain block letters, stenciled on ductwork (above and below ceilings) and shall be located near each branch connection and at least every ten feet on straight runs of ductwork. Where ductwork is aligned adjacent to each other, markings shall be neatly lined up. All markings shall be located in such a manner as to be easily legible from the floor.

D. Identify ductwork with plastic nameplates or stenciled painting. Identify with air handling unit/fan identification and area served.

E. Length of fan color field for ductwork shall be 32 inches. Lettering shall be minimum 3-1/2 inches high.

END OF SECTION 233000

SECTION 26 05 01
COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 GENERAL

A. Provide all labor, materials, equipment and services necessary for and incidental to the complete installation and operation of all electrical work.

B. All work under this Division is subject to the General Conditions and Special Requirements for the entire contract.

C. Unless otherwise specified, all shop drawings and submissions required under Division 26 shall be made to, and acceptances and approvals made by, the ENGINEER.

D. Conform to the requirements of all rules, regulations, and codes of local, state, and federal authorities having jurisdiction. Conform to the National Electrical Code and all NECA – National Electrical Installation Standards (NEIS).

E. Perform the work in a first-class, substantial, and workmanlike manner. Any materials installed which do not present an orderly and neat workmanlike appearance shall be removed and replaced when so directed by the Engineer, at the Contractor's expense.

F. Coordinate the work of all trades.

G. Arrange conduit, wiring, equipment, and other work generally as shown, providing proper clearances and access. Carefully examine all contract drawings and fit the work in each location without substantial alteration. Where departures are proposed because of field conditions or other causes, prepare and submit detailed drawings for approval in accordance with “Submittals” specified below. The right is reserved to make reasonable changes in location of equipment, conduit, and wiring up to the time of rough-in or fabrication.

H. The contract drawings are generally diagrammatic and all offsets, bends, fittings, and accessories are not necessarily shown. Provide all such items as may be required to fit the work to the conditions.

I. Be responsible for all construction means, methods, techniques, procedures, and phasing sequences used in the work. Furnish all tools, equipment and materials necessary to properly perform the work in a first class, substantial, and workmanlike manner, in accordance with the full intent and meaning of the Contract Documents.

J. The Contractor shall provide other work and services not otherwise included in the Contract Documents that are customarily forwarded in accordance with generally-accepted construction practices.

1.2 PERMITS, INSPECTIONS, AND FEES

A. The Contractor shall obtain and pay for all charges and fees, and deliver all permits, licenses, certificates of inspection, etc., required by the authorities having jurisdiction. Deliver inspection, approval, and other certificates to the Owner prior to final acceptance of the work.

B. File necessary plans, prepare documents, give proper notices, and obtain necessary approvals.

C. Permits and fees shall comply with the General Requirements of the Specification.

D. Notify Inspection Authorities to schedule inspections of work. All work shall be subject to field inspections.

E. Notify Engineer in advance of scheduled inspections.

F. An electrical foreman, superintendent or other supervisor shall be in attendance for all scheduled inspections.

G. The Contractor shall provide an electrical certificate from an independent electrical inspection agency approved by the Owner and the State of Delaware Fire Marshal. The Contractor shall submit certificate prior to final payment invoice. The Contractor shall pay all fees, including filing fees.

1.3 ELECTRICAL WORK UNDER OTHER DIVISIONS

A. Mechanical Equipment and Systems

1. In general, power wiring and motor starting equipment for mechanical equipment and systems are furnished and installed under Electrical Division 26.
2. Certain mechanical units contain starters, contacts, transformers, fuses, wiring, etc., required for fans, pumps, etc., furnished with the equipment from the factory. When this equipment is supplied from the factory, the Contractor must supply power circuit(s) to the unit and a disconnecting means. Coordinate with Contractor so that one, and only one, set of starters, fuses, switches, etc., is provided and installed.
3. In general, control and interlock equipment for HVAC systems (including associated wiring, conduit, transformers, relays, contacts, etc.) is furnished under Mechanical Divisions. Contractor shall install and connect all such equipment as necessary.
4. Controls, wiring, conduit, transformers, etc., for smoke, fire, and motor-operated dampers are provided by Mechanical. Electrical shall install and connect all such equipment.

B. Architectural Equipment: In general, any electrically operated or controlled equipment furnished under architectural divisions shall be supplied with control

wiring, transformers, contacts, etc. Contractor shall provide power circuits to such equipment and install all electrical control equipment related thereto.

C. Carefully review the contract documents and coordinate the electrical work under the various Divisions.

1.4 CONTRACTOR QUALIFICATION

A. Any Contractor performing work under this Division shall be fully qualified and acceptable to the Engineer. Submit the following evidence for approval:

1. A list of not less than five (5) comparable projects that the Contractor completed.
2. Letters of reference from not less than three (3) registered professional engineers, contractors, or building owners, explaining Contractor proficiency, quality of work, or other attribute on projects of similar size or substance.
3. Local or State license.
4. Membership in trade or professional organization where required.
5. Copy of Master Electrician’s License.

B. Contractor is any individual, partnership, corporation, or firm performing work by Contract or subcontract on this project.

C. Acceptance of a subcontractor will not relieve the Contractor of any contractual requirements or his responsibility to supervise and coordinate the various trades.

D. Supervisory Qualifications: The electrical work on the project shall be under the direct supervision of a licensed Master Electrician.

E. Qualifications of Installers:

1. For the actual fabrication, installation, and testing of the work, the Contractor shall use only thoroughly trained and experienced personnel who are completely familiar with the requirements of this work and with the installation recommendations of the manufacturers of the specified items.
2. The Electrical Installer shall utilize a full time project foreman in charge of all electrical work. This person shall be fully qualified and experienced in such work and shall be available, on site, at all times during Construction. All problems, questions, coordination, etc., relating to electrical work shall take place through this person to the Architect.

1.5 FIRE SAFE MATERIALS

A. Unless otherwise indicated, materials and equipment shall conform to UL, NFPA, or ASTM Standards for Fire Safety with Smoke and Fire Hazard Rating not exceeding flame spread of 25 and smoke developed of 50.

1.6 REFERENCED STANDARDS, CODES, ORDINANCES AND SPECIFICATIONS

A. Specifications, Codes and Standards listed below are included as part of this specification, latest edition.

CODE	CODE DESCRIPTION
ADA	Americans with Disabilities Act
ANSI	American National Standards Institute
ASHRAE	American Society of Heating, Refrigerating and Air Conditioning Engineers
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
IBC	International Building Code
CABO	Council of American Building Officials
FM	Factory Mutual
IEEE	Institute of Electrical and Electronics Engineers
NEC	National Electrical Code
NECA	National Electrical Contractors Association
NEMA	National Electrical Manufacturers Association
NFPA	National Fire Protection Association
OSHA	Occupational Safety & Health Administration
UL	Underwriters Laboratories
	Applicable State and Local Codes

B. All electrical equipment and materials shall comply with the Codes and Standards listed in the latest edition of IEEE Standard 241, Electric Power Systems in Commercial Buildings, Chapter 1, Section 1.6, entitled “Codes and Standards”.

C. Comply with all Codes applicable to the work:

1. Bidders shall inform themselves of all local and state codes and regulations.

2. In case of conflict between Contract Documents and governing Codes, the most stringent shall take precedence. Where, in any specific case, different sections of any applicable codes or when Drawings and Specifications specify different materials, methods of Construction, or other requirements, the most restrictive shall govern.
3. Where Contract Documents exceed minimum Code requirements, and are permitted under the Code, the Contract Documents take precedence and shall govern.
4. No extra payment will be allowed for work or changes required by local Code enforcement authorities.

D. Underwriters Laboratories Labels shall apply to all materials and devices, etc., except specified items not covered by existing UL Standards.

E. Conflicts with applicable regulations:

1. Resolve at Contractor's expense.
2. Prepare and submit details of alternate construction:

a. Acceptable solution of conflict.
b. List of substitute materials:

For approval of inspecting authorities.
For approval of Engineer.

F. Comply with all NECA's National Electrical Installation Standards (NEIS), including NECA 1-2000 "Standard Practices for Good Workmanship in Electrical Contracting".

1.7 INTERPRETATION OF DOCUMENTS

A. Any discrepancies between Drawings, Specifications, Drawings and Specifications, or within Drawing and Specifications shall be promptly brought to the attention of the Owner during the bidding period. No allowance shall subsequently be made to the Contractor by reason of his failure to have brought said discrepancies to the attention of the Owner during the bidding period or of any error on the Contractor's part.

B. The locations of products shown on Drawings are approximate. The Contractor shall place the devices to eliminate all interference with above-ceiling ducts, piping, etc. Where any doubt exists, the exact location shall be determined by the Owner.

C. All general trades and existing conditions shall be checked before installing any outlets, power wiring, etc.

D. Equipment sizes shown on the Drawings are estimated. Before installing any wire or conduit, the Contractor shall obtain the exact equipment requirements and install wire, conduit, or other item of the correct size for the equipment actually installed. However, wire and conduit sizes shown on the Drawings shall be taken as a minimum and shall not be reduced without written approval from the Owner.

E. Where variances occur between the drawings and specifications or within either document itself, the item or arrangement of better quality, greater quality, or higher cost shall be included in the Contract Price. The Engineer will decide on the item and manner in which the work shall be installed.

F. Contract Drawings are generally diagrammatic and all offsets, fittings, transitions, and accessories are not necessarily shown. Furnish and install all such items as may be required to fit the work to the conditions encountered. Arrange conduits, equipment, and other work generally as shown on the Contract Drawings, providing proper clearance and access. Where departures are proposed because of field conditions or other causes, prepare and submit detailed Shop Drawings for approval in accordance with “submittals” specified below. The right is reserved to make reasonable changes in location of equipment, piping, and ductwork, up to the time of rough-in or fabrication.

G. Work not specifically outlined, but reasonably incidental to the completion of the work, shall be included without additional compensation from the Owner.

1.8 COORDINATION

A. Coordinate arrangement, mounting, and support of electrical equipment:

1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
3. To allow right of way for piping and conduit installed at required slope.
4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.

B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.

C. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT

A. Material and equipment installed as a part of the permanent installation shall be new, unless otherwise indicated or specified, and shall be approved by the Underwriters' Laboratories, Inc., for installation in each particular case where standards have been established.

B. Where material or equipment is identified by proprietary name, model number, and/or manufacturer, furnish the named item or equivalent thereof, subject to acceptance.

C. Material submissions shall conform to requirements outlined in SUBMITTALS, REVIEW, AND ACCEPTANCE.

D. The suitability of named item only has been verified. Where more than one Manufacturer is named, only the first named Manufacturer has been verified as suitable. Manufacturers and items other than the first named shall be equal or better in quality and performance to that of specified items, and must be suitable for available space, required arrangement, and application. The Contractor, by providing other than the first named Manufacturer, assumes responsibility for all necessary adjustments and modifications necessary for a satisfactory installation.

E. The Contractor shall only submit those manufacturers indicated in the Specification. Proposed alternate manufacturers will not be considered unless the specific item indicates “or as approved equal”. Submit all data necessary to determine suitability of substituted items for approval.

F. All items of equipment furnished shall have a service record of at least five (5) years.

2.2 SUBSTITUTIONS

A. Substituted items or items other than those named shall be equal or better in quality and performance and must be suitable for the available space, required arrangement, and application. Submit any and all data necessary to determine the suitability of substituted items. The Contractor shall be responsible for correct application, placement, and installation of substituted equipment. Cost savings data shall also be submitted with submittal data for substituted items. Total cost savings or a per-unit saving to the Owner shall be clearly indicated. If a substituted item is accepted, all cost savings shall be returned to the Owner as a credit.

B. Substitutions will not be permitted for specific items of material or equipment where specifically indicated.

C. For substituted items, clearly list on the first page of the submittal all differences between the specified item and the proposed item. The Contractor shall be responsible for corrective action (or replacement with the specified item) while maintaining the specification requirements if differences have not been clearly indicated in the submittal.

D. Where the Contractor proposes to use an item of equipment or application other than that specified or detailed on the Drawings, which requires any redesign of the structure, partitions, foundation, HVAC, piping, wiring, or any other part of the mechanical, electrical, or architectural layout, all such redesign and all new drawings and detailing required thereafter shall be prepared by the Contractor at his own

expense for review by the Owner representative before any such work is implemented.

E. All Contractor-proposed changes and revisions shall be at the Contractor's risk and expense. The Contractor shall fully coordinate all revisions, substitutions and changes with other trades. The Contractor shall provide all necessary provisions, including HVAC, ventilation, foundations, access, etc., for a complete, code compliant, and fully functional installation.

F. Where the Contractor elects to submit a substitution for equipment or materials, he shall:

1. Submit Shop Drawings that show complete compliance to each statement or requirement of the Specifications.
2. Submit certified test data from an independent testing laboratory for each product.
3. Submit one complete working sample of the equipment or materials to be furnished. In cases involving large or heavy items of equipment, the Owner may waive the requirement to submit the sample.

G. Failure to comply with the above-required submissions shall constitute an automatic rejection of the substitution.

2.3 SUBMITTALS, REVIEW, AND ACCEPTANCE

A. General:

1. The equipment, material, installation, workmanship, arrangement of work, final instruction, and final documentation is subject to review and acceptance. No substitution will be permitted after acceptance of equipment or materials except where such substitution is considered by the Engineer to be in the best interest of the Owner. Submit for review in clear and legible form the following documents:

   a. Material and Equipment List
   b. Descriptive Data
   c. Shop Drawings
   d. Installation and Coordination Drawings
   e. Contractor As-Built Drawings
   f. Owner Instructions and Manuals
   g. Construction Phasing and Outage Schedule

2. Prepare all submittals specifically for this project and stamp each submittal in a form indicating that the documents have been Contractor reviewed, are complete, and are in compliance with the requirements of the plans and specifications. Each submittal item shall be clearly identified and numbered. Each submittal shall contain a complete schedule of Manufacturer's part numbers and quantity listings of all supplied components. Each proposed

item shall be highlighted and tagged with a star, an arrow, etc., including all options and accessories.

3. Coordinate the installation requirements and any mechanical requirements for the equipment submitted. Submittals will be reviewed for general compliance with design concept in accordance with the contract documents. The Contractor is responsible for the correctness of all submittals. Reviews will not verify dimensions, quantities, or other details.
4. Identify all submittals, indicating the intended application, location, or service of the submitted item. Refer to specification sections or paragraphs where applicable. Clearly indicate the exact type, model number, size, and special features of the proposed item. Clearly list on the first page of the Submittal all differences between the specified item and the proposed item. The Contractor shall be responsible for corrective action (or replacement with the specified item) while maintaining the specification requirements, if differences have not been clearly indicated in the submittal. Submittals of a general nature will not be acceptable.
5. Submit actual operating conditions or characteristics for all equipment where required capacities are indicated. Factory order forms showing only required capacities will not be acceptable. Indicate all options used to meet the specifications. It is not the responsibility of the Engineer or Owner to make selections of factory options other than colors. Submittals lacking proper selection of factory options or special features required by the specification shall be RETURNED WITHOUT REVIEW.
6. Acceptance will not constitute waiver of contract requirements unless deviations are specifically indicated and clearly noted.
7. Documents of general form indicating options shall be clearly marked to show what is specifically proposed for this project.
8. Submittals NOT IN COMPLIANCE with the requirements of this section will be RETURNED WITHOUT REVIEW.

B. Material, Equipment, Manufacturer and Subcontractor List: Within 30 calendar days after the award of contract, submit a complete MATERIAL, EQUIPMENT, MANUFACTURER AND SUBCONTRACTOR LIST for preliminary review. List all proposed materials and equipment, the associated proposed Manufacturer, and any proposed subcontractors. After the receipt of reviewed Material and Equipment List, submit complete Shop Drawings for approval. List all materials and equipment, indicating manufacturer, type, class, model, curves, and other general identifying information. Submittals shall be specific for each building as contained in the individual building Specifications and Drawings.

C. Upon approval of the List of Materials, the Contractor shall prepare a complete Master Submittal Register, listing all products and materials that will be submitted for approval. Items shall be listed by referenced specification paragraph in ascending order. This master list shall be included with each submittal, updated to reflect the status of approval for each item, and shall highlight the items pertaining to the submittal. A suggested Submittal Register Format is shown below:

D.

SUBMITTAL REGISTER					
Item/Material	Ref'd Spec. Paragraph	Specified or Substitute	Submittal Date	Status	Remarks

D. No Shop Drawing Submittals will be considered for approval until the complete List of Subcontractors and the complete List of Materials/Manufacturers and Equipment have been approved.

E. Descriptive Data: After acceptance of the MATERIAL and EQUIPMENT LIST, submit additional DESCRIPTIVE DATA for all items. Data shall consist of specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, installation instructions, and any other information necessary to indicate complete compliance with the contract documents. Where several ratings or sizes are shown or available, clearly indicate the exact size or rating relating to the particular device being proposed.

F. Submit complete descriptive data for all items. Data shall consist of Specifications, data sheets, samples, capacity ratings, performance curves, operating characteristics, catalog cuts, dimensional drawings, wiring diagrams, specific electrical/wiring requirements and connections including control and interlock wiring, installation instructions, and any other information necessary to indicate complete compliance with the Contract Documents. Edit submittal data specifically for application to this project.

G. Shop Drawings shall be submitted and approved for all materials and equipment prior to installation. If any material and/or equipment is installed prior to receipt by the Contractor of approved Shop Drawings, the Contractor is liable for its replacement at no additional cost to the Owner.

H. Data submitted shall include information on all materials and equipment to demonstrate compliance with the Contract Drawings and Specifications. Where installation procedures or any part thereof are required to be in accordance with manufacturer's recommendations, furnish printed copies of the recommendations prior to installation. Installation of the item shall not proceed until recommendations are received. Failure to furnish recommendations shall be cause for rejection of the equipment or material.

I. Any deviation of submitted material or equipment from the Contract Drawings or Specifications shall be clearly marked in red ink on Submittals, and itemized in a transmittal letter, in order to receive consideration for approval.

J. Approval of material or equipment submittals containing deviations not specifically identified by Contractor shall not relieve the Contractor from compliance with specified requirements.

K. All major items of mechanical equipment shall be the latest standard catalog products of reputable manufacturers. Where two (2) or more items of the same kind of equipment are required, they shall be the products of a single manufacturer.

L. Thoroughly review and stamp all submittals to indicate compliance with Contract requirements prior to submission. Coordinate installation requirements and any electrical requirements for equipment submitted. Contractor shall be responsible for correctness of all submittals.

M. Submittals will be reviewed for general compliance with design concept in accordance with Contract Documents, but dimensions, quantities, or other details will not be verified.

N. Increase, by the quantity listed below, the number of electrical related Shop Drawings, product data, and samples submitted, to allow for required distribution plus two copies of each submittal required, which will be retained by the Electrical Consulting Engineer.

1. Shop Drawings - Initial Submittal: 1 additional blue- or black-line print.
2. Shop Drawings - Final Submittal: 1 additional blue- or black-line print.
3. Product Data: 1 additional copy of each item.

O. Additional copies may be required by individual sections of these Specifications.

P. Shop Drawings:

1. Prepare and submit SHOP DRAWINGS AND/OR DIAGRAMS for all specially fabricated items, modifications to standard items, specially designed systems where detailed design is not shown on the contract drawings, or where the proposed installation differs from that shown on the contract drawings.

2. Shop drawings shall include plans, elevations, sections, mounting details of component parts, point to point interconnection diagrams, elementary diagrams, single line diagrams, and any other drawings necessary to show the fabrication and connection of the complete item or system.

3. Shop drawings shall be provided for, but not limited to the following items:

Basic Electrical Materials
Cable - 600 volt
Circuit Breakers
Conduit and Surface Raceway
Contractor and Subcontractor Qualifications
Controllers & Control Devices

Electrical Connection Coordination Schedule
Equipment Connections
Fire Alarm System
Firestopping
Fuses
Ground Conductors
Identification System
Lighting Control System
Lighting Fixtures
Material and Equipment List
Outlet Boxes
Receptacles
Record and Information Booklet
Safety Switches
Schedule of Values
Sleeves, Hangers, Supports
Submittal Schedule
Telecommunications Systems
Tests and Reports
Wiring Devices
Wiring Diagrams

Q. The Contractor, additionally, shall submit for approval any other shop drawings as required by the Engineer. No item listed above shall be delivered to the site, or installed, until approved. After the proposed materials have been approved, no substitution will be permitted except where approved by the Engineer.

R. The Contractor shall prepare and submit a Detail Schedule of Values indicating the Contract costs for the major work items. The Contractor shall provide additional detail and information as requested by the Engineer.

S. The Contractor shall prepare and submit a complete Submittal Schedule. The Schedule shall include a listing of all Submittals, Shop Drawings, and Coordination Drawings.

2.4 RECORD DRAWINGS

A. As the work progresses, record on a set of white prints the installed locations, sizes of electric feeders, equipment, etc. Upon completion of the work, submit one (1) complete set of white prints with "As-Built" information neatly recorded thereon in red ink. Use other colors to distinguish between variations in separate categories of the work. Note related change-order numbers where applicable.

B. Write step-by-step detailed instructions for turn-on, turn-off, seasonal changeover, and periodic checks of all systems and equipment. Include all precautions and warnings.

C. Prepare a list of the manufacturers of all major equipment, their local service representative and procedures for obtaining service.

D. Post one (1) copy of all instructions, lists, charts, and diagrams at the equipment or where indicated, mounted under glass or approved plastic cover.

E. Furnish to the Owner two (2) copies of the Manufacturer's installation and operations instructions. Include replacement parts lists where applicable. Also include copies of all posted instructions, lists and charts. Assemble the material in one or more heavy duty 8- 1/2" x 11" loose leaf binders with tab separators. Submit for approval before final delivery. Binder shall be labeled on spine and on cover with Project Name.

F. Deliver all instruction materials to the Owner prior to the formal instruction period.

G. Deliver two (2) complete sets of all approved submittals to the Owner for filing.

H. Prepare record documents in accordance with the requirements in the specifications. In addition to the requirements specified, indicate installed conditions for:

1. Major raceway systems, size and location, for both exterior and interior; locations of control devices; distribution and branch electrical circuitry; and circuit breaker size and arrangements.
2. Approved Substitutions, Contract Modifications, and actual equipment and materials installed.

I. The Contractor shall keep at the site at all times during construction, one set of up-to-date Contract prints for the express purpose of showing any and all changes made during construction. The Contractor shall make the prints showing each change and shall incorporate all changes in “Record/As-Built Drawings” to be submitted to the Engineer upon completion of the project.

J. The Contractor shall show proof of up-to-date record drawings to the Owner prior to submitting monthly invoice.

K. The Contractor shall conform to all drawings, including all revisions, addendums, alternates, change orders, deletions, existing conditions, and as-built conditions without extra cost to the Owner.

2.5 DEMONSTRATION AND OPERATING INSTRUCTIONS

A. Furnish the necessary technicians, skilled workers, and helpers to operate the electrical systems and equipment of the entire project. The Contractor shall provide a minimum of eight (8) hours of system demonstration and eight (8) hours of system operation for each system.

B. Where specified in technical sections, provide longer periods required for specialized equipment.

C. Contractor shall provide start-up of all systems in an orderly, organized, and coordinated manner to ensure that all systems are functioning as designed. The Contractor shall provide a detailed start-up, testing, and demonstration plan for all systems in a coordinated manner that is documented in writing at least 45 days prior to system start-up. Start-up, testing and demonstration plans shall include detailed point-by-point checklists that clearly show that systems are, in fact, functioning as designed. Instruct the Owner or designated personnel in operation, maintenance, lubrication, and adjustment of systems and equipment.

D. The Operating and Maintenance Manual shall be available at the time of the instructions, for use by Instructors and Owner personnel.

E. Videotape each instruction session, including both the sessions specified above and added sessions required in technical sections for specialized equipment. Provide one complete set of DVD video disks with each Operating and Maintenance Manual.

F. Schedule the general and specialized instruction periods for a time agreed upon by he Owner and Engineer. All operation training and demonstrations shall be complete prior to Owner acceptance of any given system.

2.6 SLEEVES FOR RACEWAYS AND CABLES

A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.

B. Sleeves for Rectangular Openings: Galvanized sheet steel.

1. Minimum Metal Thickness:

a. For sleeve cross-section rectangle perimeter less than 50 inches (1270 mm) and no side more than 16 inches (400 mm), thickness shall be 0.052 inch (1.3 mm).
b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches (1270 mm) and 1 or more sides equal to, or more than, 16 inches (400 mm), thickness shall be 0.138 inch (3.5 mm).

2.7 SLEEVE SEALS

A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.

1. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:

a. Advance Products & Systems, Inc.
b. Calpico, Inc.
c. Metraflex Co.
d. Pipeline Seal and Insulator, Inc.

2. Sealing Elements: EPDM interlocking links shaped to fit surface of cable or conduit. Include type and number required for material and size of raceway or cable.
3. Pressure Plates: Carbon steel. Include two for each sealing element.
4. Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.8 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

PART 3 - EXECUTION

3.1 EXAMINATION OF SITE, SURVEYS, AND MEASUREMENTS

A. Examine the site, determine all conditions and circumstances under which the work must be performed, and make all necessary allowances for same. No additional cost to the Owner shall be permitted for Contractor’s failure to do so.

B. Examine the site and observe the conditions under which the work will be done or other circumstances which will affect the contemplated work. Special attention shall be given to areas where work is to be done in existing buildings. No allowance will be made subsequently in this connection for any error or negligence on the Contractor's part.

C. The Contractor shall base all measurements, both horizontal and vertical, from established benchmarks. All work shall agree with these established lines and levels. Verify all measurements at the site and check the correctness of same as related to the work.

D. Any discovery of discrepancy between actual measurements and those indicated which prevents following good practice or the intent of the Drawings and Specifications shall be brought to the attention of the Owner’s Representative. Work shall not proceed until receiving instructions from the Owner’s Representative.

E. The Contractor shall follow Drawings in laying out the work and check Drawings of other trades to verify spaces in which work will be installed. Maintain maximum headroom and space conditions at all points. Where headroom or space conditions appear inadequate, the Owner’s Representative shall be notified before proceeding with the installation.

F. To prevent conflict with the work of other trades and for proper execution of the work, the Contractor, as directed by the Owner's Representative, shall make the necessary modifications in the layout as needed, at no extra charge to the Owner.

G. The Contractor shall be solely responsible for the proper arrangement of his conduit and equipment.

H. The Engineer shall make all final decisions as to any conditions that require the changing of any work.

I. The Contractor shall have competent supervision on the site at all times to lay out, check, coordinate, and supervise the installation of all electrical work and be responsible for the accuracy thereof. He shall plan the installation of all electrical work, giving consideration to the work of other trades, to prevent interference.

J. The Contractor shall determine the location, size, etc., of all chases, sleeve openings, etc., required for the proper installation of the electrical work and see that such are provided. All chases, sleeves, openings, etc., shall be set prior to erection of new work to prevent delay in the progress of other work or trades.

K. Conditions and/or situations that prevent the proper installation of any equipment or item where shown on the Drawings shall be called to the attention of the Engineer for instructions.

L. The Contractor shall have equipment shipped or fabricated in sections of suitable size for entering the building and being removed from the finished building in the future, if necessary.

M. The Contractor shall fully investigate all peculiarities and space limitations for all materials and equipment.

N. Outlet, pull, and junction boxes and other appliances that require operation, examination, adjustment, servicing or maintenance shall be readily accessible.

O. The Contractor shall take all field measurements necessary for this work and shall assume responsibility for their accuracy.

P. The Contractor shall coordinate the electrical work with all other sub-contractors. All work shall be so arranged that there will be no delay in the proper installation and completion of any part or parts of electrical equipment. All electrical work shall be installed in proper sequence with other trades without any unnecessary delay.

Q. The Drawings are to some extent diagrammatic and indicate the general arrangement of the equipment, the runs of conduit, and the manner of connection.

R. The Contractor shall confer with all sub-contractors engaged in the construction of the project, regarding the work that may, in any way, affect his installation. Whenever interference occurs, before installing any of the work in question, the Contractor shall consult with all sub-contractors and shall come to an agreement with them as to the exact location and level of his conduit parts of his equipment.

3.2 GENERAL RESPONSIBILITIES

A. The Contractor shall be responsible for systems and related damages possible, and shall hold harmless the Owner, the Architect and his consultants from malfunction of systems and equipment installed under this Contract as defined in the laws of the State of Delaware pertaining to real property for the period of time as defined by such laws.

B. It is the intent of these Specifications to fully cover without exception all required labor and materials so that the finished work will be delivered to the Owner in a complete and satisfactory working installation. Excavation, wiring, distribution, etc., shall be performed in compliance with the Contract Documents.

C. Work not specifically outlined, but reasonably incidental to the completion of the work, shall be included without additional compensation from the Owner.

D. Conflicting points in the Specifications or on the Drawings shall be called to the attention of the Architect prior to the execution of the Contract.

3.3 STORAGE AND PROTECTION OF EQUIPMENT

A. All electrical equipment to be used in the construction shall be properly stored and protected against the elements. All equipment shall be stored under cover, and shall not be stored at the construction site on the ground, in mud, water, snow, rain, sleet or dust. Large diameter cables may be stored on reels with weatherproof materials. Such weatherproof materials shall be heavy-duty, securely fastened and made impervious to the elements.

B. Conventional electrical construction materials such as building wire, outlet and junction boxes, wiring devices, conduit, lighting fixtures, fittings, etc., shall be stored in construction buildings, covered trailers or portable covered warehouses. Any equipment subject to damage or corrosion from excessive moisture shall be stored in dry, heated areas. Any equipment containing plastic or material subject to damage caused by excessive heat or sunlight shall be stored to prevent such damage. This includes plastic ducts and lenses.

C. Motor controllers, breakers, emergency lighting, and supervisory equipment, if delivered to the construction site before the building is under cover, shall be warehoused and protected as follows: All gear and equipment shall be covered and protected from the elements and other damage and shall be stored in a clean, dry, heated atmosphere, under cover.

D. All gear and equipment delivered to the construction site after the building is under cover shall be protected as described above and in addition shall be provided with auxiliary heat to prevent condensation damage. The gear shall also be protected against damage caused by installation of any building systems and equipment; or damage caused by carelessness of workmen who are installing equipment connected to or adjacent to the above electrical equipment.

E. Equipment damaged as a result of the above conditions shall be properly repaired at the Contractor's expense or shall be replaced at the Contractor's expense, if, in the opinion of the Engineer the equipment has been damaged to such an extent it cannot operate properly after repairs are made.

F. All electrical enclosures exposed to construction damages such as paint spots, spackling or plaster spatter, grout splashes, waterproofing compound, tar spots or runs and pipe covering compound splashes, shall be completely covered and protected against damage.

G. In the event leakage into the building of any foreign material or fluid occurs or may occur, the Contractor shall take all steps as described above to protect any and all equipment.

H. After connections to electrical equipment are complete and the equipment is ready for operation, all construction debris shall be removed from all enclosures. Such debris includes dust, dirt, wire clippings, tape and insulation removed in order to make the connection.

3.4 ELECTRICAL INSTALLATIONS

A. General: Sequence, coordinate, and integrate the various elements of electrical systems, materials, and equipment. Comply with the following requirements:

1. Coordinate electrical systems, equipment, materials, and installation with landscape/irrigation contractor(s).
2. Verify all dimensions by field measurements.
3. Install systems, materials, and equipment to conform with approved submittal data, including coordination drawings, to greatest extent possible. Conform to arrangements indicated by the Contract Documents, recognizing that portions of the Work are shown only in diagrammatic form. Where coordination requirements conflict with individual system requirements, refer conflict to the Engineer.
4. Install systems, materials, and equipment level and plumb, parallel and perpendicular to other building systems and components where installed exposed in finished spaces.
5. Install electrical equipment to facilitate servicing, maintenance, and repair or replacement of equipment components. As much as practical, connect equipment for ease of disconnecting, with minimum of interference with other installations. All equipment and disconnects shall maintain proper working space to conform to NEC.
6. Install systems, materials, and equipment giving right-of-way priority to systems that require installation at a specified slope.
7. Arrange for chases, slots and openings in other building components during progress of construction, to allow for electrical installation.
8. Space, coordinate, and integrate installations of electrical materials and equipment for efficient flow of the work.

3.5 SUPERVISION AND COORDINATION

A. Provide complete supervision, direction, scheduling and coordination of all work under the contract, including that of subcontractors, using full attention and the best skill. Be responsible for all work and make all subcontractors, suppliers and manufacturers fully aware of all requirements of the contract.

B. Coordinate the rough-in of all work performed under Divisions Mechanical and Electrical Divisions.

C. The Contractor shall coordinate all electrical rough-ins with approved shop drawings and coordination drawings. Any rough-in installed without complete coordination shall be at the Contractor's risk and expense.

D. Coordinate the installation of all necessary rough-in of work, sleeves, anchors and supports for conduit, wiring, and other work performed under Mechanical and Electrical Divisions. Coordinate Division 26 work with all trades.

E. Where a discrepancy exists within the Specifications or drawings or between the Specifications and Drawings, the more stringent (or costly) requirement shall apply until a clarification can be obtained from the Engineer. Failure to clarify such discrepancies with the Engineer will not relieve the Contractor of the responsibility of conforming to the requirements of the Contract.

F. Failure of the Contractor to obtain a full and complete set of Contract Documents (either before or after bidding) will not relieve the Contractor of the responsibility of complying with the intent of the Contract Documents.

G. To ensure proper electrical coordination between the electrical components supplied under the Electrical Divisions and the equipment supplied under the Mechanical Divisions, a schedule shall be submitted, prior to start of work, for review by the Engineer with the following column headings:

1.Equip or Item	2. HP or KVA	3.Voltage and Phase	4. Power Factor	5. Capacitor	6.Motor Starter	7.Disc on.	8.Controls	9.Remarks

Description of Column Headings:

1. List all the approved equipment furnished under Mechanical Division that requires electrical connections and designate the equipment as it appears in the Mechanical Divisions. Indicate the quantity, if more than one, in parentheses of identical equipment being supplied.
2. Indicate the supplied horsepower of the equipment listed under Column No. 1. If equipment listed has more than one motor, indicate each motor and its respective horsepower. Indicate the kVA rating for all other equipment requiring an electrical connection, unless the electrical connection is for a control circuit only.

3. Indicate the voltage and phase requirements for equipment listed under Column No. 1. If more than one electrical circuit or voltage is required for the listed equipment, it shall be so indicated. Indicate wiring required for connection, including all phase, neutral, and ground conductors.
4. Indicate the power factor rating for all motors listed under Column No. 2.
5. Where a capacitor is to be provided, indicate specification it is supplied under and indicate the KVAR size for any capacitor provided under Division 26.
6. Where a motor starter is required, indicate the specification division it is supplied under and the type of motor starter; across-the-line, reversible, variable speed, two speed-single winding, etc. Indicate in Column No. 9 if the motor starter provided under Division 26 is not compatible with the motor specified.
7. Where a disconnect switch is required by the National Electric Code or by the contract documents for the equipment listed under Column No. 1, indicate under which Division the disconnect switch is supplied.
8. Indicate the Division under which the controls for the equipment listed under Column No. 1 are provided.
9. Indicate any discrepancies between what is indicated in the contract documents and what is actually being provided.

H. The Contractor shall fully coordinate the electrical connections to all equipment prior to installations, with the approved Shop Drawings and the trades involved. Coordination shall include voltage, phases, quantity and size of wiring, device sizes, terminations, rough-in work, and other coordination for a complete installation.

I. Coordinate the spacing and arrangement of lighting fixtures, diffusers, grilles and access panels in ceilings to establish a symmetrical pattern.

J. Coordinate light switch locations with door swings prior to rough-in. No switches permitted behind doors.

K. Coordinate electrical work with architectural items and equipment. Typical equipment refers to, but is not limited to, the following:

1. Countertops, Casework and Cabinets.

L. This Contractor shall make all system connections required to equipment furnished and installed under other divisions. Connections shall be complete in all respects to render this equipment functional to its fullest intent. The Contractor shall make all system connections required to equipment furnished under other Divisions. Circuits shall be extended to all equipment which is incidental to, but not necessarily shown, for equipment specified under other divisions such as magnetic flow meters, ATC panels, liquid level controls, leak detection systems, etc. Connections shall be complete in all respects to render this equipment functional to its fullest extent.

M. Install work with proper clearances and access. Carefully examine all contract drawings and fit the work in each location without substantial alteration. Where departures are proposed or required, submit detailed drawings for acceptance. The

right is reserved to make reasonable changes in location of equipment, conduit and wiring up to the time of rough-in or fabrication.

N. It shall be the responsibility of the Contractor to obtain complete instructions for connections.

3.6 GUARANTEE

A. Guarantee obligations shall be as hereinbefore specified in the GENERAL AND SPECIAL CONDITIONS of these specifications, except as follows:

1. Guarantee the complete electrical system free from all mechanical and electrical defects for the period of two (2) years beginning from the day of final acceptance of the work by the Owner.
2. Also, during the guarantee period, be responsible for the proper adjustments of all systems, equipment and apparatus installed by the Contractor and do all work necessary to ensure efficient and proper functioning of the systems and equipment.
3. Upon receipt of notice from the Owner of failure of any part of the electrical installation during the guarantee period, new replacement parts shall be furnished and installed promptly at no cost.
4. Warranty From the Manufacturer: Contractor shall obtain all warranty papers and records from the Original Equipment Manufacturer according to their warranty policy and deliver the same to the Owner. Contractor shall fulfill all the Original Manufacturer's requirements to validate the warranty as offered by the Original Equipment Manufacturer.

B. Provide 24-hour service for any and all warranty problems experience in the operation of the equipment provided.

C. Any equipment or system in need of warranty work whether during regular hours or on an emergency basis, shall be immediately serviced and repaired. The warranty work and guarantee shall include all parts and labor and shall be furnished at no cost to the .

D. The Contractor shall guarantee to make good any and all defects in his work, exclusive of lamps, which may develop due to defective workmanship or materials, within one year from the date of final acceptance of the work by the Owner.

E. In addition to the warranty and correction of work obligations contained in the General and supplementary Conditions, correct the work of the system as embraced by the Specification, free from Mechanical and Electrical defects for the warranty.

F. During the warranty period, take responsibility for the proper adjustments of systems, equipment and apparatus installed and perform work necessary to ensure the efficient and proper functioning of the systems and equipment.

G. Certain items of equipment hereinafter specified shall be guaranteed for a longer time than the general warranty period. These guarantees shall be strictly adhered to and the Contractor shall be responsible for service or replacement required in connection with guarantee of these items. These guarantees shall commence on the same date as the final acceptance by the Engineer.

H. Submission of a bid proposal for this Project warrants that the Contractor has reviewed the Contract Documents and has found them free from ambiguities and sufficient for the construction and proper operation of systems installed for this project. If discrepancies are found, have them clarified by Addendum.

I. It is possible that certain areas of the building or certain systems will be accepted at a time different than as specified. The date of acceptance by the Architect for beneficial use of the Owner for these building areas or systems will be adjusted accordingly.

3.7 TEMPORARY FACILITIES

A. General: Refer to the Division 01 Sections for general requirements of temporary facilities.

B. Description: Furnish and install the necessary metering and distribution equipment for an adequate, 3-phase, 4-wire temporary electrical service and all temporary wiring and lighting, including step-down or step-up dry-type transformers as required. Exact requirements for temporary service will be determined by the General Contractor.

C. Attention is directed to the Occupational Safety and Health Act (OSHA), Americans with Disabilities Act (ADA) and National Electrical Code (NEC) requirements for electrical work on construction sites.

D. Materials:

1. One 20-ampere circuit with ground fault protection for each 7500 square feet of gross floor area per floor to which various trades may attach their cords.

E. Installation: Temporary lighting shall provide minimum foot candle levels for construction as follows:

AREA	FOOT CANDLE LEVEL
General construction area lighting, corridors, hallways and exit ways.	5

F. The Contractor shall pay for all energy charges for temporary service. Provide temporary construction power. Remove all temporary power installations and connections after permanent power is established and/or prior to completion of the project.

3.8 SCHEDULING OF WORK

A. The Contractor shall not be permitted to do any work in any area of any occupied building during normal hours, except in areas specifically assigned.

B. Coordination of work by the Contractor is essential such that power outages are kept to a minimum in quantity and duration. All required outages shall be approved by the Owner for optimum time scheduling. Written notice of not less than 15 calendar days shall precede all power outages.

3.9 DEMONSTRATION

A. As a part of this contract, the Contractor shall provide for the services of equipment manufacturers or their established representatives to demonstrate to selected maintenance personnel the correct operation, safety and maintenance of all electrical equipment under this contract.

3.10 PAINTING AND FINISHES

A. Provide protective finishes on all materials and equipment. Use coated or corrosion-resistant materials, hardware and fittings throughout the work. Paint bare, untreated ferrous surfaces with rust-inhibiting paint. All exterior components including supports, hangers, nuts, bolts, washers, vibration isolators, etc., shall be galvanized or stainless steel.

B. Clean surfaces prior to application of coatings, paint, or other finishes.

C. Provide factory-applied finishes where specified. Unless otherwise indicated factory-applied paints shall be baked enamel with proper pre-treatment.

D. Protect all finishes and restore any finishes damaged as a result of work under Division 26 to their original condition.

E. The preceding requirements apply to all work, whether exposed or concealed.

F. Remove all construction marking and writing from exposed equipment, conduit, and building surfaces. Do not paint manufacturer's labels or tags.

G. All exposed conduit, raceway, boxes, etc., shall be painted, except in electrical rooms, mechanical rooms, storage rooms, and crawl spaces. Colors shall be selected by the Architect and conform to ANSI Standards.

H. Submit color of factory-finished equipment for approval prior to ordering.

3.11 PROTECTION OF WORK

A. Protect work, material and equipment from weather and construction operations before and after installation. Properly store and handle all materials and equipment.

B. Cover temporary openings in conduit and equipment to prevent the entrance of water, dirt, debris, or other foreign matter.

C. Cover or otherwise protect all finishes.

D. Replace damaged materials, devices, finishes and equipment.

3.12 OPERATION OF EQUIPMENT

A. Clean all systems and equipment prior to initial operation for testing, retesting, or other purposes. Set, adjust, and test all equipment in accordance with manufacturer's instructions. Do not operate equipment unless all proper safety devices or controls are operational. Provide all maintenance and service for equipment that is authorized for operation during construction.

B. Where specified, or otherwise required, provide the services of the manufacturer's factory-trained servicemen or technicians to start up the equipment.

C. Do not use electrical systems for temporary services during construction unless authorized in writing by the Owner. Where such authorization is granted, temporary use of equipment shall in no way limit or otherwise affect warranties or guaranty period of the work.

D. Upon completion of work, clean and restore all equipment to new conditions; replace expendable items such as filters.

3.13 TESTING AND ADJUSTMENT

A. Perform all tests which are specified or required to demonstrate that the work is installed and operating properly. Where formal tests are required, give proper notices and perform all necessary preliminary tests to assure that the work is complete and ready for final test.

B. Adjust all systems, equipment and controls to operate in a safe, efficient and stable manner.

C. On all circuits, 600 volts or less, provide circuits that are free from ground faults, short circuits and open circuits.

D. Other tests of a specific nature for special equipment shall be as specified under the respective equipment.

3.14 IDENTIFICATIONS, ELECTRICAL DIAGRAMS AND OPERATING INSTRUCTIONS

A. Contractor shall submit for approval schematic diagrams of each electrical system installed in the building. Diagrams shall indicate device location, service, type, make, model number and the identification number of each device in the particular system. Following approval by all authorities, the diagrams shall be framed, mounted under glass and hung in each Main Equipment Room where directed. Contractor shall deliver the tracing or sepia from which the diagrams were reproduced to the Owner.

B. All equipment shall be plainly tagged.

C. All items of equipment, including motor starters, panels, etc., shall be furnished with white letters and numbers on black plastic identification plates or aluminum letters and numbers on black engraved aluminum identification plates. Lettering shall be a minimum of 1/4" high. Identification plates shall be securely affixed to each piece of equipment, starters, panels, etc., by screws or adhesive (Tuff-Bond #TB2 or as approved equal). Pressure sensitive tape backing is prohibited.

D. Provide three (3) copies of operating and maintenance instructions for all principal items of equipment furnished. This material shall be bound as a volume of the "Record and Information Booklet" as hereinafter specified.

E. Provide at least 24 hours of straight time instruction to the operating personnel. This instruction period shall consist of not less than three (3) consecutive 8-hour days. Time of instruction shall be designated by the Owner. Provide two DVD copies of all instructional periods/demonstrations.

3.15 RECORD DRAWINGS AND SPECIFICATIONS

A. Upon completion of the Electrical installations, the Contractor shall deliver to the Engineer one complete set of prints of the Electrical Contract Drawings which shall be legibly marked in red pencil to show all Addenda, approved Shop Drawings, Change Orders, changes and departures of the installation as compared with the original design. They shall be suitable for use in preparation of Record Drawings.

B. The Contractor shall provide a record specification including all Addenda and other modifications. Record substantial variations in actual work performed. Identify all substitutions.

3.16 RECORD AND INFORMATION BOOKLET

A. The Contractor shall have prepared three (3) copies of the Record and Information Booklet and deliver these copies of the booklet to the Owner. The booklet shall be as specified herein. The booklet must be approved and will not be accepted as final until so stamped.

B. The booklet shall be bound in a three-ring loose-leaf binder similar to "National" No. 3881 with the following title lettered on the front and on the spine of the binder: "Record and Information Booklet (insert name of the project)". No sheets larger than 8-1/2" x 11" shall be used, except sheets that may be neatly folded to 8-1/2" x 11" and used as a pull-out. An Index will include the section tabs for each subject included. If more than one binder is required, print covers and spines with Volume numbers. Include in the front of every binder an index to all binders.

1. Internally subdivide the binder contents with permanent page dividers, logically organized as described below; with tab titling clearly printed under reinforced laminated plastic tabs.
2. Contents: Prepare a Table of Contents for each volume, with each product or system description identified, typed on white paper.
3. Part 1: Directory, listing names, addresses, and telephone numbers of Electrical Engineers; Contractor; Electrical Subcontractors; and major Electrical equipment suppliers. Provide sales and service representative names and phone numbers of all equipment.
4. Part 2: Operation and Maintenance Instructions, arranged by Specification Section. For each category, identify names, addresses, and telephone numbers of Subcontractors and suppliers. Identify the following:

    a. Significant design criteria.
    b. List of equipment. Complete record of material list. Catalog brochures and product data for all components. Include all submittal comments, and corrected catalog data and shop drawings on each piece of equipment and each system.
    c. Parts list for each component, including recommended spare parts list. Include motor starter overload schedules.
    d. Operating instructions, including sequence of operation.

        1) Description of function, normal operating characteristics and limitations, engineering data and tests, and complete nomenclature and commercial numbers of replacement parts. Provide a description of each system installed.
        2) Manufacturer’s printed operating procedures to include start-up, break-in, and routine and normal operating instructions; control, stopping.

    e. Maintenance instructions for equipment and systems. Detailed checkout procedures to ensure operation of systems and gear, including recommended cleaning methods and materials and special precautions identifying detrimental agents.
    f. Servicing, diagnostic and troubleshooting instructions and procedures for systems and major equipment.
    g. Recommended preventative maintenance program, including a list of items requiring inspection and servicing. Provide Chart Form indicating time and type of routine and preventative maintenance of electrical equipment, etc. The chart shall also indicate tag number, model number of equipment, location and service.

1) For replacement items, indicate type, size and quantity of the replaceable items.
2) Provide lubrication schedule, including type, grade, temperature range and frequency.
3) Provide a list of each type of lighting fixture lamp used, lamp fixture used, and source.
4) Include estimated mean time between failures for major parts.

h. Wiring Diagrams, Block Diagrams, and Assembly Drawings.
i. Panelboard Circuit Directory for each panelboard, including Panel Name, Panel Location, Panel Ratings, spare circuit breakers, spaces for additional circuit breakers.
j. List of equipment keys turned over to the Owner.

5. Part 3: Project Documents and Certificates, including the following:

a. Shop Drawings and Product Data. Record Documents of the systems.
b. Photocopies of certificates.
c. Photocopies of Manufacturers' and Contractors' warranties, guarantees.
d. Test Reports: Copies of the approved results of all tests required under all sections of specifications.
e. Inspection Certificates.
f. Manufacturer's Conformance Certificates.

6. Provide one copy (DVD video disk) of video instruction session with each booklet set. Label video disk with all pertinent information.

7. Submit one copy of completed volumes in final form 15 days prior to final Inspection. This copy will be returned with Engineer comments. Revise content of documents as required prior to final submittal.

8. Submit final volumes revised, within ten days after final inspection.

C. Upon completion of the project, the Contractor shall furnish the Owner a complete list of suppliers of equipment for parts and maintenance purposes. The list shall include the name, address, and telephone number of the parts and maintenance firm on a single 8-1/2" x 11" sheet of paper.

D. This item shall include the furnishing of a complete list of equipment installed on the project, including the Manufacturer's name, the make and model number of the equipment, and address and telephone number of the nearest supplier who stocks maintenance and/or replacement parts. The list should be submitted along with as-built drawings and be typed in an organized manner.

3.17 INSTALLATION AND COORDINATION DRAWINGS

A. In congested areas, prepare, submit, and use composite installation and coordination drawings to assure proper coordination and installation of work. Drawings shall include, but not be limited, to the following: Complete Electrical Drawings showing coordination with lights, electrical equipment, mechanical, plumbing, HVAC, structural, and architectural elements and provision for access.

B. Draw plans to a scale not less than 3/8-inch equals one foot. Include plans, sections, and elevations of proposed work, showing all equipment and conduit in areas involved. Fully dimension all work including lighting fixtures, conduits, pullboxes, panelboards, and other electrical work, walls, doors, ceilings, columns, beams, joists, mechanical equipment, and other architectural and structural work.

C. Identify all equipment and devices on wiring diagrams and schematics. Where field connections are shown to factory-wired terminals, include manufacturer's literature showing internal wiring.

3.18 CUTTING AND PATCHING

A. The cutting of walls, floors, partitions, etc., for the passage and/or accommodation of conduits, etc., the closing of superfluous openings and the removal of all debris caused by said work under this contract shall be performed by and at the expense of the Contractor.

B. No cutting of any structure or finishes shall be done until the condition requiring such cutting has been examined and approved by the Architect.

C. All surfaces disturbed as a result of such cutting shall be restored under this division to match original work and all materials used for any patching, mending or finishing must conform to the class of materials originally installed.

D. Openings through precast planks for the passage of hanger rods, conduits, outlet boxes, etc., shall be drilled with power driven carbine tip drills. This drilling shall be done by the trades needing the openings and shall be in accordance with Architect's instructions. No reinforcing bars shall be cut without specific approval of the Structural Engineer.

3.19 WATERPROOFING

A. Coordinate the work to minimize penetration of waterproof construction, including roofs, exterior walls and interior waterproof construction. Where such penetrations are necessary, furnish and install all necessary sleeves, flashings, fittings, and caulking to make penetrations absolutely watertight.

B. Where conduits or other openings penetrate roofs, flash pipe with Stoneman "Stormtite", or approved equal, roof flashing assemblies, with 4-pound lead, 6 inch skirt, and caulked counterflashing sleeve similar to No. 1000-4.

C. Furnish and install pitch pockets where required.

D. Furnish and install conduit sleeves specifically designed for application to the particular roof construction, and install in accordance with the manufacturer's instructions, the National Roofing Contractors' Association, and as required by other divisions of this specification. The Contractor shall be responsible for sleeve sizes and locations.

3.20 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.

B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.

C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.

D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.

E. Cut sleeves to length for mounting flush with both surfaces of walls.

F. Extend sleeves installed in floors 2 inches (50 mm) above finished floor level.

G. Size pipe sleeves to provide 1/4-inch (6.4-mm) annular clear space between sleeve and raceway or cable, unless indicated otherwise.

H. Seal space outside of sleeves with grout for penetrations of concrete and masonry.

1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.

I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants".

J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Through-Penetration Firestop Systems."

K. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.

L. Aboveground, Exterior-Wall Penetrations: Seal penetrations using steel or cast-iron pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch (25-mm) annular clear space between pipe and sleeve for installing mechanical sleeve seals.

3.21 SLEEVE-SEAL INSTALLATION

A. Install to seal exterior wall penetrations.

B. Use type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.22 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electrical installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 26 Section "Electrical Firestopping."

END OF SECTION 26 05 01

PAGE LEFT INTENTIONALLY BLANK

SECTION 26 05 02
ELECTRICAL DEMOLITION FOR REMODELING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections apply to this Section.

1.2 SCOPE

A. Electrical demolition shall be carried out per the Contract Documents.

B. Provide all cutting and patching for electrical construction.

C. Provide temporary service and provisions to maintain existing systems.

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT

A. Materials and equipment for patching and extending work: As specified in individual sections.

PART 3 - EXECUTION

3.1 EXAMINATION

A. The Contractor shall examine the site, determine all conditions and circumstances and gather all data and information required for the work. Field investigations include, but are not limited to, performing surveys, opening of equipment enclosures, and other work as required to maintain existing systems.

B. The Contractor shall survey all new and existing wiring, circuitry, cabling, equipment and devices. Data gathering shall include, but not be limited to, equipment nameplate information, ratings, voltage, wiring configurations, conductor lengths, conductor routing, conductor sizes, equipment connections, and other information as required to maintain existing systems.

C. The Contractor shall provide complete field investigations to determine existing and new conductor, cable, and conduit routing, points of connections, and tracing of existing systems.

D. Verify that field measurements and circuiting arrangements are as shown on the Drawings.

E. Verify that abandoned wiring and equipment serve only abandoned facilities.

F. Demolition Drawings are based on casual field observation. Report discrepancies to the Owner, Engineer before disturbing existing installation.

G. Beginning of demolition means installer accepts existing conditions.

3.2 PREPARATION

A. Disconnect electrical systems in walls, floors, and ceilings scheduled for removal.

3.3 CONNECTIONS AND ALTERATIONS TO EXISTING SYSTEMS

A. Keep all existing electrical systems in operation during the progress of the work. Provide temporary electrical connections to systems of equipment, etc., where necessary to maintain continuous operation until the new systems and equipment are ready for operation.

B. When existing electrical work is removed, remove all conduit, ducts, supports, etc. to a point below the finished floors or behind finished walls and cap. Such points shall be far enough behind finished surfaces to allow for the installation of the normal thickness of finished material.

C. When the work specified hereunder connects to any existing equipment, conduit, wiring, etc., perform all necessary alterations, cuttings, fittings, etc., of the existing work as may be necessary or required to make satisfactory connections between the new and existing work and leave the complete work in a finished and workmanlike condition.

D. When the work specified under other divisions necessitates relocation of existing equipment, conduits, wiring, etc., perform all work and make all necessary changes to existing work as may be required to leave the completed work in a finished and workmanlike condition.

E. Contractor shall be responsible for removing and replacing existing ceiling tile within the lay-in ceiling areas as required. Contractor shall provide all necessary cutting and fitting of bushed holes for cable passage through tiles. Any tiles damaged during the Contract shall be replaced with like kind at no cost to the Owner.

F. Provide temporary wiring and connections to maintain existing systems in service during construction. When work must be performed on energized equipment or

circuits, use personnel experienced in such operations. In particular, all security and safety systems must be maintained in operation at all times as required by the Owner. This includes security and safety lighting.

G. Existing Electrical Service: Disable system only to make switchovers and connections. Obtain permission from Owner, Architect/Engineer and other trades at the site at least 24 hours before partially or completely disabling system. Minimize outage duration. Make temporary connections to maintain service in areas adjacent to work area.

H. Trace all circuits and controls to be disconnected to ensure that vital services to other areas are not interrupted.

3.4 PROTECTION

A. Provide protection for all existing and new cabling. Provide inner duct, conduit or other suitable means of protection to prevent damage to cables located in renovated areas.

B. Damage to wiring, cabling or equipment shall be repaired by skilled mechanics for the trade involved at no additional contract amount.

C. Fixtures, materials and equipment shall be protected at all times. The Contractor shall make good any damage caused either directly or indirectly by his workmen. Conduit openings shall be closed with caps or plugs during installation. Fixtures and equipment shall be tightly covered and protected against dirt, water and chemical or other injury. At the completion of all work, the fixtures, materials and equipment shall be thoroughly cleaned and turned over in a condition satisfactory to the Owner.

D. Damage: Where wiring, raceways, lighting fixtures, devices or equipment to remain is inadvertently damaged or disturbed, cut out and remove damaged section and provide new of equal or capacity or quality.

3.5 ELECTRICAL DEMOLITION

A. Remove from the premises and dispose of all existing wiring, conduit, material, fixtures, devices, equipment, etc., not required for re-use or re-installation.

B. Deliver on the premises where directed existing material and equipment which is removed and is desired by the Owner or is indicated to remain the property of the Owner.

C. All other equipment and materials which are removed shall become the property of the Contractor and shall be removed by him from the premises.

D. Where electrical equipment is removed, also remove all wiring back to source panelboard or switch or to last remaining device on the same circuit. All conduit, hangers, supports, etc., shall also be removed unless otherwise noted. Such

conduit may remain to be reused for new work provided said conduit is of the proper size and type as that specified and in a condition acceptable to Engineer and Owner.

E. Any conduit abandoned in concrete slabs, walls, or other inaccessible locations shall be left empty except for a nylon pull wire. Ends shall be capped with push plugs for future use.

F. Where an existing system is indicated to be removed, the Contractor shall provide complete removal of entire system including all wiring, conduit, and connected/associated fixtures and devices. The system shall be removed in its entirety unless otherwise noted.

3.6 EXISTING CONDUIT WORK

A. Remove all abandoned raceway, including abandoned raceway above accessible ceiling finishes. Cut raceway flush with walls and floors, and patch surfaces. Remove conduit back to point of penetration/exposure.

B. Remove concealed abandoned raceway to its source.

C. Abandoned Work: buried electrical work abandoned in place, shall be cut out approximately 2 inches beyond the face of adjacent construction, capped and the adjacent surface patched to match the existing finish.

D. Disconnect abandoned outlets and remove devices. Remove abandoned outlets if raceway servicing them is abandoned and removed. Provide blank cover for abandoned outlets that are not removed.

E. Ensure access to existing boxes and other installations which remain active and which require access. Modify installation or provide access panel as appropriate.

F. Extend existing raceway and box installations using materials and methods compatible with existing electrical installations, or as specified.

G. Clean and repair existing raceway and boxes that remain or are to be reinstalled.

H. Remove all abandoned wiring from exiting conduits. Abandoned wiring that cannot be removed shall be tagged at each end as “Abandoned”.

I. Contractor shall provide all cutting and patching required to connect to and extend existing conduits, wiring, circuits, etc.

3.7 EXISTING WIRING AND CABLING WORK

A. Remove all abandoned and unused wire and cable, including abandoned wire and cable above accessible ceiling finishes. Patch surfaces where removed cables pass

through building finishes. Remove abandoned and unused cabling and wiring back to the source.

B. Disconnect abandoned circuits and remove circuit wire and cable. Remove abandoned boxes if wire and cable servicing them is abandoned and removed. Provide blank cover for abandoned boxes that are not removed.

C. Ensure access to existing wiring connections which remain active and which require access. Modify installation or provide access panel as appropriate.

D. Extend existing circuits using materials and methods compatible with existing electrical installations or as specified.

E. Clean and repair existing wire and cable that remain or is to be reinstalled.

F. Provide supports for all wiring and cabling to remain as required by NEC.

G. Contractor shall provide field services for tracing out of all existing circuits to be maintained. Contractor shall locate, trace and label, all existing circuits being re-used.

3.8 EXISTING WIRING DEVICES WORK

A. Disconnect abandoned wiring devices and remove them.

B. Ensure access to existing wiring devices which remain active. Modify installation as appropriate.

C. Clean and repair existing wiring devices which remain or are to be reinstalled.

D. Provide painted blank coverplates over existing device boxes. Paint shall match existing finish of surrounding area.

E. Disconnect abandoned outlets and remove devices. Remove abandoned outlet boxes if conduit servicing them is abandoned and removed. Provide blank cover for abandoned outlet boxes which are not removed.

3.9 DEMOLITION AND EXTENSION OF EXISTING ELECTRICAL WORK

A. Demolish and extend existing electrical work to meet all requirements of these specifications.

B. If certain raceways and boxes are abandoned but not scheduled for removal, those items must be shown on the As-Built Drawings.

C. Remove, relocate, and extend existing installations to accommodate new construction.

D. Remove abandoned wiring to source of supply.

E. Disconnect and remove abandoned luminaires. Remove brackets, stems, hangers, and other accessories.

F. Repair adjacent construction and finishes damaged during demolition and extension work.

G. Maintain access to existing electrical installations which remain active. Modify installation or provide access panel as appropriate.

H. Extend existing installations using materials and methods (compatible with existing electrical installations, or) as specified. This includes the extension of the circuit from the last active device to the next device in the system to be activated.

3.10 CLEANING AND REPAIR

A. The Consultant shall show, on the drawings, all items to be cleaned or repaired.

B. Clean and repair existing equipment and materials that remain or are to be reused.

C. Panelboards: Clean exposed surfaces and check tightness of electrical connections. Replace damaged circuit breakers and provide closure plates for vacant positions. Provide typed circuit directory showing revised circuiting arrangement. Trace existing circuits to determine exact location and type of load served by each circuit breaker.

D. Provide new labels on all existing electrical equipment being re-used.

3.11 INSTALLATION

A. Install relocated materials and equipment under the provisions of other sections.

END OF SECTION 26 05 02

SECTION 26 05 19
LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Building wires and cables rated 600 V and less.
2. Connectors, splices, and terminations rated 600 V and less.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Qualification Data: For testing agency.

C. Field quality-control test reports.

1.4 QUALITY ASSURANCE

A. Testing: On installation of wires and cables and before electrical circuitry has been energized, demonstrate product capability and compliance with requirements. Procedures: Perform each visual and mechanical inspection and electrical test state din NETA ATS Section 7.3.1. Certify compliance with test parameters.

B. Correct malfunctioning conductors and cables at Project site, where possible, and retest to demonstrate compliance; otherwise, remove and replace with new units and retest.

C. Measure tightness of bolted connections and compare torque measurements with manufacturer’s recommended values.

D. Verify continuity of each branch circuit conductor.

E. Tests: Power & Lighting Distribution Feeders and Feeders to all major mechanical equipment at 60A and over (i.e., chillers, AHU's, etc.).

1. Tests shall be performed with a 1000-volt megger, and conductors shall test free from short-circuits and grounds.
2. Conductors shall be tested phase-to-phase and phase-to-ground.
3. Furnish the instruments, materials, and labor required. Perform the tests in the presence of the Contracting Officer.
4. Test readings shall be recorded and delivered to Owner and Engineer in a report.
5. Copy of Test results shall be included in O&M Manuals.

F. Demonstration: Subsequent to wire and cable hook-ups, energize circuit and demonstrate functioning in accordance with requirements. Where necessary, correct malfunctioning units, and then retest to demonstrate compliance.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Alcan Products Corporation; Alcan Cable Division.
2. American Insulated Wire Corp.; a Leviton Company.
3. General Cable Corporation.
4. Senator Wire & Cable Company.
5. Southwire Company.

B. Copper Conductors: Comply with NEMA WC 70.

C. Conductor Insulation: Comply with NEMA WC 70 for Types THHN-THWN, XHHW, USE, and SO.

D. Multiconductor Cable: Comply with NEMA WC 70/ICEA S-95-658 for metal-clad cable, Type MC, with ground wire.

2.2 CONNECTORS AND SPLICES

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. AFC Cable Systems, Inc.
2. Hubbell Power Systems, Inc.

3. O-Z/Gedney; EGS Electrical Group LLC.
4. 3M; Electrical Products Division.
5. Tyco Electronics Corp.

B. UL-listed, factory-fabricated wiring connectors of size, ampacity rating, material, type, and class for application and service indicated. Comply with Project's installation requirements and as specified in Part 3 "Wire and Insulation Applications" Article.

C. Split Bolt Connectors: Not Acceptable.

D. Solderless Pressure Connectors: High copper alloy terminal. May be used only for cable termination to equipment pads or terminals. Not approved for splicing.

E. Spring Wire Connectors: Solderless spring type pressure connector with insulating covers for copper wire splices and taps. Use for conductor sizes 10 AWG and smaller.

F. All wire connectors used in underground or exterior pull boxes shall be gel-filled twist connectors or a connector designed for damp and wet locations.

G. Mechanical Connectors: Bolted type tin-plated; high conductivity copper alloy; spacer between conductors; beveled cable entrances.

H. Compression (crimp) Connectors: Long barrel; seamless, tin-plated electrolytic high conductivity copper tubing, internally beveled barrel ends. Connector shall be clearly marked with the wire size and type and proper number and location of crimps.

I. Heat shrinkable tubing shall meet the requirements of ANSI C119.1-1986 for buried connections to 90°C and shall be material flame-retarded per IEEE 383 “Vertical Tray Flame Test”. Motor connection kits shall consist of heat-shrinkable, polymeric insulating material over the connection area and a high dielectric strength mastic to seal the ends against ingress of moisture and contamination. Motor connection kits shall accommodate a range of cable sizes for both in-line and stub-type configurations. Connection kits shall be independent of cable manufacturer’s tolerances.

J. Wire Nut Connectors:

1. Wire nuts install in wet locations, exterior, etc., shall be self-contained, waterproof and corrosion-proof units incorporating prefilled silicone grease to block out moisture and air.
2. Connectors shall be UL listed appropriately sized according to manufacturer’s recommendation for the suitable wire sizes and voltage rating (600 volt minimum).
3. Connectors body shall have a color-coded outer shell.
4. Connectors shall be as manufactured by King Technology or approved equal.

2.3 FIRE-ALARM WIRE AND CABLE

A. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.

B. Signaling Line Circuits: Twisted, shielded pair, size as recommended by system manufacturer.

1. Circuit Integrity Cable: Twisted shielded pair, NFPA 70, Article 760, Classification CI, for power-limited fire-alarm signal service Type FPL. NRTL listed and labeled as complying with UL 1424 and UL 2196 for a two-hour rating.

C. Non-Power-Limited Circuits: Solid-copper conductors with 600 V rated, 75 deg C, color-coded insulation, and complying with requirements in UL 2196 for a two-hour rating.

1. Low-Voltage Circuits: No. 16 AWG, minimum, in pathway.

2. Line-Voltage Circuits: No. 12 AWG, minimum, in pathway.

3. Multiconductor Armored Cable: NFPA 70, Type MC, copper conductors, Type TFN/THHN conductor insulation, copper drain wire, copper armor with outer jacket with red identifier stripe, NTRL listed for fire-alarm and cable tray installation, plenum rated.

2.4 SYSTEM DESCRIPTION

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with NFPA 70.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

A. Feeders: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

B. Branch Circuits: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

A. Feeders Concealed in Ceilings, Walls, and Partitions: Type THHN-THWN, single conductors in raceway.

B. Exposed Branch Circuits: Type THHN-THWN, single conductors in raceway.

C. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN-THWH, single conductors in raceway, or type MC cable where permitted by NEC.

D. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN-THWN, single conductors in raceway.

E. Conductors shall be rated 75 deg C in wet locations and 90 deg C in dry locations.

3.3 INSTALLATION OF CONDUCTORS AND CABLES

A. Conceal cables in finished walls, ceilings, and floors, unless otherwise indicated.

B. Complete raceway installation between conductor and cable termination points according to Division 26 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.

C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.

E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.

F. Support cables according to Section 26 04 29, "Hangers and Supports for Electrical Systems."

G. Identify and color-code conductors and cables according to Section 26 05 53, “Identification for Electrical Systems."

3.4 CONNECTIONS

A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

B. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.

C. Wiring at Outlets: Install conductor at each outlet, with at least 12 inches (300 mm) of slack.

D. Joints of #10 AWG and smaller shall be made with properly insulated solderless type pressure connectors. Where stranded conductors or multiple solid conductors are connected to terminals, solderless lugs manufactured by Thomas and Betts Company or equivalent shall be used.

E. Joints of #8 AWG and larger in power and lighting circuits shall be of the type indented into the conductor by means of a hand or hydraulic pressure tool. Connectors shall be Burndy “Hy-dent’, T&B “St-Kon”, or equivalent. Connectors for control wiring shall be Burndy “Hy-Lug”, or equivalent.

F. All circuits for exterior electric work shall be #10 AWG (minimum) and contain an extra #10 AWG (minimum) copper ground conductor. All exterior wiring shall be installed in conduit as specified above, unless otherwise noted as larger on the Drawings.

3.5 INSTALLATION OF FIRE-ALARM WIRE AND CABLE

A. Comply with NFPA 72.

B. Wiring Method: Install wiring in metal pathway according to Section 260529 "Hangers and Supports for Electrical Systems."

1. Install plenum cable in environmental airspaces, including plenum ceilings.
2. Fire-alarm circuits and equipment control wiring associated with fire-alarm system must be installed in a dedicated pathway system.

    a. Cables and pathways used for fire-alarm circuits, and equipment control wiring associated with fire-alarm system, may not contain any other wire or cable.

3. Fire-Rated Cables: Use of two-hour, fire-rated fire-alarm cables, NFPA 70, Types MI and CI, is permitted.
4. Signaling Line Circuits: Power-limited fire-alarm cables must not be installed in the same cable or pathway as signaling line circuits.
5. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with fire-alarm system to terminal blocks. Mark each terminal according to system's wiring diagrams. Make all connections with

approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.

C. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes; cabinets; or equipment enclosures where circuit connections are made.

D. Color-Coding: Color-code fire-alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and another for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire-alarm system junction boxes and covers red.

3.6 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 26 Section "Electrical Firestopping." and “Common Work Results for Electrical”.

3.7 SLEEVE-SEAL INSTALLATION

A. Install to seal underground exterior-wall penetrations according to Division 26 Section, “Common Work Results for Electrical”.

3.8 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Division 7 Section "Through Penetration Firestop System."

3.9 FIELD QUALITY CONTROL

A. Perform tests and inspections and prepare test reports.

B. Tests and Inspections:

1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors, and conductors feeding the mechanical equipment and services for compliance with requirements.
2. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.

C. Measure tightness of bolted connections and compare torque measurements with manufacturer’s recommended values.

D. Verify continuity of each branch circuit conductor.

E. Demonstration: Subsequent to wire and cable hook-ups, energize circuit and demonstrate functioning in accordance with requirements. Where necessary, correct malfunctioning units, and then retest to demonstrate compliance.

F. Test Reports: Prepare a written report to record the following:

1. Test procedures used.
2. Test results that comply with requirements.
3. Test results that do not comply with requirements and corrective action taken to achieve compliance with requirements.

G. Remove and replace malfunctioning units and retest as specified above.

END OF SECTION 26 05 19

SECTION 26 05 26
GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes grounding and bonding systems and equipment.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For testing agency and testing agency's field supervisor.

B. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For grounding to include in emergency, operation, and maintenance manuals.

1.6 QUALITY ASSURANCE

A. Testing Agency Qualifications: Member company of NETA or an NRTL.

1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

C. Comply with UL 467 for grounding and bonding materials and equipment.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Burndy; Part of Hubbell Electrical Systems.
2. Dossert; AFL Telecommunications LLC.
3. ERICO International Corporation.
4. Fushi Copperweld Inc.
5. Galvan Industries, Inc.; Electrical Products Division, LLC.
6. Harger Lightning and Grounding.
7. ILSCO.
8. O-Z/Gedney; A Brand of the EGS Electrical Group.
9. Robbins Lightning, Inc.

2.2 SYSTEM DESCRIPTION

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Comply with UL 467 for grounding and bonding materials and equipment.

2.3 CONDUCTORS

A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.

B. Bare Copper Conductors:

1. Solid Conductors: ASTM B 3.
2. Stranded Conductors: ASTM B 8.
3. Tinned Conductors: ASTM B 33.
4. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch (6 mm) in diameter, unless otherwise noted.
5. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor, unless otherwise noted.
6. Bonding Jumper: Copper tape, braided conductors terminated with copper ferrules; 1-5/8 inches (41 mm) wide and 1/16 inch (1.6 mm) thick.

2.4 CONNECTORS

A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for applications in which used and for specific types, sizes, and combinations of conductors and other items connected.

B. Bolted Connectors for Conductors and Pipes: Copper or copper alloy.

C. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.

D. Bus-Bar Connectors: Mechanical type, cast silicon bronze, solderless exothermic-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.

PART 3 - EXECUTION

3.1 APPLICATIONS

A. Conductors: Install solid conductor for No. 10 AWG and smaller, and stranded conductors for No. 8 AWG and larger unless otherwise indicated.

B. Conductor Terminations and Connections:

1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
2. Connections to Structural Steel: Welded connectors.

3.2 EQUIPMENT GROUNDING

A. Install insulated equipment grounding conductors with all feeders and branch circuits.

3.3 INSTALLATION

A. Grounding Conductors: Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.

B. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.

1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.

3.4 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
2. Inspect physical and mechanical condition. Verify tightness of accessible, bolted, electrical connections with a calibrated torque wrench according to manufacturer's written instructions.
3. Test completed grounding system at each location where a maximum ground-resistance level is specified.

C. Grounding system will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

END OF SECTION 26 05 26

SECTION 26 05 28
ELECTRICAL FIRESTOPPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes:

1. Through-penetration firestopping in fire rated construction.
2. Through-penetration smoke-stopping in smoke partitions.

B. Related items: Raceway seals and manufactured electrical devices: Refer to Section 26 05 01.

1.2 REFERENCES

A. Underwriters Laboratories

1. UL Fire Resistance Directory

a. Through-penetration firestop devices (XHCR)
b. Fire resistance rating (BXUV)
c. Through-penetration firestop systems (XHEZ)
d. Fill, void, or cavity material (XHHW)

B. American Society for Testing and Materials Standards: ASTM E 814-88: Standard Test Method for Fire Tests of Through-Penetration Firestops.

1.3 DEFINITIONS

A. Assembly: Particular arrangement of materials specific to given type of construction described or detailed in referenced documents.

B. Barriers: Time-rated fire walls, smoke barrier walls, time rated ceiling/floor assemblies and structural floors.

C. Firestopping: Methods and materials applied in penetrations and unprotected openings to limit spread of heat, fire, gasses and smoke.

D. Penetration: Opening or foreign material passing through or into barrier or structural floor such that full thickness of rated materials is not obtained.

E. System: Specific products and applications classified and numbered by Underwriters Laboratories, Inc. to close specific barrier penetrations.

F. Sleeve: Metal fabrication or pipe section extended through thickness of barrier and used to permanently guard penetration. Sleeves are described as part of penetrating system in other Sections and may or may not be required.

1.4 SYSTEM DESCRIPTION

A. Design Requirements

1. Fire-rated construction: Maintain barrier and structural floor fire resistance ratings including resistance to cold smoke at all penetrations, connections with other surfaces or types of construction, at separations required to permit building movement and sound or vibration absorption.
2. Smoke barrier construction: Maintain barrier and structural floor resistance to cold smoke at all penetrations, connections with other surfaces and types of construction and at all separations required to permit building movement and sound or vibration absorption.

1.5 SUBMITTALS

A. Submit in accordance with Division 01, unless otherwise indicated.

B. Product Data: Manufacturer's specifications and technical data including the following:

1. Detailed specification of construction and fabrication.
2. Manufacturer's installation instructions.

C. Shop Drawings: Indicate dimensions, description of materials and finishes, general construction, specific modifications, component connections, anchorage methods, hardware, and installation procedures, plus the following specific requirements.

1. Details of each proposed assembly identifying intended products and applicable UL system number, or UL classified devices.
2. Manufacturer or manufacturer's representative shall provide qualified engineering judgment and drawings relating to non-standard applications as needed.

D. Quality control submittals: Statement of qualifications.

E. Applicators' qualifications statement: List past projects indicating required experience.

1.6 QUALITY ASSURANCE

A. Installer's qualifications: Firm experienced in installation or application of systems similar in complexity to those required for this project, plus the following:

1. Acceptable to or licensed by manufacturer, State or local authority where applicable.
2. At least 2 years' experience with systems.
3. Successfully completed at least 5 comparable scale projects using this system.

B. Local and State regulatory requirements: Submit forms or acceptance for proposed assemblies not conforming to specific UL Firestop System numbers, or UL classified devices.

C. Materials shall have been tested to provide fire rating at least equal to that of the construction.

D. Manufacturer shall be a member of the International Firestop Council (IFC).

1.7 DELIVERY, STORAGE, AND HANDLING

A. Packing and shipping:

1. Deliver products in original unopened packaging with legible manufacturer's identification.
2. Coordinate delivery with scheduled installation date, allow minimum storage at site.

B. Storage and protection: Store materials in a clean, dry, ventilated location. Protect from soiling, abuse, moisture and freezing when required. Follow manufacturer's instructions.

1.8 PROJECT CONDITIONS

A. Existing conditions:

1. Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.
2. Proceed with installation only after penetrations of the substrate and supporting brackets have been installed.

B. Environmental requirements:

1. Furnish adequate ventilation if using solvent.
2. Furnish forced air ventilation during installation if required by manufacturer.
3. Keep flammable materials away from sparks or flame.
4. Provide masking and drop cloths to prevent contamination of adjacent surfaces by firestopping materials.

1.9 GUARANTEE

A. Submit copies of written guarantee agreeing to repair or replace joint sealers which fall in joint adhesion, extrusion resistance, migration resistance, or general durability or appear to deteriorate in any other manner not clearly specified by submitted manufacturer's data as an inherent quality of the material for the exposure indicated. The guarantee period shall be two years from date of substantial completion unless otherwise noted.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Subject to compliance with requirements, manufacturers offering products that may be incorporated into the work include, but are not limited to, the following:

1. Hilti.
2. Nelson.

2.2 THROUGH-PENETRATION FIRESTOPPING OF FIRE-RATED CONSTRUCTION

A. Systems of devices listed in the UL Fire Resistance Directory under categories XHCR and XHEZ may be used, providing that it conforms to the construction type, penetrate type, annular space requirements and fire rating involved in each separate instance, and that the system be symmetrical for wall applications. Systems or devices must be asbestos-free.

1. Additional requirements: Withstand the passage of cold smoke either as an inherent property of the system, or by the use of a separate product included as a part of the UL system or device, and designed to perform this function.
2. Acceptable manufacturers and products.

a. Those listed in the UL Fire Resistance directory for the UL System involved and as further defined in the “System and Applications Schedule” in Part 3 of this Section.
b. All firestopping products must be from a single manufacturer. All trades shall use products from the same manufacturer unless otherwise noted.

2.3 SMOKE-STOPPING AT SMOKE PARTITIONS

A. Through-penetration smoke-stopping: Any system complying with the requirements for through-penetration firestopping in fire-rated construction, as specified in “The Systems and Applications Schedule” in Part 3 of this Section, is acceptable,

provided that the system includes the specified smoke seal or will provide a smoke seal. The length of time of the fire resistance may be disregarded.

2.4 ACCESSORIES

A. Fill, void or cavity materials: As classified under category XHHW in the UL Fire Resistance Directory.

B. Forming materials: As classified under category XHKU in the UL Fire Resistance Directory.

C. Sleeves: Minimum 24 MSG galvanized steel, 12-inch diameter or smaller steel pipe. Sleeve shall project 1/2-inch from each surface of the floor/wall. Size as recommended by firestop manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.

1. Verify barrier penetrations are properly sized and in suitable condition for application of materials.
2. Do not proceed until unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean surfaces to be in contact with penetration seal materials of dirt, grease, oil, loose materials, rust, or other substances that may affect proper fitting, adhesion, or the required fire resistance.

3.3 INSTALLATION

A. Install penetration seal materials in accordance with printed instructions of the UL Fire Resistance Directory and in accordance with manufacturer's instruction.

B. Seal holes or voids made by penetrations to ensure an effective smoke barrier.

C. Protect materials from damage on surfaces subject to traffic.

D. When. large openings are created in walls or floors to permit installation of conduits, cable tray, or other items, close unused portions of opening with firestopping materials tested for the application. See UL Fire Resistance Directory of Paragraph 2.2 of this document.

E. Install smoke stopping as specified for firestopping.

F. Provide sleeves the full thickness of the assembly being penetrated and cut sleeves to a length of 1-inch more than the over-all thickness of the penetration, or as recommended by the firestop manufacturer.

G. All holes and voids shall be sealed the same day they are made.

3.4 FIELD QUALITY CONTROL

A. Examine penetration sealed areas to ensure proper installation before concealing or enclosing areas.

B. Keep areas of work accessible until inspection by applicable code authorities.

C. Perform under this section patching and repairing of firestopping caused by cutting or penetration by other trades.

3.5 ADJUSTING AND CLEANING

A. Clean up spills of liquid components.

B. Neatly cut and trim materials as required.

C. Remove equipment, materials and debris, leaving area in undamaged, clean condition.

3.6 SYSTEMS AND APPLICATION SCHEDULES*

SEE NEXT PAGE.

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/ CEILING
Metal Pipe	CAJ1001 CP25S/L, CP25N/S CAJ1006 CS-195+, FS-195+ CAJ1007 FS-195+, 1"& 2" Wide CAJ1009 2000, 2000+, 2003 CAJ1010 2000, 2000+, 2003 CAJ1012 2000, 2000+, 2003 CAJ1013 2000, 2000+, 2003 CAJ1014 2000, 2000+, 2003 CAJ1015 2000, 2000+, 2003 CAJ1017 FD 150 CAJ1021 FD 150 CAJ1027 MPS-2+ CAJ1044 CP 25WB+ CAJ1052 CP 25S/L, CP 25N/S CAJ1058 2000, 2000+, 2003 CAJ1060 2000, 2000+, 2003 CAJ1063 2000, 2000+, 2003 CAJ1066 CP 25N/S,CP 25S/L, CP 25WB+ CAJ1091 CP 25N/S,CP 25S/L, CP 25WB+ CAJ1092 CP 25WB+ CAJ1112 FS-195+ CAJ1160 CP 25S/L, CP 25N/S CAJ1175 CP 25WB+ CAJ1176 CP 25WB+ CAJ1188 2000+ CBJ1020 CS-195+, FS-	WL1001 CP 25 WL1002 FS-195+ WL1003 CP 25WB+,CP 25N/S WL1008 2000+ WL1009 2000+ WL1010 2000+ WL1016 CP 25WB+ WL1017 CP 25WB+,CP 25N/S WL1032 CP 25WB+,CP 25N/S WL1036 FD 150 WL1037 CS-195+,FS-195+ WL1067 CP 25N/S WL1073 CP 25WB+ WL1080 MPS-2+ WL1082 2000+	FC1002 CP 25 FC1003 2000,2000+,20003 FC1006 CP 25WB+

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/ CEILING
	195+ CBJ1021 CS-195+, MPS-2+ CBJ1031 2001 CBJ1032 2001 FA1002 CP 25WB+ WJ1010 CP 25WB+ WJ1023 2001		
Non-Metallic	CAJ2001 FS-195+, 1"& 2" WIDE, PPD'S CAJ2002 FS-195+ CAJ2003 CS-195+, FS-195+ CAJ2005 FS-195+ CAJ2006 FS-195+ CAJ2013 FS-195+ CAJ2019 2000, 2000+, 2003 CAJ2027 FS-195+, CP 25N/S, CP 25S/L, CP 25WB+ CAJ2028 FS-195, MPS-2+ CAJ2029 FS-195+, PPD'S CAJ2030 CS-195+, FS-195+ CAJ2040 FS-195+, CP 25WB+ CAJ2044 FS-195+, CP 25N/S, CP 25S/L CP 25 WB+ CAJ2090 FS-195+ CAJ2177 FS-195+, PPD'S FA2001 FS-195+, PPD'S FS2002 CS-195+, FS-195+, MPS-2+, PPD'S FA2011 FS-195+ WJ2012 FS-195+ 1" WIDE	WL2002 FS-195+, PPD'S WL2003 FS-195+ WL2004 FS-195+ WL2005 FS-195+ 4' WIDE WL2006 FS-195+ WL2013 FS-195+ WL2031 CS-195+, FS-195+ WL2032 CS-195+, FS-195+ WL2033 FS-195+ WL2073 FS-195+ 1" WIDE	FC2002 FS-195+, PPD'S FC2007 FS-195+, PPD'S FC2008 FS-195+ FC2009 FS-195+, PPD'S FC2024 FS-195+ FC2026 FS-195+ FC2028 FS-195+, 1' & 2" WIDE, PPD'S

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/ CEILING
Insulated Cable	CAJ3001 CP 25N/S, CP 25S/L CAJ3005 CS 195+, FS-195+ CAJ3007 2001 CAJ3009 2000, 2000+, 2003 CAJ3010 2000, 2000+, 2003 CAJ3011 2001 CAJ3014 FD 150 CAJ3015 FD 150 CAJ3021 MPS-2+ CAJ3029 2000, 2000+, 2003 CAJ3030 CP 25WB+ CAJ3031 CP 25N/S, CP 25S/L CAJ3041 2000, 2000+, 2003 CAJ3044 CS-195+, FS-195+ CAJ3058 FS-195+, MPS-2+ CAJ3071 CP 25N/S, CP 25S/L CAJ3074 CP 25N/S, CP 25S/L CAJ3075 2001 CAJ3080 CP 25WB+ CBJ3016 CS-195+, FS-195+ CBJ3017 CS-195+, MPS-2+ FA3001 CP 25WB+ FB3004 CS-195+, MP WJ3015 2001 WJ3016 2001	WL3001 CP 25, MPS-2+ WL3008 2000+ WL3009 2000+ WL3015 CP 25WB+, CP 25N/S WL3022 2000+ WL3030 FS-195+ WL3031 MPS-2+ WL3032 CP 25WB+ WL3041 2000+ WL3051 CP 25N/S WL3056 CP25N/S WL3062 CP 25WB+	FC3001 CP 25S/L, CP 25N/S FC3002 2000+ FC3003 2000, 2000+, 20003 FC3007 CP 25WB+, MPS-2+ FC3008 FS-195+
Mixed Penetratin	CAJ8001 CS-195+ FS-195+	WL8002 CS-195+, FS-195+	

PENETRATING ITEM	CONCRETE	GYPSUM	WOOD FLOOR/ CEILING
g Items Combos	CAJ8003 2000, 2000+, 20003 CAJ8004 2000, 2000+, 20003 CAJ8006 2001 CAJ8013 FS-195+, CP 25 CBJ8004 CS-195, FS-195+ CBJ8005 CS-195+, MPS-2+ CBJ8008 2001 FA8001 FS-195+, CP 25WB+		

* Underwriter's Laboratories, Inc., Fire Resistance Directory.

END OF SECTION 26 05 28

SECTION 26 05 29
HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Hangers and supports for electrical equipment and systems.

B. Related Sections include the following:

1. Metal Fabrications – For requirements for miscellaneous metal items involved in supports and fastenings.
2. Joint Sealants – For requirements for firestopping at sleeves through walls and floors that are fire barriers.

1.3 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. IMC: Intermediate metal conduit.

C. RMC: Rigid metal conduit.

1.4 PERFORMANCE REQUIREMENTS

A. Design supports for multiple raceways capable of supporting combined weight of supported systems and its contents.

B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

C. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

1.5 SUBMITTALS

A. Product Data: For the following:

1. Steel slotted support systems.

1.6 QUALITY ASSURANCE

A. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

A. Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Allied Tube & Conduit.
b. Cooper B-Line, Inc.; a division of Cooper Industries.
c. ERICO International Corporation.
d. GS Metals Corp.
e. Thomas & Betts Corporation.
f. Unistrut; Tyco International, Ltd.
g. Wesanco, Inc.

2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
3. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
4. Channel Dimensions: Selected for applicable load criteria.

B. Raceway and Cable Supports: As described in NECA 1 and NECA 101.

C. Conduit and Cable Support Devices: Steel and malleable-iron hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.

D. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.

E. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:

1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.

    a. Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

        1) Hilti Inc.
        2) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
        3) MKT Fastening, LLC.
        4) Simpson Strong-Tie Co., Inc.; Masterset Fastening Systems Unit.

2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.

    a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

        1) Cooper B-Line, Inc.; a division of Cooper Industries.
        2) Empire Tool and Manufacturing Co., Inc.
        3) Hilti Inc.
        4) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
        5) MKT Fastening, LLC.

3. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.
4. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
6. Toggle Bolts: All-steel springhead type.
7. Hanger Rods: Threaded steel.

2.2 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

B. Materials: Comply with requirements in Division 05 Section "Metal Fabrications" for steel shapes and plates.

C. Submit structural calculations for load and strength of each component and detailing of each assembly.

PART 3 - EXECUTION

3.1 APPLICATION

A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.

B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT, IMC, and RMC as required by NFPA 70. Minimum rod size shall be 1/4 inch (6 mm) in diameter.

C. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.

1. Secure raceways and cables to these supports with two-bolt conduit clamps.

3.2 SUPPORT INSTALLATION

A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.

B. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb (90 kg).

C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:

1. To Wood: Fasten with lag screws or through bolts.
2. To New Concrete: Bolt to concrete inserts.
3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
4. To Existing Concrete: Expansion anchor fasteners.
5. To Steel: Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69.
6. To Light Steel: Sheet metal screws.
7. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures,

pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate.

D. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

A. Comply with installation requirements in Division 05 Section "Metal Fabrications" for site-fabricated metal supports.

B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.

C. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 PAINTING

A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.

1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils (0.05 mm).

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 26 05 29

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 05 33
RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes raceways, fittings, boxes, enclosures, and cabinets for electrical wiring.

1.3 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. FMC: Flexible metal conduit.

C. IMC: Intermediate metal conduit.

D. LFMC: Liquidtight flexible metal conduit.

E. LFNC: Liquidtight flexible nonmetallic conduit.

F. RNC: Rigid nonmetallic conduit.

1.4 SUBMITTALS

A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.

B. Shop Drawings: For the following raceway components. Include plans, elevations, sections, details, and attachments to other work.

1. Custom enclosures and cabinets.

C. Source quality-control test reports.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 METAL CONDUIT AND TUBING

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. AFC Cable Systems, Inc.
2. Allied Tube & Conduit; a Tyco International Ltd. Co.
3. Electri-Flex Co.

B. Rigid Steel Conduit: ANSI C80.1.

C. IMC: ANSI C80.6.

D. EMT: ANSI C80.3.

E. FMC: Zinc-coated steel.

F. LFMC: Flexible steel conduit with PVC jacket.

G. Fittings for Conduit (Including all Types and Flexible and Liquidtight), EMT, and Cable: NEMA FB 1; listed for type and size raceway with which used, and for application and environment in which installed.

1. Conduit Fittings for Hazardous (Classified) Locations: Comply with UL 886.
2. Fittings for EMT: Steel or die-cast or compression type.
3. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.

H. Joint Compound for Rigid Steel Conduit or IMC: Listed for use in cable connector assemblies, and compounded for use to lubricate and protect threaded raceway joints from corrosion and enhance their conductivity.

2.2 NONMETALLIC CONDUIT AND TUBING

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. AFC Cable Systems, Inc.
2. Anamet Electrical, Inc.; Anaconda Metal Hose.
3. Arnco Corporation.
4. Electri-Flex Co.

B. RNC: NEMA TC 2, Type EPC-40-PVC, unless otherwise indicated.

C. LFNC: UL 1660.

D. Fittings for RNC: NEMA TC 3; match to conduit or tubing type and material.

E. Fittings for LFNC: UL 514B.

2.3 METAL WIREWAYS AND AUXILIARY GUTTERS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Cooper B-Line, Inc.
2. Hoffman.
3. Mono-Systems, Inc.
4. Square D.

B. Description: Sheet metal, complying with UL 870 and NEMA 250, Type 1 unless otherwise indicated, and sized according to NFPA 70.

1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

C. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.

D. Wireway Covers: Hinged type unless otherwise indicated.

E. Finish: Manufacturer's standard enamel finish.

2.4 SURFACE RACEWAYS

A. Listing and Labeling: Surface raceways shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Surface Metal Raceways: Galvanized steel with snap-on covers Finish with manufacturer's standard prime coating. Provide size and all components, fittings, etc. required for a complete installation.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Wiremold / Legrand
b. Mono-Systems, Inc.
c. Panduit Corp.
d. Hubbell.

2.5 BOXES, ENCLOSURES, AND CABINETS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Cooper Crouse-Hinds; Div. of Cooper Industries, Inc.
2. Erickson Electrical Equipment Company.
3. Hoffman.
4. O-Z/Gedney; a unit of General Signal.
5. Spring City Electrical Manufacturing Company.
6. Thomas & Betts Corporation.
7. Walker Systems, Inc.; Wiremold Company (The).

B. Sheet Metal Outlet and Device Boxes: NEMA OS 1.

C. Cast-Metal Outlet and Device Boxes: NEMA FB 1, aluminum, Type FD, with gasketed cover.

D. Nonmetallic Outlet and Device Boxes: NEMA OS 2.

E. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.

F. Cast-Metal Access, Pull, and Junction Boxes: NEMA FB 1, cast aluminum with gasketed cover.

G. Box extensions used to accommodate new building finishes shall be of same material as recessed box.

H. Device Box Dimensions: 4 inches square by 2-1/8 inches deep (100 mm square by 60 mm deep.

I. Gangable boxes are allowed.

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

A. Outdoors: Apply raceway products as specified below, unless otherwise indicated:

1. Exposed Conduit: Rigid steel conduit.
2. Concealed Conduit, Aboveground: Rigid steel conduit.
3. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC
4. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.

B. Comply with the following indoor applications, unless otherwise indicated:

1. Exposed, Not Subject to Physical Damage: EMT.
2. Exposed, Not Subject to Severe Physical Damage: EMT.
3. Exposed and Subject to Severe Physical Damage: Rigid steel conduit. Includes raceways in the following locations:

   a. Mechanical rooms to 8’ AFF.

4. Concealed in Ceilings and Interior Walls and Partitions: EMT.
5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
6. Damp or Wet Locations: Rigid steel conduit.
7. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4X, stainless steel in damp or wet locations.

C. Minimum Raceway Size: 3/4-inch (21-mm) trade size.

D. Raceway Fittings: Compatible with raceways and suitable for use and location.

1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings, unless otherwise indicated.
2. EMT: Use compression, steel fittings. Comply with NEMA FB 2.10.
3. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.

E. Install surface raceways only in finished spaces where conduit/cabling cannot be installed concealed.

3.2 INSTALLATION

A. Comply with NECA 1 for installation requirements applicable to products specified in Part 2 except where requirements on Drawings or in this Article are stricter.

B. Keep raceways at least 6 inches (150 mm) away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.

C. Complete raceway installation before starting conductor installation.

D. Support raceways as specified in Division 26 Section "Hangers and Supports for Electrical Systems."

E. Arrange stub-ups so curved portions of bends are not visible above the finished slab.

F. Install no more than the equivalent of three 90-degree bends in any conduit run except for communications conduits, for which fewer bends are allowed.

G. Conceal conduit and EMT within accessible ceilings space unless otherwise indicated. Install conduits parallel or perpendicular to building lines.

H. Support conduit within 12 inches (300 mm) of enclosures to which attached.

I. Stub-ups to Above Recessed Ceilings:

1. Use EMT, or RMC for raceways.
2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.

J. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.

K. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors, including conductors smaller than No. 4 AWG.

L. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.

M. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.

N. Cut conduit perpendicular to the length. For conduits 2-inch (53-mm) trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.

O. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.

P. Surface Raceways:

1. Surface metal raceway shall only be utilized where devices and/or wiring cannot be concealed in existing walls in finished areas, such as classrooms, offices, corridors, toilets, etc. unless otherwise indicated on the Contract Documents.

    a. New devices installed in existing metal stud/GWB walls shall be cut in with conduit/wiring concealed within the wall.

    b. New devices installed in existing CMU walls may be installed in surface-mounted outlet boxes served by surface metal raceway as specified in this Section.

2. Exposed raceways shall be run in corners, beneath chalk and tackboard frames, adjacent to door trims, and in other ways to be as inconspicuous as possible, even when requiring additional lengths.
3. Horizontal runs of raceways shall be kept to an absolute minimum. Exposed raceway shall be run vertically into ceiling spaces above and below.
4. All exposed raceways shall be installed in a manner approved by the Architect/Engineer.
5. Install surface raceway with a minimum 2-inch (50-mm) radius control at bend points.
6. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inches (1200 mm) and with no less than two supports per straight raceway section. Support surface raceway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
7. Two-hole straps are required.

Q. Raceways Below Slabs:

1. Refer to section 260543 for additional requirements.
2. Arrange raceways to cross building expansion joints at right angles with expansion fittings.
3. Do not embed threadless fittings in concrete unless specifically approved by Engineer for each specific location.
4. Change from PVC to GRC before rising above floor.
5. Arrange stub-ups so curved portions of bends are not visible above finished slab.
6. Conduits in close proximity to each other shall be located and wrapped with wire mesh to prevent cracking of slab.

7. Permitted below slab where specifically indicated on the Drawings. Branch circuit conduits shall stub-up at nearest wall or panel, whichever is closer.

R. Install raceway sealing fittings at suitable, approved, and accessible locations and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install raceway sealing fittings at the following points:

1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
2. Where otherwise required by NFPA 70.

S. Expansion-Joint Fittings for RNC: Install in each run of aboveground conduit that is located where environmental temperature change may exceed 30 deg F (17 deg C), and that has straight-run length that exceeds 25 feet (7.6 m).

1. Install expansion-joint fittings for each of the following locations, and provide type and quantity of fittings that accommodate temperature change listed for location:

   a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F (70 deg C) temperature change.
   b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F (86 deg C) temperature change.
   c. Indoor Spaces: Connected with the Outdoors without Physical Separation: 125 deg F (70 deg C) temperature change.
   d. Attics: 135 deg F (75 deg C) temperature change.

2. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F (0.06 mm per meter of length of straight run per deg C) of temperature change.
3. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at the time of installation.

3.3 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Division 26 Section "Common Work Results for Electrical."

3.4 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 26 Section "Electrical Firestopping."

3.5 PROTECTION

A. Provide final protection and maintain conditions that ensure coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.

1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
2. Repair damage to PVC or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 26 05 33

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 05 53
IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Identification for raceways.
2. Identification of power and control cables.
3. Identification for conductors.
4. Warning labels and signs.
5. Instruction signs.
6. Equipment identification labels.
7. Miscellaneous identification products.

1.3 SUBMITTALS

A. Product Data: For each electrical identification product indicated.

1.4 QUALITY ASSURANCE

A. Comply with ANSI A13.1 and IEEE C2.

B. Comply with NFPA 70.

C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.

D. Comply with ANSI Z535.4 for safety signs and labels.

E. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.

1.5 COORDINATION

A. Coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and the Operation and

Maintenance Manual; and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.

B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

C. Coordinate installation of identifying devices with location of access panels and doors.

D. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 POWER RACEWAY IDENTIFICATION MATERIALS

A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each raceway size.

B. Colors for Raceways Carrying Circuits at 600 V or Less:

1. Black letters on an orange field for normal feeders, black letters on a yellow field for emergency feeders.
2. Legend: Indicate voltage and system or service type.

C. Snap-Around Labels for Raceways Carrying Circuits at 600 V or Less: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of raceway or cable it identifies and to stay in place by gripping action.

2.2 POWER AND CONTROL CABLE IDENTIFICATION MATERIALS

A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each cable size.

B. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of cable it identifies and to stay in place by gripping action.

2.3 CONDUCTOR IDENTIFICATION MATERIALS

A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils (0.08 mm) thick by 1 to 2 inches (25 to 50 mm) wide.

2.4 WARNING LABELS AND SIGNS

A. Comply with NFPA 70 and 29 CFR 1910.145.

B. Baked-Enamel Warning Signs:

1. Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application.
2. 1/4-inch (6.4-mm) grommets in corners for mounting.
3. Nominal size, 7 by 10 inches (180 by 250 mm).

C. Metal-Backed, Butyrate Warning Signs:

1. Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate signs with 0.0396-inch (1-mm) galvanized-steel backing; and with colors, legend, and size required for application.
2. 1/4-inch (6.4-mm) grommets in corners for mounting.
3. Nominal size, 10 by 14 inches (250 by 360 mm).

D. Warning label and sign shall include, but are not limited to, the following legends:

1. Multiple Power Source Warning: "DANGER - ELECTRICAL SHOCK HAZARD - EQUIPMENT HAS MULTIPLE POWER SOURCES."
2. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES (915 MM)."

2.5 EQUIPMENT IDENTIFICATION LABELS

A. Engraved, Laminated Acrylic or Melamine Label: Punched or drilled for screw mounting. White letters on a dark-gray background. Minimum letter height shall be 3/8 inch (10 mm).

B. Stenciled Legend: In nonfading, waterproof, black ink or paint. Minimum letter height shall be 1 inch (25 mm).

2.6 CABLE TIES

A. General-Purpose Cable Ties: Fungus inert, self extinguishing, one piece, self locking, Type 6/6 nylon.

1. Minimum Width: 3/16 inch (5 mm).
2. Tensile Strength at 73 deg F (23 deg C), According to ASTM D 638: 12,000 psi (82.7 MPa).
3. Temperature Range: Minus 40 to plus 185 deg F (Minus 40 to plus 85 deg C).
4. Color: Black except where used for color-coding.

B. UV-Stabilized Cable Ties: Fungus inert, designed for continuous exposure to exterior sunlight, self extinguishing, one piece, self locking, Type 6/6 nylon.

1. Minimum Width: 3/16 inch (5 mm).
2. Tensile Strength at 73 deg F (23 deg C), According to ASTM D 638: 12,000 psi (82.7 MPa).
3. Temperature Range: Minus 40 to plus 185 deg F (Minus 40 to plus 85 deg C).
4. Color: Black.

C. Plenum-Rated Cable Ties: Self extinguishing, UV stabilized, one piece, self locking.

1. Minimum Width: 3/16 inch (5 mm).
2. Tensile Strength at 73 deg F ((23 deg C)), According to ASTM D 638: 7000 psi (48.2 MPa).
3. UL 94 Flame Rating: 94V-0.
4. Temperature Range: Minus 50 to plus 284 deg F (Minus 46 to plus 140 deg C).
5. Color: Black.

2.7 MISCELLANEOUS IDENTIFICATION PRODUCTS

A. Paint: Comply with requirements in painting Sections for paint materials and application requirements. Select paint system applicable for surface material and location (exterior or interior).

B. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Verify identity of each item before installing identification products.

B. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.

C. Apply identification devices to surfaces that require finish after completing finish work.

D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.

E. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.

F. System Identification Color-Coding Bands for Raceways and Cables: Each color-coding band shall completely encircle cable or conduit. Place adjacent bands of two-color markings in contact, side by side. Locate bands at changes in direction, at penetrations of walls and floors, at 50-foot (15-m) maximum intervals in straight runs, and at 25-foot (7.6-m) maximum intervals in congested areas.

G. Cable Ties: For attaching tags. Use general-purpose type, except as listed below:

1. Outdoors: UV-stabilized nylon.
2. In Spaces Handling Environmental Air: Plenum rated.

H. Painted Identification: Comply with requirements in painting Sections for surface preparation and paint application.

3.2 IDENTIFICATION SCHEDULE

A. Accessible Raceways and Metal-Clad Cables, 600 V or Less, for Service, Feeder, and Branch Circuits More Than 50A, and 120 V to ground: Identify with snap around label applied in bands. Install labels at 10-foot (3-m) maximum intervals.

B. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with self-adhesive vinyl labels with the wiring system legend and system voltage. System legends shall match the existing identification scheme, or otherwise be as follows:

1. Power - Orange.
2. Fire Alarm System – Red.
3. Security System – Blue and Yellow.\
4. Mechanical and Electrical Supervisory System – Green and Blue.
5. Telecommunications Systems – Green and Yellow.
6. Control Wiring – Green and Red.

C. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.

1. Color-Coding for Phase and Voltage Level Identification, 600 V or Less: Use colors listed below for ungrounded service, feeder, and branch-circuit conductors.

a. Color shall be factory applied or field applied for sizes larger than No. 8 AWG, if authorities having jurisdiction permit.
b. Colors for 208/120-V Circuits:

1) Phase A: Black.
2) Phase B: Red.
3) Phase C: Blue.

4) Neutral: White.

c. Colors for 480/277-V Circuits:

1) Phase A: Brown.
2) Phase B: Orange.
3) Phase C: Yellow.
4) Neutral: Grey.

d. All control wiring shall be color coded when using wires of different color from the type used to designate phase wires.

e. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches (150 mm) from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.

D. Power-Circuit Conductor Identification, More than 600 V: For conductors in vaults, pull and junction boxes, manholes, and handholes, use nonmetallic plastic tag holder with adhesive-backed phase tags, and a separate tag with the circuit designation.

E. Install instructional sign including thecolor-code for grounded and ungrounded conductors using adhesive-film-type labels.

F. Control-Circuit Conductor Identification: For conductors and cables in pull and junction boxes, use self-adhesive vinyl labels with the conductor or cable designation, origin, and destination.

G. Control-Circuit Conductor Termination Identification: For identification at terminations provide self-adhesive vinyl labels with the conductor designation.

H. Conductors to Be Extended in the Future: Attach marker tape to conductors and list source.

I. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.

1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
2. Use system of marker tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual.

J. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Baked-enamel warning signs or Metal-backed, butyrate warning signs.

1. Comply with 29 CFR 1910.145.

2. Identify system voltage with black letters on an orange background.

3. Apply to exterior of door, cover, or other access.

4. For equipment with multiple power or control sources, apply to door or cover of equipment including, but not limited to, the following:

    a. Controls with external control power connections.

K. Operating Instruction Signs: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.

L. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and the Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.

1. Labeling Instructions:

    a. Indoor Equipment: Engraved, laminated acrylic or melamine label. Unless otherwise indicated, provide a single line of text with 1/2-inch- (13-mm-) high letters on 1-1/2-inch- (38-mm-) high label; where two lines of text are required, use labels 2 inches (50 mm) high.
    b. Outdoor Equipment: Engraved, laminated acrylic or melamine label.
    c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
    d. Unless provided with self-adhesive means of attachment, fasten labels with appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.

2. Equipment to Be Labeled:

    a. Enclosures and electrical cabinets.
    b. Access doors and panels for concealed electrical items.
    c. Enclosed switches.
    d. Enclosed circuit breakers.
    e. Push-button stations.
    f. Contactors.
    g. Remote-controlled switches and control devices.
    h. Monitoring and control equipment.

END OF SECTION 26 05 53

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 08 00
COMMISSIONING OF ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1. RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

A. This Section includes requirements for commissioning the electrical system and its subsystems and equipment. This Section supplements the general requirements specified in Division 01 Section "General Commissioning Requirements."

B. Related Sections include the following:

1. Division 01 Section "General Commissioning Requirements" for general requirements for commissioning processes that apply to this Section.

C. The following systems and/or equipment shall be commissioned:

1. Lighting Control System(s)

1.3. DEFINITIONS

A. Architect: Includes Architect identified in the Contract for Construction between Owner and Contractor, plus consultant/design professionals responsible for design of electrical systems, electrical, communications, and other related systems.

B. CxA: Commissioning Authority.

C. Systems, Subsystems, and Equipment: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, and equipment.

1.4. CONTRACTOR'S RESPONSIBILITIES

A. The following responsibilities are in addition to those specified in Division 01 Section "General Commissioning Requirements."

B. Electrical Contractor:

1. Provide certified and calibrated measuring instruments and logging devices

to record test data, and data acquisition equipment to record data for the complete range of testing for the required test period.

1.5. COMMISSIONING DOCUMENTATION

A. The following are in addition to documentation specified in Division 01 Section "General Commissioning Requirements."

B. Test Checklists: CxA with assistance of Contractor shall develop test checklists for electrical systems, subsystems, and equipment, including interfaces and interlocks with other systems. CxA shall prepare separate checklists for each mode of operation and provide space to indicate whether the mode under test responded as required. In addition to the requirements specified in Division 01 Section "General Commissioning Requirements," checklists shall include, but not be limited to, the following:

1. Calibration of sensors and sensor function.
2. Testing conditions under which test was conducted, including (as applicable) ambient conditions, set points, override conditions, and status and operating conditions that impact the results of test.
3. Control sequences for electrical and emergency systems.
4. Sequence of response(s) to control signals at specified conditions.
5. Expected performance of systems, subsystems, and equipment at each step of test.
6. Interaction of auxiliary equipment.
7. Issues log.

1.6. SUBMITTALS

A. The following submittals are in addition to those specified in Division 01 Section "General Commissioning Requirements."

B. Testing Procedures: CxA shall submit detailed testing plan, procedures, and checklists for each series of tests. Submittals shall include samples of data reporting sheets that will be part of the reports.

C. Certificate of Readiness: CxA shall compile certificates of readiness from Contractor certifying that systems, subsystems, equipment, and associated controls are ready for testing.

D. Certificate of Completion of Installation, Prestart, and Startup: CxA shall certify that installation, prestart, and startup activities have been completed.

E. Test and Inspection Reports: CxA shall compile and submit test and inspection reports and certificates, and shall include them in systems manual and commissioning report.

F. Corrective Action Documents: CxA shall submit corrective action documents.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1. TESTING PREPARATION

A. Prerequisites for Testing:

1. Certify that electrical systems, subsystems, and equipment have been completed, calibrated, and started; are operating according to the Contract Documents; and that Certificates of Readiness are signed and submitted.
2. Certify that electrical instrumentation and control systems have been completed and calibrated; are operating according to the Contract Documents; and that pretest set points have been recorded.
3. Test systems and intersystem performance after approval of test checklists for systems, subsystems, and equipment.
4. Set systems, subsystems, and equipment into operating mode to be tested (e.g., normal shut down, normal auto position, normal manual position, unoccupied cycle, emergency power, and alarm conditions).
5. Verify each operating cycle after it has been running for a specified period and is operating in a steady-state condition.
6. Inspect and verify the position of each device and interlock identified on checklists. Sign off each item as acceptable, or failed. Repeat this test for each operating cycle that applies to system being tested.
7. Check safety cutouts, alarms, and interlocks with life-safety systems during each mode of operation.
8. Annotate checklist or data sheet when a deficiency is observed.
9. Verify proper responses of monitoring and control system controllers and sensors to include the following:

    a. For each controller or sensor, record the indicated monitoring and control system reading and the test instrument reading. If initial test indicates that the test reading is outside of the control range of the installed device, check calibration of the installed device and adjust as required. Retest malfunctioning devices and record results on checklist or data sheet.
    b. Report deficiencies and prepare an issues log entry.

3.2. TESTING

A. Test systems and intersystem performance after test checklists for systems, subsystems, and equipment have been approved.

B. Perform tests using design conditions whenever possible.

1. Simulate conditions by imposing an artificial load when it is not practical to test under design conditions and when written approval for simulated conditions is received from CxA. Before simulating conditions, calibrate testing instruments. Set and document simulated conditions and methods of simulation. After tests, return settings to normal operating conditions.

C. Scope of Electrical Contractor Testing:

1. Test all operating modes, interlocks, control responses, responses to abnormal or emergency conditions, and verify proper response of building automation system controllers and sensors.

D. Detailed Testing Procedures: CxA, with Electrical Contractor shall prepare detailed testing plans, procedures, and checklists for electrical systems, subsystems, and equipment.

E. Electrical System Testing: Electrical Contractor shall prepare a testing plan to verify performance of systems identified in Part 1 of this section. Plan shall include the following:

1. Sequence of testing and testing procedures for each item of equipment and section of wiring to be tested, identified by identification marker. Markers shall be keyed to Drawings for each wiring sector showing the physical location of each item of equipment and electrical wiring test section. Drawings shall be formatted to allow each item of equipment and section of wiring to be physically located and identified when referred to in the system testing plan.
2. Tracking checklist for managing and ensuring that all wiring systems have been tested.

F. Deferred Testing:

1. If tests cannot be completed because of a deficiency outside the scope of the electrical system, the deficiency shall be documented and reported to Owner. Deficiencies shall be resolved and corrected by appropriate parties and test rescheduled.
2. If the testing plan indicates specific seasonal testing, appropriate initial performance tests shall be completed and documented and additional tests scheduled.

G. Testing Reports:

1. Reports shall include measured data, data sheets, and a comprehensive summary describing the operation of systems at the time of testing.
2. Include data sheets for each electrical systems to verify proper operation of the electrical systems, the system it serves, the service it provides, and its location. Provide space for testing personnel to sign off on each data sheet.

3. Prepare a preliminary test report. Deficiencies will be evaluated by Architect to determine corrective action. Deficiencies shall be corrected and test repeated.

END OF SECTION 26 08 00

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 09 23
LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Provide lighting controls that can operate as standalone local room network(s) and have the capability to expand to a central building wide network. The building wide network shall provide control, monitoring, adjustment and scheduling functionality. The system shall be PC based with software and historical data storage. The system shall support third party integration with the building management system through BACnet/IP.

B. This Section includes the following lighting control devices:

1. Time switches.
2. Photoelectric switches.
3. Daylight-harvesting controls.
4. Indoor occupancy/vacancy sensors.
5. Low voltage switches.
6. Contactors.

C. Related Sections include the following:

1. Division 26 Section 262726, *Wiring Devices* for snap switches.
2. Section 260943 “Network Lighting Controls”.

1.3 DEFINITIONS

A. LED: Light-emitting diode.

B. PIR: Passive infrared.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Coverage Plans: Provide full scale plans showing locations and coverage patterns for all occupancy/vacancy sensors.

C. Location Plans: Provide full scale plans showing locations and coverage patterns for all devices.

D. Shop Drawings: Show installation details for occupancy and light-level sensors.

1. Interconnection diagrams showing field-installed wiring.
2. Include diagrams for power, signal, and control wiring.
3. Include riser diagrams showing all devices and wiring.

E. Field quality-control test reports.

F. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.6 SUBSTITUTIONS

A. The lighting control specification and lighting control details represent the basis of design. Acceptable manufacturers must meet the criteria listed in the system requirements as well as intent demonstrated through control details. Compliant systems are required to achieve the design intent and are not required to have all the parts and pieces listed.

B. Manufacturers not listed in the list of Acceptable Manufacturers must submit for approval within 10 days prior to bid.

C. Acceptable Manufacturers

1. Basis of Design

a. Acuity Brand Controls; nLight.

2. Alternative Manufacturers

a. Wattstopper; Digital Lighting Management
b. Hubbell NX
c. Eaton; Room Controller System

1.7 COORDINATION

A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression system, and partition assemblies.

PART 2 - PRODUCTS

2.1 GENERAL

A. Provide a wired digital networked lighting control system as indicated on the drawings. The system shall include, but not be limited to, occupancy/vacancy sensor(s), photo sensor(s), digital room controller(s), digital switches, and all interconnecting wiring required for a complete operational system. The Basis-of-Design System is the Acuity Brand Controls; nLight.

2.2 TIME SWITCHES

A. Basis-of-Design product: Subject to compliance with requirements, provide Acuity or a comparable product by one of the following:

1. Wattstopper.
2. Leviton Manufacturing Company, Inc.
3. Pass & Seymour.
4. Cooper Industries, Inc.
5. Intermatic, Inc.

B. Digital Time Switches: Wall switch style, electroluminescent back-lit LCD display shows timer countdown, time-out adjustments from 5 minutes to 12 hours, compatible with electronic ballasts; UL listed, five-year warranty.

2.3 DAYLIGHT-HARVESTING DIMMING CONTROLS

A. Basis-of-Design Product: Subject to compliance with requirements, provide nLight nCm ADCX RJB or comparable product by one of the following:

1. Wattstopper DLM
2. Hubbell NX
3. Eaton

B. System Description: Sensing daylight and electrical lighting levels, the system adjusts the indoor electrical lighting levels. As daylight increases, the lights are dimmed.

1. Lighting control set point is based on two lighting conditions:

a. When no daylight is present (target level).
b. When significant daylight is present.

2. System programming is done with a hand held digital configuration tool or a PC with appropriate software.

a. Initial setup tool: a hand held digital configuration tool. Sensor adjustments may also be made using configuration pushbuttons on the sensors.
b. USB interface and PC software: capability to program, read, store, modify and document device and system configuration.

C. Ceiling-Mounted Dimming Controls: Solid-state, digital light-level sensor unit, with separate controller unit, to detect changes in lighting levels that are perceived by the eye in order to automatically dim a lighting zone.

D. Electrical Components, Devices, and Accessories:

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
2. Operating Ambient Conditions: Dry interior conditions, 32 to 104 deg F (0 to 40 deg C).
3. Sensor Output: Digitally communicates with room controller to dim loads based on lighting conditions. Sensor is powered from the room controller.

E. Light-Level Sensor Set-Point Adjustment Range: 10 to 200 fc (108 to 2152 lux)

F. Provide unit suitable for Low Temp/High Humidity environments in SHOPS and other unconditioned spaces.

G. Provide single or dual zone control capability, as applicable.

2.4 INDOOR OCCUPANCY/VACANCY SENSORS

A. Basis-of-Design Product: Subject to compliance with requirements, provide nLight nCM PDT RJB, nWV PDT, or comparable product by one of the following:

1. Wattstopper DLM
2. Hubbell NX
3. Eaton

B. General Requirements for Sensors: Wall- or ceiling-mounted, solid-state digital indoor occupancy/vacancy sensors with a separate controller unit.

1. Systems programming is done with a hand held digital configuration tool or a PC with appropriate software.

a. Initial setup tool: a hand held digital configuration tool. Sensor adjustments may also be made using configuration pushbuttons on the sensors.

b. USB interface and PC software: capability to program, read, store, modify and document device and system configuration.

2. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

3. Operation:

a. Occupancy Sensor: Automatic-on when coverage area is occupied, and automatic-off when unoccupied.
b. Vacancy Sensor: Manual-on when coverage area is occupied, and automatic-off when unoccupied.
c. Time Delay for turning lights off adjustable over a minimum range of 1 to 30 minutes in 1-minute increments. Default setting: 20 minutes.

4. Sensor Output: Digitally communicates with room controller to turn loads on and off based on occupancy. Sensor is powered from the room controller.

5. Mounting:

a. Sensor: Suitable for mounting, ceiling mounting and corner mounting.
b. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind removable cover.

6. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.

C. PIR Type: Ceiling mounted; detect occupants in coverage area by their heat and movement.

1. Detector Sensitivity: Detect occurrences of 6-inch- (150-mm-) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm).
2. Detection Coverage (Standard Room): Detect occupancy anywhere in a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch-(2440-mm-) high ceiling.
3. Detection Coverage Large Room): Detect occupancy anywhere in a circular area of 2000 sq.ft. (186 sq.m) when mounted on a 96-inch-(2440-mm) high ceiling.

D. Ultrasonic/Microphonic Type: Ceiling mounted; detect occupants in coverage area through pattern changes of reflected ultrasonic energy.

1. Detector Sensitivity: Detect a person of average size and weight moving not less than 12 inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12 inches/s (305 mm/s).

2. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.

E. Dual-Technology Type: Ceiling mounted; detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of
technologies that control on-off functions is selectable in the field by operating controls on unit.

1. Sensitivity Adjustment: Separate for each sensing technology.
2. Detector Sensitivity: Detect occurrences of 6-inch- (150-mm-) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm), and detect a person of average size and weight moving not less than 12 inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12 inches/s (305 mm/s).
3. Detection Coverage (Corridor): Detect occupancy anywhere within 48 feet (18.0 m) when mounted on a 10-foot- (3-m-) high ceiling in a corridor not wider than 12 feet (3.7 m).
4. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.
5. Detection Coverage (corner mount): Detect occupancy anywhere within a 30 foot (9145 mm) radius when corner mounted at ceiling or on wall at 120-inches (3058 mm) above the finished floor. Provide stem mount as required to maintain manufacturer’s recommended mounting height.
6. Detection Coverage (high bay): Detect occupancy anywhere within a 20 foot (6096 mm) radius when mounted at ceiling at 180-inches (4572 mm) above the finished floor. Provide stem mount as required to maintain manufacturer’s recommended mounting height.

2.5 SWITCHBOX-MOUNTED LOW VOLTAGE OCCUPANCY/VACANCY SENSORS

A. Subject to compliance with requirements, provide Sensor Switch nWSX-PDT-LV or nWSX-PDT-LV-DX (On/Off or Dimming to match function indicated on the drawings) or comparable product by one of the following:

1. Wattstopper DLM
2. Hubbell NX
3. Eaton

B. General Description: Wall-mounting, solid-state units suitable for mounting in a single-gang switchbox.

1. Operation:

a. Occupancy Sensor Mode: Automatic-on when coverage area is occupied, and automatic-off when unoccupied.

b. Vacancy Sensor Mode: Manual-on when coverage area is occupied, and automatic-off when unoccupied.
c. Time Delay for turning lights off, adjustable over a minimum range of 1 to 30 minutes in 1-minute increments. Default setting: 15 minutes.

2. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A.
3. Mounting:

a. Sensor: Suitable for mounting in a standard outlet box.
b. Time-Delay and Sensitivity Adjustments: Recessed and concealed.

4. Indicator: LED, to show when motion is being detected during testing and normal operation of the sensor.
5. Bypass Switch: Override the on function in case of sensor failure.

C. Dual-Technology Type: Wall mounting; detect occupancy by using a combination of PIR and ultrasonic or microphonic detection methods in area of coverage. Particular technology or combination of technologies that controls on-off functions shall be selectable in the field by operating controls on unit.

1. Sensitivity Adjustment: separate for each sensing technology.
2. Detector Sensitivity: Detect occurrences of 6-inch (150 mm) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm), and detect a person of average size and weight moving not less than 12-inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12-inches/s (305 mm/s).
3. Detection Coverage: (Standard Room): Detect occupancy anywhere within a 15 foot radius (4572 mm) when wall mounted at 48-inches (1220 mm) above finished floor.

2.6 LOW VOLTAGE SWITCHES

A. Basis-of-Design Product: Subject to compliance with requirements, provide nLight PODM, or comparable product by one of the following:

1. Wattstopper DLM
2. Hubbell NX
3. Eaton

B. General Description: Low-voltage, momentary pushbutton switches in 1, 2, 3, 4, 5, and 8 button configuration with the following features.

1. Two-way infrared (IR) transceiver for use with personal, and configuration remote controls.

2. Removable buttons for field replacement with engraved buttons and/or alternate color buttons. Button replacement may be completed without removing the switch from the wall.
3. Configuration LED on each switch that blinks to indicate data transmission.
4. Load/Scene Status LED on each switch button with the following characteristics:

    a. Bi-level LED
    b. Dim locator level indicates power to switch
    c. Bright status level indicates that load or scene is active

5. Dimming switches shall include seven bi-level LEDs to indicate load levels using 14 steps.

C. Two RJ-45 ports for connection to local network.

D. Multiple digital wall switches may be installed in a room by simply connecting them to the free topology local network. No additional configuration will be required to achieve multi-way switching.

E. The following switch attributes may be changed or selected using a wireless configuration tool:

1. Load and Scene button function may be reconfigured for individual buttons (from Load to Scene, and vice versa).
2. Individual button function may be configured to Toggle, On only, or Off only.
3. Individual scenes may be locked to prevent unauthorized change.
4. Fade Up and Fade Down times for individual scenes may be adjusted from 0 seconds to 18 hours.
5. Ramp rate may be adjusted for each dimmer switch.
6. Switch buttons may be bound to any load on a room controller and are not load type dependent; each button may be bound to multiple loads.

2.7 DIGITAL ROOM CONTROLLERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide nLight nPP16 or comparable product by one of the following:

1. Wattstopper DLM
2. Hubbell NX
3. Eaton

B. Description: Self configuring, digitally addressable one, two or three relay controllers with 0-10 volt control for drivers and single relay application-specific plug load controllers (if applicable) Room controllers shall be provided to match room lighting load and control requirements and have the following features:

1. Automatic room configuration to the most energy-efficient sequence of operation based upon the devices in the room.
2. Simple replacement – Using the default automatic configuration capabilities, a room controller may be replaced with an off-the-shelf unit without requiring any configuration or setup.
3. Device Status LEDs to indicate:

    a. Data transmission.
    b. Device has power.
    c. Status for each load.
    d. Configuration status.

4. Quick installation features including:
    a. Standard junction box mounting.
    b. Quick low voltage connections using standard RJ-45 patch

5. Plenum rated.
6. Manual override and LED indication for each load.
7. Dual voltage (120/277 VAC, 60 Hz)
8. Zero cross circuitry for each load.
9. Controllers shall be equipped for fail-safe operation and shall be evaluated for this purpose.
10. Controllers shall be activated by activation of the building fire alarm system.
11. Controllers shall be equipped for activation by the building security system.

C. On/Off/Dimming enhanced room controllers shall include:

1. Real time current monitoring.
2. One, two or three relay configuration.
3. Efficient 250 mA switching power supply.
4. Four RJ-45 local network ports.
5. One 0-10 volt analog output per relay for control of compatible LED drivers.
6. Optional Network Bridge for BACnet MS/TP communications (LMRC-3xx).
7. The following dimming attributes may be changed or selected using a wireless configuration tool:

    a. Establish preset level for each load from 0-100%.

    b. Set high and low trim for each load.
    c. Set lamp burn in time for each load up to 100 hours.

8. Discrete model listed for connection to receptacles, for occupancy-based control of plug loads within the space.

    a. One relay configuration only.
    b. Automatic-ON/OFF configuration.

2.8 CONFIGURATION TOOL

A. Basis-of-Design Product: Subject to compliance with requirements, provide nLight, or comparable products by one of the following:

1. Wattstopper DLM
2. Hubbell NX
3. Eaton

B. A configuration tool facilitates customization of local networks, and is used to set up open loop daylighting sensors. A wireless configuration tool features infrared communications, while PC software connects to each local network via a USB interface. Features and functionality of the wireless configuration tool shall include:

1. Two-way infrared (IR) communication with IR-enabled devices within a range of approximately 30 feet.
2. High visibility organic LED (OLED) display, pushbutton user interface and menu-driven operation.
3. Read, modify and send parameters for occupancy sensors, daylighting sensors, room controllers and buttons on digital wall switches.
4. Save up to nine occupancy sensor setting profiles, and apply profiles to selected sensors.
5. Temporarily adjust light level of any load(s) on the local network, and incorporate those levels in scene setting.
6. Adjust or fine-tune daylighting settings established during auto-commissioning, and input light level data to complete commissioning of open loop daylighting controls.

2.9 EMERGENCY SHUNT RELAY

A. Basis-of-Design Product: Subject to compliance with requirements, provide Bodine or comparable product by one of the following:

1. Lighting Control and Design, Inc.
2. Nine Twenty Four.

B. Description: Normally closed, electrically held relay, arranged for wiring in parallel with manual or automatic switching contacts; complying with UL 1008 and/or UL 924.

1. Coil Rating: 120 / 277 V.

2.10 CONDUCTORS AND CABLES

A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than No. 12 AWG. Comply with requirements in Division 26 Section, Low-Voltage Electrical Power Conductors and Cables.

B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 24 AWG. Comply with requirements in Division 26 Section 260519, *Low-Voltage Electrical Power Conductors and Cables*.

C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Division 26 Section 260519, *Low-Voltage Electrical Power Conductors and Cables*."

PART 3 - EXECUTION

3.1 SENSOR INSTALLATION

A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression systems, and partition assemblies.

B. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.

3.2 CONTACTOR INSTALLATION

A. Mount electrically held lighting contactors with elastomeric isolator pads, to eliminate structure-borne vibration, unless contactors are installed in an enclosure with factory-installed vibration isolators.

3.3 WIRING INSTALLATION

A. Wiring Method: Comply with Division 26 Section 260519, *Low-Voltage Electrical Power Conductors and Cables*. Minimum conduit size shall be 1/2 inch (13 mm).

B. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and nonpower-limited conductors according to conductor manufacturer's written instructions.

C. Size conductors according to lighting control device manufacturer's written instructions, unless otherwise indicated.

D. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

3.4 IDENTIFICATION

A. Identify components and power and control wiring according to Division 26 Section 260553, *Electrical Identification*.

1. Identify controlled circuits in lighting contactors.
2. Identify circuits or luminaries controlled by photoelectric and occupancy sensors at each sensor.

B. Label time switches and contactors with a unique designation.

3.5 FIELD QUALITY CONTROL

A. Perform the following field tests and inspections and prepare test reports:

1. After installing time switches and sensors, and after electrical circuitry has been energized, adjust and test for compliance with requirements.
2. Operational Test: Verify operation of each lighting control device, and adjust time delays.

B. Lighting control devices that fail tests and inspections are defective work.

C. Prepare test and inspection reports.

3.6 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting sensors to suit occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

1. For occupancy and motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.
2. For daylighting controls, adjust set points and deadband controls to suit Owner's operations.

3.7 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain lighting control devices. Refer to Division 01 Section 017900, *Demonstration and Training*.

END OF SECTION 26 09 23

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 24 16
PANELBOARDS

PART 1 - GENERAL

1.1. RELATED DOCUMENTS

A. Drawings and general provision of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2. SUMMARY

A. This Section includes distribution panelboards, lighting and power panelboards and fusible circuit breaker panelboards with associated auxiliary equipment rated 600 V and less.

B. Related Sections include the following:

1. Division 26 Section 264300, Surge Protection Devices.

1.3. SUBMITTALS

A. Product Data: For each type of panelboard, switching and overcurrent protective device, transient voltage suppression device, accessory, and component indicated. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, and finishes.

B. Shop Drawings: For each panelboard and related equipment.

1. Include dimensioned plans, elevations, sections, and details. Show tabulations of installed devices, equipment features, and ratings.
2. Detail enclosure types and details for types other than NEMA 250, Type 1.
3. Detail bus configuration, current, and voltage ratings.
4. Short-circuit current rating of panelboards and overcurrent protective devices.
5. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
6. Include wiring diagrams for power, signal, and control wiring.
7. Include time-current coordination curves for each type and rating of overcurrEnt protective device included in panelboards. Submit on translucent log-log graft paper; include selectable ranges for each type of overcurrent protective device.

C. Qualification Data: For qualified testing agency.

D. Field Quality-Control Reports:

1. Test procedures used.
2. Test results that comply with requirements.
3. Results of failed tests and corrective action taken to achieve test results that comply with requirements.

E. Panelboard Schedules: For installation in panelboards. Submit final versions after load balancing.

F. Operation and Maintenance Data: For panelboards and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:

1. Manufacturer's written instructions for testing and adjusting overcurrent protective devices.

G. Time current curves, including selectable ranges for each type of overcurrent protective device that allows adjustments.

1.4. QUALITY ASSURANCE

A. Testing Agency Qualifications: Member company of NETA or an NRTL.

1. Testing Agency's Field Supervisor: Currently certified by NETA to supervise on-site testing.

B. Source Limitations: Obtain panelboards, overcurrent protective devices, components, and accessories from single source from single manufacturer.

C. Product Selection for Restricted Space: Drawings indicate maximum dimensions for panelboards including clearances between panelboards and adjacent surfaces and other items. Comply with indicated maximum dimensions.

D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

E. Comply with NEMA PB 1.

F. Comply with NFPA 70.

1.5. EXTRA MATERIALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Keys: 2 spares of each type for panelboard cabinet lock.

2. Fuses for Fused Switches: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.

3. Fuses for Fused Power-Circuit Devices: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.

1.6. DELIVERY, STORAGE, AND HANDLING

A. Remove loose packing and flammable materials from inside panelboards; install temporary electric heating (250 W per panelboard) to prevent condensation.

B. Handle and prepare panelboards for installation according to NEMA PB 1.

1.7. PROJECT CONDITIONS

A. Environmental Limitations:

1. Do not deliver or install panelboards until spaces are enclosed and weathertight, wet work in spaces is complete and dry, work above panelboards is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.
2. Rate equipment for continuous operation under the following conditions unless otherwise indicated:

    a. Ambient Temperature: Not exceeding 23 deg F (minus 5 deg C) to plus 104 deg F (plus 40 deg C).
    b. Altitude: Not exceeding 6600 feet (2000 m).

B. Service Conditions: NEMA PB 1, usual service conditions, as follows:

1. Ambient temperatures within limits specified.
2. Altitude not exceeding 6600 feet (2000 m).

1.8. COORDINATION

A. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

1.9. WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace transient voltage suppression devices that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1. GENERAL REQUIREMENTS FOR PANELBOARDS

A. Product Selection for Restricted Space: Drawings indicate maximum dimensions for panelboards including clearances between panelboards and adjacent surfaces and other items. Comply with indicated maximum dimensions.

B. Enclosures: Flush- and surface-mounted cabinets. Piano hinged doors and covers.

1. Rated for environmental conditions at installed location.

a. Indoor Dry and Clean Locations: NEMA 250, Type 1.
b. Other Wet or Damp Indoor Locations: NEMA 250, Type 4X, stainless steel.
c. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 12.

2. Hinged Front Cover: Entire front trim piano hinged to box and with piano hinged door within hinged trim cover.

3. Finishes:

a. Panels and Trim: Steel, factory finished immediately after cleaning and pretreating with manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
b. Back Boxes: Same finish as panels and trim.

4. Directory Card: Inside panelboard door, mounted in metal frame with transparent protective cover.
5. Multiple-Section Panelboards shall consist of two or more cabinets with identical interiors mounted under separate trims. Cabinets, trim, and doors shall be of the same size. Main lugs and busses of each section shall be rated as indicated on the Drawings. Where main breakers are indicated in multi-section panelboards, the main breaker shall be contained in one section with through-feed lugs and sub-feed cables installed within panel, equal to the incoming feeder size. All busses and lugs shall have ampere capacity equal to or greater than the main breaker

ampere rating. Loads shall be divided as evenly as practical between the sections, in addition to being balanced over the phases.

C. Incoming Mains Location: Top and bottom.

D. Phase, Neutral, and Ground Buses:

1. Material: Hard-drawn copper, 98 percent conductivity.
2. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment grounding conductors; bonded to box.
3. Extra-Capacity Neutral Bus: Neutral bus rated 200 percent of phase bus and UL listed as suitable for nonlinear loads.

E. Conductor Connectors: Suitable for use with conductor material and sizes.

1. Material: Hard-drawn copper, 98 percent conductivity.
2. Main and Neutral Lugs: Compression type.
3. Ground Lugs and Bus-Configured Terminators: Compression type.
4. Feed-Through Lugs: Compression type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.
5. Subfeed (Double) Lugs: Compression type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.
6. Extra-Capacity Neutral Lugs: Rated 200 percent of phase lugs mounted on extra-capacity neutral bus.

F. Future Devices: Mounting brackets, bus connections, filler plates, and necessary appurtenances required for future installation of devices.

G. Short-Circuit Current Rating: Fully rated to interrupt symmetrical short-circuit current available at terminals.

H. Provide integral surge suppression device for each panel with SPD disconnect indicated in schedule on the drawings.

2.2. LIGHTING AND APPLICANCE PANELBOARDS

A. Basis-of-Design Product: Subject to compliance with requirements, provide Square D; a brand of Schneider Electric or comparable product by one of the following:

1. ABB-GE Electrification Equipment
2. Eaton Corp.; Cutler-Hammer.
3. Siemens Energy & Automation, Inc.

B. Panelboards: NEMA PB 1, lighting and appliance branch-circuit type.

C. Mains: Circuit breaker or lugs only, as indicated.

D. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.

E. Doors: Piano hinged doors and covers. Concealed hinges; secured with flush latch with tumbler lock; keyed alike.

2.3. DISCONNECTION AND OVERCURRENT PROTECTIVE DEVICES

A. Basis-of-Design Product: Subject to compliance with requirements, provide Square D; a brand of Schneider Electric or comparable product by one of the following:

1. ABB-GE Electrification Equipment
2. Eaton Corp.; Cutler-Hammer.
3. Siemens Energy & Automation, Inc.

B. Molded-Case Circuit Breaker (MCCB): Comply with UL 489, with interrupting capacity to meet available fault currents.

1. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads, and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 100A through 225A, field adjustable short-time and continuous current setting for frame sizes 250A and larger.
2. GFCI Circuit Breakers: Single-and two-pole configurations with Class A ground-fault protection (6-mA trip).
3. Ground Fault Equipment Protection (GFEP) Circuit Breakers; Class B Ground Fault Protection (30-mA trip).
4. Molded-Case Circuit-Breaker (MCCB) Features and Accessories:

a. Standard frame sizes, trip ratings, and number of poles.
b. Lugs: Compression style, suitable for number, size, trip ratings, and conductor materials.
c. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and high-intensity discharge (HID) lighting circuits.
d. Ground-Fault Protection: Integrally mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
e. Shunt Trip: 120-V trip coil energized from separate circuit, set to trip at 55 percent of rated voltage.
f. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.
g. Handle Clamp: Loose attachment for holding circuit breaker handle in ON position for breakers serving clocks, telephone, and communications equipment, refrigerators, exit signs, fire alarm systems, controls, etc., to prevent accidental operation.

PART 3 - EXECUTION

3.1. EXAMINATION

A. Receive, inspect, handle, and store panelboards according to NEMA PB 1.1.

B. Examine panelboards before installation. Reject panelboards that are damaged or rusted or have been subjected to water saturation.

C. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of the Work.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2. INSTALLATION

A. Install panelboards and accessories according to NEMA PB 1.1.

B. Mount top of trim 90 inches (2286 mm) above finished floor unless otherwise indicated.

C. Mount panelboard cabinet plumb and rigid without distortion of box. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.

D. Install overcurrent protective devices and controllers not already factory installed.

1. Set field-adjustable, circuit-breaker trip ranges.

E. Install filler plates in unused spaces.

F. Arrange conductors in gutters into groups and bundle and wrap with wire ties after completing load balancing.

G. Comply with NECA 1.

H. Conduits entering the tops and bottoms of flush panels shall be located back from the front ledge of the panels to allow approximately 2-inches between the finished wall and the edge of the conduits.

I. Surge protective device units shall be installed immediately above or below panelboard enclosure, per manufacturer’s recommendations, connected to circuit breaker disconnecting means with lead length of conductors less than 18 inches.

3.3. IDENTIFICATION

A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs complying with Division 26 Section "Identification for Electrical Systems."

B. Create a directory to indicate installed circuit loads after balancing panelboard loads; incorporate Owner's final room designations. Obtain approval before installing. Use a computer or typewriter to create directory; handwritten directories are not acceptable.

C. Panelboard Nameplates: Label each panelboard with a nameplate complying with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."

D. Device Nameplates: Label each branch circuit device in distribution panelboards with a nameplate complying with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."

E. Install warning signs complying with requirements in Section 260553 "Identification for Electrical Systems" identifying source of remote circuit.

3.4. FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.

B. Acceptance Testing Preparation:

1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
2. Test continuity of each circuit.

C. Tests and Inspections:

1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.

D. Panelboards will be considered defective if they do not pass tests and inspections.

E. Prepare test and inspection reports, including a certified report that identifies panelboards included and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5. ADJUSTING

A. Adjust moving parts and operable component to function smoothly, and lubricate as recommended by manufacturer.

B. Set field-adjustable circuit-breaker trip ranges as indicated.

C. Load Balancing: After Substantial Completion, but not more than 60 days after Final Acceptance, measure load balancing and make circuit changes.

1. Measure as directed during period of normal system loading.
2. Perform load-balancing circuit changes outside normal occupancy/working schedule of the facility and at time directed. Avoid disrupting critical 24-hour services such as fax machines and on-line data processing, computing, transmitting, and receiving equipment.
3. After circuit changes, recheck loads during normal load period. Record all load readings before and after changes and submit test records.
4. Tolerance: Difference exceeding 20 percent between phase loads, within a panelboard, is not acceptable. Rebalance and recheck as necessary to meet this minimum requirement.
5. Set field-adjustable circuit-breaker trip ranges as specified in Section 260.

3.6. PROTECTION

A. Temporary Heating: Apply temporary heat to maintain temperature according to manufacturer's written instructions.

END OF SECTION 26 24 16

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 27 26
WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Receptacles and associated device plates.
2. Wall-switch.

B. Related sections include the following:

1. Section 260923 – Lighting Control Devices

1.3 DEFINITIONS

A. EMI: Electromagnetic interference.

B. GFCI: Ground-fault circuit interrupter.

C. Pigtail: Short lead used to connect a device to a branch-circuit conductor.

D. RFI: Radio-frequency interference.

E. SPD: Surge suppression device.

F. UTP: Unshielded twisted pair.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Receptacles for Owner-Furnished Equipment: Match plug configurations.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: List of legends and description of materials and process used for premarking wall plates.

1.6 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

1.7 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packing-label warnings and instruction manuals that include labeling conditions.

1.8 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers' Names: Shortened versions (shown in parentheses) of the following manufacturers' names are used in other Part 2 articles:

1. Hubbell Incorporated; Wiring Device-Kellems (Hubbell).
2. Leviton Mfg. Company Inc. (Leviton).
3. Pass & Seymour/Legrand (Pass & Seymour).

B. Source Limitations: Obtain each type of wiring device and associated wall plate from single source from single manufacturer.

2.2 STRAIGHT-BLADE RECEPTACLES

A. General Requirements

1. Straight blade receptacles shall have the following basic features:

a. One-piece brass mounting strap with integral ground for low resistance of fault currents.

b. Auto-ground clip to assure positive ground.

c. Impact-resistant nylon/thermoplastic face and base housing.

d. #10 large head brass terminal and ground screws.

B. Duplex Convenience Receptacles

1. Duplex convenience receptacles shall be extra heavy-duty, specification grade, 20A, 125V.
2. Comply with NEMA WD-1, NEMA WD-6 configuration 5-20R, UL 498 and Federal Specification W-C-596.
3. Hubbell HBL5362, or approved equal by acceptable manufacturer.

C. Single Convenience Receptacles

1. Single convenience receptacles shall be extra heavy-duty, specification grade, 20A, 125V.
2. Comply with NEMA WD-1, NEMA WD-6 configuration 5-20R, UL 498 and Federal Specification W-C-596.
3. Hubbell HBL5361, or approved equal by acceptable manufacturer.

D. Special Purpose Receptacles

1. Special purpose receptacles shall have ratings and NEMA configurations as indicated on the Drawings, or as required to match equipment plug configuration, and shall be black with device plate to match outlet type.

E. Controlled/Switched Receptacle

1. Controlled/Switched Receptacles shall be 125 V, 20 A and comply with NEMA WD 1, NEMA WD 6 Configuration 5-20R, UL 498 Supplement sd, and FS W-C-596.
2. Hubbell; BR20* or approved equal by acceptable manufacturer.
3. Provide with controlled receptacle marking with custom engraving/pad printing on device plate device with the words “Controlled Receptacle.”

F. Hospital-Grade Duplex Receptacles

1. Duplex hospital-grade receptacles shall be 20A, 125V.
2. Description: Single-piece, rivetless, nickel-plated, all-brass grounding system. Nickel-plated, brass mounting strap. Two pole, three wire, and self-grounding.
3. Configuration: NEMA WD 6, Configuration 5-20R.
4. Standards: Comply with UL 498 Supplement sd and FS W-C-596.
5. Marking: Listed and labeled as complying with NFPA 70, "Health Care Facilities" Article.

2.3 TOGGLE SWITCHES

A. General Requirements

1. Switches shall have the following basic features:

   a. Heavy-gauge one-piece copper alloy contact arm.
   b. Fast "make" and positive "break" to minimize arcing.
   c. Heavy-duty bumper pads for quiet operation.
   d. High strength thermoplastic polycarbonate toggle.
   e. Oversized silvery alloy contacts for long life and heat dissipation.
   f. Nickel-plated steel strap with integral ground.
   g. Auto-ground clip to assure positive ground.

B. Toggle Switches

1. Toggle switches shall be quiet-type, extra heavy-duty, industrial grade, 120/277V, 20A: Comply with NEMA WD 1, UL 20 and Federal Specification W-S-896.
2. Hubbell HBL1221 (single-pole), HBL1222 (two-pole), HBL1223 (three-way), HBL1224 (four-way), or approved equal by acceptable manufacturer.

C. Key (Locking) Switches

1. Key (locking) switches shall be quiet-type, extra heavy-duty, industrial grade, 120/277V, 20A with the following features:

   a. Furnished with key for locking switch.

2. Comply with NEMA WD 1, UL 20 and Federal Specification W-S-896.
3. Hubbell HBL1221L (single-pole), HBL1222L (two-pole), HBL1223L (three-way), HBL1224L (four-way), or approved equal by acceptable manufacturer.

2.4 WALL PLATES

A. Device plates shall be provided for all switches and receptacles. Device plates shall be as manufactured to fit each type of single device, to fit devices which are ganged together, and they shall be same manufacturer as wiring devices with finish as follows:

1. Material for Finished Spaces: 0.04-inch thick, Type 430 satin finished stainless steel.
2. Material for Unfinished Spaces: Galvanized steel.
3. Color: Matches wiring device, except as otherwise indicated. To match existing device plates.
4. Plate-Securing Screws: Metal with heads colored to match plate finish.

B. Provide jumbo size plates for outlets installed in masonry walls.

2.5 FINISHES

A. Device Color:

1. Wiring Devices Connected to Normal Power System: White unless otherwise indicated or required by NFPA 70 or device listing.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Comply with NECA 1, including mounting heights listed in that standard, unless otherwise indicated.

B. Coordination with Other Trades:

1. Protect installed devices and their boxes. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of boxes.
2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
4. Install wiring devices after all wall preparation, including painting, is complete.

C. Conductors:

1. Do not strip insulation from conductors until right before they are spliced or terminated on devices.
2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70, Article 300, without pigtails.
4. Existing Conductors:

a. Cut back and pigtail, or replace all damaged conductors.
b. Straighten conductors that remain and remove corrosion and foreign matter.
c. Pigtailing existing conductors is permitted, provided the outlet box is large enough.

D. Device Installation:

1. Replace devices that have been in temporary use during construction and that were installed before building finishing operations were complete.
2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
4. Connect devices to branch circuits using pigtails that are not less than 6 inches (152 mm) in length.
5. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, two-thirds to three-fourths of the way around terminal screw.
6. Use a torque screwdriver when a torque is recommended or required by manufacturer.
7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
8. Tighten unused terminal screws on the device.
9. When mounting into metal boxes, remove the fiber or plastic washers used to hold device-mounting screws in yokes, allowing metal-to-metal contact.

E. Receptacle Orientation:

1. Install ground pin of vertically mounted receptacles up, and on horizontally mounted receptacles to the left, unless otherwise noted.

F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.

G. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.

3.2 IDENTIFICATION

A. Comply with Division 26 Section "Identification for Electrical Systems."

B. Identify each receptacle with panelboard identification and circuit number. Use hot, stamped, or engraved machine printing with black-filled lettering on face of plate, and durable wire markers or tags inside outlet boxes.

3.3 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Test Instruments: Use instruments that comply with UL 1436.
2. Test Instrument for Convenience Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.

B. Tests for Convenience Receptacles:

1. Line Voltage: Acceptable range is 105 to 132 V.
2. Percent Voltage Drop under 15-A Load: A value of 6 percent or higher is unacceptable.
3. Ground Impedance: Values of up to 2 ohms are acceptable.
4. Using the test plug, verify that the device and its outlet box are securely mounted.
5. Tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.

C. Wiring device will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

3.4 CLEANING

A. Internally clean devices, device outlet boxes, and enclosures. Replace stained or improperly painted wall plates or devices.

END OF SECTION 26 27 26

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 43 13
SURGE PROTECTIVE DEVICES

PART 1. GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract including General and Supplementary Conditions and Division 01 Specification Sections apply to this section.

1.2 SUMMARY

A. Description: This section describes the materials and installation requirements for integral and stand alone Surge Protective Devices (SPDs) for the protection of all AC electrical circuits from the effects of lightning induced currents, substation switching transients and internally generated transients resulting from inductive and/or capacitive load switching. SPD's shall be installed integral with equipment unless otherwise indicated.

1.3 DEFINITIONS

A. Inominal: Nominal discharge current.

B. MCOV: Maximum continuous operating voltage.

C. Mode(s), also Modes of Protection: air of electrical connections where the VPR applies.

D. MOV: Metal-oxide varistor; an electronic component with a significant non-ohmic current-voltage characteristic.

E. NRTL: Nationally recognized testing laboratory.

F. OCPD: Overcurrent protective device.

G. SCCR: Short-circuit current rating.

H. SPD: Surge protective device.

I. Type 1 SPDs: Permanently connected SPDs intended for installation between the secondary of the service transformer and the line side of the service disconnect overcurrent device.

J. Type 2 SPDs: Permanently connected SPDs intended for installation on the load side of the service disconnect overcurrent device, including SPDs located at the branch panel.

K. VPR: Voltage protection rating.

1.4 REFERENCES

A. ANSI/IEEE C62.41 - IEEE Recommended Practice on Surge Voltages in Low Voltage AC Power Circuits.

B. ANSI/EEE C62.45 - IEEE Recommended Practice on Surge Suppressor Testing.

C. FIPS Pub 94 (1983) - Guide on Electrical Power for ADP Installation.

D. National Electrical Code - Article 285

E. National Fire Protection Association - NFPA-20, NFPA-70, NFPA-75, NFPA-78.

F. NEMA LS-1 Low Voltage Surge Protection Devices.

G. NEMA 250 - Enclosures for Electrical Equipment.

H. UL 486A - Wire Connectors and Soldering Lugs for Use with Copper Conductors.

I. UL 1283 - Electromagnetic Interference Filters.

J. UL 1449, Fourth Edition - Surge Protective Devices.

1.5 SUBMITTALS

A. Product Data: Include rated capacities; shipping, installed, and operating weights; furnished specialties; and accessories for each model indicated. Indicate overcurrent protection requirements.

B. Field Test Reports: Indicate and interpret test results for compliance with performance requirements.

C. Maintenance Data: For surge protective devices to include in the maintenance manuals specified in Division 01.

D. Warranties: Special warranties as specified in this Section.

E. The submittals shall include:

1. UL 1449, Fourth Edition Listing documentation verifying:

A. Short Circuit Current Rating (SCCR)
B. Voltage Protection Ratings (VPRs) for all modes
C. Maximum Continuous Operating Voltage (MCOV) rating
D. I-nominal (I-n) rating
E. Type 1 Device listing

2. VPR, MCOV, I-n and Type 1 information is posted at www.UL.com, under Certifications. SCCRs are posted in manufacturer's UL documents.
3. UL Standard 1283 Listing, documentation.
4. UL data and visual inspection take precedence over manufacturer's published documentation.

F. Submittals shall include shop drawings including the following:

1. Manufacturer's installation instruction manual and line drawings detailing dimensions and weights of enclosure.
2. Internal wiring diagram illustrating all modes of protection in each type of SPD required.
3. Wiring diagram showing all field connections and manufacturer's recommended wire and circuit breaker sizes.

G. Upon request, an encapsulated but complete SPD shall be presented for visual inspection. MOV type & quantity shall reflect kA ratings on product data sheets, verification of diagnostic monitoring, thermal & overcurrent protection, etc.

1.6 QUALITY ASSURANCE

A. Listing and Labeling: Provide electrically operated equipment specified in this Section that is listed and labeled.

1. The Terms *Listed* and *Labeled*: As defined in the National Electrical Code, Article 100.
2. Listing and Labeling Agency Qualifications: A *Nationally Recognized Testing Laboratory* as defined in OSHA Regulation 1910.7.
3. Comply with NFPA-70.

1.7 WARRANTY

A. General Warranty: The special warranty specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the contract Documents and shall be in addition to, and run concurrent with, other warranties made under requirements of the Contract Documents.

B. Special Warranty: A written warranty, executed by manufacturer, agreeing to repair or replace components of Surge Protective Devices that fail in materials or workmanship within the specified warranty period.

1. Warranty Period: Five (5) years (minimum) from date of Substantial Completion.

PART 2. PRODUCTS

2.1 MANUFACTURERS

A. Provide integral SPD from equipment manufacturer that meets the following requirements. For external devices, the following listed manufacturers provide units of acceptable quality. Verify that all proposed units meet the specified requirements.
   1. Advanced Protection Technologies, Inc.
   2. EFI Electronics Corporation.
   3. Liebert Corporation.
   4. Current Technology, Inc.
   5. LEA Dynatech, Inc.

2.2 SURGE PROTECTIVE DEVICES

A. SPD shall be UL labeled with 200kA Short Circuit Current Rating (SCCR). Fuse ratings shall not be considered in lieu of demonstrated withstand testing of SPD, per NEC 285.6.

B. SPD shall be UL labeled as Type 1 (verifiable at UL.com), intended for use without need for external or supplemental overcurrent controls. Every suppression component of every mode, including N-G, shall be protected by internal overcurrent and thermal over-temperature controls. SPDs relying upon external or supplementary installed safety disconnects do not meet the intent of this specification.

C. SPD shall be UL labeled with 20kA I-nominal (I-n) (verifiable at UL.com) for compliance to UL 96A Lightning Protection Master Label and NFPA 780.

D. Suppression components shall be heavy duty ‘large block’ MOVs, each exceeding 30mm diameter.

E. Minimum surge current capability (single pulse rated) per phase shall be:

   Branch Panelboards: 100kA

F. SPD shall provide surge current paths for all modes of protection: L-N, L-G, L-L and N-G for Wye systems; L-L, L-G in Delta and impedance grounded Wye systems.

G. UL 1449 Listed Voltage Protection Ratings (VPRs) shall not exceed the following:

System Voltage	L-N	L-G	L-L	N-G
208Y/120	700V	700V	1200V	700V

(Mode VPRs verifiable at UL.com. Numerically lower is allowed/preferred; old-style Suppressed Voltage Ratings (SVRs) shall not be submitted, nor evaluated due to outdated less-strenuous testing)

H. UL 1449 Listed Maximum Continuous Operating Voltage (MCOV):

System Voltage	Allowable System Voltage Fluctuation (%)	MCOV
208Y/120	25%	150V

I. SPD shall include a serviceable, replaceable module (excluding Branch).

J. SPD shall have UL 1283 EMI/RFI filtering with minimum attenuation of -50dB at 100kHz.

K. SPD shall include visual LED diagnostics including a minimum of one green LED indicator per phase, and one red service LED. SPD shall include an audible alarm with on/off silence function and diagnostic test function (excluding branch).

L. SPD shall be provided with the following options:

1. One (1) set of NO/NC dry contacts
2. Surge event counter with back-up power source
3. Integral disconnect switch.

2.3 ENCLOSURES

A. Mount integral in panel enclosure unless otherwise indicated. For applications where stand alone mounting is indicated or required, provide the following enclosures:

1. Indoor Enclosures: NEMA 250, Type 1.

PART 3. EXECUTION

3.1 INSTALLATION

A. Comply with NECA 1.

B. Install an OCPD or disconnect as required to comply with the UL listing of the SPD.

C. Install SPDs with conductors between suppressor and points of attachment as short and straight as possible, and adjust circuit-breaker positions to achieve shortest and straightest leads. Do not splice and extend SPD leads unless specifically permitted by manufacturer. Do not exceed manufacturer's recommended lead length. Do not bond neutral and ground.

D. Use crimped connectors and splices only. Wire nuts are unacceptable.

E. Tighten electrical connectors and terminals according to manufacturer’s published torque-tightening values. If manufacturer’s torque values are not indicated, use those specified in UL 486A and UL 486B.

3.2 FIELD QUALITY CONTROL

A. Perform the following tests and inspections with the assistance of a factory-authorized service representative.

1. Compare equipment nameplate data for compliance with Drawings and Specifications.

2. Before energizing electrical circuitry, verify that the unit voltage and connecting equipment voltage is the same.

3. Inspect anchorage, alignment, grounding, and clearances.

4. Verify that electrical wiring installation complies with manufacturer's written installation requirements.

B. An SPD will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.3 STARTUP SERVICE

A. Complete startup checks according to manufacturer's written instructions. Do not perform insulation-resistance tests of the distribution wiring equipment with SPDs installed. Disconnect SPDs before conducting insulation-resistance tests, and reconnect them immediately after the testing is over.

B. Do not perform insulation-resistance tests of the distribution wiring equipment with SPDs installed. Disconnect SPDs before conducting insulation-resistance tests; reconnect them immediately after the testing is over.

C. Energize SPDs after power system has been energized, stabilized, and tested.

3.4 DEMONSTRATION

A. Train Owner's maintenance personnel to operate and maintain SPDs.

END OF SECTION 26 43 13

SECTION 26 51 00
INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Interior lighting fixtures.
2. LED lamps and drivers.
3. Emergency lighting units.
4. Exit signs.
5. Integral Emergency Lighting Power Units.
6. Lighting fixture supports.

B. Related Sections:

1. Division 26 Section "Lighting Control Devices" for automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors.
2. Division 26 Section "Wiring Devices" for snap switches and wall switches.

1.3 DEFINITIONS

A. CCT: Correlated color temperature.

B. CRI: Color-rendering index.

C. Fixture: See “Luminaire.”

D. IP: Ingress Protection or International Protection Rating.

E. LED: Light emitting diode.

F. Lumen: Measured output of lamp and luminaire, or both.

G. Luminaire: Complete lighting unit, including lamp, driver, reflector, and housing.

1.4 SUBMITTALS

A. Product Data: For each type of lighting fixture, arranged in order of fixture designation. Include data on features, accessories, finishes, and the following:

1. Physical description of lighting fixture including dimensions.
2. Emergency lighting units including battery and charger.
3. Drivers, including energy-efficiency data.
4. Energy-efficiency data.
5. Life, output (lumens, CCT, and CRI), and energy-efficiency data for lamps.
6. Photometric data and adjustment factors based on laboratory tests, complying with IESNA Lighting Measurements Testing & Calculation Guides, for each lighting fixture type. The adjustment factors shall be for lamps, ballasts, and accessories identical to those indicated for the lighting fixture as applied in this Project. Comply with IES LM-79, IES LM-80.

    a. Manufacturer Certified Data: Photometric data shall be certified by a manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products.

B. Shop Drawings: For nonstandard or custom lighting fixtures. Include plans, elevations, sections, and mounting and attachment details.

1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Wiring Diagrams: For power, signal, and control wiring.

C. Samples: For each lighting fixture indicated in the Interior Lighting Fixture Schedule. Each Sample shall include the following:

1. Lamps and drivers, installed.
2. Cords and plugs.

D. Installation instructions.

E. Product Certificates: For each type of driver for bi-level and dimmer-controlled fixtures, from manufacturer.

F. Field quality-control reports.

G. Operation and Maintenance Data: For lighting equipment and fixtures to include in emergency, operation, and maintenance manuals.

1. Provide a list of all lamp types used on Project; use ANSI and manufacturers' codes.

H. Warranty: Sample of special warranty.

1.5 QUALITY ASSURANCE

A. Luminaire Photometric Data Testing Laboratory Qualifications: Provided by manufacturers' laboratories that are accredited under the National Volunteer Laboratory Accreditation Program for Energy Efficient Lighting Products and complying with applicable IES testing standards.

B. Provide luminaires from a single manufacturer for each luminaire type.

C. Each luminaire type shall be binned within a three-step MacAdam Ellipse to ensure color consistency among luminaires.

D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

E. Comply with NFPA 70.

1.6 COORDINATION

A. Coordinate layout and installation of lighting fixtures and suspension system with other construction that penetrates ceilings or is supported by them, including HVAC equipment, fire-suppression system, and partition assemblies.

1.7 WARRANTY

A. Special Warranty for Emergency Lighting Batteries: Manufacturer's standard form in which manufacturer of battery-powered emergency lighting unit agrees to repair or replace components of rechargeable batteries that fail in materials or workmanship within specified warranty period.

1. Warranty Period for Emergency Lighting Unit Batteries: 10 years from date of Substantial Completion. Full warranty shall apply for first year, and prorated warranty for the remaining nine years.
2. Warranty Period for Emergency Battery Pack and Self-Powered Exit Sign Batteries: Seven years from date of Substantial Completion. Full warranty shall apply for first year, and prorated warranty for the remaining six years.

B. Special Warranty for Drivers: Manufacturer’s standard form in which driver manufacturer agrees to repair or replace drivers that fail in materials or workmanship within specified warranty period.

1. Warranty Period for Electronic Drivers: Five years from date of Substantial Completion.

1.8 EXTRA MATERIALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Lamps: 10 for every 100 of each type and rating installed. Furnish at least one of each type.
2. Plastic Diffusers and Lenses: One for every 100 of each type and rating installed. Furnish at least one of each type.
3. Battery and Charger Data: One for each emergency lighting unit.
4. Globes and Guards: One for every 20 of each type and rating installed. Furnish at least one of each type.
5. LED Modules (light engine and driver): Furnish at least (1) of each type.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. In Interior Lighting Fixture Schedule where titles below are column or row headings that introduce lists, the following requirements apply to product selection.

1. Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are limited to manufacturers specified, or equal per Lighting Fixture Schedule.

2.2 GENERAL REQUIREMENTS FOR LIGHTING FIXTURES AND COMPONENTS

A. Luminaires shall comply with UL 1598 and be listed and labeled for installation in wet locations by an NRTL acceptable to authorities having jurisdiction.

B. Metal Parts: Free of burrs and sharp corners and edges.

C. Sheet Metal Components: Steel unless otherwise indicated. Form and support to prevent warping and sagging.

D. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

E. Diffusers and Globes:

1. Acrylic Lighting Diffusers: 100 percent virgin acrylic plastic. High resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.

a. Lens Thickness: At least 0.125-inch (3.175 mm) minimum unless otherwise indicated.
b. UV stabilized.

2. Glass: Annealed crystal glass unless otherwise indicated.

F. Factory-Applied Labels: Comply with UL 1598. Include recommended lamps and ballasts. Labels shall be located where they will be readily visible to service personnel, but not seen from normal viewing angles when lamps are in place.

1. Label shall include the following lamp and ballast characteristics:

a. "USE ONLY" and include specific lamp type.
b. Lamp diameter, shape, size, wattage and coating.
c. CCT and CRI for all luminaires.

G. Recessed luminaires shall comply with NEMA LE 4.

2.3 EXIT SIGNS

A. General Requirements for Exit Signs: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply with authorities having jurisdiction.

B. Internally Lighted Signs:

1. Lamps for AC Operation: LEDs, 70,000 hours minimum rated lamp life.

2.4 LED LAMPS/LUMINAIRES

A. LED Luminaires: A LED luminaire consists of LED light engine and driver, heat-sink, fixture housing, and optic assembly where applicable.

1. Temperature: Minimum starting temperature of -30 deg C (-22 deg F), minimum 40 deg C (104 deg F) ambient temperature rating.
2. Life and Lumen Maintenance: L70 lamp life of 50,000 hours.
3. CRI and CCT: 3500 deg K (+/- 275 K) CCT and greater than 80 CRI.
4. Transient Voltage Protection: Rated to withstand 2.5 kV of transient line surge.
5. Photometric Data and Test Reports: Comply with IESNA LM-79-19, IESNA LM-80-15, and ANSI C78.377-17.
6. Radio Frequency Interference: Comply with CAP 106B Telecommunications (Control of Interference) Regulations.
7. Luminaires and components thereof shall comply with UL 8750 Standard of Safety.
8. Five-year warranty on luminaire including LED light engine and driver.
9. Power Factor: 90 percent minimum.
10. Total Harmonic Distortion Rating: Less than 20 percent.
11. RoHS compliant.
12. Sound Rating: Class A.

13. Overload, short circuit, and thermal protection.
14. Comply with UL 1598-14 NMX-J-307/1-ANCE/C22.2 NO.250-0-14, *Luminaires, LEDs.*

2.5 INTEGRAL EMERGENCY LIGHTING POWER UNITS

A. Provide emergency lighting power supply units for fixtures indicated on the drawings with integral emergency battery unit as specified herein.

1. Each fixture indicated to be provided with an emergency ballast shall be provided with an emergency power supply unit which consists of a package assembly containing a rechargeable sealed, maintenance-free nickel-cadmium battery, a rectifier/battery charger, a DC to AC inverter, and an electronic fluorescent ballast as specified elsewhere in these specifications. The battery shall have a normal life expectancy of 10 to 15 years with sufficient capacity to operate the lamp load at full normal brightness for 90 minutes. The float type charger shall be configured for operation at 120 volts. Units shall be UL approved for compliance with UL Standard 924 “Emergency Lighting and Power Equipment.”
2. Each unit shall be unconditionally guaranteed for a period of three years, with an additional three year pro-rated guarantee on the storage battery.

B. Operating Modes

1. Each emergency power supply unit shall automatically operate the lamp in the event of an AC power system failure for 90 minutes. When AC power is restored, the emergency power supply unit shall automatically return to the charging mode.

    a. MODE 1: Lamp is controlled by a switched AC ON/OFF circuit. Lamp automatically turns ON when AC power is lost. The unit is shipped from the factory connected for this mode of operation.
    b. MODE 2: Same as MODE 1 except lamp does not automatically turn ON when AC power is lost. This mode is established by adding a jumper between the AUTO and GND terminals.
    c. MODE 3: The unit can be used to provide continuous unswitched, uninterruptible light. A switched AC circuit is not used for this mode. To establish this mode of operation, connect a jumper between the OVER and GND terminals.
    d. MODE 4: The unit can be used to provide an unswitched light which is normally OFF but which automatically turns on when AC power is lost. This mode of operation is established by connecting only the unswitched AC circuit to the power supply unit.
    e. MODE 5: Lamp is turned on by external switch or relay contacts. The switched AC ON/OFF circuit is optional in this mode. The switch contacts "override" the (optional) switched AC circuit to turn the lamp on. In order for the lamp to be OFF, the external switch contacts must be open AND the switched AC circuit (if used) must be OFF. This mode is established by connecting the switch

contacts to OVER and GND. In this mode, the lamp will also be automatically turned ON in the event of AC power failure, unless this feature is disabled by connecting a jumper between the AUTO and GROUND terminals.

C. Power supply units for emergency lighting shall be provided with remote test switch to be mounted flush in ceiling adjacent to fixture. Power supply units shall be Lithonia Power Sentry PS3000, equal by Bodine, Emergi-Lite, or the same manufacturer of the lighting fixture as noted in the Lighting Fixture Schedule.

2.6 LIGHTING FIXTURE SUPPORT COMPONENTS

A. Comply with Division 26 Section "Hangers and Supports for Electrical Systems" for channel- and angle-iron supports and nonmetallic channel and angle supports.

B. Single-Stem Hangers: 1/2-inch (13-mm) steel tubing with swivel ball fittings and ceiling canopy. Finish same as fixture.

C. Twin-Stem Hangers: Two, 1/2-inch (13-mm) steel tubes with single canopy designed to mount a single fixture. Finish same as fixture.

D. Wires: ASTM A 641/A 641M, Class 3, soft temper, zinc-coated steel, 12 gauge (2.68 mm).

E. Wires for Humid Spaces: ASTM A 580/A 580M, Composition 302 or 304, annealed stainless steel, 12 gauge (2.68 mm).

F. Rod Hangers: 3/16-inch (5-mm) minimum diameter, cadmium-plated, threaded steel rod.

G. Hook Hangers: Integrated assembly matched to fixture and line voltage and equipped with threaded attachment, cord, and locking-type plug.EXECUTION

2.7 GENERAL

A. Comply with NECA/IESNA 500-2006 “Standard for Installing Indoor Commercial Lighting systems.”

2.8 INSTALLATION

A. Lighting fixtures:

1. Set level, plumb, and square with ceilings and walls unless otherwise indicated.
2. Install lamps in each luminaire.

B. Temporary Lighting: If it is necessary, and approved by Architect, to use permanent luminaires for temporary lighting, install and energize the minimum number of luminaires necessary. When construction is sufficiently complete, remove the temporary luminaires, disassemble, clean thoroughly, install new lamps, and reinstall.

C. Remote Mounting of Drivers: Distance between the driver and fixture shall not exceed that recommended by driver manufacturer. Verify, with driver manufacturers, maximum distance between driver and luminaire.

D. Integral Emergency Lighting Power Units:

1. Power supply units for emergency lighting shall be mounted on the top of the fixture housing as recommended by the manufacturer. If required, the units shall be permitted to be remote mounted up to 50 feet from the fixture per manufacturer's distant limitations, mounted on the building structure above the ceiling space. Where units are remote mounted, the final four-foot length of connecting raceway shall be Greenfield flexible metallic conduit to facilitate fixture removal.
2. Note that wherever an emergency lighting power supply unit is used in a circuit controlled by a light switch, a four wire connection to the AC power source is required - the switched wire, the hot wire, the neutral and ground.

E. Lay-in Ceiling Luminaire Supports: Use grid as a support element.

1. Install ceiling support system wires (Solid#12AWG safety wire), independent of the ceiling suspension devices, for each fixture. Locate not more than 6 inches (150 mm) from lighting fixture corners.
2. Support Clips: Fasten to lighting fixtures and to ceiling grid members at or near each fixture corner with clips that are UL listed for the application.
3. Fixtures of Sizes Less Than Ceiling Grid: Install as indicated on reflected ceiling plans or center in acoustical panel, and support fixtures independently with at least two 3/4-inch (20-mm) metal channels spanning and secured to ceiling tees.

F. Suspended Luminaire Support:

1. Pendants and Rods: Where longer than 48 inches (1200 mm), brace to limit swinging.
2. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
3. Continuous Rows: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of fixture chassis, including one at each end.

4. Do not use grid as support for pendant luminaires. Connect support wires or rods to building structure.

G. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

2.9 IDENTIFICATION

A. Install labels with panel and circuit numbers on concealed junction and outlet boxes. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."

2.10 FIELD QUALITY CONTROL

A. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.

B. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery and retransfer to normal.

C. Luminaire will be considered defective if it does not pass operation tests and inspections.

D. Prepare a written report of tests, inspections, observations, and verifications indicating and interpreting results. If adjustments are made to lighting system, retest to demonstrate compliance with standards.

2.11 STARTUP SERVICE

A. Comply with requirements for startup specified in Section 26 09 23 “Lighting Control Devices.”

2.12 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting aimable luminaires to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose. Some of this work may be required after dark.

1. During adjustment visits, inspect all luminaires. Replace lamps or luminaires that are defective.
2. Parts and supplies shall be manufacturer’s authorized replacement parts and supplies.
3. Adjust aimable luminaires in the presence of Architect.

PART 3 – EXECUTION (Not Used)

END OF SECTION 26 51 00

SECTION 27 15 13
DATA, VOICE AND VIDEO SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes an extension of the existing data, voice and video systems.:

1. Category 6 twisted pair cable.
2. Twisted pair cable hardware, including plugs and jacks.
3. Cabling identification products.
4. Source quality control requirements for twisted pair cable.
5. A/V cabling and jacks.

B. Related Sections include the following:

1. Division 26 Section 26 05 01 “Common Work Results for Electrical” for general materials and installation methods.
2. Division 26 Section 26 05 53 “Identification for Electrical Systems” for labeling materials.

1.3 DEFINITIONS

A. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.

B. EMI: Electromagnetic interference.

C. LAN: Local area network.

D. Jack: Also commonly called an "outlet," it is the fixed, female connector.

E. Plug: Also commonly called a "connector," it is the removable, male telecommunications connector.

F. RCDD: Registered Communications Distribution Designer.

G. UTP: Unscreened (unshielded) twisted pair.

1.4 COPPER HORIZONTAL CABLING DESCRIPTION

A. Horizontal cable cabling system shall provide interconnections between Distributor A, Distributor B, or Distributor C, and the equipment outlet, otherwise known as "Cabling Subsystem 1," in the telecommunications cabling system structure. Cabling system consists of horizontal cables, intermediate and main cross-connects, mechanical terminations, and patch cords or jumpers used for horizontal-to-horizontal cross-connection.

1. TIA-568-C.1 requires that a minimum of two equipment outlets be installed for each work area.
2. Horizontal cabling shall contain no more than one transition point or consolidation point between the horizontal cross-connect and the telecommunications equipment outlet.
3. Bridged taps and splices shall not be installed in the horizontal cabling.

B. A work area is approximately 100 sq. ft. (9.3 sq. m), and includes the components that extend from the equipment outlets to the station equipment.

C. The maximum allowable horizontal cable length is 295 feet (90 m). This maximum allowable length does not include an allowance for the length of 16 feet (4.9 m) to the workstation equipment or in the horizontal cross-connect.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Reviewed and stamped by RCDD.

1. System Labeling Schedules: Electronic copy of labeling schedules, in software and format selected by Owner.
2. Cabling administration Drawings and printouts.
3. Wiring diagrams and installation details of telecommunications equipment, to show location and layout of telecommunications equipment, including the following:

    a. Telecommunications pathways.
    b. Telecommunications conductor drop locations.
    c. Typical telecommunications details.

C. Twisted pair cable testing plan.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer, installation supervisor, and field inspector.

B. Product Certificates: For each type of product.

C. Source quality-control reports.

D. Field quality-control reports.

1.7 CLOSEOUT SUBMITTALS

A. Maintenance Data: For splices and connectors to include in maintenance manuals.

1.8 QUALITY ASSURANCE

A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.

1. Layout Responsibility: Preparation of Shop Drawings by an RCDD.
2. Installation Supervision: Installation shall be under the direct supervision of Technician who shall be present at all times when Work of this Section is performed at Project site.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Test cables upon receipt at Project site.

1. Test each pair of twisted pair cable for open and short circuits.

1.10 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.11 COORDINATION

A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General Performance: Horizontal cabling system shall comply with transmission standards in TIA-568-C.1, when tested according to test procedures of this standard.

B. Telecommunications Pathways and Spaces: Comply with TIA-569-D.

C. Grounding: Comply with TIA-607-B.

2.2 MANUFACTURERS

A. Acceptable manufacturers for cables, connectors, patch panels and patch cords include the following:

1. AMP
2. Hubbell
3. Leviton
4. Ortronics
5. Superior Essex
6. Corning

2.3 GENERAL CABLE CHARACTERISTICS

A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with the applicable standard and NFPA 70 for the following types:

1. Communications, Plenum Rated: Type CMP complying with UL 1685 or Type CMP in listed plenum communications raceway or Type CMP in listed cable routing assembly.

B. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 50 or less.

C. RoHS compliant.

2.4 CATEGORY 6 TWISTED PAIR CABLE

A. Description: Four-pair, balanced-twisted pair cable, certified to meet transmission characteristics of Category 6 cable at frequencies up to 100 MHz.

B. Standard: Comply with ICEA S-90-661, NEMA WC 63.1, and TIA-568-C.2 for Category 6 cables.

C. Conductors: 100-ohm, 24 AWG solid copper.

D. Shielding/Screening: Unshielded twisted pairs (UTP).

E. Cable Rating: Plenum.

F. Jacket: Colored thermoplastic to match the existing building systems. (Blue for data)

2.5 TWISTED PAIR CABLE HARDWARE

A. Description: Hardware designed to connect, splice, and terminate twisted pair copper communications cable.

B. General Requirements for Twisted Pair Cable Hardware:

1. Comply with the performance requirements of Category 6.
2. Comply with TIA-568-C.2, IDC type, with modules designed for punch-down caps or tools.
3. Cables shall be terminated with connecting hardware of same category or higher.

C. Source Limitations: Obtain twisted pair cable hardware from same manufacturer as twisted pair cable, from single source.

D. Patch Cords: Factory-made, four-pair cables in 48-inch (1200-mm) lengths; terminated with an eight-position modular plug at each end.

1. Patch cords shall have color-coded boots for circuit identification.

E. Plugs and Plug Assemblies:

1. Male; eight position; color-coded modular telecommunications connector designed for termination of a single four-pair, 100-ohm, unshielded or shielded twisted pair cable.
2. Standard: Comply with TIA-568-C.2.

F. Jacks and Jack Assemblies:

1. Female; eight position; modular; fixed telecommunications connector designed for termination of a single four-pair, 100-ohm, unshielded or shielded twisted pair cable.
2. Designed to snap-in to a patch panel or faceplate.
3. Standard: Comply with TIA-568-C.2.

G. Faceplate:

1. Six port, vertical single gang faceplates designed to mount to single gang wall boxes.
2. Metal Faceplate: Stainless steel, complying with requirements in Section 26 27 26 "Wiring Devices."

H. Legend:

1. Machine printed, in the field, using adhesive-tape label.
2. Snap-in, clear-label covers and machine-printed paper inserts.

2.6 IDENTIFICATION PRODUCTS

A. Comply with TIA-606-B and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

2.7 SOURCE QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to evaluate cables.

B. Factory test cables on reels according to TIA-568-C.1.

C. Factory test twisted pair cables according to TIA-568-C.2.

D. Cable will be considered defective if it does not pass tests and inspections.

E. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 WIRING METHODS

A. Wiring Method: Install cables in raceways and cable trays, except within consoles, cabinets, desks, and counters and except in accessible ceiling spaces, attics, and gypsum board partitions where unenclosed wiring method may be used. Conceal raceway and cables, except in unfinished spaces.

1. Install plenum cable in environmental air spaces, including plenum ceilings.
2. Comply with requirements for raceways and boxes specified in Section 26 05 33 "Raceways and Boxes for Electrical Systems."

B. Wiring Method: Conceal conductors and cables in accessible ceilings, walls, and floors where possible.

C. Wiring within Enclosures: Bundle, lace, and train cables within enclosures. Connect to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools. Install conductors parallel with or at right angles to sides and back of enclosure.

3.2 INSTALLATION OF PATHWAYS

A. Comply with Section 26 05 33 "Raceways and Boxes for Electrical Systems."

B. Comply with Section Section 26 05 29 "Hangers and Supports for Electrical Systems."

3.3 INSTALLATION OF TWISTED-PAIR HORIZONTAL CABLES

A. Comply with NECA 1 and NECA/BICSI 568.

B. General Requirements for Cabling:

1. Comply with TIA-568-C.0, TIA-568-C.1, and TIA-568-C.2.
2. Comply with BICSI's "Information Transport Systems Installation Methods Manual (ITSIMM), Ch. 5, "Copper Structured Cabling Systems," "Cable Termination Practices" Section.
3. Install 110-style IDC termination hardware unless otherwise indicated.
4. Do not untwist twisted pair cables more than 1/2 inch (12 mm) from the point of termination to maintain cable geometry.
5. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
6. MUTOA shall not be used as a cross-connect point.
7. Consolidation points may be used only for making a direct connection to equipment outlets:

    a. Do not use consolidation point as a cross-connect point, as a patch connection, or for direct connection to workstation equipment.
    b. Locate consolidation points for twisted-pair cables at least 49 feet (15 m) from communications equipment room.

8. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches (760 mm) and not more than 6 inches (150 mm) from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
9. Install lacing bars to restrain cables, prevent straining connections, and prevent bending cables to smaller radii than minimums recommended by manufacturer.
10. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI Information Transport Systems Installation Methods Manual , Ch. 5, "Copper Structured Cabling Systems," "Cable Termination Practices" Section. Use lacing bars and distribution spools.
11. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation, and replace it with new cable.
12. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
13. In the communications equipment room, install a 10-foot- (3-m-) long service loop on each end of cable.
14. Pulling Cable: Comply with BICSI Information Transport Systems Installation Methods Manual, Ch. 5, "Copper Structured Cabling Systems," "Pulling and Installing Cable" Section. Monitor cable pull tensions.

C. Open-Cable Installation:

1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
2. Suspend twisted pair cabling, not in a wireway or pathway, a minimum of 8 inches (200 mm) above ceilings by cable supports not more than 48 inches (1200 mm) apart.
3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.

D. Group connecting hardware for cables into separate logical fields.

E. Separation from EMI Sources:

1. Comply with recommendations from BICSI's "Telecommunications Distribution Methods Manual" and TIA-569-D for separating unshielded copper communication cable from potential EMI sources, including electrical power lines and equipment.
2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:

    a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches (127 mm).
    b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches (300 mm).
    c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches (600 mm).

3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:

    a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches (64 mm).
    b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches (150 mm).
    c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches (300 mm).

4. Separation between communications cables in grounded metallic raceways, power lines, and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:

    a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
    b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches (76 mm).
    c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches (150 mm).

5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches (1200 mm).
6. Separation between Communications Cables and Fluorescent Fixtures: A minimum of 5 inches (127 mm).

3.4 FIRESTOPPING

A. Comply with requirements in Section 078413 "Penetration Firestopping" and Section 26 05 28 “Electrical Firestopping.”

B. Comply with TIA-569-D, Annex A, "Firestopping."

C. Comply with "Firestopping Systems" Article in BISCI's "Telecommunications Distribution Methods Manual."

3.5 IDENTIFICATION

A. Identify system components, wiring, and cabling complying with TIA-606-B.

1. Color-code cross-connect fields and apply colors to voice and data service backboards, connections, covers, and labels to match existing.

B. Cable and Wire Identification:

1. Label each cable within 4 inches (100 mm) of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
2. Each wire connected to building-mounted devices is not required to be numbered at the device if wire color is consistent with associated wire connected and numbered within panel or cabinet.
3. Exposed Cables and Cables in Cable Trays and Wire Troughs: Label each cable at intervals not exceeding 15 feet (4.5 m).
4. Label each terminal strip, and screw terminal in each cabinet, rack, or panel.

    a. Individually number wiring conductors connected to terminal strips, and identify each cable or wiring group, extended from a panel or cabinet to a building-mounted device, with the name and number of a particular device.
    b. Label each unit and field within distribution racks and frames.

5. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and -connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.

C. Labels shall be preprinted or computer-printed type, with a printing area and font color that contrast with cable jacket color but still comply with TIA-606-B requirements for the following:

1. Cables use flexible vinyl or polyester that flexes as cables are bent.

3.6 FIELD QUALITY CONTROL

A. Perform tests and inspections with the assistance of a factory-authorized service representative.

B. Tests and Inspections:

1. Visually inspect jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA-568-C.1.
2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
3. Test twisted pair cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.

a. Test instruments shall meet or exceed applicable requirements in TIA-568-C.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.

C. Data for each measurement shall be documented. Data for submittals shall be printed in a summary report that is formatted similarly to Table 10.1 in BICSI's "Telecommunications Distribution Methods Manual," or shall be transferred from the instrument to the computer, saved as text files, printed, and submitted.

D. Remove and replace cabling where test results indicate that they do not comply with specified requirements.

E. End-to-end cabling will be considered defective if it does not pass tests and inspections.

F. Prepare test and inspection reports.

END OF SECTION 27 15 13

SECTION 28 31 11
FIRE ALARM SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This specification provides the requirements for the installation, programming and configuration of an extension of the existing Fire Alarm System. The system shall include, but not be limited to: Fire Alarm Control Panel, Automatic and Manually activated alarm Initiating and Indicating Peripheral Devices and Appliances, conduit, wire and accessories required to furnish a complete and operational Fire Alarm System. System shall include, but not be limited to, the following:

1. Initiation devices.
2. Notification appliances.

B. The system shall include all wiring, raceways, pull boxes, terminal cabinets, outlet and mounting boxes, alarm initiating devices, alarm indicating devices, and control equipment, and all other accessories and miscellaneous items required for an operating system.

C. The Fire Alarm System supplied under this specification shall be a microprocessor-based network system. All Control Panel Assemblies and connected Field Appliances shall be both designed and manufactured by the same company, and shall be tested and cross-listed as compatible to ensure that a fully functioning Life Safety System is designed and Fire installed.

D. Existing system devices shall be re-used and maintained fully operational unless otherwise noted. Reconnect and reprogram existing system circuits/devices as required, for a fully functional system.

Test system prior to performing any modifications and report any defects, etc. to the owner in writing. Any defects, malfunctions of the system not reported in advance of performing work shall be the responsibility of the contractor to correct.

E. All related work specified in other sections shall be properly coordinated with the fire alarm equipment.

1.3 REFERENCES

A. The system, equipment, installation, and operation shall comply with the current provisions of the following standards and publications.

1. National Electric Code, Article 70.
2. National Fire Protection Association Standards:

    a. NFPA72 National Fire Alarm Code
    b. NFPA 90A Air Conditioning & Ventilation Systems
    c. NFPA101 Life Safety Code

3. Local and State Building Codes.
4. Local Authorities Having Jurisdiction.
5. Underwriters Laboratories Inc.: The system and all components shall be listed by Underwriters Laboratories Inc. for use in fire protective signaling system under the following standards as applicable:

    a. UL 864/UOJZ, APOU - Control Units for Fire Protective Signaling Systems.
    b. UL 268 - Smoke Detectors for Fire Protective Signaling Systems.
    c. UL 268A - Smoke Detectors for Duct Applications.
    d. UL 217 - Smoke Detectors Single Station.
    e. UL 521 - Heat Detectors for Fire Protective Signaling Systems.
    f. UL 228 - Door Holders for Fire Protective Signaling Systems.
    g. UL 464 - Audible Signaling Appliances.
    h. UL 1638 - Visual Signaling Appliances.
    i. UL 38 - Manually Activated Signaling Boxes.
    j. UL 346 - Waterflow Indicators for Fire Protective Signaling Systems.
    k. UL 1971 - Standard for Signaling Devices for the Hearing Impaired.
    l. UL 1481 - Power Supplies for Fire Protective Signaling Systems.
    m. UL 1711 - Amplifiers for Fire Protective Signaling Systems.
    n. UL Fire Protection Equipment Directory.
    o. UL Electrical Construction Materials Directory.

6. Americans with Disabilities Act (ADA)
7. International Standards Organization (ISO)

    a. ISO-9000
    b. ISO-9001

8. Factory Mutual Approval Guide.
9. State of Delaware Fire Prevention Code.
10. American Insurance Association Fire Protection Code (Article 14).
11. Delaware Occupational Safety & Health Act.
12. International Building Code (IBC).

1.4 DEFINITIONS

A. FACP: Fire Alarm Control Panel.

B. HLI: High Level Interface.

C. NICET: National Institute for Certification in Engineering Technologies.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product, including furnished options and accessories:

1. Include construction details, material descriptions, dimensions, profiles, and finishes.
2. Include rated capacities, operating characteristics, and electrical characteristics.

B. Shop Drawings: For fire-alarm system.

1. Comply with recommendations and requirements in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
2. Include plans, elevations, sections, details, and attachments to other work.
3. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and locations. Indicate conductor sizes, indicate termination locations and requirements, and distinguish between factory and field wiring.
4. Detail assembly and support requirements.
5. Include voltage drop calculations for notification-appliance circuits.
6. Include battery-size calculations.
7. Include input/output matrix.
8. Include statement from manufacturer that all equipment and components have been tested as a system and meet all requirements in this Specification and in NFPA 72.
9. Include performance parameters and installation details for each detector.
10. Include floor plans to indicate final outlet locations showing address of each addressable device. Show size and route of cable and conduits and point-to-point wiring diagram
11. Submit wiring diagrams for all new equipment connected to fire alarm system.

C. General Submittal Requirements:

1. Submittals shall be approved by authorities having jurisdiction prior to submitting them to Architect.

a. Secure permits and approvals prior to installation.

b. Prior to commencement and after completion of work, notify Authorities Having Jurisdiction.
c. Submit letter of approval for installation before requesting acceptance of system.

2. Shop Drawings shall be prepared by persons with the following qualifications:

a. Trained and certified by manufacturer in fire-alarm system design.
b. NICET-certified, fire-alarm technician; Level III minimum.
c. Licensed or certified by authorities having jurisdiction.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Field quality-control reports.

1.7 WARRANTY

A. For materials and workmanship for a period of two years from final system acceptance.

1.8 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Division 01 "Operation and Maintenance Data," include the following and deliver copies to authorities having jurisdiction:

a. Comply with the "Records" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
b. Provide "Fire Alarm and Emergency Communications System Record of Completion Documents" according to the "Completion Documents" Article in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
c. Complete wiring diagrams showing connections between all devices and equipment. Each conductor shall be numbered at every junction point with indication of origination and termination points.
d. Riser diagram.
e. Device addresses.
f. Record copy of site-specific software.

g. Provide "Inspection and Testing Form" according to the "Inspection, Testing and Maintenance" chapter in NFPA 72, and include the following:

1) Equipment tested.
2) Frequency of testing of installed components.
3) Frequency of inspection of installed components.
4) Requirements and recommendations related to results of maintenance.
5) Manufacturer's user training manuals.

h. Manufacturer's required maintenance related to system warranty requirements.

i. Abbreviated operating instructions for mounting at fire-alarm control unit and each annunciator unit.

1.9 QUALITY ASSURANCE

A. Installer Qualifications: Personnel shall be trained and certified by manufacturer for installation of units required for this Project.

B. NFPA Certification: Obtain certification according to NFPA 72 by a UL-listed alarm company.

1.10 PROJECT CONDITONS

A. Use of Devices during Construction: Protect devices during construction unless devices are placed in service to protect the facility during construction.

1.11 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace new fire-alarm system equipment and components that fail in materials or workmanship within specified warranty period.

1. Warranty Extent: All equipment and components not covered in the Maintenance Service Agreement.

2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

A. Source Limitations for Fire-Alarm System and Components: Components shall be compatible with, and operate as one system. Provide system manufacturer's

certification that all components provided have been tested as, and will operate as, a system.

B. Noncoded, UL-certified addressable system, with multiplexed signal transmission and /strobe evacuation.

C. Automatic sensitivity control of certain smoke detectors.

D. All components provided shall be listed for use with the selected systems:

E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 MANUAL FIRE-ALARM BOXES

A. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes shall be finished in red with molded, raised-letter operating instructions in contrasting color; shall show visible indication of operation; and shall be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.

1. Single-action mechanism, pull-lever type; with integral addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to fire-alarm control unit.
2. Station Reset: Key- or wrench-operated switch.
3. Weatherproof Protective Shield: Factory-fabricated, clear plastic enclosure hinged at the top to permit lifting for access to initiate an alarm. Provide for all manual fire alarm boxes.

2.3 NOTIFICATION APPLIANCES

A. General Requirements for Notification Appliances: Connected to notification-appliance signal circuits, zoned as indicated, equipped for mounting as indicated, and with screw terminals for system connections.

B. Combination Devices: Factory-integrated audible and visible devices in a single-mounting assembly, equipped for mounting as indicated, and with screw terminals for system connections.

C. Visible Notification Appliances: Xenon strobe lights complying with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch- (25-mm-) high letters on the lens.

1. Rated Light Output:

a) 1530/75/110 cd, selectable in the field.

2. Mounting: Wall or ceiling mounted as noted on the drawings.

3. For units with guards to prevent physical damage, light output ratings shall be determined with guards in place.
4. Flashing shall be in a temporal pattern, synchronized with other units.
5. Strobe Leads: Factory connected to screw terminals.
6. Mounting Faceplate: Factory finished, red for wall mounted devices; white for ceiling mounted devices.

D. Voice/Tone Notification Appliances:

1. Comply with UL 1480.
2. Speakers for Voice Notification: Locate speakers for voice notification to provide the intelligibility requirements of the "Notification Appliances" and "Emergency Communications Systems" chapters in NFPA 72.
3. High-Range Units: Rated 2 to 15 W.
4. Cone Speakers

   a) Wall Mount: Provide speakers with a 4” mylar cone. Paper type cones are not acceptable. The rear of the speaker shall be completely sealed protecting the cone during and after installation. In - Out screw terminals shall be provided for wiring. Speaker housings shall be white. Speakers shall provide power taps at 1/4w, 1/2w, 1w, and 2w. Speakers shall provide UL confirmed 90 dBA sound output at 2w. Speakers shall mount in a North American 4” electrical box with extension ring using the 2 screws provided with ring. It must not be necessary to completely remove the screws to facilitate mounting.
   b) Ceiling Mount (4”): Provide speakers with a 4” mylar cone. Paper type cones are not acceptable. The rear of the speaker shall be completely sealed, protecting the cone during and after installation. In-Out screw terminals shall be provided for wiring. Speaker baffles shall be round, steel with white finish. Speakers shall provide power taps at 1/4w, 1/2w, 1w, and 2w. Speakers shall provide UL confirmed 90 dBA sound output at 2w. Speakers shall mount in a North American 4” electrical box with extension ring.
   c) Ceiling Mount (8”): Provide speakers with an 8” cone. In-Out screw terminals shall be provided for wiring. Speaker baffles shall be round, steel with white finish. Speakers shall provide power taps at 1/2w, 1w, 2w, and 4w. Provide square surface mount boxes with matching white finish.
   d) High Output: Provide speakers with a 4” mylar cone. Paper type cones are not acceptable. The rear of the speaker shall be completely sealed, protecting the cone during and after installation. In-Out screw terminals shall be provided for wiring. Speaker baffles shall be round, steel with white finish. Speakers shall provide power taps at 1w, 2w, 4w, and 8w. Speakers shall provide UL confirmed 90 dBA sound output at 2w. Speakers shall mount in a North American 4” electrical box with extension

5. Re-entrant Speakers: Re-entrant speakers shall have a white housing. Power taps shall be provided at 2w, 4w, 8w, and 15w. Re-entrant speakers shall provide 102 dBA peak sound output at 15w. A metal compression driver shall be

inherent to the re-entrant speaker. Cone type drivers are not acceptable. Provide weatherproof wall boxes for outdoor mounting.

6. Matching Transformers: Tap range matched to acoustical environment of speaker location.

E. Color: ceiling mounted devices shall be white, wall mounted devices shall be red.

2.4 ADDRESSABLE INTERFACE DEVICE

A. General:

1. Include address-setting means on the module.
2. Store an internal identifying code for control panel use to identify the module type.
3. Listed for controlling HVAC fan motor controllers.

B. Monitor Module: Microelectronic module providing a system address for alarm-initiating devices for wired applications with normally open contacts. Provide for all sprinkler flow and tamper switches, and as required.

C. Integral Relay: Capable of providing a direct signal to elevator controller to initiate elevator recall, to circuit-breaker shunt trip for power shutdown, etc.

1. Allow the control panel to switch the relay contacts on command.
2. Have a minimum of two normally open and two normally closed contacts available for field wiring.

D. Control Module:

1. Operate notification devices.
2. Operate solenoids for use in sprinkler service.
3. Mute sound system(s).
4. Unlock sound system(s).

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and conditions for compliance with requirements for ventilation, temperature, humidity, and other conditions affecting performance of the Work.

1. Verify that manufacturer's written instructions for environmental conditions have been permanently established in spaces where equipment and wiring are installed, before installation begins.

B. Examine roughing-in for electrical connections to verify actual locations of connections before installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 EQUIPMENT INSTALLATION

A. Comply with NFPA 72, NFPA 101, and requirements of authorities having jurisdiction for installation and testing of fire-alarm equipment. Install all electrical wiring to comply with requirements in NFPA 70 including, but not limited to, Article 760, "Fire Alarm Systems."

1. Devices placed in service before all other trades have completed cleanup shall be replaced.
2. Devices installed but not yet placed in service shall be protected from construction dust, debris, dirt, moisture, and damage according to manufacturer's written storage instructions.

B. Connecting to Existing Equipment: Verify that existing fire-alarm system is operational before making changes or connections.

1. Connect new equipment to existing control panel in existing part of the building.
2. Connect new equipment to existing monitoring equipment at the supervising station.
3. Expand, modify, and supplement existing control and monitoring equipment as necessary to extend existing functions to the new points. New components shall be capable of merging with existing configuration without degrading the performance of either system.

C. Audible Alarm-Indicating Devices: Install not less than 6 inches (150 mm) below the ceiling. Install bells and horns on flush-mounted back boxes with the device-operating mechanism concealed behind a grille. Install all devices at the same height unless otherwise indicated.

D. Visible Alarm-Indicating Devices: Install adjacent to each alarm bell or alarm horn and at least 6 inches (150 mm) below the ceiling. Install all devices at the same height unless otherwise indicated.

3.3 PATHWAYS

A. The Fire Alarm System shall be installed in dedicated raceway, except fire rated type MC cable may be used where concealed above accessible ceilings. The entire system shall be installed in a skillful manner in accordance with approved manufacturers' manuals and wiring diagrams. The Contractor shall furnish all conduit, wiring, outlet boxes, junction boxes, cabinets and similar devices necessary for the complete installation. All wiring shall be of the type recommended by the NEC, approved by local authorities having jurisdiction for the purpose.

1. Exposed pathways located less than 96 inches (2440 mm) above the floor shall be installed in raceway. Raceway shall be conduit in unfinished spaces and surface metal raceway in finished spaces, painted to match existing wall(s).

B. All junction boxes shall be sprayed red and labeled “Fire Alarm”. Wiring color code shall be maintained throughout the installation.

3.4 CONNECTIONS

A. For fire-protection systems related to doors in fire-rated walls and partitions and to doors in smoke partitions, comply with requirements in Division 08 "Door Hardware." Connect hardware and devices to fire-alarm system.

1. Verify that hardware and devices are listed for use with installed fire-alarm system before making connections

B. Make addressable connections with a supervised interface device to the following devices and systems. Install the interface device less than 36 inches (910 mm) from the device controlled. Make an addressable confirmation connection when such feedback is available at the device or system being controlled.

1. Magnetically held-open doors.
2. Electronically locked doors and access gates.

C. Where it is necessary to interface conventional initiating devices, provide intelligent input modules to supervise Class B zone wiring.

3.5 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems.”

3.6 GROUNDING

A. Ground shielded cables at the control panel location only. Insulate shield at device location.

3.7 FIELD QUALITY CONTROL

A. Field tests shall be witnessed by authorities having jurisdiction.

B. Manufacturer’s Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

C. Perform the following tests and inspections with the assistance of a factory-authorized service representative:

1. Visual Inspection: Conduct visual inspection prior to testing.

    a. Inspection shall be based on completed record Drawings and system documentation that is required by the "Completion Documents, Preparation" table in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
    b. Comply with the "Visual Inspection Frequencies" table in the "Inspection" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.

2. System Testing: Comply with the "Test Methods" table in the "Testing" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
4. Test audible appliances for the private operating mode according to manufacturer's written instructions.
5. Test visible appliances for the public operating mode according to manufacturer's written instructions.
6. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" section of the "Fundamentals" chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.

D. Reacceptance Testing: Perform reacceptance testing to verify the proper operation of added or replaced devices and appliances.

E. Fire-alarm system will be considered defective if it does not pass tests and inspections.

F. Prepare test and inspection reports.

G. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.

H. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.8 MAINTENANCE SERVICE

A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by skilled employees of manufacturer's designated service organization. Include preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

1. Include visual inspections according to the "Visual Inspection Frequencies" table in the "Testing" paragraph of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
2. Perform tests in the "Test Methods" table in the "Testing" paragraph of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
3. Perform tests per the "Testing Frequencies" table in the "Testing" paragraph of the "Inspection, Testing and Maintenance" chapter in NFPA 72.

END OF SECTION 28 31 11

SECTION 32 13 13
CONCRETE PAVING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes: Concrete paving for walks and includes the following:

1. Forms.
2. Steel reinforcement.
3. Concrete materials.
4. Fiber reinforcement.
5. Curing materials.
6. Special finish materials.

B. Related Requirements:

1. Section 321373 "Concrete Paving Joint Sealants" for joint sealants in expansion and contraction joints within concrete paving and in joints between concrete paving and asphalt paving or adjacent construction.

1.2 DEFINITIONS

A. Cementitious Materials: Portland cement alone or in combination with one or more of blended hydraulic cement, fly ash, slag cement, and other pozzolans.

B. W/C Ratio: The ratio by weight of water to cementitious materials.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

B. Samples for Initial Selection: For each type of product, ingredient, or admixture requiring color selection.

C. Samples for Verification: For each type of product or exposed finish, prepared as Samples of size indicated below:

1. Exposed Aggregate: 10-lb sample of each mix.

D. Design Mixtures: For each concrete paving mixture. Include alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

1.4 INFORMATIONAL SUBMITTALS

A. Material Certificates: For the following, from manufacturer:

1. Cementitious materials.
2. Steel reinforcement and reinforcement accessories.
3. Fiber reinforcement.
4. Admixtures.
5. Curing compounds.
6. Special finish materials.
7. Joint fillers.
8. Bonding agent.
9. Epoxy-bonding adhesive.

B. Field Quality Control Reports: For specified tests and inspections.

1.5 QUALITY ASSURANCE

A. Ready-Mix-Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C94/C94M requirements for production facilities and equipment.

1. Manufacturer certified in accordance with NRMCA's "Certification of Ready Mixed Concrete Production Facilities" (Quality Control Manual - Section 3, "Plant Certification Checklist").

B. Stamped Detectable Warning Installer Qualifications: An employer of workers trained and approved by manufacturer of stamped concrete paving systems

C. Testing Agency Qualifications: Qualified in accordance with ASTM C1077 and ASTM E329 for testing indicated.

1. Personnel conducting field tests must be qualified as ACI Concrete Field Testing Technician, Grade 1, in accordance with ACI CP-1 or an equivalent certification program.

1.6 PRECONSTRUCTION TESTING

A. Preconstruction Testing Service: Engage a qualified independent testing agency to perform preconstruction testing on concrete paving mixtures.

1.7 FIELD CONDITIONS

A. Traffic Control: Maintain access for vehicular and pedestrian traffic as required for other construction activities.

B. Cold-Weather Concrete Placement: Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing, or low temperatures.

Comply with ACI 306.1 and the following:

1. When air temperature has fallen to or is expected to fall below 40 deg F, uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg F and not more than 80 deg F at point of placement.
2. Do not use frozen materials or materials containing ice or snow.
3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in design mixtures.

C. Hot-Weather Concrete Placement: Comply with ACI 301 and as follows when hot-weather conditions exist:

1. Cool ingredients before mixing to maintain concrete temperature below 90 deg F at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated in total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.
2. Cover steel reinforcement with water-soaked burlap, so steel temperature will not exceed ambient air temperature immediately before embedding in concrete.
3. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade moisture uniform without standing water, soft spots, or dry areas.

PART 2 - PRODUCTS

2.1 CONCRETE, GENERAL

A. ACI Publications: Comply with ACI 301 unless otherwise indicated.

2.2 FORMS

A. Form Materials: Plywood, metal, metal-framed plywood, or other approved panel-type materials to provide full-depth, continuous, straight, and smooth exposed surfaces.

1. Use flexible or uniformly curved forms for curves with a radius of 100 feet or less. Do not use notched and bent forms.

B. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and that will not impair subsequent treatments of concrete surfaces.

2.3 STEEL REINFORCEMENT

A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

B. Plain-Steel Welded-Wire Reinforcement: ASTM A1064/A1064M, fabricated from galvanized- steel wire into flat sheets.

C. Epoxy-Coated Reinforcing Bars: ASTM A775/A775M or ASTM A934/A934M; with ASTM A615/A615M, Grade 60 deformed bars.

D. Plain-Steel Wire: ASTM A1064/A1064M, galvanized.

E. Epoxy-Coated-Steel Wire: ASTM A884/A884M, Class A; coated, plain.

F. Epoxy-Coated, Joint Dowel Bars: ASTM A775/A775M; with ASTM A615/A615M, Grade 60 plain-steel bars.

G. Tie Bars: ASTM A615/A615M, Grade 60; deformed.

H. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars, welded-wire reinforcement, and dowels in place. Manufacture bar supports in accordance with CRSI's "Manual of Standard Practice" from steel wire, plastic, or precast concrete of greater compressive strength than concrete specified, and as follows:

1. Equip wire bar supports with sand plates or horizontal runners where base material will not support chair legs.
2. For epoxy-coated reinforcement, use epoxy-coated or other dielectric-polymer-coated wire bar supports.

I. Epoxy Repair Coating: Liquid, two-part, epoxy repair coating, compatible with epoxy coating on reinforcement.

2.4 CONCRETE MATERIALS

A. Cementitious Materials: Use the following cementitious materials, of same type, brand, and source throughout Project:

1. Portland Cement: ASTM C150/C150M, white portland cement Type I/II.

2. Blended Hydraulic Cement: ASTM C595/C595M, Type IL, Portland-limestone cement.

B. Normal-Weight Aggregates: ASTM C33/C33M, Class 4M, uniformly graded. Provide aggregates from a single source.

1. Maximum Coarse-Aggregate Size: 1-1/2 inches nominal.
2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.

C. Air-Entraining Admixture: ASTM C260/C260M.

D. Chemical Admixtures: Admixtures certified by manufacturer to be compatible with other admixtures and to contain not more than 0.1 percent water-soluble chloride ions by mass of cementitious material.

1. Water-Reducing Admixture: ASTM C494/C494M, Type A.
2. Retarding Admixture: ASTM C494/C494M, Type B.
3. Water-Reducing and Retarding Admixture: ASTM C494/C494M, Type D.
4. High-Range, Water-Reducing Admixture: ASTM C494/C494M, Type F.
5. High-Range, Water-Reducing and Retarding Admixture: ASTM C494/C494M, Type G.
6. Plasticizing and Retarding Admixture: ASTM C1017/C1017M, Type II.

E. Water: Potable and complying with ASTM C94/C94M.

2.5 CURING MATERIALS

A. Water: Potable.

2.6 ACCESSORY MATERIALS

A. Joint Fillers: ASTM D1751, asphalt-saturated cellulosic fiber in preformed strips.

B. Bonding Agent: ASTM C1059/C1059M, Type II, non-redispersible, acrylic emulsion or styrene butadiene.

C. Epoxy-Bonding Adhesive: ASTM C881/C881M, two-component epoxy resin capable of humid curing and bonding to damp surfaces; of class suitable for application temperature, of grade complying with requirements, and of the following types:

1. Types IV and V, load bearing, for bonding hardened or freshly mixed concrete to hardened concrete.

2.7 CONCRETE MIXTURES

A. Prepare design mixtures, proportioned in accordance with ACI 301, for each type and strength of normal-weight concrete, and as determined by either laboratory trial mixtures or field experience.

1. Use a qualified independent testing agency for preparing and reporting proposed concrete design mixtures for the trial batch method.
2. When automatic machine placement is used, determine design mixtures and obtain laboratory test results that comply with or exceed requirements.

B. Cementitious Materials: Use fly ash, pozzolan, slag cement, and silica fume as needed to reduce the total amount of portland cement, which would otherwise be

used, by not less than 40 percent.

1. Fly Ash or Pozzolan: 25 percent.
2. Slag Cement: 50 percent.
3. Combined Fly Ash or Pozzolan, and Slag Cement: 50 percent, with fly ash or pozzolan not exceeding 25 percent.

C. Air-Entraining Admixture: Add admixture at manufacturer's prescribed rate to result in normal-weight concrete at point of placement having an air content as follows:

1. Air Content, 1-1/2-inch Nominal Maximum Aggregate Size: 4-1/2 percent plus or minus 1-1/2 percent.

D. Limit water-soluble, chloride-ion content in hardened concrete to 0.30 percent by weight of cement.

E. Chemical Admixtures: Use admixtures in accordance with manufacturer's written instructions.

1. Use high-range, water-reducing admixture in concrete as required for placement and workability.
2. Use water-reducing and retarding admixture when required by high temperatures, low humidity, or other adverse placement conditions.

F. Fiber Reinforcement: Uniformly disperse synthetic fiber in concrete mixture at manufacturer's recommended rate, but not less than 1.0 lb/cu. yd..

G. Concrete Mixtures: Normal-weight concrete.

1. Compressive Strength (28 Days): 4000 psi.
2. Maximum W/C Ratio at Point of Placement: 0.45.
3. Slump Limit: 4 inches, plus or minus 1 inch.

2.8 CONCRETE MIXING

A. Ready-Mixed Concrete: Measure, batch, and mix concrete materials and concrete in accordance with ASTM C94/C94M. Furnish batch certificates for each batch discharged and used in the Work.

1. Fiber Reinforcement: Add to concrete mixture in accordance with ASTM C1116/C1116M and manufacturer's written instructions.
2. When air temperature is between 85 and 90 deg F, reduce mixing and delivery time from 1-1/2 hours to 75 minutes; when air temperature is above 90 deg F, reduce mixing and delivery time to 60 minutes.

B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete in accordance with ASTM C94/C94M. Mix concrete materials in appropriate drum-type batch machine mixer.

1. For concrete batches of 1 cu. yd. or smaller, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released.
2. For concrete batches larger than 1 cu. yd., increase mixing time by 15 seconds for each additional 1 cu. yd..
3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixing time, quantity, and amount of water added.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine exposed subgrades and subbase surfaces for compliance with requirements for dimensional, grading, and elevation tolerances.

B. Proof-roll prepared subbase surface below concrete paving to identify soft pockets and areas of excess yielding.

1. Correct subbase with soft spots and areas of pumping or rutting exceeding depth of 1/2 inch in accordance with requirements in Section 312000 "Earth Moving."

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove loose material from compacted subbase surface immediately before placing concrete.

3.3 INSTALLATION OF FORMS

A. Set, brace, and secure edge forms, bulkheads, and intermediate screed guides to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.

B. Clean forms after each use and coat with form-release agent to ensure separation from concrete without damage.

3.4 INSTALLATION OF STEEL REINFORCEMENT

A. General: Comply with CRSI's "Manual of Standard Practice" for fabricating, placing, and supporting reinforcement.

B. Clean reinforcement of loose rust and mill scale, earth, ice, or other bond-reducing materials.

C. Arrange, space, and securely tie bars and bar supports to hold reinforcement in position during concrete placement. Maintain minimum cover to reinforcement.

D. Install welded-wire reinforcement in lengths as long as practicable. Lap adjoining pieces at least one full mesh, and lace splices with wire. Offset laps of adjoining widths to prevent continuous laps in either direction.

E. Zinc-Coated Reinforcement: Use galvanized-steel wire ties to fasten zinc-coated reinforcement. Repair cut and damaged zinc coatings with zinc repair material.

F. Epoxy-Coated Reinforcement: Use epoxy-coated steel wire ties to fasten epoxy-coated reinforcement. Repair cut and damaged epoxy coatings with epoxy repair coating in accordance with ASTM D3963/D3963M.

G. Install fabricated bar mats in lengths as long as practicable. Handle units to keep them flat and free of distortions. Straighten bends, kinks, and other irregularities, or replace units as required before placement. Set mats for a minimum 2-inch overlap of adjacent mats.

3.5 FORMING OF JOINTS

A. General: Form construction, isolation, and contraction joints and tool edges true to line, with faces perpendicular to surface plane of concrete. Construct transverse joints at right angles to centerline unless otherwise indicated.

1. When joining existing paving, place transverse joints to align with previously placed joints unless otherwise indicated.

B. Construction Joints: Set construction joints at side and end terminations of paving and at locations where paving operations are stopped for more than one-half hour unless paving terminates at isolation joints.

1. Continue steel reinforcement across construction joints unless otherwise indicated. Do not continue reinforcement through sides of paving strips unless otherwise indicated.
2. Provide tie bars at sides of paving strips where indicated.
3. Butt Joints: Use epoxy-bonding adhesive at joint locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
4. Keyed Joints: Provide preformed keyway-section forms or bulkhead forms with keys unless otherwise indicated. Embed keys at least 1-1/2 inches into concrete.
5. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or coat with asphalt one-half of dowel length to prevent concrete bonding to one side of joint.

C. Isolation Joints: Form isolation joints of preformed joint-filler strips abutting

concrete curbs, catch basins, manholes, inlets, structures, other fixed objects, and where indicated.

1. Locate expansion joints at intervals of 50 feet unless otherwise indicated.
2. Extend joint fillers full width and depth of joint.
3. Terminate joint filler not less than 1/2 inch or more than 1 inch below finished surface if joint sealant is indicated.
4. Place top of joint filler flush with finished concrete surface if joint sealant is not indicated.
5. Furnish joint fillers in one-piece lengths. Where more than one length is required, lace or clip joint-filler sections together.
6. During concrete placement, protect top edge of joint filler with metal, plastic, or other temporary preformed cap. Remove protective cap after concrete has been placed on both sides of joint.

D. Contraction Joints: Form weakened-plane contraction joints, sectioning concrete into areas as indicated on Drawings. Construct contraction joints for a depth equal to at least one-fourth of the concrete thickness, as follows, to match jointing of existing adjacent concrete paving:

1. Grooved Joints: Form contraction joints after initial floating by grooving and finishing each edge of joint with grooving tool to a 1/4-inch radius. Repeat grooving of contraction joints after applying surface finishes. Eliminate grooving-tool marks on concrete surfaces.

    a. Tolerance: Ensure that grooved joints are within 3 inches either way from centers of dowels.

2. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before developing random contraction cracks.

    a. Tolerance: Ensure that sawed joints are within 3 inches either way from centers of dowels.

3. Doweled Contraction Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or coat with asphalt one-half of dowel length to prevent concrete bonding to one side of joint.

E. Edging: After initial floating, tool edges of paving, gutters, curbs, and joints in concrete with an edging tool to a 1/4-inch radius. Repeat tooling of edges after applying surface finishes. Eliminate edging-tool marks on concrete surfaces.

3.6 PLACEMENT OF CONCRETE

A. Before placing concrete, inspect and complete formwork installation, steel reinforcement, and items to be embedded or cast-in.

B. Remove snow, ice, or frost from subbase surface before placing concrete. Do

not place concrete on frozen surfaces.

C. Moisten subbase to provide a uniform dampened condition at time concrete is placed. Do not place concrete around manholes or other structures until they are at required finish elevation and alignment.

D. Comply with ACI 301 requirements for measuring, mixing, transporting, and placing concrete.

E. Do not add water to concrete during delivery or at Project site. Do not add water to fresh concrete after testing.

F. Deposit and spread concrete in a continuous operation between transverse joints. Do not push or drag concrete into place or use vibrators to move concrete into place.

G. Consolidate concrete in accordance with ACI 301 by mechanical vibrating equipment supplemented by hand spading, rodding, or tamping.

1. Consolidate concrete along face of forms and adjacent to transverse joints with an internal vibrator. Keep vibrator away from joint assemblies, reinforcement, or side forms. Use only square-faced shovels for hand spreading and consolidation. Consolidate with care to prevent dislocating reinforcement dowels and joint devices.

H. Screed paving surface with a straightedge and strike off.

I. Commence initial floating using bull floats or darbies to impart an open-textured and uniform surface plane before excess moisture or bleedwater appears on the surface. Do not further disturb concrete surfaces before beginning finishing operations or spreading surface treatments.

3.7 FLOAT FINISHING

A. General: Do not add water to concrete surfaces during finishing operations.

B. Float Finish: Begin the second floating operation when bleedwater sheen has disappeared and concrete surface has stiffened sufficiently to permit operations. Float surface with power-driven floats or by hand floating if area is small or inaccessible to power units. Finish surfaces to true planes. Cut down high spots and fill low spots. Refloat surface immediately to uniform granular texture.

1. Burlap Finish: Drag a seamless strip of damp burlap across float-finished concrete, perpendicular to line of traffic, to provide a uniform, gritty texture.
2. Medium-to-Fine-Textured Broom Finish: Draw a soft-bristle broom across float-finished concrete surface, perpendicular to line of traffic, to provide a uniform, fine-line texture.
3. Medium-to-Coarse-Textured Broom Finish: Provide a coarse finish by striating float-finished concrete surface 1/16 to 1/8 inch deep with a stiff-bristled broom, perpendicular to line of traffic.

3.8 CURING OF CONCRETE

A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.

B. Comply with ACI 306.1 for cold-weather protection.

C. Begin curing after finishing concrete but not before free water has disappeared from concrete surface.

D. Curing Methods: Cure concrete by moisture curing moisture-retaining-cover curing curing compound or a combination of these as follows:

1. Moisture Curing: Keep surfaces continuously moist for not less than seven days with the following materials:

    a. Water.
    b. Continuous water-fog spray.

2. Curing Compounds: Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating, and repair damage during curing period.

3.9 PAVING TOLERANCES

A. Comply with tolerances in ACI 117 and as follows:

1. Elevation: 3/4 inch.
2. Thickness: Plus 3/8 inch, minus 1/4 inch.
3. Surface: Gap below 10-feet- long; unleveled straightedge not to exceed 1/2 inch.
4. Alignment of Tie-Bar End Relative to Line Perpendicular to Paving Edge: 1/2 inch per 12 inches of tie bar.
5. Lateral Alignment and Spacing of Dowels: 1 inch.
6. Vertical Alignment of Dowels: 1/4 inch.
7. Alignment of Dowel-Bar End Relative to Line Perpendicular to Paving Edge: 1/4 inch per 12 inches of dowel.
8. Joint Spacing: 3 inches.
9. Contraction Joint Depth: Plus 1/4 inch, no minus.
10. Joint Width: Plus 1/8 inch, no minus.

3.10 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Testing Services: Testing and inspecting of composite samples of fresh concrete

obtained in accordance with ASTM C172/C172M will be performed in accordance with the following requirements:

1. Testing Frequency: Obtain at least one composite sample for each 100 cu. yd. or fraction thereof of each concrete mixture placed each day.

    a. When frequency of testing will provide fewer than five compressive-strength tests for each concrete mixture, testing to be conducted from at least five randomly selected batches or from each batch if fewer than five are used.

2. Slump: ASTM C143/C143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture. Perform additional tests when concrete consistency appears to change.
3. Air Content: ASTM C231/C231M, pressure method; one test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
4. Concrete Temperature: ASTM C1064/C1064M; one test hourly when air temperature is 40 deg F and below and when it is 80 deg F and above, and one test for each composite sample.
5. Compression Test Specimens: ASTM C31/C31M; cast and laboratory cure one set of three standard cylinder specimens for each composite sample.
6. Compressive-Strength Tests: ASTM C39/C39M; test one specimen at seven days and two specimens at 28 days.

    a. A compressive-strength test to be the average compressive strength from two specimens obtained from same composite sample and tested at 28 days.

C. Strength of each concrete mixture will be satisfactory if average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi.

D. Test results to be reported in writing to Architect, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests to contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.

E. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.

F. Additional Tests: Testing and inspecting agency will make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect.

G. Concrete paving will be considered defective if it does not pass tests and inspections.

H. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

I. Prepare test and inspection reports.

3.11 PROTECTION

A. Remove and replace concrete paving that is broken, damaged, or defective or that does not comply with requirements in this Section. Remove work in complete sections from joint to joint unless otherwise approved by Architect.

B. Drill test cores, where directed by Architect, when necessary to determine magnitude of cracks or defective areas. Fill drilled core holes in satisfactory paving areas with portland cement concrete bonded to paving with epoxy adhesive.

C. Protect concrete paving from damage. Exclude traffic from paving for at least 14 days after placement. When construction traffic is permitted, maintain paving as clean as possible by removing surface stains and spillage of materials as they occur.

D. Maintain concrete paving free of stains, discoloration, dirt, and other foreign material. Sweep paving not more than two days before date scheduled for Substantial Completion inspections.

END OF SECTION 32 13 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 32 13 73
CONCRETE PAVING JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cold-applied joint sealants.

2. Joint-sealant backer materials.
3. Primers.

B. Related Requirements:

1. Section 079200 "Joint Sealants" for sealing nontraffic and traffic joints in locations not specified in this Section.

1.2 ACTION SUBMITTALS

A. Product Data:

1. Concrete pavement joint sealants.
2. Joint-sealant backer materials.

B. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type of joint sealant.

C. Paving-Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.3 QUALITY ASSURANCE

A. Qualifications:

1. Installers: Entity that employs installers and supervisors who are trained and approved by manufacturer.

1.4 FIELD CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

PART 2 - PRODUCTS

2.1 JOINT SEALANTS, GENERAL

A. Compatibility: Provide joint sealants, backer materials, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.

2.2 COLD-APPLIED JOINT SEALANTS

A. Multicomponent, Pourable, Urethane, Elastomeric Joint Sealant: ASTM C920, Type M, Grade P, Class 25, for Use T.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Pecora Corporation Urexpan NR-200 or comparable product by one of the following:

a. Sika
b. Bostik

2.3 JOINT-SEALANT BACKER MATERIALS

A. Joint-Sealant Backer Materials: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by joint-sealant manufacturer, based on field experience and laboratory testing.

B. Round Backer Rods for Cold- and Hot-Applied Joint Sealants: ASTM D5249, Type 1, of diameter and density required to control sealant depth and prevent bottom-side adhesion of sealant.

C. Round Backer Rods for Cold-Applied Joint Sealants: ASTM D5249, Type 3, of diameter and density required to control joint-sealant depth and prevent bottom-side adhesion of sealant.

D. Backer Strips for Cold- and Hot-Applied Joint Sealants: ASTM D5249; Type 2; of thickness and width required to control joint-sealant depth, prevent bottom-side adhesion of sealant, and fill remainder of joint opening under sealant.

2.4 PRIMERS

A. Primers: Product recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Before installing joint sealants, clean out joints immediately to comply with joint-sealant manufacturer's written instructions.

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.

B. Joint Priming: Prime joint substrates where indicated or where recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

3.3 INSTALLATION OF JOINT SEALANTS

A. Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated unless more stringent requirements apply.

B. Joint-Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions.

C. Install joint-sealant backers to support joint sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of joint-sealant backer materials.
2. Do not stretch, twist, puncture, or tear joint-sealant backer materials.
3. Remove absorbent joint-sealant backer materials that have become wet

before sealant application and replace them with dry materials.

D. Install joint sealants immediately following backer material installation, using proven techniques that comply with the following:

1. Place joint sealants so they fully contact joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

E. Tooling of Nonsag Joint Sealants: Immediately after joint-sealant application and before skinning or curing begins, tool sealants in accordance with the following requirements to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint:

1. Remove excess joint sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by joint-sealant manufacturer and that do not discolor sealants or adjacent surfaces.

F. Provide joint configuration to comply with joint-sealant manufacturer's written instructions unless otherwise indicated.

3.4 CLEANING AND PROTECTION

A. Clean off excess joint sealant as the Work progresses, by methods and with cleaning materials approved in writing by joint-sealant manufacturers.

B. Protect joint sealants, during and after curing period, from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately and replace with joint sealant so installations in repaired areas are indistinguishable from the original work.

3.5 PAVING-JOINT-SEALANT SCHEDULE

A. Joints within Concrete Paving:

1. Joint Location:

a. Expansion and isolation joints in concrete paving.
b. Contraction joints in concrete paving.
c. Other joints as indicated.

2. Joint Sealant: Multicomponent, pourable, urethane, elastomeric joint sealant.
3. Joint-Sealant Color: Manufacturer's standard.

END OF SECTION 32 13 73

PAGE LEFT INTENTIONALLY BLANK

SECTION 32 91 13
SOIL PREPARATION

PART 1 - GENERAL

1.1 SUMMARY

A. Work of This Section Includes:

1. Planting soils specified by composition of the mixes.

B. Related Requirements:

1. Section 329200 "Turf and Grasses" for placing planting soil for turf and grasses.

1.2 DEFINITIONS

A. Backfill: The earth used to replace or the act of replacing earth in an excavation. This can be amended or unamended soil as indicated.

B. Imported Soil: Soil that is transported to Project site for use.

C. Manufactured Soil: Soil produced by blending soils, sand, stabilized organic soil amendments, and other materials to produce planting soil.

D. Organic Matter: The total of organic materials in soil exclusive of undecayed plant and animal tissues, their partial decomposition products, and the soil biomass; also called "humus" or "soil organic matter."

E. Planting Soil: Existing, on-site soil; imported soil; or manufactured soil that has been modified as specified with soil amendments and perhaps fertilizers to produce a soil mixture best for plant growth.

F. Subgrade: Surface or elevation of subsoil remaining after excavation is complete, or the top surface of a fill or backfill before planting soil is placed.

G. Subsoil: Soil beneath the level of subgrade; soil beneath the topsoil layers of a naturally occurring soil profile, typified by less than 1 percent organic matter and few soil organisms.

H. Surface Soil: Soil that is present at the top layer of the existing soil profile. In undisturbed areas, surface soil is typically called "topsoil"; but in disturbed areas such as urban environments, the surface soil can be subsoil.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of specified product.

1. Include recommendations for application and use.
2. Include test data substantiating that products comply with requirements.
3. Include sieve analyses for aggregate materials.
4. Material Certificates: For each type of soil amendment and fertilizer before delivery to the site, according to the following:

a. Manufacturer's qualified testing agency's certified analysis of standard products.
b. Analysis of fertilizers, by a qualified testing agency, made according to AAPFCO methods for testing and labeling and according to AAPFCO's SUIP #25.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and compliance with state and Federal laws if applicable.

B. Bulk Materials:

1. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
2. Provide erosion-control measures to prevent erosion or displacement of bulk materials, discharge of soil-bearing water runoff, and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
3. Do not move or handle materials when they are wet or frozen.
4. Accompany each delivery of bulk fertilizers and soil amendments with appropriate certificates.

PART 2 - PRODUCTS

2.1 PLANTING SOILS SPECIFIED BY COMPOSITION

A. General: Soil amendments, fertilizers, and rates of application specified in this article are guidelines that may need revision based on testing laboratory's recommendations after preconstruction soil analyses are performed.

B. Existing Planting-Soil Type : Existing, on-site surface soil, with the duff layer, if any, retained; and stockpiled on-site; modified to produce viable planting soil. Blend existing, on-site surface soil with the following soil amendments and fertilizers in the following quantities to produce planting soil:

2.2 FERTILIZERS

A. Superphosphate: Commercial, phosphate mixture, soluble; a minimum of [**20**][**33**][**50**] percent available phosphoric acid.

B. Commercial Fertilizer: Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:

1. Composition:

a. **1 lb/1000 sq. ft.** of actual nitrogen, 4 percent phosphorous, and 2 percent potassium, by weight.
b. Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified testing agency.

C. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:

1. Composition:

a. 20 percent nitrogen, 10 percent phosphorous, and 10 percent potassium, by weight.
b. Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified testing agency.

D. Chelated Iron: Commercial-grade FeEDDHA for dicots and woody plants, and commercial-grade FeDTPA for ornamental grasses and monocots.

PART 3 - EXECUTION

3.1 GENERAL

A. Place planting soil and fertilizers according to requirements in other Specification Sections.

B. Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in planting soil.

C. Proceed with placement only after unsatisfactory conditions have been corrected.

3.2 PREPARATION OF UNAMENDED, ON-SITE SOIL BEFORE AMENDING

A. Excavation: Excavate soil from designated area(s) to a depth of 6 inches and stockpile until amended.

B. Unacceptable Materials: Clean soil of concrete slurry, concrete layers or chunks, cement, plaster, building debris, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, acid, and other extraneous materials that are harmful to plant growth.

C. Unsuitable Materials: Clean soil to contain a maximum of 8 percent by dry weight of stones, roots, plants, sod, clay lumps, and pockets of coarse sand.

D. Screening: Pass unamended soil through a 3-inch sieve to remove large materials.

3.3 PROTECTION

A. Protection Zone: Identify protection zones according to Section 015639 "Temporary Tree and Plant Protection."

B. Protect areas of in-place soil from additional compaction, disturbance, and contamination. Prohibit the following practices within these areas except as required to perform planting operations:

1. Storage of construction materials, debris, or excavated material.

2. Foot traffic.

3. Impoundment of water.
4. Excavation or other digging unless otherwise indicated.

C. If planting soil or subgrade is overcompacted, disturbed, or contaminated by foreign or deleterious materials or liquids, remove the planting soil and contamination; restore the subgrade as directed by Architect and replace contaminated planting soil with new planting soil.

3.4 CLEANING

A. Protect areas adjacent to planting-soil preparation and placement areas from contamination. Keep adjacent paving and construction clean and work area in an orderly condition.

B. Remove surplus soil and waste material including excess subsoil, unsuitable materials, trash, and debris and legally dispose of them off Owner's property unless otherwise indicated.

1. Dispose of excess subsoil and unsuitable materials on-site where directed by Owner.

END OF SECTION 32 91 13

PAGE LEFT INTENTIONALLY BLANK

SECTION 32 92 00
TURF AND GRASSES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Meadow grasses and wildflowers.
2. Fertilizers.

B. Related Requirements:

1. Section 329300 "Plants" for trees, shrubs, ground covers, and other plants as well as border edgings and mow strips.

1.2 DEFINITIONS

A. Finish Grade: Elevation of finished surface of planting soil.

B. Pesticide: A substance or mixture intended for preventing, destroying, repelling, or mitigating a pest. Pesticides include insecticides, miticides, herbicides, fungicides, rodenticides, and molluscicides. They also include substances or mixtures intended for use as a plant regulator, defoliant, or desiccant.

C. Pests: Living organisms that occur where they are not desired or that cause damage to plants, animals, or people. Pests include insects, mites, grubs, mollusks (snails and slugs), rodents (gophers, moles, and mice), unwanted plants (weeds), fungi, bacteria, and viruses.

D. Planting Soil: Existing, on-site soil; imported soil; or manufactured soil that has been modified with soil amendments and perhaps fertilizers to produce a soil mixture best for plant growth. See Section 329113 "Soil Preparation" and drawing designations for planting soils.

E. Subgrade: The surface or elevation of subsoil remaining after excavation is complete, or the top surface of a fill or backfill before planting soil is placed.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance Data: Recommended procedures to be established by Owner for maintenance of turf during a calendar year. Submit before expiration of required maintenance periods.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Seed and Other Packaged Materials: Deliver packaged materials in original, unopened containers showing weight, certified analysis, name and address of manufacturer, and indication of compliance with state and Federal laws, as applicable.

B. Bulk Materials:

1. Do not dump or store bulk materials near structures, utilities, walkways and pavements, or on existing turf areas or plants.
2. Provide erosion-control measures to prevent erosion or displacement of bulk materials; discharge of soil-bearing water runoff; and airborne dust reaching adjacent properties, water conveyance systems, or walkways.
3. Accompany each delivery of bulk materials with appropriate certificates.

1.5 FIELD CONDITIONS

A. Planting Restrictions: Plant during one of the following periods. Coordinate planting periods with initial maintenance periods to provide required maintenance from date of Substantial Completion.

B. Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit planting to be performed when beneficial and optimum results may be obtained. Apply products during favorable weather conditions according to manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 MEADOW GRASSES AND WILDFLOWERS

A. Native-Grass Seed : Fresh, clean, and dry new seed, of mixed species to match existing.

FERTILIZERS

B. Commercial Fertilizer : Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:

1. Composition:

a. 1 lb/1000 sq. ft. of actual nitrogen, 4 percent phosphorous, and 2 percent potassium, by weight.
b. Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing laboratory.

2.2 PESTICIDES

A. General: Pesticide, registered and approved by the EPA, acceptable to authorities having jurisdiction, and of type recommended by manufacturer for each specific problem and as required for Project conditions and application. Do not use restricted pesticides unless authorized in writing by authorities having jurisdiction.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to be planted for compliance with requirements and other conditions affecting installation and performance of the Work.

1. Verify that no foreign or deleterious material or liquid such as paint, paint washout, concrete slurry, concrete layers or chunks, cement, plaster, oils, gasoline, diesel fuel, paint thinner, turpentine, tar, roofing compound, or acid has been deposited in soil within a planting area.
2. Suspend planting operations during periods of excessive soil moisture until the moisture content reaches acceptable levels to attain the required results.
3. Uniformly moisten excessively dry soil that is not workable or which is dusty.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

C. If contamination by foreign or deleterious material or liquid is present in soil within a planting area, remove the soil and contamination as directed by Architect and replace with new planting soil.

3.2 PREPARATION

A. Protect structures; utilities; sidewalks; pavements; and other facilities, trees, shrubs, and plantings from damage caused by planting operations.

1. Protect adjacent and adjoining areas from hydroseeding and hydromulching overspray.
2. Protect grade stakes set by others until directed to remove them.

B. Install erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.

3.3 PREPARATION OF TURF AREA

A. General: Prepare planting area for soil placement and mix planting soil according to Section 329113 "Soil Preparation."

B. Placing Planting Soil: Place and mix planting soil in place over exposed subgrade.

1. Reduce elevation of planting soil to allow for soil thickness of sod.

C. Moisten prepared area before planting if soil is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.

D. Before planting, obtain Architect's acceptance of finish grading; restore planting areas if eroded or otherwise disturbed after finish grading.

3.4 SEEDING OF MEADOW GRASSES AND WILDFLOWERS

A. Sow seed with spreader or seeding machine. Do not broadcast or drop seed when wind velocity exceeds 5 mph.

1. Before sowing, mix seed with seed carrier at a ratio of not less than three parts seed carrier to one part seed.
2. Evenly distribute seed by sowing equal quantities in two directions at right angles to each other.
3. Do not use wet seed or seed that is moldy or otherwise damaged.

B. Sow seed at a total rate of 4 oz./1000 sq. ft..

C. Brush seed into top 1/16 inch of soil, roll lightly, and water with fine spray.

D. Protect seeded areas from hot, dry weather or drying winds by applying peat mulch within 24 hours after completing seeding operations. Soak areas, scatter mulch uniformly to a thickness of 3/16 inch, and roll surface smooth.

E. Water newly planted areas and keep moist until meadow is established.

3.5 MAINTENANCE OF MEADOW GRASSES AND WILDFLOWERS

A. Maintain and establish meadow by watering, weeding, mowing, trimming, replanting, and performing other operations as required to establish a healthy, viable meadow. Roll, regrade, and replant bare or eroded areas and remulch. Provide materials and installation the same as those used in the original installation.

1. Fill in as necessary soil subsidence that may occur because of settling or other processes. Replace materials and meadow damaged or lost in areas of subsidence.
2. In areas where mulch has been disturbed by wind or maintenance

operations, add new mulch and anchor as required to prevent displacement.

3. Apply treatments as required to keep meadow and soil free of pests and pathogens or disease. Use integrated pest management practices whenever possible to minimize the use of pesticides and reduce hazards.

B. Watering: Install and maintain temporary piping, hoses, and meadow-watering equipment to convey water from sources and to keep meadow uniformly moist.

1. Schedule watering to prevent wilting, puddling, erosion, and displacement of seed or mulch. Lay out temporary watering system to avoid walking over muddy or newly planted areas.
2. Water meadow with fine spray at a minimum rate of 1/2 inch per week for six weeks after planting unless rainfall precipitation is adequate.

3.6 CLEANUP

A. Promptly remove soil and debris created by turf work from paved areas. Clean wheels of vehicles before leaving site to avoid tracking soil onto roads, walks, or other paved areas.

B. Remove surplus soil and waste material, including excess subsoil, unsuitable soil, trash, and debris, and legally dispose of them off Owner's property.

C. Remove nondegradable erosion-control measures after grass establishment period.

3.7 PROTECTION

A. Erect temporary fencing or barricades and warning signs as required to protect newly planted areas from traffic. Maintain fencing and barricades throughout initial maintenance period and remove after plantings are established.

3.8 MAINTENANCE SERVICE FOR MEADOW GRASSES AND WILDFLOWERS

A. Meadow Maintenance Service: Provide full maintenance by skilled employees of landscape Installer. Maintain as required in "Meadow Maintenance" Article. Begin maintenance immediately after each area is planted and continue until acceptable meadow is established, but for not less than maintenance period below.

1. Maintenance Period: 40 days from date of Substantial Completion.

END OF SECTION 32 92 00

PAGE LEFT INTENTIONALLY BLANK