



HILLSBOROUGH COUNTY AVIATION AUTHORITY

INVITATION TO BID

FOR

REHABILITATE RUNWAY 1L-19R AND ASSOCIATED
TAXIWAYS AND NORTHWEST REMAIN OVERNIGHT (RON)
PARKING APRON

POST DATE: August 25, 2026

QUESTION AND CLARIFICATION DEADLINE: September 23, 2026, 5:00 pm

BID DEADLINE: October 8, 2026, 2:00 pm

RESPONSES MUST BE SUBMITTED ELECTRONICALLY TO:
<https://procurement.opengov.com/portal/tampaairport/>

HILLSBOROUGH COUNTY AVIATION AUTHORITY
INVITATION TO BID

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest
Remain Overnight (RON) Parking Apron

1. Introduction
2. Respondent Questionnaire
3. Bid Schedule

Attachments:

A - Division 0

B - Division 1

C - Technical Specifications

D - Construction Safety and Phasing Plan (CSPP)

E - Plans - Volume 1

F - Plans - Volume 2

1. Introduction

The Hillsborough County Aviation Authority (Owner) has a Cone of Silence applicable to all competitive procurement processes which places restrictions on communications. Refer to the Cone of Silence in the Solicitation document for more information. All inquiries regarding this Solicitation must be submitted in writing to the Procurement Agent assigned to this Solicitation.

The Bidder must supply all information and documents required by the Solicitation documents through the Owner's e-Procurement Portal located at <https://procurement.opengov.com/portal/tampaairport> by the Bid Submittal Time and Date.

1.1. Summary

This Project consists of the rehabilitation of the Runway 1L-19R and associated taxiways and the construction of a new Northwest Remain Overnight (RON) aircraft parking apron at Tampa International Airport.

1.2. Contact Information

Rayesha Cotton

Senior Procurement Agent

P.O. Box 22287

Tampa, FL 33622

Email: rcotton@tampaairport.com

Phone: [\(813\) 554-1448](tel:(813)554-1448)

Department:

Planning and Development

1.3. Timeline

Contract Documents Posted	August 25, 2026
---	-----------------

Mandatory Pre-Bid Conference (Mandatory)	September 9, 2026, 10:00am The mandatory Pre-Bid Conference will be held in the SkyCenter Boardroom, which is located on the fourth floor of the SkyCenter One Office Building at 5411 SkyCenter Dr., Tampa, FL 33607. OR Microsoft Teams ® Call-In: +1 813-694-2596 Phone Conference ID: 562 252 24# Click here to join the Microsoft Teams Meeting: https://teams.microsoft.com/meet/263455750451480?p=EAEp731HLXnRM6fAZN
Mandatory Site Inspection	September 9, 2026, as a part of the scheduled Mandatory Pre-Bid Conference. Details will be announced during the Mandatory Pre-Bid Conference. The Mandatory Site Inspection will commence immediately following the conclusion of the Pre-Bid Conference.
Non-Mandatory Site Inspection (Non-Mandatory)	September 15, 2026, 10:00am Bus will depart from SkyCenter Curb at 10:00 am for this site inspection. The site inspection will give participants an opportunity to get on Runway 1L-19R and Associated Taxiways.
Request for Clarification Deadline	September 23, 2026, 5:00pm
Addendum posted on Owner's e-Procurement Portal website	September 30, 2026, 5:00pm

Bid Submittal Time and Date	October 8, 2026, 2:00pm RCC Conference Room - Rental Car Center OR Microsoft Teams ® Call-In: +1 813-694-2596 Phone Conference ID: 501 669 884# Click here to join the Microsoft Teams Meeting: https://teams.microsoft.com/meet/244672451649541?p=69HaggakIPFXfr0dIA
Award by Authority's Board	November 5, 2026

2. Respondent Questionnaire

Bidder shall review and complete the Respondent Questionnaire in its entirety. Failure to complete the Respondent Questionnaire may deem the Bid as non-responsive.

2.1. Minimum Qualifications

Minimum qualifications have been established as a basis for determining the eligibility of each submitted Bid. A submitted Bid will be determined non-responsive and will not be considered unless sufficient documentation is provided to determine whether the Bidder meets the minimum qualifications listed below:

2.1.1. Bidder is registered with the Florida Department of State, Division of Corporations to do business in the State of Florida. (www.sunbiz.org)*

Attach proof of registration

*Response required

2.1.2. Bidder is required to confirm that, if awarded by the Board, Bidder will register with PaymentWorks and select one of the Authority's electronic payment methods.*

☐ Please confirm

*Response required

2.1.3. Bidder is NOT listed on the Florida Department of Management Services, Convicted Vendor List as defined in Section 287.133(3)(d), Florida Statutes.*

☐ Please confirm

*Response required

2.1.4. Bidder is NOT listed on the Scrutinized Companies with Activities in Sudan List or the Scrutinized Companies with Activities in the Iran Petroleum Energy Sector List or the Scrutinized Companies that Boycott Israel List or is engaged in business operations in Cuba or Syria, as detailed in this Solicitation. *

☐ Please confirm

*Response required

2.1.5. Bidder is NOT listed on the Federal Convicted Vendor list. (www.sam.gov)*

☐ Please confirm

*Response required

2.1.6. Bidder is NOT listed on the Florida Department of Transportation Contractor Suspension List. *

☐ Please confirm

*Response required

2.1.7. Bidder had a representative sign-in and attend the Mandatory Pre-Bid Conference or had a representative attend the Mandatory Pre-Bid Conference on-line via Microsoft Teams®. *

NOTE: To be considered as attending the Mandatory Pre-Bid Conference, the prospective Bidder must have signed in on a sign-in sheet prior to the start of the Mandatory Pre-Bid Conference or signed in to Microsoft Teams® and be identified by the Procurement Agent at the start of the Mandatory Pre-Bid Conference.

Provide the name of Bidder's representative who attended the mandatory Pre-Bid Conference in-person or via Microsoft Teams®

*Response required

2.1.8. Bidder had a representative sign-in and attend the Mandatory Site Inspection. *

NOTE: To be considered as attending the Mandatory Site Inspection, a prospective Bidder must have signed in on a sign-in sheet prior to the start of the Mandatory Site Inspection.

Provide the name of Bidder's representative who attended the Mandatory Site Inspection.

*Response required

2.1.9. Bidder confirms that the Bidder has the ability to obtain the insurance coverage and limits as required in Section 00650 - INSURANCE REQUIREMENTS.*

☐ Please confirm

*Response required

2.1.10. Bidder has completed Section 00300 - BID FORM.*

Please download the below documents, complete, and upload.

- [00300 bid form.pdf](#)

*Response required

2.1.11. Bidder confirms that its Bid includes any applicable Tariffs imposed by the Bid Submittal Due Date and Time.*

☐ Please confirm

*Response required

2.1.12. Bidder has completed Section 00350 - BID AFFIDAVIT*

Please download the below documents, complete, and upload.

- [00350 - bid affidavit.pdf](#)

*Response required

2.1.13. Bidder has submitted Section 00400-1 - BID BOND or Cashier's Check and Section

00400-2 SURETY BOND AFFIDAVIT.*

Please download the below documents, complete, and upload.

- [00400-1 - bid bond 7-29-26.pdf](#)

*Response required

2.2. Additional Required Documents

2.2.1. Bidder has completed Section 00415 - TRENCH SAFETY CERTIFICATION.*

Please download the below documents, complete, and upload.

- [00415-TrenchSafety 7-29-26.pdf](#)

*Response required

2.2.2. Bidder has completed Section 00417 - SMALL BUSINESS ENTERPRISE (SBE) ASSURANCE AND PARTICIPATION.*

Please download the below documents, complete, and upload.

- [00417-SBE.pdf](#)

*Response required

2.2.3. Bidder has completed Section 00420 – BIDDER’S GENERAL BUSINESS INFORMATION.*

Please download the below documents, complete, and upload.

- [00420 Bidder's General Busi...](#)

*Response required

2.2.4. Bidder has completed Section 00421 – SCRUTINIZED COMPANY CERTIFICATION.*

Please download the below documents, complete, and upload.

- [00421 - Scrutinized Company...](#)

*Response required

2.2.5. Bidder has completed Section 00422 – E-VERIFY CERTIFICATION.*

Please download the below documents, complete, and upload.

- [00422 - E-Verify Certificat...](#)

*Response required

2.2.6. Bidder has completed Section 00423 – NON-COLLUSION CERTIFICATION.*

Please download the below documents, complete, and upload.

- [00423 Non-Collusion Certifi...](#)

*Response required

2.2.7. Bidder has completed Section 00430 – SUBCONTRACTORS LIST *

Please download the below documents, complete, and upload.

- [00430 - sub contractor list...](#)

*Response required

2.2.8. Bidder has completed Section 00440 - PAYMENT METHOD*

Please download the below documents, complete, and upload.

- [00440 - Payment Method 7-29...](#)

*Response required

2.2.9. Bidder has completed Section 00450 - Affidavit of Compliance with Anti-Human Trafficking Laws.*

Please download the below documents, complete, and upload.

- [00450 - Trafficking Cert 7-...](#)

*Response required

2.2.10. Bidder has included their Financial Statement(s).*

*Response required

2.2.11. Bidder has provided a copy of a current and active Contractor's License that qualifies Bidder to bid on the work.*

*Response required

2.2.12. If the Bid Affidavit is signed by a person other than the President or Vice President of the corporation, such person will furnish a corporate resolution showing their authority to bind the corporation.

3. Bid Schedule

The Owner will be accepting electronic submissions of the Bid Schedule via the Owner's e-Procurement portal partner, OpenGov Procurement. Bidder will submit Bidder's pricing using the online Bid Schedule.

TABLE 1

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
C-100-14.1	CONTRACTOR QUALITY CONTROL PROGRAM (CQCP)	1	LS		
C-102-5.1	EROSION CONTROL MEASURES	1	LS		
C-105-10.1	MOBILIZATION (MOBILIZATION IS LIMITED TO TEN PERCENT (10%) OF THE TOTAL PROJECT COST)	1	LS		
C-105-10.2	MAINTENANCE OF TRAFFIC	1	LS		
C-105-10.3	PORTABLE RUNWAY CLOSURE MARKERS	2	EA		
C-105-10.4	PROJECT SURVEY AND STAKEOUT	1	LS		
M-104-10.1	SAFETY AND SECURITY	1	LS		
P-101-5.1	ASPHALT PAVEMENT SURFACE MILLING (2-3" NOMINAL)	42,000	SY		
P-101-5.2	FULL DEPTH ASPHALT PAVEMENT REMOVAL	37,000	SY		
P-101-5.3	ISOLATED PAVEMENT REMOVAL CONCRETE PAVEMENT VARIABLE (17" NOMINAL)	2,500	SY		
P-101-5.4	ISOLATED PAVEMENT REMOVAL CONCRETE BASE (LCB OR AGGREGATE BASE 6")	750	SY		
P-101-5.5	FULL DEPTH CONCRETE PAVEMENT REMOVAL INCLUDING BASE (17" PCC+6" BASE)	51,000	SY		
P-101-5.6	JOINT AND CRACK REPAIR (CONCRETE)	1,000	LF		
P-101-5.7	CONCRETE SPALL REPAIR	800	SF		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
P-101-5.8	CONCRETE VALLEY GUTTER REMOVAL	2,600	LF		
P-101-5.9	FENCE DEMOLITION	2,900	LF		
P-101-5.10	FUEL LINE DEMOLITION	2,800	LF		
P-101-5.11	DEMO EXISTING STORM PIPE	3,000	LF		
P-101-5.12	DEMO EXISTING UNDERDRAIN PIPE	10,700	LF		
P-101-5.13	DEMO EXISTING STORM STRUCTURE	37	EA		
P-101-5.14	REMOVE AND DISPOSE OF DERELECT EQUIPMENT ON EXISTING APRON	20	EA		
P-101-5.15	GENERAL DEMOLITION	1	LS		
P-101-5.16	TAXIWAY A BRIDGE MSE WALL EROSION REPAIR	1	LS		
P-152-4.1	UNCLASSIFIED EXCAVATION	37,000	CY		
P-152-4.2	OFFSITE BORROW	28,000	CY		
P-152-4.3	UNSUITABLE EXCAVATION	2,000	CY		
P-160-1	SUBGRADE STABILIZATION (6" THICK) (LBR = 75)	153,000	SY		
P-211-5.1	LIMEROCK BASE COURSE, SHOULDERS (8" THICK)	38,000	SY		
P-219-5.1	RECYCLED CONCRETE BASE COURSE (6" THICK)	18,000	SY		
P-219-5.2	RECYCLED CONCRETE BASE COURSE (4" THICK)	1,300	SY		
P-306-8.1	LEAN CONCRETE BASE COURSE (6" THICK)	132,000	SY		
P-403-8.1	ASPHALT MIXTURE SURFACE COURSE (VARIOUS THICKNESSES)	15,900	TN		
520-1-10	FDOT TYPE F CURB	220	LF		
P-501-8.1	CEMENT CONCRETE PAVEMENT (18" THICK)	100,300	SY		

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
P-501-8.2	CEMENT CONCRETE PAVEMENT, THICKENED EDGE (18"-23" THICK)	6,200	SY		
P-501-8.3	CEMENT CONCRETE PAVEMENT (10" THICK)	15,000	SY		
P-501-8.4	CEMENT CONCRETE PAVEMENT, THICKENED EDGE (10"-13" THICK)	2,700	SY		
P-501-8.5	CEMENT CONCRETE PAVEMENT (12" THICK)	19,000	SY		
P-501-8.6	CEMENT CONCRETE PAVEMENT, THICKENED EDGE (12"-15" THICK)	3,100	SY		
P-501-8.7	CEMENT CONCRETE PAVEMENT, FIBER REINFORCED (17" THICKNESS) FOR ISOLATED SLABS	1,800	SY		
P-501-8.8	CEMENT CONCRETE PAVEMENT, FIBER REINFORCED (19" THICKNESS) FOR ISOLATED SLABS	700	SY		
P-605-5.1	CLEAN AND RESEAL CONCRETE / CONCRETE - CONSTRUCTION, CONTRACTION, AND EXPANSION JOINTS	230,000	LF		
P-605-5.2	CLEAN AND RESEAL CONCRETE / ASPHALT JOINTS	19,000	LF		
P-620-4	RUNWAY AND TAXIWAY PAINT REMOVAL	363,000	SF		
P-620-5.1	WATERBORNE PAVEMENT MARKING, WHITE WITH GLASS BEADS	164,000	SF		
P-620-5.2	WATERBORNE PAVEMENT MARKING, YELLOW WITH GLASS BEADS	129,000	SF		
P-620-5.3	WATERBORNE PAVEMENT MARKING, RED WITH GLASS BEADS	15,000	SF		
P-620-5.4	WATERBORNE PAVEMENT MARKING, BLACK WITHOUT GLASS BEADS	195,000	SF		
P-620-5.5	WATERBORNE PAVEMENT MARKING, GREEN WITHOUT GLASS BEADS	30,000	SF		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
P-620-5.6	TEMPORARY PAVEMENT MARKINGS WITH GLASS BEADS	94,000	SF		
P-620-5.7	TEMPORARY PAVEMENT MARKINGS WITHOUT GLASS BEADS	96,000	SF		
P-621-5.1	SAW-CUT GROOVING	300	SY		
P-631-7.1	REFINED COAL TAR EMULSION WITH ADDITIVES FOR SLURRY COAT (TWO COATS WITH SAND)	660,000	SF		
F-162-5.1	NEW 8 FT HIGH FENCE WITH 3 STRANDS BARBED WIRE, 1 FT BARBED WIRE EXTENSION ARMS, TOP RAIL, AND BOTTOM TENSION WIRE, INCLUDING GROUNDING AND SIGNS, INSTALLED IN TURF	1,900	LF		
F-162-5.2	NEW 8 FT HIGH DOUBLE SWING VEHICLE GATE WITH 3 STRANDS BARBED WIRE, 1 FT BARBED WIRE EXTENSION ARMS, TOP RAIL, AND BOTTOM TENSION WIRE, INCLUDING GROUNDING AND SIGNS	2	EA		
D-701-5.1	15" REINFORCED CONCRETE PIPE (CLASS V)	142	LF		
D-701-5.2	18" REINFORCED CONCRETE PIPE (CLASS V)	140	LF		
D-701-5.3	24" REINFORCED CONCRETE PIPE (CLASS V)	450	LF		
D-701-5.4	30" REINFORCED CONCRETE PIPE (CLASS V)	1,005	LF		
D-701-5.5	36" REINFORCED CONCRETE PIPE (CLASS V)	531	LF		
D-701-5.6	42" REINFORCED CONCRETE PIPE (CLASS V)	80	LF		
D-701-5.7	48" REINFORCED CONCRETE PIPE (CLASS V)	1,000	LF		
D-701-5.8	72" REINFORCED CONCRETE PIPE (CLASS V)	460	LF		

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
D-701-5.9	12"x18" HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE	200	LF		
D-701-5.10	43"x68" HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE	960	LF		
D-701-5.11	16-INCH DUCTILE IRON PIPE (CLASS 52)	571	LF		
D-701-5.12	24-INCH DUCTILE IRON PIPE (CLASS 52)	18.57	LF		
D-705-5.1	6 INCH PERFORATED, INCLUDING BACKFILL, FILTER FABRIC AND CONNECTION TO DRAINAGE STRUCTURES	9,000	LF		
D-705-5.2	8 INCH NON-PERFORATED, INCLUDING BACKFILL AND CONNECTION TO DRAINAGE STRUCTURES	1,500	LF		
D-705-5.3	INSTALL CLEAN OUT AND/OR INSPECTION PORT	113	EA		
D-705-5.4	ELECTRICAL DRAIN PIPES (1")	1	LS		
D-751-5.1	TRENCH DRAIN (12" WIDE CHANNEL - 3' TOTAL WIDTH - W/ 6' FIRESTOPS)	2,560	LF		
D-751-5.2	SEGMENTED TRENCH DRAIN (12" WIDE CHANNEL - 3' TOTAL WIDTH - W/ 6' FIRESTOPS)	195	LF		
D-751-5.3	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE A (8' DIA)	5	EA		
D-751-5.4	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE A (10' DIA)	1	EA		
D-751-5.5	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (4'X6')	4	EA		
D-751-5.6	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (5'X5')	1	EA		

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
D-751-5.7	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (5'X6')	1	EA		
D-751-5.8	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (6'X6')	1	EA		
D-751-5.9	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (7'X8')	1	EA		
D-751-5.10	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (8'X8')	2	EA		
D-751-5.11	AIRCRAFT RATED DRAINAGE MANHOLE STRUCTURE - TYPE B (8'X10')	1	EA		
D-751-5.12	AIRCRAFT RATED DRAINAGE INLET STRUCTURE - TYPE C (5'X5')	3	EA		
D-751-5.13	AIRCRAFT RATED DRAINAGE INLET STRUCTURE - TYPE C (5'X6')	1	EA		
D-751-5.14	AIRCRAFT RATED DRAINAGE INLET STRUCTURE - TYPE C (6'X6')	1	EA		
D-751-5.15	AIRCRAFT RATED DRAINAGE INLET STRUCTURE - TYPE C (7'X10')	1	EA		
D-751-5.16	AIRCRAFT RATED DRAINAGE INLET STRUCTURE - TYPE C (10'X10')	1	EA		
D-751-5.17	AIRCRAFT RATED DRAINAGE INLET STRUCTURE - TYPE D (8'X7')	5	EA		
D-751-5.18	FDOT MANHOLE (TYPE J8, 5' DIA), INDEX 425-010	1	EA		
D-751-5.19	FDOT INLET (TYPE D), INDEX 425-052	1	EA		
D-751-5.20	CURB INLET (TYPE 2) FDOT INDEX 425-020	1	EA		
D-751-5.21	CURB INLET (TYPE 1) FDOT INDEX 425-020	1	EA		
D-751-5.22	BOX CULVERT MODIFICATION - CONNECT 36" RCP TO EXISTING BOX CULVERT	1	EA		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
D-751-5.23	BOX CULVERT MODIFICATION - CONNECT 48" RCP TO EXISTING BOX CULVERT	1	EA		
D-751-5.24	BOX CULVERT MODIFICATION - CONNECT 68"X43" HERCP TO EXISTING BOX CULVERT	1	EA		
D-751-5.25	EXISTING STRUCTURE MODIFICATION - CASE 1 AIRCRAFT RATED MANHOLE STRUCTURE WITH RISER TO BE RAISED OR LOWERED WITH H < 2'-0"	2	EA		
D-751-5.26	EXISTING STRUCTURE MODIFICATION - CASE 2 REMOVE EXISTING MANHOLE RISER AND INSTALL NEW AIRCRAFT RATED RISER AT THE TOP OF EXISTING BOX CULVERT	2	EA		
D-751-5.27	EXISTING STRUCTURE MODIFICATION - CASE 3 AIRCRAFT RATED MANHOLE STRUCTURE WITHOUT RISER TO BE LOWERED	2	EA		
D-751-5.28	CORE DRILL/MODIFY EXISTING DRAINAGE MANHOLE AS NEEDED TO PROVIDE FOR INSTALLATION OF NEW DRAINAGE PIPE	2	EA		
D-752-1	DOUBLE 24" MITERED END SECTION (1:4 SLOPE) FDOT INDEX 430-021	2	EA		
D-752-2	SINGLE 12"X18" MITERED END SECTION (1:4 SLOPE) FDOT INDEX 430-021	2	EA		
T-904-5.1	SODDING	70,000	SY		
T-904-5.2	SHOULDER EDGE DRESSING (INCLUDING SOD)	5,200	SY		
L-100-01	VERIFICATION OF EXISTING CONDITIONS	1	LS		
L-100-02	ELECTRICAL CLOSE OUT DOCUMENTS	1	LS		
L-104-01	TEMPORARY WIRING, BYPASSES, AND SIGN & FIXTURE COVERING	1	LS		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
L-105-01	ELECTRICAL GENERAL DEMOLITION REQUIREMENTS	1	LS		
L-105-11	REMOVAL LIGHT FIXTURE - ELEVATED TYPE (EXCLUDING BASE)	326	EA		
L-105-12	REMOVAL LIGHT FIXTURE - INSET TYPE (EXCLUDING BASE)	729	EA		
L-105-21	REMOVAL OF AIRFIELD LIGHTING CABLE - 1-1/C #8 AWG L-824	330,000	LF		
L-105-31	REMOVAL OF LIGHT BASE - WITHIN CIVIL DEMOLITION AREAS	224	EA		
L-105-32	REMOVAL OF LIGHT BASE - WITHIN NON-DEMOLISHED PAVEMENT AREAS	74	EA		
L-105-41	REMOVAL OF HANDHOLE - NOT PLANNED FOR REUSE	11	EA		
L-105-42	REMOVAL OF HANDHOLE - PLANNED FOR REUSE	2	EA		
L-105-51	REMOVAL OF DUCT BANK - 1W2" OR GREATER, NON ENCASED	21,900	LF		
L-105-52	REMOVAL OF DUCT BANK - 1W4" OR GREATER, CONCRETE ENCASED	3,200	LF		
L-108-01	PRIMARY CABLE - 1-1/C #8 AWG, 5 KV, L-824, TYPE C CABLE, INSTALLED WITHIN RACEWAY	43,200	LF		
L-108-02	PRIMARY CABLE - 2-1/C #8 AWG, 5 KV, L-824, TYPE C CABLE, INSTALLED WITHIN RACEWAY	134,000	LF		
L-108-11	LIGHTNING ARRESTOR FOR PRIMARY CABLE	128	EA		
L-110-01	CLEAR EXISTING CONDUIT/DUCT BANK RACEWAY BY WAY OF MANDREL OF EXISTING RACEWAYS.	1	LS		
L-110-11	DUCT BANK - 1W2" SCH 40 PVC DIRECT BURIED W/ COUNTERPOISE	4,400	LF		

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
L-110-12	DUCT BANK - 2W2" SCH 40 PVC DIRECT BURIED W/ COUNTERPOISE	300	LF		
L-110-13	DUCT BANK - 4W4" SCH 40 PVC DIRECT BURIED W/ COUNTERPOISE	1,100	LF		
L-110-21	DUCT BANK - 1W2" SCH 40 PVC CONCRETE ENCASED W/ COUNTERPOISE	1,650	LF		
L-110-22	DUCT BANK - 2W4" SCH 40 PVC CONCRETE ENCASED W/ COUNTERPOISE	60	LF		
L-110-23	DUCT BANK - 4W4" SCH 40 PVC CONCRETE ENCASED W/ COUNTERPOISE	830	LF		
L-110-24	DUCT BANK - 6W4" SCH 40 PVC CONCRETE ENCASED W/ COUNTERPOISE	70	LF		
L-110-25	DUCT BANK - 8W4" SCH 40 PVC CONCRETE ENCASED W/ COUNTERPOISE	300	LF		
L-110-41	DUCT BANK - 1W2" SCH 40 PVC IN ASPHALT W/ COUNTERPOISE	11,400	LF		
L-110-42	DUCT BANK - 2W4" SCH 40 PVC IN ASPHALT W/ COUNTERPOISE	70	LF		
L-110-43	DUCT BANK - 4W4" SCH 40 PVC IN ASPHALT W/ COUNTERPOISE	1,700	LF		
L-110-44	DUCT BANK - 6W4" SCH 40 PVC IN ASPHALT W/ COUNTERPOISE	130	LF		
L-110-45	DUCT BANK - 8W4" SCH 40 PVC IN ASPHALT W/ COUNTERPOISE	130	LF		
L-110-51	KERF CUT CONDUIT - 1W2" SCH 40 PVC CONDUIT INSTALLED WITHIN EXISTING PAVEMENT (4"W X 8"D)	1,400	LF		
L-113-01	DIRECTIONAL BORE - 1W2" HDPE W/ COUNTERPOISE	500	LF		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
L-113-02	DIRECTIONAL BORE - 2W4" HDPE W/ COUNTERPOISE	260	LF		
L-113-03	DIRECTIONAL BORE - 4W4" HDPE W/ COUNTERPOISE	600	LF		
L-113-04	DIRECTIONAL BORE - 6W4" HDPE W/ COUNTERPOISE	140	LF		
L-115-01	CABLE PULLING STRUCTURE - L-867D TYPE, SINGLE ELEMENT, CONCRETE ENCASED, WITH 3/8" COVER PLATE	2	EA		
L-115-11	AIRCRAFT RATED HANDHOLE - NEW 4' X 4' X 4' WITH SPRING ASSIST LID	11	EA		
L-115-12	AIRCRAFT RATED HANDHOLE - RELOCATED 4' X 4' X 4'	2	EA		
L-124-01	LIGHT BASE - TYPE NB1 - L-867B IA, ADJUSTABLE STYLE, LOCATED IN NEW SHOULDER, CONNECTED WITH TRENCH CONDUIT	148	EA		
L-124-02	LIGHT BASE - TYPE NB2 - L-867B IA, ADJUSTABLE STYLE, LOCATED IN EXISTING SHOULDER	18	EA		
L-124-11	LIGHT BASE - TYPE NBB - L-868B IA, SINGLE-SECTION ASSEMBLY, LOCATED IN EXISTING FULL-STRENGTH CONCRETE, CONNECTED VIA KERF CUT CONDUITS	45	EA		
L-124-12	LIGHT BASE - TYPE NBD - L-868B IA, SINGLE-SECTION ASSEMBLY, LOCATED IN RENOVATED FULL STRENGTH SLAB, CONNECTED WITH CONDUITS IN RENOVATED SLAB.	39	EA		
L-124-13	REFLECTOR BASE - TYPE NBZ - 2' DIA. 8" DEEP FORMED FOUNDATION	2	EA		
L-124-21	STUDY OF EXISTING LIGHT BASES	1	LS		
L-124-22	RETROFIT EXISTING LIGHT BASE - ADD INTERNAL GROUND LUG AND 6' #6 AWG, INSULATED, STRANDED EQUIPMENT GROUND	736	EA		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
L-125-01	RUNWAY LIGHTING DEVICE - L-850A(L) LED INSET RUNWAY CENTERLINE LIGHT	219	EA		
L-125-02	RUNWAY LIGHTING DEVICE - L-850B(L) LED INSET RUNWAY TOUCHDOWN LIGHT	180	EA		
L-125-03	RUNWAY LIGHTING DEVICE - L-850C(L) LED INSET RUNWAY EDGE LIGHT	20	EA		
L-125-04	RUNWAY LIGHTING DEVICE - L-862(L) LED ELEVATED RUNWAY EDGE LIGHT OR L-862E(L) LED ELEVATED RUNWAY THRESHOLD END LIGHT	118	EA		
L-125-11	TAXIWAY LIGHTING DEVICE - L-852C(L) INSET TAXIWAY CENTERLINE LIGHT	81	EA		
L-125-12	TAXIWAY LIGHTING DEVICE - L-852D(L) INSET TAXIWAY CENTERLINE LIGHT	46	EA		
L-125-13	TAXIWAY LIGHTING DEVICE - L-852K(L) INSET TAXIWAY CENTERLINE LIGHT	14	EA		
L-125-14	TAXIWAY LIGHTING DEVICE - L-861T(L) ELEVATED TAXIWAY EDGE LIGHT	239	EA		
L-125-21	INTERSECTION LIGHTING DEVICE - L-852G(L) LED INSET RUNWAY GUARD LIGHTS	46	EA		
L-125-31	EDGE MARKING DEVICE - L-853 RETROREFLECTIVE TAXIWAY MARKER (BLUE, YELLOW, OR RED)	32	EA		
L-125-41	COVER PLATE - L-894 3/8" FOR L-867B LIGHT BASE	31	EA		
L-125-42	COVER PLATE - L-894 3/4" FOR L-868B LIGHT BASE	24	EA		
L-126-1	SIGNAGE DEMOLITION	1	LS		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
L-126-2	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 2 MODULE	3	EA		
L-126-2.2	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 2 MODULE (A)	4	EA		
L-126-2.3	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 2 MODULE (N)	1	EA		
L-126-3	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 3 MODULE	22	EA		
L-126-3.2	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 3 MODULE (A)	1	EA		
L-126-3.3	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 3 MODULE (N)	5	EA		
L-126-3.4	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 3 MODULE (C)	1	EA		
L-126-4	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 4 MODULE	7	EA		
L-126-4.2	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 4 MODULE (A)	2	EA		
L-126-4.4	L-858(L) SIGN – SINGLE/DOUBLE FACE, LED, SIZE 3 - 4 MODULE (C)	3	EA		
L-126-5	L-858B(L) SIGN – RUNWAY DISTANCE REMAINING SIGN, LED, SIZE 4	10	EA		
L-126-6	NON-LIGHTED BOUNDARY SIGN	1	EA		
L-126-7	NON-LIGHTED TRAFFIC SIGN	2	EA		
L-126-8	NEW SIGN PANEL	46	EA		
L-131-01	REMOVAL OF CONSTANT CURRENT REGULATOR	4	EA		
L-131-11	CCR - L-828, 10 KW, 5-STEP, WITH L-827 MONITOR IRMS TESTING OPTION	1	EA		
L-131-12	CCR - L-828, 15 KW, 5-STEP, WITH L-827 MONITOR IRMS TESTING OPTION	1	EA		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
L-131-21	CCR - INSTALL OWNER FURNISHED 10 KW CCR FROM CLIENT STORAGE	1	EA		
L-131-31	CONSTANT CURRENT REGULATOR COMMISSIONING REPORT	1	LS		
L-142-01	PHOTOMETRIC TESTING OF FIELD FIXTURES	1	LS		
L-143-01	FLIGHT CHECK COORDINATION AND SUPPORT	1	LS		
L-152-01	ALCMS GRAPHICS / RE-CONFIGURATION - ALCMS VENDOR	1	AL		
L-152-02	ALCMS GRAPHICS / RE-CONFIGURATION - CONTRACTOR	1	LS		
L-198-01	AIRFIELD LIGHTING MAINTENANCE TOOLS PACKAGE	1	LS		
L-199-01	AIRFIELD LIGHTING SPARE PARTS PACKAGE	1	LS		
05 50 00-1	NEW STEEL BOLLARD AND FOUNDATION, IN PAVEMENT	57	EA		
05 50 00-2	NEW STEEL BOLLARD AND FOUNDATION, IN TURF	8	EA		
05 50 00-3	REPAINTING EXISTING BOLLARD	35	EA		
26 05 19-1	MODIFICATION TO EXISTING ELECTRICAL DISTRIBUTION SYSTEM AT EXISTING BLDG.	1	LS		
26 05 33-1	CONDUIT AND WIRE (HML CIRCUITS, CIB CIRCUITS, SPARES)	1	LS		
26 05 33-2	ELECTRICAL PULL BOX	9	EA		
26 09 23-1	LIGHTING CONTACTORS	2	EA		
26 22 00-1	LOW VOLTAGE TRANSFORMERS	1	LS		
26 24 16 -1	PANELBOARDS	1	LS		

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
26 56 00-1	HIGH MAST LIGHT POLE (FIXTURES, LIGHTNING PROTECTION, GROUNDING)	9	EA		
27 10 00-1	6-STRAND SINGLE MODE FIBER	4,000	LF		
27 10 00-2	(2) 2" FIBER OPTIC DUCT	3,000	LF		
27 10 00-3	EXTENSION OF EXISTING FIBER BACKBONE	1	LS		
27 10 00 -4	FIBER PULL BOXES	9	EA		
28 15 00-1	PLWS CIRCUITS AND DISCONNECTS	1	LS		
28 20 00-1	CCTV CAMERAS AND CAMERA INTERFACE BOXES	5	EA		
331100-1	RELOCATE/REMOVE EXISTING FIRE HYDRANTS	2	EA		
331100-2	UTILITY PIPE, REMOVE OUT OF SERVICE, PVC, WATER, 5.0-7.9" (EXISTING WATER MAINS -REMOVE 6" WM)	600	LF		
331100-3	INSTALL NEW FIRE HYDRANT (FURNISH AND INSTALL INCLUDING NEW 6" GATE VALVES AND NEW 8" X 6" TEES)	3	EA		
331100-4	INSTALL NEW 8" PVC WATERLINE	900	LF		
331100-5	INSTALL NEW 6" PVC WATERLINE	81	LF		
331100-6	INSTALL NEW 8" GATE VALVE	4	EA		
331100-7	INSTALL NEW 8" INSERTION VALVE	2	EA		
331100-8	INSTALL NEW 8"X8" TEE	1	EA		
331100-9	INSTALL NEW 8"X6" TEE	1	EA		
331100-10	INSTALL NEW 8"X6" TAPPING SLEEVE	1	EA		
331100-11	INSTALL NEW 8" CAP	2	EA		
331100-12	ADJUST SANITARY SEWER MANHOLE	1	EA		

Tampa International Airport

Invitation to Bid

Rehabilitate Runway 1L-19R and Associated Taxiways and Northwest Remain Overnight (RON) Parking Apron

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
1020A	OWNER'S ALLOWANCE	1	AL	\$2,000,000.00	
TOTAL					